



Transportation Research Division



Technical Report 18-2

Instrumentation During Live Load Testing and Load Rating of Five Slab-On-Girder Bridges

December 2016

Technical Report Documentation Page

| | | | |
|---|--------------------------------|--|-----------|
| 1. Report No. ME 18-2 | 2. | 3. Recipient's Accession No. | |
| 4. Title and Subtitle Instrumentation During Live Load Testing and Load Rating of Five Slab-On-Girder Bridges | | 5. Report Date December 2016 | |
| | | 6. | |
| 7. Author(s) Scott Tomlinson P.E., William Davids Ph.D, P.E. | | 8. Performing Organization Report No. 17-11-1414 | |
| 9. Performing Organization Name and Address Advanced Structures and Composites Center University of Maine 35 Flagstaff Rd. Orono, ME 04469 | | 10. Project/Task/Work Unit No. Project 017666.00 & 020832.00 | |
| | | 11. Contract © or Grant (G) No. Contract # 20160413000000003122 | |
| 12. Sponsoring Organization Name and Address Maine Department of Transportation | | 13. Type of Report and Period Covered | |
| | | 14. Sponsoring Agency Code | |
| 15. Supplementary Notes | | | |
| 16. Abstract (Limit 200 words) Five slab-on-girder bridges were tested during the summer of 2016 by the University of Maine (UMaine) as part of this program for the Maine Department of Transportation (MaineDOT): 1. Steuben No. 3067 Dyer Bay Road over Dyer Creek, 2. Waltham No. 3238 Route 179 over Union River, 3. Pembroke No. 3884 Pembroke Cross Road over Pennamaquan River, 4. Windham No. 5298 Windham Center Road over Pleasant River, 5. Buckfield No. 5452 North Buckfield Road over Nezinscot River (West Branch). Revised load ratings were computed using data collected during live load testing. Details of bridge instrumentation, load cases, and strain plots for each bridge are provided in Appendices A.1, A.3, A.3.5, A.4.5, and A.5.5. The results of the tests and analyses are summarized below and are compared with the existing ratings. Use of these revised load ratings, live load test data, and extrapolation of these results to other structures is at the sole discretion of the bridge owner. | | | |
| 17. Document Analysis/Descriptors Bridge load rating, steel girder, live load testing | | 18. Availability Statement | |
| 19. Security Class (this report) | 20. Security Class (this page) | 21. No. of Pages 143 | 22. Price |

Instrumentation During Live Load Testing and Load Rating of Five Slab-On-Girder Bridges

Prepared for:
Dale Peabody P.E.
Director Transportation Research
Maine Dept. of Transportation
16 State House Station
Augusta ME 04333-0016
University of Maine's Advanced Structures and Composites Center
Report Number: 17-11-1414

2016-12-29-Rev00

Prepared by:

Bill Davids PhD, PE
John C. Bridge Professor of Civil and
Environmental Engineering

Scott Tomlinson PE, SCWI, Research Engineer
Mahmood Jaleel Albraheemi, Graduate Researcher
Andrew Schanck, Undergraduate Research Assistant

Reviewed by:

Joshua Clapp PE
Research Engineer

This report shall not be reproduced, except in full, without the written approval of
University of Maine's Advanced Structures and Composites Center.

*The University of Maine Advanced Structures and Composites Center is an ISO 17025 accredited testing laboratory, accredited by the
International Accreditation Service.*



Document Log

| Name/ Organization | Date | Version | Action |
|---|------------|---------|------------------------------|
| William Davids, Author Scott Tomlinson, Author Mahmood Albraheemi, Author Andrew Schanck, Author Joshua Clapp, Reviewer | 2016-12-29 | Rev00 | Initial release to MaineDOT. |
| | | | |

Table of Contents

| | |
|---|-----------|
| Index of Figures..... | 3 |
| Index of Tables | 5 |
| Acronyms | 6 |
| Executive Summary | 7 |
| 1 Bridge Testing Program..... | 8 |
| 1.1 Instrumentation..... | 9 |
| 1.2 Loading..... | 11 |
| 1.3 Typical Results..... | 12 |
| 1.4 Analysis Methodology..... | 15 |
| 1.4.1 Analysis Overview..... | 15 |
| 1.4.2 Bridge Characteristics..... | 15 |
| 1.4.3 AASHTO Distribution Factors | 16 |
| 1.4.4 AASHTO Live Loads with Impact..... | 16 |
| 1.4.5 Non-composite Rating Factor..... | 16 |
| 1.4.6 Live Loads Applied during Testing..... | 16 |
| 1.4.7 Percent Composite Action and Measured Section Properties..... | 17 |
| 1.4.8 Distribution Factors Determined from Live Load Testing | 18 |
| 1.4.9 Modified Rating Factor..... | 18 |
| 1.4.10 Shear Flow | 19 |
| 2 Live Load Test Results | 19 |
| 2.1 Steuben No. 3067..... | 19 |
| 2.2 Waltham No. 3238 | 21 |
| 2.3 Pembroke No. 3884..... | 23 |
| 2.4 Windham No. 5298 | 25 |
| 2.5 Buckfield No. 5452..... | 27 |
| 3 Summary of Live Load Test Data Conclusions..... | 29 |
| 4 References..... | 30 |
| A.1 Experimental Configuration and Data Collected | 30 |
| A.1.1 Input Data..... | 30 |
| A.1.2 Experimental Configuration | 31 |

| | | |
|------------|--|------------|
| A.1.3 | <i>Collected Data</i> | 31 |
| A.2 | Steuben No. 3067 | 32 |
| A.2.1 | <i>Input Data, Experimental Configuration, and Experimental Data Collected</i> | 32 |
| A.2.2 | <i>Instrumentation</i> | 32 |
| A.2.3 | <i>Loading</i> | 33 |
| A.2.4 | <i>Representative Data Plots</i> | 37 |
| A.2.5 | <i>Rating Factor Calculations</i> | 43 |
| A.3 | Waltham No. 3238 | 57 |
| A.3.1 | <i>Input Data, Experimental Configuration, and Experimental Data Collected</i> | 57 |
| A.3.2 | <i>Instrumentation</i> | 57 |
| A.3.3 | <i>Loading</i> | 58 |
| A.3.4 | <i>Representative Data Plots</i> | 62 |
| A.3.5 | <i>Rating Factor Calculations</i> | 66 |
| A.4 | Pembroke No. 3884 | 80 |
| A.4.1 | <i>Input Data, Experimental Configuration, and Experimental Data Collected</i> | 80 |
| A.4.2 | <i>Instrumentation</i> | 80 |
| A.4.3 | <i>Loading</i> | 81 |
| A.4.4 | <i>Representative Data Plots</i> | 85 |
| A.4.5 | <i>Rating Factor Calculations</i> | 89 |
| A.5 | Windham No. 5298 | 101 |
| A.5.1 | <i>Input Data, Experimental Configuration, and Experimental Data Collected</i> | 101 |
| A.5.2 | <i>Instrumentation</i> | 101 |
| A.5.3 | <i>Loading</i> | 102 |
| A.5.4 | <i>Representative Data Plots</i> | 106 |
| A.5.5 | <i>Rating Factor Calculations</i> | 110 |
| A.6 | Buckfield No. 5452 | 124 |
| A.6.1 | <i>Input Data, Experimental Configuration, and Experimental Data Collected</i> | 124 |
| A.6.2 | <i>Instrumentation</i> | 124 |
| A.6.3 | <i>Loading</i> | 125 |
| A.6.4 | <i>Representative Data Plots</i> | 129 |
| A.6.5 | <i>Rating Factor Calculations</i> | 131 |

Index of Figures

| | | |
|-----------|--|----|
| Figure 1: | Typical strain sensors mounted under bridge connected to wireless nodes | 9 |
| Figure 2: | BDI STS-Wi-Fi network setup for bridge sensor setup. | 10 |
| Figure 3: | MaineDOT UBIT utilized to install sensors..... | 11 |
| Figure 4: | Maine DOT trucks used for bridge loading..... | 11 |
| Figure 5: | State highway patrol certified portable crane scales used to verify vehicle weight for each test | 12 |

| | |
|---|----|
| Figure 6: Pembroke No. 3884 – 4 trucks, 2 lanes, test 2, strains in center girder | 13 |
| Figure 7: Pembroke No. 3884 - 4 trucks, 2 lanes, test 2, slip between girder and slab | 13 |
| Figure 8: Buckfield No. 5452 - 4 trucks, 2 lanes, test 1, strain in center girder | 14 |
| Figure 9: Buckfield No. 5452 - 4 trucks, 2 lanes, test 1, slip between girder and slab..... | 15 |
| Figure 10: Typical linear strain distribution | 17 |
| Figure 11: Steuben No. 3067 general condition | 20 |
| Figure 12: Waltham No. 3238 general condition..... | 22 |
| Figure 13: Pembroke No. 3884 General condition | 24 |
| Figure 14: Windham No. 5298 general condition | 26 |
| Figure 15: Buckfield No. 5452 general condition | 28 |
| Figure 16: Steuben No. 3067 sensor layout | 32 |
| Figure 17: Steuben No. 3067 Truck T01-137 loading | 33 |
| Figure 18: Steuben No. 3067 Truck T01-157 loading | 34 |
| Figure 19: Steuben No. 3067 Truck T01-166 loading..... | 35 |
| Figure 20: Steuben No. 3067 Truck T01-198 loading | 36 |
| Figure 21: Steuben No. 3067- 2 trucks 2 lanes test 1 strain | 37 |
| Figure 22: Steuben No. 3067- 2 trucks 2 lanes test 1 shear slip | 38 |
| Figure 23: Steuben No. 3067- 4 trucks 2 lanes test 1 strains | 39 |
| Figure 24: Steuben No. 3067- 4 trucks 2 lanes test 1 shear slip | 40 |
| Figure 25: Steuben No. 3067- 4 trucks 2 lanes test 2 strains | 41 |
| Figure 26: Steuben No. 3067- 4 trucks 2 lanes test 2 shear slip | 42 |
| Figure 27: Steuben No. 3067 Calculations | 43 |
| Figure 28: Waltham No. 3238 sensor layout | 57 |
| Figure 29: Waltham No. 3238 Truck T01-119 loading | 58 |
| Figure 30: Waltham No. 3238 Truck T01-257 loading | 59 |
| Figure 31: Waltham No. 3238 Truck T01-280 loading | 60 |
| Figure 32: Waltham No. 3238 Truck T01-287 loading | 61 |
| Figure 33: Waltham No. 3238 - 2 trucks 2 lanes test 2 strains | 62 |
| Figure 34: Waltham No. 3238 - 2 trucks 2 lanes test 2 shear slip | 63 |
| Figure 35: Waltham No. 3238 - 4 trucks 2 lanes test 1 strains | 64 |
| Figure 36: Waltham No. 3238 - 4 trucks 2 lanes test 1 shear slip | 65 |
| Figure 37: Waltham No. 3238 Calculations | 66 |
| Figure 38: Pembroke No. 3884 sensor layout..... | 80 |
| Figure 39: Pembroke No. 3884 Truck T01-223 loading..... | 81 |
| Figure 40: Pembroke No. 3884 Truck T01-231 loading..... | 82 |
| Figure 41: Pembroke No. 3884 Truck T01-242 loading..... | 83 |
| Figure 42: Pembroke No. 3884 Truck T01-244 loading..... | 84 |
| Figure 43: Pembroke No. 3884 - 4 trucks 2 lanes test 1 strains..... | 85 |
| Figure 44: Pembroke No. 3884 - 4 trucks 2 lanes test 1 shear slip..... | 86 |
| Figure 45: Pembroke No. 3884 - 4 trucks 2 lanes test 2 strains..... | 87 |

| | |
|---|-----|
| Figure 46: Pembroke No. 3884 - 4 trucks 2 lanes test 2 shear slip..... | 88 |
| Figure 47: Pembroke No. 3884 Calculations..... | 89 |
| Figure 48: Windham No. 5298 sensor layout..... | 101 |
| Figure 49: Windham No. 5298 Truck T01-164 loading..... | 102 |
| Figure 50: Windham No. 5298 Truck T01-197 loading..... | 103 |
| Figure 51: Windham No. 5298 Truck T01-247 loading..... | 104 |
| Figure 52: Windham No. 5298 Truck T01-259 loading..... | 105 |
| Figure 53: Windham No. 5298 - 2 trucks 2 lanes test 1 strains..... | 106 |
| Figure 54: Windham No. 5298 - 2 trucks 2 lanes test 1 shear slip..... | 107 |
| Figure 55: Windham No. 5298 - 4 trucks 2 lanes test 2 strains..... | 108 |
| Figure 56: Windham No. 5298 - 4 trucks 2 lanes test 2 shear slip..... | 109 |
| Figure 57: Windham No. 5298 Calculations..... | 110 |
| Figure 58: Buckfield No. 5452 sensor layout..... | 124 |
| Figure 59: Buckfield No. 5452 Truck T01-129 loading..... | 125 |
| Figure 60: Buckfield No. 5452 Truck T01-220 loading..... | 126 |
| Figure 61: Buckfield No. 5452 Truck T01-246 loading..... | 127 |
| Figure 62: Buckfield No. 5452 Truck T01-273 loading..... | 128 |
| Figure 63: Buckfield No. 5425 - 4 trucks 2 lanes test 1 strains..... | 129 |
| Figure 64: Buckfield No. 5425 - 4 trucks 2 lanes test 1 shear slip..... | 130 |
| Figure 65: Buckfield No. 5452 Calculations..... | 131 |

Index of Tables

| | |
|---|----|
| Table 1: Bridge Characteristics..... | 8 |
| Table 2: Steuben No. 3067 Strain and Neutral Axis Data..... | 21 |
| Table 3: Steuben No. 3067 distribution factors..... | 21 |
| Table 4: Waltham No. 3238 Strain and Neutral Axis Data..... | 23 |
| Table 5: Waltham No. 3238 distribution factors..... | 23 |
| Table 6: Pembroke No. 3884 Strain and Neutral Axis Data..... | 24 |
| Table 7: Pembroke No. 3884 distribution factors..... | 25 |
| Table 8: Windham No. 5298 Strain and Neutral Axis Data..... | 26 |
| Table 9: Windham No. 5298 distribution factors..... | 27 |
| Table 10: Buckfield No. 5452 Strain and Neutral Axis..... | 28 |
| Table 11: Buckfield No. 5452 distribution factors..... | 29 |
| Table 12: Steuben No. 3067 Bridge Input Data, Experimental Configuration, and Experimental Data Collected..... | 32 |
| Table 13: Waltham No. 3238 Bridge Input Data, Experimental Configuration, and Experimental Data Collected..... | 57 |

Table 144: Windham No. 5298 Bridge Input Data, Experimental Configuration, and Experimental Data Collected..... 101

Table 15: Buckfield No. 5452 Bridge Input Data, Experimental Configuration, and Experimental Data Collected..... 124

Acronyms

Cases

AASHTO: American Association of State Highway and Transportation Officials 29

BDI: Bridge Diagnostics Inc..... 9

LVDT: Linear Variable Differential Transformer 9

Maine DOT: Maine Department of Transportation 7

STS-WiFi: Wireless Structural Testing System 9

UBIT: Under Bridge Inspection Truck 10

UMaine: The University of Maine..... 7

Executive Summary

Five slab-on-girder bridges were tested during the summer of 2016 by the University of Maine (UMaine) as part of this program for the Maine Department of Transportation (MaineDOT):

1. Steuben No. 3067 Dyer Bay Road over Dyer Creek,
2. Waltham No. 3238 Route 179 over Union River,
3. Pembroke No. 3884 Pembroke Cross Road over Pennamaquan River,
4. Windham No. 5298 Windham Center Road over Pleasant River,
5. Buckfield No. 5452 North Buckfield Road over Nezinscot River (West Branch).

Revised load ratings were computed using data collected during live load testing. Details of bridge instrumentation, load cases, and strain plots for each bridge are provided in Appendices A.1, A.3, A.3.5, A.4.5, and A.5.5. The results of the tests and analyses are summarized below and are compared with the existing ratings. Use of these revised load ratings, live load test data, and extrapolation of these results to other structures is at the sole discretion of the bridge owner.

1. Steuben No. 3067: On July 21, 2016, four trucks were used to produce 78% of an HL-93 service load with impact. The rating factors based on non-composite response were 0.80 for interior and 1.04 for exterior girders, which made this span the lowest capacity bridge tested. Applied loads were near the predicted capacity. Not surprisingly, the strains measured were the highest for any of the bridges and it was among those exhibiting the least observed partial composite action, which led to the most modest rating factor increases for this set of bridges. However, using the provisions of the *AASHTO Manual for Bridge Evaluation* (AASHTO 2012), the rating factor for HL-93 was still increased to 1.09 for the interior girder and 1.13 for exterior girder bringing the rating factors above 1.0.
2. Waltham No. 3238: On July 14, 2016 87% of an HL-93 loading with impact was produced with four trucks. This was the highest loading for all bridges, but this structure also had the highest non-composite rating factors of 1.17 for the interior girder and 1.61 for the exterior girder. Full composite action was observed for this bridge, and measured strains were relatively small. Rating factors were increased for this structure to 1.68 for interior girders and 2.82 for exterior girders.
3. Pembroke No. 3884: On July 19, 2016 81% of an HL-93 loading with impact was produced for this span using four trucks. The initial non-composite rating factors were 0.86 for interior girders and 1.09 for exterior girders. Fairly high strain was produced compared to other bridges in the group, but full composite action was observed. Live load testing results allowed the rating factors to be increased to 1.33 for interior girders and 2.52 for exterior girders.
4. Windham No. 5298: On August 23, 2016 77% of an HL-93 loading with impact was achieved with four trucks. This structure had low non-composite rating factors of 0.81 for the interior and 0.99 for the exterior girders. Due to the observed full composite action, measured strains were low and rating factor increases to 1.26 and 1.29 for interior and exterior girders, respectively, were justified.

5. Buckfield No. 5452: On July 12, 2016 four trucks were used to produce 74% of an HL-93 loading with impact. Despite only partial composite action, this bridge saw the highest increase in rating factors from 0.96 and 1.18 to 1.61 and 1.76 for interior and exterior girders respectively.

1 Bridge Testing Program

Five concrete slab on steel girder bridges were tested during the summer of 2016 as part of this program:

1. Steuben No. 3067 Dyer Bay Road over Dyer Creek
2. Waltham No. 3238 Route 179 over Union River,
3. Pembroke No. 3884 Pembroke Cross Road over Pennamaquan River,
4. Windham No. 5298 Windham Center Road over Pleasant River,
5. Buckfield No. 5452 North Buckfield Road over Nezinscot River (West Branch).

All bridges were instrumented with a strain measuring system, loaded with heavy trucks, and then analyzed to determine whether it is reasonable to change the bridge rating factors based on the test results. These bridges were all constructed between 1935 and 1951, and were originally designed as non-composite with no shear studs. However, the top flanges of the girders were fully embedded in the concrete deck for all structures, which can result in significant composite action. The primary objective of this study was to assess the magnitude and significance of unintended composite action between the deck and girders. Additionally, the live load testing permitted quantification of partial support fixity, actual live load distribution, and the contribution of non-structural elements such as curbs, wearing surfaces, and partial concrete embedment of girder ends. Finally, recommendations for rating factor modifications are made based on the observed and computed response of these structures. Characteristics of the bridges tested and analyzed in this study are summarized in Table 1.

Table 1: Bridge Characteristics

| Bridge | Steuben | Waltham | Pembroke | Windham | Buckfield |
|-------------------------------------|----------------|----------------|-----------------|----------------|------------------|
| Number | 3067 | 3238 | 3884 | 5298 | 5452 |
| Year Built | 1949 | 1935 | 1944 | 1950 | 1951 |
| Span (feet) | 50.00 | 55.00 | 45.25 | 46.00 | 42.50 |
| Interior Girder Size | W30x108 | W36x150 | W27x98 | W30x108 | W27x102 |
| Number of Girders | 5 | 5 | 5 | 5 | 5 |
| Girder Spacing (in) | 64 | 66 | 69 | 69 | 69 |
| Total depth (in) | 29.83 | 35.85 | 27.00 | 29.83 | 27.09 |
| Girder flange width (in) | 10.48 | 11.98 | 10.00 | 10.48 | 10.02 |
| Girder flange thickness (in) | 0.76 | 0.94 | 0.79 | 0.76 | 0.83 |
| Girder web thickness (in) | 0.55 | 0.63 | 0.50 | 0.55 | 0.52 |
| Haunch (in) | -6.25 | 2.00 | -0.792 | 0.50 | 2.00 |
| Slab Thickness (in) | 6.75 | 11.0 | 6.75 | 9.00 | 9.00 |

1.1 Instrumentation

The strain measurement system utilized in this research is a partially Wireless Structural Testing System (STS-Wi-Fi) produced by Bridge Diagnostics Inc. (BDI). The system used for this testing utilized a mobile base station to communicate with up to 6 nodes, with up to 4 strain sensors or linear variable differential transformers (LVDTs) connected to each node. This system communicated with a dedicated laptop running BDI-specific WinSTS data acquisition software. A sample setup in the field is shown in Figure 1, with strain sensors mounted under the bridge at mid-span connected to battery operated wireless nodes. A clear diagram of the entire network is shown in Figure 2 including strain and displacement sensors, wireless nodes, the wireless base station, autoclicker, and the data recording laptop.




Figure 1: Typical strain sensors mounted under bridge connected to wireless nodes




Figure 2: BDI STS-Wi-Fi network setup for bridge sensor setup.

Strain and displacement sensors were mounted under the bridges using a MaineDOT Under Bridge Inspection Truck (UBIT) as shown in Figure 3. The sensors were mounted to the girders by first grinding the steel to a fresh, unpainted surface, then using the recommended adhesive to connect the strain sensor tabs to the steel. All structures had three strain gages mounted to the top flange, mid-depth and bottom flange of at least three girders at mid-span to give a complete picture of load distribution and peak flexural strains in each girder type: center, interior non-center, and exterior. Strain gages were also installed near the ends of selected girders to assess the support rotational restraint. LVDTs were placed near the ends of selected girders with one end attached to a girder top flange and one end attached to the bottom of the slab to measure slip between the slab and girder top flange. Strain sensor layout varied slightly for each bridge, with individual sensor layouts shown in the appendices A.2.2 for Steuben, A.3.2 for Waltham, A.4.2 for Pembroke, A.5.2 for Windham, and A.6.2 for Buckfield.



Figure 3: MaineDOT UBIT utilized to install sensors

1.2 Loading

The vehicles used for this testing were Maine DOT standard three-axle dump trucks as shown in Figure 4. Each truck wheel or pair of wheels was weighed using state patrol certified portable scales as shown in Figure 5. Loading cases included one, two, and four trucks in designated lanes along loading paths. Trucks were positioned sequentially such that they produced maximum moment or significant shear in the bridge girders. In general, a set of tests included a single truck in one lane, two trucks in one lane back-to-back, two trucks side-by-side in opposite lanes, and four trucks, two back-to-back per lane, although not all bridges were subjected to all load cases.




Figure 4: Maine DOT trucks used for bridge loading



Figure 5: State highway patrol certified portable crane scales used to verify vehicle weight for each test

1.3 Typical Results

Results from two bridges are presented in this section to demonstrate two distinct types of behavior in the bridges tested in this study. The first bridge, Pembroke No. 3884, is typical of bridges with observed full composite action. Figure 6 shows a time history of the strains in the center interior girder as the bridge is loaded in the four truck, two lane, second test, and Figure 7 shows the slip between the girder and the slab in inches over the same test. Positive slip indicates the girder moving toward the pinned end relative to the slab, with negative slip indicating the slab is moving toward the pinned end relative to the girder. First the trucks are positioned back to back to incrementally increase shear to a maximum value, typically producing the maximum slip shown in Figure 7, although in some instances maximum slip was seen with the trucks positioned to produce maximum moment. After shear maximization tests, the trucks were then positioned to maximize moment in the bridge where strains in the center girder are maximized as shown in Figure 6. The strains in this test are typical of those three bridges showing full composite action, in that the midspan of the center girder shows high positive strains at the bottom, near zero strains at the top of the midspan gage set, and the middle gage splits the difference. This indicates high composite action with the neutral axis near the top of the girder. The slip is small compared to bridges showing only partial composite action. One note is that this bridge is typical of all bridges with much greater slip being measured at the interior girder than the exterior girder, likely because the interior girder carried much larger live load. Another important note is that the two end gages located at the bottom of the girder recorded negative strains. This is typical of all bridges and girders, and indicates partial rotational restraint at the abutments. It is unknown if this fixity will continue to be observed at higher load levels, or if there are seasonal or local causes of this partial

fixity that cannot be extrapolated to other bridges of this type. Full moment connections would yield approximately twice the strain readings as the magnitude of the midspan readings, and simply supported would yield small positive strain readings. This shows that the girder is closer to simply supported than fixed, but that the rotational restraint is still significant.




Figure 6: Pembroke No. 3884 – 4 trucks, 2 lanes, test 2, strains in center girder




Figure 7: Pembroke No. 3884 - 4 trucks, 2 lanes, test 2, slip between girder and slab

The other bridge shown in this section is the Buckfield No. 5452 bridge undergoing four truck, two lane loading. Figure 8 shows a time series of the strains in the center interior girder and Figure 9 shows the slip between the girder and slab as the bridge is loaded in the same manner as described above for Pembroke No. 3884. This bridge is typical of the two bridges that were observed to have

partial composite action. The midspan of the center interior girder shows large positive strains at the bottom, near zero strains at the middle of the girder at midspan, and large negative strains at the top of the girder at midspan. This indicates a neutral axis much closer to that of the non-composite girder than the neutral axis location predicted by fully composite action. However, this bridge is typical of all bridges tested in that negative strains were observed in the bottom flanges of the ends of the girders. This indicates that rotational restraint is provided at the abutments. Again, it is uncertain if this fixity will remain at higher loads or if it is affected by seasonal or local effects unique to these bridges. Full strain and slip plots for all bridge two and four truck tests are presented in the appendices. See section A.2.4 for Steuben No. 3067, A.3.4 for Waltham No. 3238, A.4.4 for Pembroke No. 3884, A.5.4 for Windham No. 5298, and A.6.4 for Buckfield No. 5452.




Figure 8: Buckfield No. 5452 - 4 trucks, 2 lanes, test 1, strain in center girder




Figure 9: Buckfield No. 5452 - 4 trucks, 2 lanes, test 1, slip between girder and slab

1.4 Analysis Methodology

1.4.1 Analysis Overview

Material properties, load and resistance factors, and design live loads were taken as specified in the *AASHTO Manual For Bridge Evaluation* and used with field-measured geometry to determine original non-composite rating factors for the bridges. Bridges were then tested using heavily loaded trucks and strains were measured and correlated with these applied loads. Resulting strains from live load testing were then used to compute percent composite action, effective section properties that reflected composite action, distribution factors determined from live load testing, modified rating factors, and shear flows. These calculation sheets are included in the appendices of this report. Appendix A.2.5 contains calculations for Steuben No. 3067, A.3.5 pertains to Waltham No. 3238, A.4.5 corresponds to Pembroke No. 3884, A.5.5 is for Windham No. 5298, and A.6.5 is for Buckfield No. 5452.

1.4.2 Bridge Characteristics

First, necessary parameters were defined for use in calculations. These included material properties for each bridge, as well as general bridge geometry (i.e. span length, girder section properties, and slab section properties). These were taken from each bridge's most recent available rating report or based on minimum material properties specified by the *AASHTO Manual for Bridge Evaluation*. Dead load moments and shears were determined from the bridge geometry and typical unit weights as specified in *AASHTO Manual for Bridge Evaluation*.

1.4.3 AASHTO Distribution Factors

Distribution factors for moment and shear for interior and exterior girders are calculated based on in-situ measured bridge characteristics along with nominal values for dimensions that could not be verified in the field in accordance with AASHTO *LRFD Bridge Design Specifications*. All distribution factors of live load per lane for moment and shear are taken as cross-section “a” from Table 4.6.2.2.1-1 and Concrete Deck on Steel. For moment on interior beams this is per Table 4.6.2.2.2b-1, with all of the ranges of applicability met. For shear in interior beams the values calculated are from Table 4.6.2.2.3a-1 with all the ranges of applicability met. For the exterior girder moment distribution factors are per Table 4.6.2.2.2d-1 and the exterior girder shear distribution factors are per Table 4.6.2.2.3b-1.

1.4.4 AASHTO Live Loads with Impact

AASHTO live loads with impact (LL + IM) are determined as the maximum load effect with HL-93 per (6A.2.3) and AASHTO LRFD Design 3.6.1.2 and 3.6.2. This includes the worst case of truck or tandem loading with lane loads and impact as applicable.

1.4.5 Non-composite Rating Factor

Non-composite flexural rating factors are computed per AASHTO Manual for Bridge Evaluation (6A.4.2.1-1) with terms as defined in that section. Values specific to the bridges in this study are as shown in Equation 1. The live load per section 1.4.4 with impact is modified by the AASHTO distribution factors as described in section 1.4.3.

$$RF = \frac{C - \gamma_{DC}DC - \gamma_{DW}DW \pm \gamma_P P}{\gamma_{LL}(LL + IM)} \quad \text{Equation 1}$$

$$C = \varphi_c \varphi_s \varphi R_n \quad (6A.4.2.1-1)$$

$$\varphi_c = 1.0 \text{ per Table 6A.4.2.3-1}$$

$$\varphi_s = 1.0 \text{ per Table 6A.4.2.4-1}$$

$$\varphi = 1.0 \text{ per LRFD Design 6.5.4.2}$$

$$\gamma_{DC} = 1.25 \text{ per Table 6A.4.2.2-1}$$

$$\gamma_{DW} = 1.50 \text{ per Table 6A.4.2.2-1}$$

$$\gamma_{LL} = 1.75 \text{ per Table 6A.4.2.2-1}$$

$$\text{Non-composite flexural } R_n = F_y Z \text{ per Table LRFD Design 6.10.7.1.2}$$

$$P = 0 \text{ for all bridges in this study}$$

1.4.6 Live Loads Applied during Testing

Applied moment and shear live loadings were determined based on measured truck axle weights for both the load cases of two trucks, side-by-side in two lanes, and four trucks, two trucks back-to-back in each of two lanes. The average of axle loads for side-by-side trucks was used to allow

live load distribution factors to be applied. The trucks were first positioned to maximize shear at distances of 2.0, 1.5, 1.0, and 0.5 times the depth from the center of the support. The trucks were then positioned to produce the maximum moment effect on the bridge. For each set of truck positions, strains were allowed to plateau and then measured before moving the trucks to the next set of truck positions.

Applied moments and shears were calculated based on simply supported beam assumptions. The percentage of AASHTO HL-93 loading achieved is the ratio of the moment produced by the live loads applied during testing and the moment produced by the AASHTO HL-93 loading as described in section 1.4.4.

1.4.7 Percent Composite Action and Measured Section Properties

For each girder, the percent composite action is calculated based on strains measured during testing. Using girder strains recorded during load testing at the top and bottom of the girders at midspan, linear strain distributions were calculated through the depth for each girder. This strain distribution was then used to calculate actual neutral axis (NA) location for each girder. This linear strain distribution is shown schematically in Figure 10.




Figure 10: Typical linear strain distribution

The effective slab width – defined as the slab width that produces the NA location – was calculated. A completely non-composite girder has zero effective slab width, and a fully composite slab width is the full tributary slab width. In the case of the interior girders, the tributary slab width is the interior girder spacing. The percent composite action was then calculated as the effective slab width divided by the AASHTO-defined slab width for a fully composite girder, which is the width of slab tributary to the girder. This effective slab width is then used to calculate an effective section

modulus which is used for determining distribution factors described in 1.4.8, modified rating factors described in 1.4.9, and shear stresses at the slab-girder interface as described in 1.4.10.

1.4.8 Distribution Factors Determined from Live Load Testing

Based on the neutral axis as determined by measured strains and the corresponding effective slab width, the section modulus for each girder is calculated. The moment carried by each girder is calculated as per Equation 2.

$$M_i = ES_i\varepsilon_i \quad \text{Equation 2}$$

M_i = Moment carried by girder i
 E = Modulus of Elasticity of girder
 S_i = Section modulus of girder i
 ε_i = Strain measured in girder i

The distribution factor for each girder was then calculated by Equation 3.

$$DF_i = \frac{M_i}{\sum_{i=1}^5 M_i} \quad \text{Equation 3}$$

DF_i = Distribution factor for girder i
 M_i = Moment carried by girder i

1.4.9 Modified Rating Factor

In accordance with the AASHTO *Manual for Bridge Evaluation*, the ratio of computed strain ε_c (based on the measured effective section properties) to measured strain ε_T was then used to compute a rating factor modification factor as detailed below in Equation 4 to Equation 6. This analysis is based on the critical interior center girder.

$$RF_T = RF_c K \quad \text{Equation 4}$$

In Equation 4, RF_T is the modified rating factor taking into account test results, RF_c is the rating factor based on standard calculations which assumes non-composite action, and K is an adjustment factor which incorporates the test results. K is computed per Equation 5 below.

$$K = 1 + K_a K_b \quad \text{Equation 5}$$

K_a accounts for the difference between measured response based on load testing and expected response as shown below in Equation 6. K_b accounts for the magnitude of the applied test load and confidence in extrapolating results, and is defined in Table 8.8.2.3.1-1 in the AASHTO *Manual for Bridge Evaluation*. For all structures K_b was taken as 0.5, which reflects both the magnitude of the applied load and assumes results cannot be extrapolated to higher loads.

$$K_a = \frac{\varepsilon_c}{\varepsilon_T} - 1 \quad \text{Equation 6}$$

1.4.10 Shear Flow

Using the maximum measured shear loading per section 1.4.6, the measured section properties from 1.4.7, and the measured distribution factors per section 1.4.8, the shear flow achieved during live load testing was calculated according to Equation 7. This value is compared to the recommended maximum shear flow of 100 psi recommended by the AASHTO *Manual for Bridge Evaluation*.

$$\tau = \frac{DF \cdot V \cdot Q}{I \cdot b} \quad \text{Equation 7}$$

τ = shear flow

V = calculated shear applied to bridge

DF = distribution factor calculated from measured values

Q = First moment of area calculated from measured values

I = second moment of area calculated from measured values

b = shear area between slab and girder flange

2 Live Load Test Results

2.1 Steuben No. 3067

The Steuben bridge No. 3067 over Dyer Creek is shown in Figure 11. Testing was conducted on July 21, 2016 with two trucks and with four trucks producing 53% and 78% of an HL-93 loading with impact, respectively. The rating factors based on non-composite girder behavior are 0.80 for interior and 1.04 for exterior girders, making this the lowest capacity bridge tested. The measured strains were as expected the highest for any of the bridges and partial composite action was observed. The composite action was only 47% for the two truck loading and 57% for the four truck loading. Table 2 shows the maximum measured strains and inferred neutral axis locations for this bridge. These conditions led to the most modest rating factor increases for this set of bridges. However, the rating factor for HL-93 was still able to be increased to 1.09 for the interior girder and 1.13 for exterior girder bringing the rating factors above 1.0.

The live load distribution factors determined from the measured strains and those calculated per AASHTO are shown in in Table 3, and generally indicate that the AASHTO distribution factors are somewhat conservative. This is likely due in part to the presence of integral concrete curb and guardrail visible in Figure 6 which will tend to attract load to the exterior girders. Calculated shear flows and measured slip between the girder and slab for Steuben were 69.2 psi with 1.76 mils slip for the two-truck loading and 85.6 psi with 3.43 mils slip for the four-truck loading. These shear

flows were among the lowest and the slips were among the highest. This corresponds to the low degree of composite action observed in this bridge. These shear flows were below the 100 psi maximum recommended by AASHTO, and assuming a linear extrapolation gives 99.6 psi at 100% of HL-93 loading with impact. As shown in Table 2, strain measured at the ends of the girders indicates that there was rotational restraint leading to partial fixity and end moments. The strains at the girder ends for Steuben were lower as a percentage of measured midspan strain than those of other bridges in this study.



Figure 11: Steuben No. 3067 general condition

Table 2: Steuben No. 3067 Strain and Neutral Axis Data

| Steuben | | Two Trucks | | | | Four Trucks | | | |
|---------|----------|---------------|-------------------|---------------|---------------|---------------|-------------------|---------------|---------------|
| Girder | Location | Midspan | | Pinned End | Opposite End | Midspan | | Pinned End | Opposite End |
| | | $\mu\epsilon$ | Neutral Axis (in) | $\mu\epsilon$ | $\mu\epsilon$ | $\mu\epsilon$ | Neutral Axis (in) | $\mu\epsilon$ | $\mu\epsilon$ |
| 1 | Top | 3.8 | 30.1 | -1.36 | - | 5.7 | 30.0 | -2.9 | - |
| | Bottom | 111.1 | | -11.8 | -25.8 | 182.7 | | -16.4 | -19.7 |
| 2 | Top | -20.7 | 25.7 | - | - | -28.0 | 26.0 | - | - |
| | Bottom | 157.5 | | -25.2 | -33.1 | 238.4 | | -48.0 | -41.3 |
| 3 | Top | -86.4 | 19.7 | 46.7 | - | -109.8 | 20.7 | 65.5 | - |
| | Bottom | 180.4 | | -30.6 | -33.1 | 270.3 | | -47.9 | -48.0 |
| 4 | Top | -10.5 | 27.5 | - | - | -18.3 | 27.2 | - | - |
| | Bottom | 181.6 | | - | - | 263.4 | | - | - |
| 5 | Top | -0.9 | 28.9 | - | - | -1.2 | 28.9 | - | - |
| | Bottom | 145.8 | | - | - | 205.5 | | - | - |

Table 3: Steuben No. 3067 distribution factors

| Steuben | | Two Truck Loading | | Four Truck Loading | |
|---------|-----------|-------------------|--------------|--------------------|--------------|
| Girder | AASHTO DF | Measured DF | % Difference | Measured DF | % Difference |
| 1 | 0.416 | 0.362 | -13% | 0.395 | -5% |
| 2 | 0.468 | 0.366 | -22% | 0.368 | -21% |
| 3 | 0.468 | 0.371 | -21% | 0.381 | -19% |
| 4 | 0.468 | 0.422 | -10% | 0.407 | -13% |
| 5 | 0.416 | 0.479 | 15% | 0.449 | 8% |

2.2 Waltham No. 3238

The bridge in Waltham, No. 3238 over Union River, is shown in Figure 12. Testing was conducted on July 14, 2016 with two truck and four truck load cases producing 55% and 87% of an HL-93 load with impact, respectively. This is the highest percentage of HL-93 load applied among all the bridges. However, with a non-composite rating factor of 1.17 for the interior girder and 1.61 for the exterior girder, Waltham also had the highest capacity. Given that full composite action was observed for this bridge, the strains were generally lower than those observed for the other four structures as shown in Table 4. The measured composite action was more than 100% of the theoretical value for the two trucks and four trucks, giving this bridge one of the largest rating factor increases in this set to 1.68 for interior girders and 2.82 for exterior girders. The distribution factors shown in Table 5 indicate relatively stiff interior girders and less stiff exterior girders. This is surprising given the condition of the relatively new guardrail, and may be due to more restraint

at the interior girder ends than the exterior ends producing lower than expected mid span maximum strains.

Shear flows and corresponding slip between the girder and slab for Waltham were calculated/measured to be 57.1 psi with 0.83 mils of slip for the two-truck loading and 109.3 psi with 1.20 mils slip for the four-truck loading. This shear flow and slip correspond to the high degree of composite action observed in this bridge. The shear flow for the four trucks exceeded the 100 psi maximum recommended by AASHTO, and assuming a linear trend the shear flow would reach 131.5 psi at 100% HL-93 loading with impact. There was partial fixity observed at the ends of the girders as measured by the negative strains at the bottom of these girders and given in Table 4. The fixity for Waltham was greater than that of Steuben as a proportion of midspan strain, but lower than that observed in Windham and Buckfield.



Figure 12: Waltham No. 3238 general condition

Table 4: Waltham No. 3238 Strain and Neutral Axis Data

| Waltham | | Two Trucks | | | | Four Trucks | | | |
|---------|----------|---------------|-------------------|---------------|---------------|---------------|-------------------|---------------|---------------|
| Girder | Location | Midspan | | Pinned End | Opposite End | Midspan | | Pinned End | Opposite End |
| | | $\mu\epsilon$ | Neutral Axis (in) | $\mu\epsilon$ | $\mu\epsilon$ | $\mu\epsilon$ | Neutral Axis (in) | $\mu\epsilon$ | $\mu\epsilon$ |
| 1 | Top | 4.1 | 37.6 | - | - | 5.2 | 37.2 | - | - |
| | Bottom | 58.2 | | - | - | 84.9 | | - | - |
| 2 | Top | 11.5 | 41.1 | - | - | 23.2 | 43.2 | - | - |
| | Bottom | 76.8 | | - | - | 121.3 | | - | - |
| 3 | Top | 1.0 | 35.3 | 11.9 | - | 5.5 | 36.3 | 17.5 | - |
| | Bottom | 91.4 | | -41.7 | -41.8 | 140.9 | | -66.5 | -68.6 |
| 4 | Top | 18.5 | 46.6 | - | - | 17.1 | 41.1 | - | - |
| | Bottom | 74.1 | | -6.8 | -22.7 | 114.1 | | -7.7 | -31.8 |
| 5 | Top | 15.7 | 50.5 | -2.4 | - | 17.7 | 45.1 | -2.1 | - |
| | Bottom | 50.8 | | -33.8 | -24.4 | 78.5 | | -66.9 | -38.3 |

Table 5: Waltham No. 3238 distribution factors

| Waltham | | Two Trucks | | Four Trucks | |
|---------|-----------|-------------|--------------|-------------|--------------|
| Girder | AASHTO DF | Measured DF | % Difference | Measured DF | % Difference |
| 1 | 0.38 | 0.319 | -16% | 0.304 | -20% |
| 2 | 0.493 | 0.444 | -10% | 0.457 | -7% |
| 3 | 0.493 | 0.529 | 7% | 0.530 | 8% |
| 4 | 0.493 | 0.429 | -13% | 0.429 | -13% |
| 5 | 0.38 | 0.279 | -27% | 0.281 | -26% |

2.3 *Pembroke No. 3884*

The bridge in Pembroke, No. 3884 over Pennamaquan River, is shown in Figure 13. Testing on July 19, 2016 with two trucks and four trucks produced 49% and 81% of HL-93 loading with impact, respectively. The non-composite rating factors were 0.86 for interior girders and 1.09 for exterior girders. Observed strains are shown in Table 6. Full composite action was observed, with more than 100% of theoretical composite action achieved for both two and four truck loadings. The rating factors were increased to 1.33 for interior girders and 2.52 for exterior girders. The distribution factors shown in Table 7 show stiffer interior girders than exterior, but in all cases the distribution factors were less than those computed per AASHTO.

Shear flows and corresponding slip between the girder and slab for Pembroke were calculated/measured to be 86.7 psi with 0.74 mils slip for the two-truck loading and 107.4 psi with 1.78 mils slip for the four-truck loading. This shear flow and slip corresponds to the high degree of composite action observed in this bridge. The shear flow for the four trucks exceeded the 100 psi maximum recommended by AASHTO, and assuming a linear trend would reach 120.1 psi at

100% HL-93 loading with impact. There was partial fixity observed in Pembroke as shown by the negative strains at the bottom of the girders given in Table 6. These negative strains were the largest in magnitude observed at the girder ends.



Figure 13: Pembroke No. 3884 General condition

Table 6: Pembroke No. 3884 Strain and Neutral Axis Data

| Pembroke | | Two Trucks | | | | Four Trucks | | | |
|----------|----------|---------------|-------------------|---------------|---------------|---------------|-------------------|---------------|---------------|
| Girder | Location | Midspan | | Pinned End | Opposite End | Midspan | | Pinned End | Opposite End |
| | | $\mu\epsilon$ | Neutral Axis (in) | $\mu\epsilon$ | $\mu\epsilon$ | $\mu\epsilon$ | Neutral Axis (in) | $\mu\epsilon$ | $\mu\epsilon$ |
| 1 | Top | -0.4 | 26.1 | 9.6 | - | -3.9 | 25.2 | 7.1 | - |
| | Bottom | 63.6 | | -27.4 | -20.7 | 99.5 | | -43.1 | -29.9 |
| 2 | Top | -24.0 | 22.0 | - | - | -24.4 | 23.2 | - | - |
| | Bottom | 125.5 | | -26.4 | -4.8 | 190.1 | | -55.9 | -19.8 |
| 3 | Top | -16.0 | 23.6 | 12.8 | - | -20.8 | 24.0 | 9.4 | - |
| | Bottom | 144.5 | | -55.8 | -82.3 | 220.4 | | -88.1 | -147.3 |
| 4 | Top | -41.1 | 18.7 | - | - | -53.4 | 19.7 | - | - |
| | Bottom | 102.6 | | - | - | 160.9 | | - | - |
| 5 | Top | 10.3 | 29.9 | - | - | 11.0 | 28.9 | - | - |
| | Bottom | 82.3 | | - | - | 118.1 | | - | - |

Table 7: Pembroke No. 3884 distribution factors

| Pembroke | | Two Trucks | | Four Trucks | |
|-----------------|------------------|--------------------|---------------------|--------------------|---------------------|
| Girder | AASHTO DF | Measured DF | % Difference | Measured DF | % Difference |
| 1 | 0.449 | 0.291 | -35% | 0.297 | -34% |
| 2 | 0.544 | 0.453 | -17% | 0.459 | -16% |
| 3 | 0.544 | 0.536 | -1% | 0.532 | -2% |
| 4 | 0.544 | 0.343 | -37% | 0.359 | -34% |
| 5 | 0.449 | 0.377 | -16% | 0.352 | -22% |

2.4 Windham No. 5298

The bridge in Windham, No. 5298 over the Pleasant River, is shown in Figure 14. On August 23, 2016 two truck and four truck loadings were applied producing 53% and 77% of an HL-93 load with impact, respectively. This bridge had low non-composite rating factors for both interior (at 0.81) and exterior (at 0.99) girders. Due to the full composite action observed during testing, with both two truck and four truck loading indicating more than 100% of theoretical composite action, the strains as shown in Table 8 were low and the rating factors can be increased to 1.26 and 1.29 for interior and exterior girders, respectively. The comparison between AASHTO-computed and measured distribution factors given in Table 9 indicate relatively stiff exterior girders.

Shear flows and corresponding slip between the girder and slab for Windham were calculated/measured to be 75.5 psi with 2.20 mils slip for the two-truck loading and 118.0 psi with 4.11 mils slip for the four-truck loading. The high shear flow coupled with high slip is an outlier for the group of bridges tested, especially given the high degree of composite action observed in this bridge. However, the slip of 4.11 mils is still quite small. The shear flow for the four trucks was 20% greater than the 100 psi capacity recommended by AASHTO, and is the highest observed in this study. Assuming a linear trend, the shear flow would reach 159.4 psi at 100% HL-93 loading with impact. Partial rotational restraint was observed at the girder ends as shown by the negative strains in the bottom of the girder ends and noted in Table 8. As with the other bridges in this study the fixity was consistent across the girders.



Figure 14: Windham No. 5298 general condition

Table 8: Windham No. 5298 Strain and Neutral Axis Data

| Windham | | Two Trucks | | | | Four Trucks | | | |
|---------|----------|---------------|-------------------|---------------|---------------|---------------|-------------------|---------------|---------------|
| Girder | Location | Midspan | | Pinned End | Opposite End | Midspan | | Pinned End | Opposite End |
| | | $\mu\epsilon$ | Neutral Axis (in) | $\mu\epsilon$ | $\mu\epsilon$ | $\mu\epsilon$ | Neutral Axis (in) | $\mu\epsilon$ | $\mu\epsilon$ |
| 1 | Top | -0.3 | 29.0 | -4.1 | - | -6.5 | 27.6 | -7.3 | - |
| | Bottom | 80.1 | | -12.8 | -21.2 | 126.0 | | -26.4 | -23.9 |
| 2 | Top | -46.6 | 19.1 | - | - | -76.7 | 17.9 | - | - |
| | Bottom | 89.6 | | -28.2 | -15.9 | 122.2 | | -55.6 | -5.9 |
| 3 | Top | 7.2 | 28.1 | 31.4 | - | 5.8 | 28.1 | 44.3 | - |
| | Bottom | 108.1 | | -48.5 | -64.1 | 154.9 | | -78.4 | -88.1 |
| 4 | Top | -29.7 | 17.9 | - | - | -46.2 | 16.8 | - | - |
| | Bottom | 47.4 | | - | - | 62.9 | | - | - |
| 5 | Top | 15.1 | 33.6 | - | - | 17.3 | 33.6 | - | - |
| | Bottom | 89.2 | | - | - | 123.1 | | - | - |

Table 9: Windham No. 5298 distribution factors

| Windham | | Two Trucks | | Four Trucks | |
|----------------|------------------|--------------------|---------------------|--------------------|---------------------|
| Girder | AASHTO DF | Measured DF | % Difference | Measured DF | % Difference |
| 1 | 0.431 | 0.479 | 11% | 0.518 | 20% |
| 2 | 0.523 | 0.309 | -41% | 0.285 | -46% |
| 3 | 0.523 | 0.470 | -10% | 0.480 | -8% |
| 4 | 0.523 | 0.155 | -70% | 0.139 | -74% |
| 5 | 0.431 | 0.588 | 36% | 0.579 | 34% |

2.5 Buckfield No. 5452

The bridge in Buckfield, No. 5452 over the West Branch of the Nezinscot River is shown in Figure 15. On July 12, 2016 four trucks were used to produce 74% of an HL-93 loading with impact for this span, the lowest of the four truck configurations observed in this study. Despite a relatively low degree of partial composite action (35.7%), this bridge saw the highest increase in rating factors from 0.96 to 1.61 for interior and from 1.18 to 1.76 for exterior girders. Measured strains are given in Table 10, and distribution factors in Table 11.

Shear flows and corresponding slip between the girder and slab for Buckfield were calculated/measured to be 69.0 psi with 5.05 mils slip for the four-truck loading. This shear flow is the smallest observed in this study, for four trucks, and slip is the highest observed in this study. This is consistent with Buckfield exhibiting the lowest degree of partial composite action of all bridges. The partial fixity at girder ends observed in Buckfield is indicated by the strains given in Table 10.



Figure 15: Buckfield No. 5452 general condition

Table 10: Buckfield No. 5452 Strain and Neutral Axis

| Buckfield | | Four Trucks | | |
|-----------|----------|---------------|-------------------|---------------|
| Girder | Location | Midspan | | Pinned End |
| | | $\mu\epsilon$ | Neutral Axis (in) | $\mu\epsilon$ |
| 1 | Top | 18.2 | 30.0 | - |
| | Bottom | 144.9 | | - |
| 2 | Top | 47.8 | 39.1 | - |
| | Bottom | 145.7 | | - |
| 3 | Top | -71.0 | 18.4 | - |
| | Bottom | 166.8 | | -106.6 |
| 4 | Top | -99.5 | 15.1 | - |
| | Bottom | 134.5 | | -66.4 |
| 5 | Top | 12.1 | 28.1 | -7.3 |
| | Bottom | 186.5 | | -94.3 |

Table 11: Buckfield No. 5452 distribution factors

| Buckfield | | Four Trucks | |
|------------------|------------------|--------------------|---------------------|
| Girder | AASHTO DF | Measured DF | % Difference |
| 1 | 0.44 | 0.366 | -17% |
| 2 | 0.53 | 0.493 | -7% |
| 3 | 0.53 | 0.421 | -20% |
| 4 | 0.53 | 0.301 | -43% |
| 5 | 0.44 | 0.418 | -5% |

3 Summary of Live Load Test Data Conclusions

Analysis of the bridges tested is described in detail in Section 2. In general, calculations were based on mechanics of materials principles and AASHTO code requirements including the *Manual for Bridge Evaluation*.

Overall, a high percentage of HL-93 loading with impact was applied to the structures. For all structures, the four trucks were successful in loading the bridges to desired percentages to justify rating factor increases. While three of the five bridges showed full composite action, with slightly more than 100% of theoretical values of effective slab width computed based on measured response, significantly less composite action was observed for Steuben (56.6%) and Buckfield (35.7%).

Live load distribution factors inferred from the test data showed reasonably good agreement with AASHTO-recommended values, although the AASHTO values are conservative for four of the five bridges. The maximum percent differences are observed in Steuben and Buckfield, the two bridges that showed very little composite action compared to the other bridges in this study.

Shear stresses and slips between the girder and slab were determined for all bridges. Slip was measured directly by installing LVDTs connected to the girder and pushing against plates adhered to the slab. The shear flow was computed based on applied load and field-observed girder properties. Detailed calculations are given in Appendix A.2.5 for Steuben, A.3.5 for Waltham, A.4.5 for Pembroke, A.5.5 for Windham, and A.6.5 for Buckfield. In general, the two bridges with the least composite action, Steuben and Buckfield, not surprisingly show the largest degree of slip as well as the lowest calculated shear stress at the girder flange-slab interface. The three bridges showing full composite action had relatively little slip, except for one girder at Windham that appears to be an outlier.

One important observation was that measured strains near the girder ends for all bridges indicated some rotational restraint at each abutment. This rotational restraint was likely responsible for reductions in girder flexural strain at mid-span compared to a simple-span condition, and therefore contributed to the rating factor increases. However, the presence of this rotational restraint at higher loads and over the full range of seasonal temperature variations is not guaranteed.

The test results and analyses presented here justify significant increases in the rating factors for all the bridges according to the *AASHTO Manual for Bridge Evaluation*. Even those bridges showing partial composite action, Steuben and Buckfield, had increases in the rating factor of 36% and 23% for interior girders. The average increase in rating factors for the critical interior girders of all bridges was 43%, with minimum and maximum increases of 23% and 56%. All rating factor increases have been calculated based on the assumption that the observed results cannot be confidently extrapolated to loads 30% beyond that produced by an HL-93 load with impact, due in part to uncertainty regarding the presence of support rotational restraint and at higher loads.

4 References

1. AASHTO (2010). "The Manual for Bridge Evaluation Second Edition," American Association of State Highway and Transportation Officials Washington DC. (with 2015 Interim Revisions).
2. AASHTO (2012). "AASHTO LRFD Bridge Design Specifications Customary U.S. Units", American Association of State Highway and Transportation Officials Washington DC. doi:978-1-56051-523-4.

A.1 Experimental Configuration and Data Collected

For each of the five bridges tested, a collection of data files is provided which contains input data, experimental configuration data, and data collected during tests. The files pertaining to each bridge are tabulated in the following appendices.

A.1.1 Input Data

Input data for each bridge includes bridge geometries, material properties, and sensor layouts. General geometry (i.e. span length, girder spacing, etc.) and material properties are tabulated in a Comma Separated Variable (.csv) file, each value listed with a description and unit. Section properties for interior and exterior girders are also listed in separate csv files, labeled and in units of inches to the appropriate power.

A .csv is also provided which gives a list of sensors in the order of collection, and another giving the layout of those sensors on each bridge. The sensor list .csv provides sensors in the order that they are used by the data acquisition system, and consequently in resulting test data. The sensor layout gives relative positions of sensors as they appeared for each bridge. Each girder is represented by three rows representing its top, middle and bottom respectively. Each collection of rows is placed in its relative position as it appears on the bridge. From left to right, columns represent the non-pinned end, mid-span, pinned end, and LVDT position on the bridge respectively. By this way, the position of each sensor can be determined. For example, a sensor in

the second column of the second row would represent a sensor placed on the web of the first girder at mid-span.

A.1.2 Experimental Configuration

Experimental configuration data includes data on the loading trucks, as well as the positions of trucks at the beginning of tests. Each test includes a MATLAB variable file (a .mat file) containing information on the trucks used to test it. The truck .mat file contains structured arrays for each truck, containing its plate number, truck number in relation to each test, individual wheel weights (in pounds), lengths (center to center of wheels; side, front and back in inches), wheel bearing surface widths (front to back in inches), and wheel bearing lengths (front to back in inches). The start positions are packaged together in a single .mat file containing a structured array for each bridge. Each of those arrays contain cell arrays which show relative placements for each truck at the beginning of a test, the pinned-end of the bridge always being on the right.

A.1.3 Collected Data

Collected data includes rectified strain data (in microstrain) at critical points during each test, as well as the time index of their occurrence. For each test configuration, a Microsoft Excel file is provided which contains strain data at critical points during the test. This data has been rectified to correct for the sensors' tendency to drift its zero-point during a test, as well as to convert LVDT data to microstrain. A .csv file accompanies each Excel file, providing a description of the critical point recorded and its time of occurrence (in 1/10 seconds from the beginning of the test).

A.2 Steuben No. 3067

A.2.1 Input Data, Experimental Configuration, and Experimental Data Collected

Table 12: Steuben No. 3067 Bridge Input Data, Experimental Configuration, and Experimental Data Collected

| File Contents | File Name | File Type |
|--------------------------------------|--------------------------------|------------------|
| Bridge Geometry and Materials | Br3067_Geom.csv | CSV Format |
| Exterior Section Data | Br3067_Ext.csv | CSV Format |
| Interior Section Data | Br3067_Int.csv | CSV Format |
| Sensors | Br3067_Sensors.csv | CSV Format |
| Sensor Layout | Br3067_SensorLayout.csv | CSV Format |
| Truck Weight and Dimensions | Br3067_SensorLayout.mat | MATLAB Data File |
| Truck Starting Position | TestStart.m > Br3067_TestStart | MATLAB Data File |
| Truck Position Measurements | Br3067_Tk_Positions.mat | MATLAB Data File |
| Sensor Data | Br3067_1Tks_1Lns_1.xlsx | Microsoft Excel |
| | Br3067_2Tks_1Lns_1.xlsx | Microsoft Excel |
| | Br3067_2Tks_2Lns_1.xlsx | Microsoft Excel |
| | Br3067_4Tks_2Lns_1.xlsx | Microsoft Excel |
| | Br3067_4Tks_2Lns_2.xlsx | Microsoft Excel |
| Data Time Indices | Br3067_1Tks_1Lns_1_Time.csv | CSV Format |
| | Br3067_2Tks_1Lns_1_Time.csv | CSV Format |
| | Br3067_2Tks_2Lns_1_Time.csv | CSV Format |
| | Br3067_4Tks_2Lns_1_Time.csv | CSV Format |
| | Br3067_4Tks_2Lns_2_Time.csv | CSV Format |

A.2.2 Instrumentation




Figure 16: Steuben No. 3067 sensor layout

A.2.3 Loading




Figure 17: Steuben No. 3067 Truck T01-137 loading




Figure 18: Steuben No. 3067 Truck T01-157 loading




Figure 19: Steuben No. 3067 Truck T01-166 loading




Figure 20: Steuben No. 3067 Truck T01-198 loading

A.2.4 Representative Data Plots




Figure 21: Steuben No. 3067- 2 trucks 2 lanes test 1 strain




Figure 22: Steuben No. 3067- 2 trucks 2 lanes test 1 shear slip




Figure 23: Steuben No. 3067- 4 trucks 2 lanes test 1 strains




Figure 24: Steuben No. 3067- 4 trucks 2 lanes test 1 shear slip




Figure 25: Steuben No. 3067- 4 trucks 2 lanes test 2 strains




Figure 26: Steuben No. 3067- 4 trucks 2 lanes test 2 shear slip

A.2.5 Rating Factor Calculations

Figure 27: Steuben No. 3067 Calculations

Bridge #3067 STEUBENME
Route DYER BAY Rd
Crossing DYER CR

Prepared By: Mahmood J. Abraheemi
Checked By: SMT
Date : 201611-03

| Year of Construction | Compressive Strength, f'_c , ksi |
|----------------------|------------------------------------|
| Prior to 1959 | 2.5 |
| 1959 and Later | 3.0 |

$f'_c := 2.5 \text{ ksi}$

| Year of Construction | Minimum Yield Point or Minimum Yield Strength, F_y , ksi | Minimum Tensile Strength, F_u , ksi |
|----------------------|--|---------------------------------------|
| Prior to 1905 | 26 | 52 |
| 1905 to 1936 | 30 | 60 |
| 1936 to 1963 | 33 | 66 |
| After 1963 | 36 | 66 |

$f_y := 33 \text{ ksi}$

$\gamma_c := 150 \text{ pcf}$ $\gamma_s := 490 \text{ pcf}$

$\gamma_{c_mod} := 145 \text{ pcf}$ $E_s := 29000 \text{ ksi}$

LRFD Design
Eq. 54.2.4.1

$$E_c := 33000 \cdot \gamma_{c_mod}^{1.5} \cdot \sqrt{f'_c}$$

$E_c := 2875.9 \text{ ksi}$

Bridge Length $L := 50 \text{ ft}$

Spacing between Girders $S := 5.33 \text{ ft}$


Deck thickness $t_s := 6.75 \text{ in}$

Wearing surface thickness $t_{w.s.} := 4.5 \text{ in}$ $\gamma_{w.s.} := 140 \text{ pcf}$

Bridge #3067 STEUBENME
 Route DYER BAY Road
 Crossing DYER CREEK

Prepared By: Mahmood J. Abraheemi
 Checked By: SMT
 Date : 201611-03

Trucks Weight & Dimensions



Bridge #3067 STEUBENME
Route DYER BAY Road
Crossing DYER CRIDGE

Prepared By: Mahmood J. Abraheemi
Checked By: SMT
Date : 201611-03

Loads on the Interior Girder

DeadLoad:

$M_{DC} := 328 \text{ ft} \cdot \text{kip}$ VHB report

$M_{DW} := 87 \text{ ft} \cdot \text{kip}$ VHB report

$d := 29.83 \text{ in}$ $b_f := 10.48 \text{ in}$

Live Load :

We use the average truck weight and dimensions in this calculation


| | Trucks Weight | | | |
|------------------|---------------|---------|---------|---------|
| | T01-198 | T01-137 | T01-166 | T01-157 |
| Front wheel | 15100 | 13700 | 13700 | 15850 |
| front rear wheel | 20200 | 19800 | 20350 | 21400 |
| Last Wheel | 20400 | 20100 | 20450 | 22350 |

Bridge #3067 STEUBENME
Route DYER BAY Road
Crossing DYER CREEK

Prepared By: Mahmood J. Abraheemi
Checked By: SMT
Date : 201611-03

Trucks at Maximum Moment location:

d1 distance between front wheel and the support



$$R_b(d1) := \frac{(p1 \cdot d1) + (p2 \cdot (d1 + d3)) + (p3 \cdot (d1 + d2 + d3))}{L}$$

$$M(d1) := R_b(d1) \cdot (L - (d1 + d3)) - p3 \cdot (d2)$$

$$R_b(108 \text{ in}) = 25.11 \text{ kip}$$

$$M(108 \text{ in}) = 545.808 \text{ ft} \cdot \text{kip}$$


$$M_{\text{maxmomenttwo trucks}} := 545.81 \cdot \text{ft} \cdot \text{kip}$$

Bridge #3067 STEUBENME
Route DYER BAY Road
Crossing DYER CR

Prepared By: Mahmood J. Abraheemi
Checked By: SMT
Date : 201611-03

Trucks at Maximum Moment location:

d1 distance between front wheel and the support ; d4 distance between trucks



At Maximum Moment:

$$R_b(d1, d4) := \frac{p1 \cdot d1 + p2 \cdot (d1 + d3) + p3 \cdot (d1 + d3 + d2) + p3 \cdot (d1 + d3 + d2 + d4) + p2 \cdot (d1 + d3 + 2 \cdot d2 + d4)}{L}$$

$$M(d1, d4) := (R_b(d1, d4) \cdot (L - (d1 + d3 + d2))) - (p2 \cdot (d2 + d4)) - (p3 \cdot d4)$$

$$R_b(66 \text{ in}, 90 \text{ in}) = 49.81 \text{ kip}$$

$$M(66 \text{ in}, 90 \text{ in}) = 809.345 \text{ ft} \cdot \text{kip}$$

$$M_{\text{maxmomentfourtrucks}} := 809.35 \cdot \text{ft} \cdot \text{kip}$$

Bridge #3067 STEUBENME
Route DYER BAY Road
Crossing DYER CRIDGE

Prepared By: Mahmood J. Abraheemi
Checked By: SMT
Date : 201611-03

Section Properties and Distribution Factors

| Interior Girder Section Properties | | | | | |
|------------------------------------|-------|-----------|---------------|--------------|------|
| component | width | thickness | modular ratio | transf. area | y |
| Slab | 64 | 6.75 | 10.00 | 43.2 | 32.6 |

Moment Distribution factors (Interior Girders)

VHB report

$$DF_{onelane} = 0.419$$

$$DF_{twolanes} = 0.468$$

Calculated Distribution factors based on actual measurements

$$DF_{onelane} := 0.398$$

$$DF_{twolanes} := 0.516$$

$$DF_{shear} := 0.621$$

Section Properties: Fully composite

$$y' := 25.1 \text{ in} \quad I := 10218 \cdot \text{in}^4 \quad S_{bot} := 406.9 \cdot \text{in}^3 \quad Q_{slab} := 305.0 \cdot \text{in}^3$$

Bridge #3067 STEUBENME
Route DYER BAY Road
Crossing DYER CR

Prepared By: Mahmood J. Abraheemi
Checked By: SMT
Date : 201611-03

Maximum Live Load Moment calculation in each load case for the interior girder

Two trucks in two lanes

$$Mt_{0.5dtwotrucks} := DF_{twolanes} \cdot M_{0.5dtwotrucks} = 72 \text{ ft} \cdot \text{kip}$$

$$Mt_{1.0dtwotrucks} := DF_{twolanes} \cdot M_{1.0dtwotrucks} = 93 \text{ ft} \cdot \text{kip}$$

$$Mt_{1.5dtwotrucks} := DF_{twolanes} \cdot M_{1.5dtwotrucks} = 113 \text{ ft} \cdot \text{kip}$$

$$Mt_{2.0dtwotrucks} := DF_{twolanes} \cdot M_{2.0dtwotrucks} = 131 \text{ ft} \cdot \text{kip}$$

$$Mt_{maxmomenttwotrucks} := DF_{twolanes} \cdot M_{maxmomenttwotrucks} = 281 \text{ ft} \cdot \text{kip}$$

Four trucks in two lanes

$$Mt_{2.0dfourtrucks} := DF_{twolanes} \cdot M_{2.0dfourtrucks} = 360 \text{ ft} \cdot \text{kip}$$

$$Mt_{maxmomentfourtrucks} := DF_{twolanes} \cdot M_{maxmomentfourtrucks} = 418 \text{ ft} \cdot \text{kip}$$

Actual section Response

| Four Trucks | | | | | |
|-------------|----------|-------------|------------|-------------|--------------|
| Position | LV4521 | B3076 | B3075 | B3811 | LV4523 |
| 4T @ 2.0d | 0.003426 | -34.1729012 | 4.25192093 | 61.05499361 | -6.56099E-06 |
| Max mom | 0.002915 | -47.9403656 | -0.545197 | 65.50389684 | -2.12E-05 |
| Two Trucks | | | | | |

Bridge #3067 STEUBENME
Route DYER BAY Road
Crossing DYER CR

Prepared By: Mahmood J. Abraheemi
Checked By: SMT
Date : 201611-03

Four Trucks

Look at the critical girder the interior girder

$$y'_{2.0d} := 21.9 \text{ in} \quad S_{2.0d} := 381.8 \text{ in}^3 \quad Q_{2.0d} := 209.3 \text{ in}^3 \quad \text{Partial composite}$$

$$y'_{maxmoment} := 20.7 \text{ in} \quad S_{maxmoment} := 370.7 \text{ in}^3 \quad Q_{maxmoment} := 174.3 \text{ in}^3 \quad \text{Partial composite}$$

$$M_{fourtrucks} := \begin{bmatrix} Mt_{2.0dfourtrucks} \\ Mt_{maxmomentfourtrucks} \end{bmatrix}; \quad y_{fourtrucks} := \begin{bmatrix} y'_{2.0d} \\ y'_{maxmoment} \end{bmatrix}; \quad S_{fourtrucks} := \begin{bmatrix} S_{2.0d} \\ S_{maxmoment} \end{bmatrix}$$

Strain based on actual response

$$\epsilon_{computed} := \begin{bmatrix} \frac{Mt_{2.0dfourtrucks}}{S_{2.0d} \cdot 29000 \text{ ksi}} \\ \frac{Mt_{maxmomentfourtrucks}}{S_{maxmoment} \cdot 29000 \text{ ksi}} \end{bmatrix} \cdot 10^6 = \begin{bmatrix} 389.79 \\ 466.17 \end{bmatrix}$$

$$Kb := 0.5$$

$$Ka := \frac{466.17}{270.32} - 1$$

$$K := 1 + Kb \cdot Ka = 1.36$$

Bridge #3067 STEUBENME
Route DYER BAY Road
Crossing DYER CR

Prepared By: Mahmood J. Abraheemi
Checked By: SMT
Date : 201611-03

Two Trucks

Look at the critical girder the interior girder

| | | |
|--|--|-------------------|
| $y'_{0.5d} := 30.8 \text{ in}$ | $S_{0.5d} := 406.9 \text{ in}^3$ | Fully composite |
| $y'_{1.0d} := 29.0 \text{ in}$ | $S_{1.0d} := 406.9 \text{ in}^3$ | Fully composite |
| $y'_{1.5d} := 27.6 \text{ in}$ | $S_{1.5d} := 406.9 \text{ in}^3$ | Fully composite |
| $y'_{2.0d} := 28.3 \text{ in}$ | $S_{2.0d} := 406.9 \text{ in}^3$ | Fully composite |
| $y'_{\text{maxmoment}} := 19.7 \text{ in}$ | $S_{\text{maxmoment}} := 360.6 \text{ in}^3$ | Partial composite |

$$M_{\text{two trucks}} := \begin{bmatrix} Mt_{0.5d \text{ two trucks}} \\ Mt_{1.0d \text{ two trucks}} \\ Mt_{1.5d \text{ two trucks}} \\ Mt_{2.0d \text{ two trucks}} \\ Mt_{\text{maxmoment two trucks}} \end{bmatrix} \quad y_{\text{two trucks}} := \begin{bmatrix} y'_{0.5d} \\ y'_{1.0d} \\ y'_{1.5d} \\ y'_{2.0d} \\ y'_{\text{maxmoment}} \end{bmatrix} \quad S_{\text{two trucks}1} := \begin{bmatrix} S_{0.5d} \\ S_{1.0d} \\ S_{1.5d} \\ S_{2.0d} \\ S_{\text{maxmoment}} \end{bmatrix}$$

Strain based on actual response

$$\epsilon_{\text{computed}} := \begin{bmatrix} \frac{Mt_{0.5d \text{ two trucks}}}{S_{0.5d} \cdot 29000 \text{ ksi}} \\ \frac{Mt_{1.0d \text{ two trucks}}}{S_{1.0d} \cdot 29000 \text{ ksi}} \\ \frac{Mt_{1.5d \text{ two trucks}}}{S_{1.5d} \cdot 29000 \text{ ksi}} \\ \frac{Mt_{2.0d \text{ two trucks}}}{S_{2.0d} \cdot 29000 \text{ ksi}} \\ \frac{Mt_{\text{maxmoment two trucks}}}{S_{\text{maxmoment}} \cdot 29000 \text{ ksi}} \end{bmatrix} \cdot 10^6 = \begin{bmatrix} 73.28 \\ 94.66 \\ 114.66 \\ 133.29 \\ 323.18 \end{bmatrix}$$

$Kb := 0.5$

$Ka := \frac{322.6}{180.41} - 1 = 0.79$

$K := 1 + Kb \cdot Ka = 1.39$

Bridge #3067 STEUBENME
Route DYER BAY Road
Crossing DYER CR

Prepared By: Mahmood J. Abraheemi
Checked By: SMT
Date : 201611-03

Shear Flow Calculation

Four Trucks maximum moment

maximum shearforce $V := 49.81 \text{ kip}$ $Q_{2.0d} = 209.3 \text{ in}^3$ $I_{2.0d} := 8361 \text{ in}^4$

$$\tau := \frac{V \cdot DF_{shear} \cdot Q_{2.0d}}{I_{2.0d} \cdot b_f} = 73.89 \text{ psi} \quad \text{Actual shear flow}$$

$$\tau := \frac{V \cdot DF_{shear} \cdot Q_{slab}}{I \cdot b_f} = 88.1 \text{ psi} \quad \text{shear flow with fully composite}$$

Four Trucks maximum shear

maximum shearforce $V := 63.631 \text{ kip}$ $Q_{maxmoment} = 174.3 \text{ in}^3$ $I_{maxmoment} := 7679 \text{ in}^4$

$$\tau := \frac{V \cdot DF_{shear} \cdot Q_{maxmoment}}{I_{maxmoment} \cdot b_f} = 85.584 \text{ psi} \quad \text{Actual shear flow}$$

$$\tau := \frac{V \cdot DF_{shear} \cdot Q_{slab}}{I \cdot b_f} = 112.55 \text{ psi} \quad \text{shear flow with fully composite}$$

Two Trucks maximum shear

maximum shearforce $V_{shear2t} = 39.11 \text{ kip}$

$$\tau := \frac{V_{shear2t} \cdot DF_{shear} \cdot Q_{slab}}{I \cdot b_f} = 69.17 \text{ psi} \quad \text{fully composite}$$

Bridge #3067 STEUBENME
Route DYER BAY Road
Crossing DYER CREEK

Prepared By: Mahmood J. Abraheemi
Checked By: SMT
Date : 201611-03

Calculation of Actual Distribution Factors

| | | | | | | |
|-------------|--------|----------|---------|---------|--------|----------|
| Four Trucks | | | | | | |
| Position | LV4521 | B3076 | B3075 | B3811 | LV4523 | B3066 |
| Max moment | 0.0029 | -47.9404 | -0.5452 | 65.5039 | 0.0000 | -16.4265 |
| Two Trucks | | | | | | |
| Position | LV4521 | B3076 | B3075 | B3811 | LV4523 | B3066 |

Four Trucks max moment DF analysis

Total_moment := 1273 ft·kip

Girder Actual_DF AASHTO_DF

| <i>Girder</i> | <i>Actual_DF</i> | <i>AASHTO_DF</i> |
|---------------|------------------|------------------|
| "girder1" | 0.395 | 0.416 |
| "girder2" | 0.368 | 0.516 |
| "girder3" | 0.381 | 0.516 |
| "girder4" | 0.407 | 0.516 |
| "girder5" | 0.449 | 0.416 |

Two Trucks max moment DF analysis

Total_moment := 847 ft·kip

Girder Actual_DF AASHTO_DF

| <i>Girder</i> | <i>Actual_DF</i> | <i>AASHTO_DF</i> |
|---------------|------------------|------------------|
| "girder1" | 0.362 | 0.416 |
| "girder2" | 0.366 | 0.516 |
| "girder3" | 0.371 | 0.516 |
| "girder4" | 0.422 | 0.516 |
| "girder5" | 0.479 | 0.416 |

Bridge #3067 STEUBENME
Route DYER BAY Road
Crossing DYER CREEK

Prepared By: Mahmood J. Abraheemi
Checked By: SMT
Date : 201611-03

$$DF_{external} := 0.416$$

Four trucks maximum moment

$$M_{max\ moment\ four\ trucks} = 809.35 \text{ ft} \cdot \text{kip}$$

$$S_{4\ truck\ external} := 575.1 \text{ in}^3$$

$$measured_strain_4 := 205.52$$

$$\epsilon_{4\ external} := \frac{M_{max\ moment\ four\ trucks} \cdot DF_{external}}{S_{4\ truck\ external} \cdot 29000 \cdot \text{ksi}} \cdot 10^6 = 242.25$$

$$K_b := 0.5$$

$$K_{a4} := \frac{\epsilon_{4\ external}}{measured_strain_4} - 1$$

$$K_4 := 1 + K_b \cdot K_{a4} = 1.09$$

Two trucks maximum moment

$$M_{max\ moment\ two\ trucks} = 545.81 \text{ ft} \cdot \text{kip}$$

$$S_{2\ truck\ external} := 575.1 \text{ in}^3$$

$$measured_strain_2 := 145.83$$

$$\epsilon_{2\ external} := \frac{M_{max\ moment\ two\ trucks} \cdot DF_{external}}{S_{2\ truck\ external} \cdot 29000 \cdot \text{ksi}} \cdot 10^6 = 163.37$$

$$K_{a2} := \frac{\epsilon_{2\ external}}{measured_strain_2} - 1 = 0.12$$

$$K_2 := 1 + K_b \cdot K_{a2} = 1.06$$

A.3 Waltham No. 3238

A.3.1 Input Data, Experimental Configuration, and Experimental Data Collected

Table 13: Waltham No. 3238 Bridge Input Data, Experimental Configuration, and Experimental Data Collected

| File Contents | File Name | File Type |
|--------------------------------------|--------------------------------|------------------|
| Bridge Geometry and Materials | Br3238_Geom.csv | CSV Format |
| Exterior Section Data | Br3238_Ext.csv | CSV Format |
| Interior Section Data | Br3238_Int.csv | CSV Format |
| Sensors | Br3238_Sensors.csv | CSV Format |
| Sensor Layout | Br3238_SensorLayout.csv | CSV Format |
| Truck Weight and Dimensions | Br3238_SensorLayout.mat | MATLAB Data File |
| Truck Starting Position | TestStart.m > Br3238_TestStart | MATLAB Data File |
| Truck Position Measurements | Br3238_Tk_Positions.mat | MATLAB Data File |
| Sensor Data | Br3238_1Tks_1Lns_1.xlsx | Microsoft Excel |
| | Br3238_2Tks_1Lns_1.xlsx | Microsoft Excel |
| | Br3238_2Tks_2Lns_1.xlsx | Microsoft Excel |
| | Br3238_4Tks_2Lns_1.xlsx | Microsoft Excel |
| Data Time Indices | Br3238_1Tks_1Lns_1_Time.csv | CSV Format |
| | Br3238_2Tks_1Lns_1_Time.csv | CSV Format |
| | Br3238_2Tks_2Lns_1_Time.csv | CSV Format |
| | Br3238_4Tks_2Lns_1_Time.csv | CSV Format |

A.3.2 Instrumentation




Figure 28: Waltham No. 3238 sensor layout

A.3.3 Loading




Figure 29: Waltham No. 3238 Truck T01-119 loading




Figure 30: Waltham No. 3238 Truck T01-257 loading




Figure 31: Waltham No. 3238 Truck T01-280 loading




Figure 32: Waltham No. 3238 Truck T01-287 loading

A.3.4 Representative Data Plots




Figure 33: Waltham No. 3238 - 2 trucks 2 lanes test 2 strains




Figure 34: Waltham No. 3238 - 2 trucks 2 lanes test 2 shear slip




Figure 35: Waltham No. 3238 - 4 trucks 2 lanes test 1 strains




Figure 36: Waltham No. 3238 - 4 trucks 2 lanes test 1 shear slip

A.3.5 Rating Factor Calculations

Figure 37: Waltham No. 3238 Calculations

Bridge #3238 Waltham ME
Route 179 crossing Union
River

Prepared By: Mahmood J. Abraheemi
Checked By: Scott Tomlinson PE
Date : 201611-02

Year Built: 1935

Table 6A.5.2.1-1—Minimum Compressive Strength of Concrete by Year of Construction

| Year of Construction | Compressive Strength, f'_c , ksi |
|----------------------|------------------------------------|
| Prior to 1959 | 2.5 |
| 1959 and Later | 3.0 |

$f'_c := 2.5 \text{ ksi}$

$\gamma_c := 150 \text{ pcf}$

$\gamma_{c_mod} := 145 \text{ pcf}$

LRFD Design
Eq. 54.2.4.1

$$E_c := 33000 \cdot \gamma_{c_mod}^{1.5} \cdot \sqrt{f'_c}$$

$E_c := 2880.95 \text{ ksi}$

$\gamma_{w.s.} := 156 \text{ pcf}$

Table 6A.6.2.1-1—Minimum Mechanical Properties of Structural Steel by Year of Construction

| Year of Construction | Minimum Yield Point or Minimum Yield Strength, F_y , ksi | Minimum Tensile Strength, F_u , ksi |
|----------------------|--|---------------------------------------|
| Prior to 1905 | 26 | 52 |
| 1905 to 1936 | 30 | 60 |
| 1936 to 1963 | 33 | 66 |
| After 1963 | 36 | 66 |

$f_y := 30 \text{ ksi}$

$\gamma_s := 490 \text{ pcf}$

$E_s := 29000 \text{ ksi}$

Bridge Length $L := 55 \text{ ft}$

Deck thickness $t_s := 7 \text{ in}$


Wearing surface thickness $t_{w.s.} := 4 \text{ in}$

Spacing between Girders $S := 5.5 \text{ ft}$

Bridge #3238 Wabam ME
 Route 179 crossing Union
 River

Prepared By: Mahmood J. Abraheemi
 Checked By: Scott Tomlinson PE
 Date : 201611-02

Trucks Weight & dimensions



Bridge #3238 Waham ME
Route 179 crossing Union
River

Prepared By: Mahmood J. Abraheemi
Checked By: Scott Tomlinson PE
Date : 201611-02

Loads on the Interior Girder

DeadLoad:

$M_{DC} := 328 \text{ ft} \cdot \text{kip}$ VHB report

$M_{DW} := 87 \text{ ft} \cdot \text{kip}$ VHB report

Live Load :

We use the average truck weight and dimensions in this calculation


| | T01-280 | T01287 | T01-257 | T01119 |
|------------------|---------|--------|---------|--------|
| Front wheel | 19150 | 15700 | 14800 | 14300 |
| front rear wheel | 23450 | 21200 | 23400 | 23700 |
| rear Wheel | 24250 | 22350 | 23050 | 23200 |

Bridge #3238 Waham ME
Route 179 crossing Union
River

Prepared By: Mahmood J. Abraheemi
Checked By: Scott Tomlinson PE
Date : 201611-02

Trucks at Maximum Moment location:

d1 distance between front wheel and the support



$$R_b(d1) := \frac{(p1 \cdot d1) + (p2 \cdot (d1 + d3)) + (p3 \cdot (d1 + d2 + d3))}{L}$$

$$M(d1) := R_b(d1) \cdot (L - (d1 + d3)) - p3 \cdot (d2)$$

$$R_b(11.5 \text{ ft}) = 29.385 \text{ kip}$$

$$M(11.5 \text{ ft}) = 662.215 \text{ ft} \cdot \text{kip}$$

$$M_{\text{maxmomenttwo trucks}} := 662.215 \text{ ft} \cdot \text{kip}$$

Bridge #3238 Waham ME
Route 179 crossing Union
River

Prepared By: Mahmood J. Abraheemi
Checked By: Scott Tomlinson PE
Date : 201611-02

Trucks at Maximum Moment location:

d1 distance between front wheel and the support ; d4 distance between trucks

$$R_b(d1, d4) := \frac{p1 \cdot d1 + p2 \cdot (d1 + d3) + p3 \cdot (d1 + d3 + d2) + p3 \cdot (d1 + d3 + d2 + d4) + p2 \cdot (d1 + d3 + 2 \cdot d2 + d4)}{L}$$

$$M(d1, d4) := (R_b(d1, d4) \cdot (L - (d1 + d3 + d2))) - (p2 \cdot (d2 + d4)) - (p3 \cdot d4)$$

$$R_b(6.8 \text{ ft}, 7.3 \text{ ft}) = 54.7 \text{ kip}$$

$$M(6.8 \text{ ft}, 7.3 \text{ ft}) = 1036.805 \text{ ft} \cdot \text{kip}$$

$$M_{\text{maxmomentfourtrucks}} := 1036.8 \cdot \text{ft} \cdot \text{kip}$$

Bridge #3238 Waham ME
Route 179 crossing Union
River

Prepared By: Mahmood J. Abraheemi
Checked By: Scott Tomlinson PE
Date : 201611-02

Section Properties and Distribution Factors

| | | | | | |
|------------------------------------|-------|-----------|-------------------|--------------|---|
| Q_slab = | | 435.4 | in^3 | | |
| External Girder Section Properties | | | Second assumption | | |
| component | width | thickness | modular ratio | transf. area | y |

Moment Distribution factors (Interior Girders)

VHBreport

$$DF_{onelane} = 0.375$$

$$DF_{twolanes} = 0.49$$

Calculated Distribution factors based on actual measurements

$$DF_{onelane} := 0.377$$

$$DF_{twolanes} := 0.493$$

$$DF_{shear} := 0.634$$

Section Properties: Fully composite

$$y' := 33.9 \text{ in} \quad I := 27314 \cdot \text{in}^4 \quad S_{bot} := 806.1 \cdot \text{in}^3 \quad Q_{slab} := 698.0 \cdot \text{in}^3$$

$$b_f := 11.98 \text{ in}$$

Bridge #3238 Waham ME
Route 179 crossing Union
River

Prepared By: Mahmood J. Abraheemi
Checked By: Scott Tomlinson PE
Date : 201611-02

Maximum Live Load Moment calculation in each loadcase for the interior girder

Two trucks in two lanes

$$Mt_{0.5dtwo\ trucks} := DF_{two\ lanes} \cdot M_{0.5dtwo\ trucks} = 80 \text{ ft} \cdot \text{kip}$$

$$Mt_{1.0dtwo\ trucks} := DF_{two\ lanes} \cdot M_{1.0dtwo\ trucks} = 105 \text{ ft} \cdot \text{kip}$$

$$Mt_{1.5dtwo\ trucks} := DF_{two\ lanes} \cdot M_{1.5dtwo\ trucks} = 130 \text{ ft} \cdot \text{kip}$$

$$Mt_{2.0dtwo\ trucks} := DF_{two\ lanes} \cdot M_{2.0dtwo\ trucks} = 152 \text{ ft} \cdot \text{kip}$$

$$Mt_{max\ moment\ two\ trucks} := DF_{two\ lanes} \cdot M_{max\ moment\ two\ trucks} = 326 \text{ ft} \cdot \text{kip}$$

Four trucks in two lanes

$$Mt_{0.5d\ four\ trucks} := DF_{two\ lanes} \cdot M_{0.5d\ four\ trucks} = 359 \text{ ft} \cdot \text{kip}$$

$$Mt_{1.0d\ four\ trucks} := DF_{two\ lanes} \cdot M_{1.0d\ four\ trucks} = 390 \text{ ft} \cdot \text{kip}$$

$$Mt_{1.5d\ four\ trucks} := DF_{two\ lanes} \cdot M_{1.5d\ four\ trucks} = 415 \text{ ft} \cdot \text{kip}$$

$$Mt_{2.0d\ four\ trucks} := DF_{two\ lanes} \cdot M_{2.0d\ four\ trucks} = 436 \text{ ft} \cdot \text{kip}$$

$$Mt_{max\ moment\ four\ trucks} := DF_{two\ lanes} \cdot M_{max\ moment\ four\ trucks} = 511 \text{ ft} \cdot \text{kip}$$

Actual section Response

| | | | | | | | | |
|--------------|--------------|-----------|----------|----------|----------|----------|----------|----------|
| 1.0d | -4.329146915 | 55.489869 | 22.41063 | 0.288809 | -34.0286 | 6.025945 | 66.6797 | -9.96326 |
| 1.5d | -3.231458311 | 58.234414 | 18.40945 | -1.68524 | -25.1511 | 7.947325 | 72.28859 | -9.93835 |
| 2.0d | -2.886442548 | 55.091825 | 20.77649 | -1.60974 | -39.5641 | 8.930679 | 79.44879 | -10.6193 |
| Max Moment | 23.18579254 | 84.933748 | 39.37371 | 5.162854 | -38.2792 | 5.548775 | 121.3018 | -7.66561 |
| Two Trucks 1 | | | | | | | | |

Bridge #3238 Wabam ME
Route 179 crossing Union
River

Prepared By: Mahmood J. Abraheemi
Checked By: Scott Tomlinson PE
Date : 201611-02

Four Trucks

| | | |
|-------------------------------------|---------------------------------------|-----------------|
| $y'_{0.5d} := 37.4 \text{ in}$ | $S_{0.5d} := 806.1 \text{ in}^3$ | Fully composite |
| $y'_{1.0d} := 38.0 \text{ in}$ | $S_{1.0d} := 806.1 \text{ in}^3$ | Fully composite |
| $y'_{1.5d} := 38.7 \text{ in}$ | $S_{1.5d} := 806.1 \text{ in}^3$ | Fully composite |
| $y'_{2.0d} := 38.7 \text{ in}$ | $S_{2.0d} := 806.1 \text{ in}^3$ | Fully composite |
| $y'_{maxmoment} := 36.3 \text{ in}$ | $S_{maxmoment} := 806.1 \text{ in}^3$ | Fully composite |

$$M_{fourtrucks} := \begin{bmatrix} M_{0.5dfourtrucks} \\ M_{1.0dfourtrucks} \\ M_{1.5dfourtrucks} \\ M_{2.0dfourtrucks} \\ M_{maxmomentfourtrucks} \end{bmatrix} ; y_{fourtrucks} := \begin{bmatrix} y'_{0.5d} \\ y'_{1.0d} \\ y'_{1.5d} \\ y'_{2.0d} \\ y'_{maxmoment} \end{bmatrix} ; S_{fourtrucks} := \begin{bmatrix} S_{0.5d} \\ S_{1.0d} \\ S_{1.5d} \\ S_{2.0d} \\ S_{maxmoment} \end{bmatrix}$$

Strain based on actual response

$$\epsilon_{computed} := \begin{bmatrix} \frac{M_{0.5dfourtrucks}}{S_{0.5d} \cdot 29000 \text{ ksi}} \\ \frac{M_{1.0dfourtrucks}}{S_{1.0d} \cdot 29000 \text{ ksi}} \\ \frac{M_{1.5dfourtrucks}}{S_{1.5d} \cdot 29000 \text{ ksi}} \\ \frac{M_{2.0dfourtrucks}}{S_{2.0d} \cdot 29000 \text{ ksi}} \\ \frac{M_{maxmomentfourtrucks}}{S_{maxmoment} \cdot 29000 \text{ ksi}} \end{bmatrix} \cdot 10^6 = \begin{bmatrix} 184.52 \\ 200.112 \\ 212.928 \\ 223.949 \\ 262.383 \end{bmatrix}$$

$Kb := 1.0$

$Kb := 0.5$

$Ka := \frac{259.19}{200.71} - 1 = 0.291$

$Ka := \frac{262.38}{140.87} - 1 = 0.863$

$K := 1 + Kb \cdot Ka = 1.291$

$K := 1 + Kb \cdot Ka = 1.43$

Bridge #3238 Waham ME
Route 179 crossing Union
River

Prepared By: Mahmood J. Abraheemi
Checked By: Scott Tomlinson PE
Date : 201611-02

Two Trucks 1

| | | |
|--|--|-----------------|
| $y'_{0.5d} := 41.4 \text{ in}$ | $S_{0.5d} := 806.1 \text{ in}^3$ | Fully composite |
| $y'_{1.0d} := 41.8 \text{ in}$ | $S_{1.0d} := 806.1 \text{ in}^3$ | Fully composite |
| $y'_{1.5d} := 42.6 \text{ in}$ | $S_{1.5d} := 806.1 \text{ in}^3$ | Fully composite |
| $y'_{2.0d} := 33.9 \text{ in}$ | $S_{2.0d} := 806.1 \text{ in}^3$ | Fully composite |
| $y'_{\text{maxmoment}} := 35.3 \text{ in}$ | $S_{\text{maxmoment}} := 806.1 \text{ in}^3$ | Fully composite |

$$M_{\text{two trucks}} := \begin{bmatrix} Mt_{0.5d \text{ two trucks}} \\ Mt_{1.0d \text{ two trucks}} \\ Mt_{1.5d \text{ two trucks}} \\ Mt_{2.0d \text{ two trucks}} \\ Mt_{\text{maxmoment two trucks}} \end{bmatrix} \quad y_{\text{two trucks}} := \begin{bmatrix} y'_{0.5d} \\ y'_{1.0d} \\ y'_{1.5d} \\ y'_{2.0d} \\ y'_{\text{maxmoment}} \end{bmatrix} \quad S_{\text{two trucks 1}} := \begin{bmatrix} S_{0.5d} \\ S_{1.0d} \\ S_{1.5d} \\ S_{2.0d} \\ S_{\text{maxmoment}} \end{bmatrix}$$

Strain based on actual response

$$\epsilon_{\text{computed}} := \begin{bmatrix} \frac{Mt_{0.5d \text{ two trucks}}}{S_{0.5d} \cdot 29000 \text{ ksi}} \\ \frac{Mt_{1.0d \text{ two trucks}}}{S_{1.0d} \cdot 29000 \text{ ksi}} \\ \frac{Mt_{1.5d \text{ two trucks}}}{S_{1.5d} \cdot 29000 \text{ ksi}} \\ \frac{Mt_{2.0d \text{ two trucks}}}{S_{2.0d} \cdot 29000 \text{ ksi}} \\ \frac{Mt_{\text{maxmoment two trucks}}}{S_{\text{maxmoment}} \cdot 29000 \text{ ksi}} \end{bmatrix} \cdot 10^6 = \begin{bmatrix} 41.263 \\ 54.779 \\ 67.351 \\ 78.978 \\ 167.587 \end{bmatrix}$$

$Kb := 1.0$

$Kb := 0.5$

$Ka := \frac{165.547}{133.15} - 1 = 0.243$

$Ka := \frac{167.587}{91.42} - 1 = 0.833$

$K := 1 + Kb \cdot Ka = 1.243$

$K := 1 + Kb \cdot Ka = 1.42$

Bridge #3238 Waham ME
Route 179 crossing Union
River

Prepared By: Mahmood J. Abraheemi
Checked By: Scott Tomlinson PE
Date : 201611-02

Shear Flow Calculation

Four Trucks maximum moment

maximum shearforce $V := 54.7 \text{ kip}$

$$\tau := \frac{V \cdot DF_{shear} \cdot Q_{slab}}{I \cdot b_f} = 73.98 \text{ psi} \quad \text{Fully composite}$$

Four Trucks maximum shear

maximum shearforce $V := 80.835 \text{ kip}$

$$\tau := \frac{V \cdot DF_{shear} \cdot Q_{slab}}{I \cdot b_f} = 109.321 \text{ psi} \quad \text{Fully composite}$$

Two Trucks maximum shear

maximum shearforce $V_{shear2t} = 42.238 \text{ kip}$

$$\tau := \frac{V_{shear2t} \cdot DF_{shear} \cdot Q_{slab}}{I \cdot b_f} = 57.123 \text{ psi}$$

Bridge #3238 Waham ME
Route 179 crossing Union
River

Prepared By: Mahmood J. Abraheemi
Checked By: Scott Tomlinson PE
Date : 201611-02

Calculation of Actual Distribution Factors

| | | | | | |
|------------|-------------|--|--|----------------|------------|
| S_bottom = | 765.6 in^3 | | | | |
| Mmidspan | 94.04172333 | | | | |
| | | | | | |
| | | | | Total I | 674 |

Four Trucks max moment DF analysis

Total_moment := 1035 ft·kip

Girder Actual_DF AASHTO_DF

| <i>Girder</i> | <i>Actual_DF</i> | <i>AASHTO_DF</i> |
|---------------|------------------|------------------|
| "girder1" | 0.304 | 0.38 |
| "girder2" | 0.457 | 0.493 |
| "girder3" | 0.530 | 0.493 |
| "girder4" | 0.429 | 0.493 |
| "girder5" | 0.281 | 0.38 |

Two Trucks max moment DF analysis

Total_moment := 674 ft·kip

Girder Actual_DF AASHTO_DF

| <i>Girder</i> | <i>Actual_DF</i> | <i>AASHTO_DF</i> |
|---------------|------------------|------------------|
| "girder1" | 0.319 | 0.38 |
| "girder2" | 0.444 | 0.493 |
| "girder3" | 0.529 | 0.493 |
| "girder4" | 0.429 | 0.493 |
| "girder5" | 0.279 | 0.38 |

Bridge #3238 Waham ME
Route 179 crossing Union
River

Prepared By: Mahmood J. Abraheemi
Checked By: Scott Tomlinson PE
Date : 201611-02

$DF_{external} := 0.38$

Four trucks maximum moment

$M_{max\ moment\ four\ trucks} = (1.037 \cdot 10^3) \text{ ft} \cdot \text{kip}$

$S_{4\ truck\ external} := 765.6 \text{ in}^3$

$measured_strain_4 := 84.93$

$\epsilon_{4\ external} := \frac{M_{max\ moment\ four\ trucks} \cdot DF_{external}}{S_{4\ truck\ external} \cdot 29000 \cdot \text{ksi}} \cdot 10^6 = 212.941$

$K_b := 0.5$

$K_{a4} := \frac{\epsilon_{4\ external}}{measured_strain_4} - 1$

$K_4 := 1 + K_b \cdot K_{a4} = 1.754$

Two trucks maximum moment

$M_{max\ moment\ two\ trucks} = 662.215 \text{ ft} \cdot \text{kip}$

$S_{2\ truck\ external} := 765.6 \text{ in}^3$

$measured_strain_2 := 58.19$

$\epsilon_{2\ external} := \frac{M_{max\ moment\ two\ trucks} \cdot DF_{external}}{S_{2\ truck\ external} \cdot 29000 \cdot \text{ksi}} \cdot 10^6 = 181.06$

$K_{a2} := \frac{\epsilon_{2\ external}}{measured_strain_2} - 1 = 2.112$

$K_2 := 1 + K_b \cdot K_{a2} = 2.056$

A.4 Pembroke No. 3884

A.4.1 Input Data, Experimental Configuration, and Experimental Data Collected

Table 13: Pembroke No. 3884 Bridge Input Data, Experimental Configuration, and Experimental Data Collected

| File Contents | File Name | File Type |
|--------------------------------------|--------------------------------|------------------|
| Bridge Geometry and Materials | Br3884_Geom.csv | CSV Format |
| Exterior Section Data | Br3884_Ext.csv | CSV Format |
| Interior Section Data | Br3884_Int.csv | CSV Format |
| Sensors | Br3884_Sensors.csv | CSV Format |
| Sensor Layout | Br3884_SensorLayout.csv | CSV Format |
| Truck Weight and Dimensions | Br3884_SensorLayout.mat | MATLAB Data File |
| Truck Starting Position | TestStart.m > Br3884_TestStart | MATLAB Data File |
| Truck Position Measurements | Br3884_Tk_Positions.mat | MATLAB Data File |
| Sensor Data | Br3884_1Tks_1Lns_1.xlsx | Microsoft Excel |
| | Br3884_2Tks_1Lns_1.xlsx | Microsoft Excel |
| | Br3884_4Tks_2Lns_1.xlsx | Microsoft Excel |
| Data Time Indices | Br3884_1Tks_1Lns_1_Time.csv | CSV Format |
| | Br3884_2Tks_1Lns_1_Time.csv | CSV Format |
| | Br3884_4Tks_2Lns_1_Time.csv | CSV Format |

A.4.2 Instrumentation




Figure 38: Pembroke No. 3884 sensor layout

A.4.3 Loading




Figure 39: Pembroke No. 3884 Truck T01-223 loading




Figure 40: Pembroke No. 3884 Truck T01-231 loading




Figure 41: Pembroke No. 3884 Truck T01-242 loading




Figure 42: Pembroke No. 3884 Truck T01-244 loading

A.4.4 Representative Data Plots




Figure 43: Pembroke No. 3884 - 4 trucks 2 lanes test 1 strains




Figure 44: Pembroke No. 3884 - 4 trucks 2 lanes test 1 shear slip




Figure 45: Pembroke No. 3884 - 4 trucks 2 lanes test 2 strains




Figure 46: Pembroke No. 3884 - 4 trucks 2 lanes test 2 shear slip

A.4.5 Rating Factor Calculations

Figure 47: Pembroke No. 3884 Calculations

Bridge#3884PembrokeME
Pembroke CrossRoad
OverPENNAMAQUAN River

Prepared By: Mahmood J. Abraheemi
Checked By: SMT
Date : 201611-16

YearBuilt: 1944

Table 6A.5.2.1-1—Minimum Compressive Strength of Concrete by Year of Construction

| Year of Construction | Compressive Strength, f'_c , ksi |
|----------------------|------------------------------------|
| Prior to 1959 | 2.5 |
| 1959 and Later | 3.0 |

$f'_c := 2.5 \text{ ksi}$

$\gamma_c := 150 \text{ pcf}$

$\gamma_{c_mod} := 145 \text{ pcf}$

LRFD Design
Eq. 54.2.4.1

$$E_c := 33000 \cdot \gamma_{c_mod}^{1.5} \cdot \sqrt{f'_c}$$

$E_c := 2875.9 \text{ ksi}$

Table 6A.6.2.1-1—Minimum Mechanical Properties of Structural Steel by Year of Construction

| Year of Construction | Minimum Yield Point or Minimum Yield Strength, F_y , ksi | Minimum Tensile Strength, F_u , ksi |
|----------------------|--|---------------------------------------|
| Prior to 1905 | 26 | 52 |
| 1905 to 1936 | 30 | 60 |
| 1936 to 1963 | 33 | 66 |
| After 1963 | 36 | 66 |

$f_y := 33 \text{ ksi}$

$\gamma_s := 490 \text{ pcf}$

$E_s := 29000 \text{ ksi}$

Bridge Length $L := 45.25 \text{ ft}$

Spacing between Girders $S := 5.75 \text{ ft}$


Deck thickness $t_s := 6.75 \text{ in}$

Wearing surface thickness $t_{w.s.} := 0 \text{ in}$ $\gamma_{w.s.} := 140 \text{ pcf}$

Bridge#3884PembrokeME
Pembroke CrossRoad
OverPENNAQUAN River

Prepared By: Mahmood J. Abraheemi
Checked By: SMT
Date : 201611-16

TrucksWeight & Dimensions



Bridge#3884PembrokeME
Pembroke CrossRoad
OverPENNAQUAN River

Prepared By: Mahmood J. Abraheemi
Checked By: SMT
Date : 201611-16

Loads on the Interior Girder

DeadLoad:

$M_{DC} := 188 \text{ ft} \cdot \text{kip}$ VHB report

$d := 27.0 \text{ in}$ $b_f := 10.0 \text{ in}$

Live Load :

We use the average truck weight and dimensions in this calculation

| | Trucks Weight | | | |
|------------------|---------------|---------|---------|------------|
| | T01-231 | T01-242 | T01-223 | T01-157244 |
| Front wheel | 14350 | 14400 | 15150 | 15000 |
| front rear wheel | 19500 | 20250 | 20850 | 20900 |
| Last Wheel | 19650 | 20600 | 21450 | 21200 |

Bridge#3884PembrokeME
 Pembroke CrossRoad
 OverPENNAQUAN River

Prepared By: Mahmood J. Abraheemi
 Checked By: SMT
 Date : 201611-16


Four trucks in two lanes

$p1 := 14.7 \text{ kip}$ $p2 := 20.4 \text{ kip}$ $p3 := 20.7 \text{ kip}$ page #3 average axle weight

$d2 := 4.5 \text{ ft}$
 $d3 := 15.6 \text{ ft}$

Trucks at Maximum Moment location:

$d1$ distance between front wheel and the support ; $d4$ distance between trucks



At Maximum Moment:

$$R_b(d1, d4) := \frac{p1 \cdot d1 + p2 \cdot (d1 + d3) + p3 \cdot (d1 + d3 + d2) + p3 \cdot (d1 + d3 + d2 + d4) + p2 \cdot (d1 + d3 + 2 \cdot d2 + d4)}{L}$$

$$M(d1, d4) := (R_b(d1, d4) \cdot (L - (d1 + d3 + d2))) - (p2 \cdot (d2 + d4)) - (p3 \cdot d4)$$

$$R_b(2.125 \text{ ft}, 83 \text{ in}) = 47.35 \text{ kip}$$

$$M(2.125 \text{ ft}, 83 \text{ in}) = 714.067 \text{ ft} \cdot \text{kip}$$

$$M_{\text{maxmomentfourtrucks}} := 714.1 \text{ ft} \cdot \text{kip}$$

Bridge#3884PembrokeME
Pembroke CrossRoad
OverPENNAQUAN River

Prepared By: Mahmood J. Abraheemi
Checked By: SMT
Date : 201611-16

Section Properties and Distribution Factors

| | | | |
|------------------------------------|--|-------------------|---------|
| Exterior Girder Section Properties | | second assumption | |
| | | modular | transf. |

Moment Distribution factors (Interior Girders)

VHB report

$$DF_{onelane} = 0.375$$

$$DF_{twolanes} = 0.484$$

Calculated Distribution factors based on actual measurements

$$DF_{onelane} := 0.421$$

$$DF_{twolanes} := 0.544$$

$$DF_{shear} := 0.652$$

Section Properties: Fully composite

$$y' := 23.4 \text{ in}$$

$$I := 8152 \cdot \text{in}^4$$

$$S_{bot} := 347.8 \cdot \text{in}^3$$

$$Q_{slab} := 283.7 \cdot \text{in}^3$$

Bridge#3884PembrokeME
Pembroke CrossRoad
OverPENNAQUAN River

Prepared By: Mahmood J. Abraheemi
Checked By: SMT
Date : 201611-16

Maximum Live Load Moment calculation in each load case for the interior girder

Two trucks in two lanes

$$M_{t_{maxmomenttwo trucks}} := DF_{two lanes} \cdot M_{maxmomenttwo trucks} = 237 \text{ ft} \cdot \text{kip}$$

Four trucks in two lanes

$$M_{t_{maxmomentfour trucks}} := DF_{two lanes} \cdot M_{maxmomentfour trucks} = 388 \text{ ft} \cdot \text{kip}$$

Actual section Response

| | | | | |
|------|-----------|------------|-----------|-------------------------------------|
| Mid | B3056 | 29.458648 | B3061 | 46.8835476 |
| bot. | B3057 | 63.5795879 | B3060 | 125.5109165 |
| | y' | 26.0514948 | y' | 22.0061647 |
| | component | width | thickness | modular transf. ratio area |

Bridge#3884PembrokeME
Pembroke CrossRoad
OverPENNAQUAN River

Prepared By: Mahmood J. Abraheemi
Checked By: SMT
Date : 201611-16

Four Trucks

Look at the critical girder the interior
girder

$$y'_{maxmoment} := 24.0 \text{ in}$$

$$S_{maxmoment} := 347.8 \text{ in}^3$$

Fully composite

Strain based on actual response

$$\epsilon_{computed} := \frac{M_{t_{maxmoment, fourtrucks}}}{S_{maxmoment} \cdot 29000 \text{ ksi}} \cdot 10^6 = 462.18$$

$$Kb := 0.5$$

$$Ka := \frac{462.18}{220.4} - 1$$

$$K := 1 + Kb \cdot Ka = 1.55$$

Bridge#3884PembrokeME
Pembroke CrossRoad
OverPENNAQUAN River

Prepared By: Mahmood J. Abraheemi
Checked By: SMT
Date : 201611-16

Two Trucks

Look at the critical girder the interior
girder

$$y'_{maxmoment} := 23.6 \text{ in}$$

$$S_{maxmoment} := 347.8 \text{ in}^3$$

Fully composite

Strain based on actual response

$$\epsilon_{computed} := \frac{M_{t_{maxmomenttwotrucks}}}{S_{maxmoment} \cdot 29000 \text{ ksi}} \cdot 10^6 = 281.54$$

$$Kb := 0.5$$

$$Ka := \frac{281.54}{144.48} - 1$$

$$K := 1 + Kb \cdot Ka = 1.47$$

Bridge#3884PembrokeME
Pembroke CrossRoad
OverPENNAQUAN River

Prepared By: Mahmood J. Abraheemi
Checked By: SMT
Date : 201611-16

Shear Flow Calculation

Four Trucks maximum shear

maximum shearforce $V := 47.35 \text{ kip}$

$$\tau := \frac{V \cdot DF_{shear} \cdot Q_{slab}}{I \cdot b_f} = 107.439 \text{ psi} \quad \text{Fully composite}$$

Two Trucks maximum shear

maximum shearforce $V_{shear2t} = 38.22 \text{ kip}$

$$\tau := \frac{V_{shear2t} \cdot DF_{shear} \cdot Q_{slab}}{I \cdot b_f} = 86.72 \text{ psi}$$

Bridge#3884PembrokeME
Pembroke CrossRoad
OverPENNAQUAN River

Prepared By: Mahmood J. Abraheemi
Checked By: SMT
Date : 201611-16

Calculation of Actual Distribution Factors

| | | | | |
|-------------------|-----------|----------------|----|----------|
| | | | 97 | 2.56E+03 |
| y_bar = | 26.4 | in from bottom | | |
| Moment of Inertia | 1.131E+04 | in^4 | | |
| S_bottom = | 428.9 | in^3 | | |
| Mmidspan | 122.45 | | | |

Four Trucks max moment DF analysis

Total_moment := 696 *ft · kip*

Girder Actual_DF AASHTO_DF

| <i>Girder</i> | <i>Actual_DF</i> | <i>AASHTO_DF</i> |
|---------------|------------------|------------------|
| "girder1" | 0.297 | 0.449 |
| "girder2" | 0.459 | 0.544 |
| "girder3" | 0.532 | 0.544 |
| "girder4" | 0.359 | 0.544 |
| "girder5" | 0.353 | 0.449 |

Two Trucks max moment DF analysis

Total_moment := 453.1 *ft · kip*

Girder Actual_DF AASHTO_DF

| <i>Girder</i> | <i>Actual_DF</i> | <i>AASHTO_DF</i> |
|---------------|------------------|------------------|
| "girder1" | 0.291 | 0.449 |
| "girder2" | 0.453 | 0.544 |
| "girder3" | 0.536 | 0.544 |
| "girder4" | 0.343 | 0.544 |
| "girder5" | 0.377 | 0.449 |

Bridge#3884PembrokeME
Pembroke CrossRoad
OverPENNAMAQUAN River

Prepared By: Mahmood J. Abraheemi
Checked By: SMT
Date : 201611-16

$$DF_{external} := 0.449$$

Four trucks maximum moment

$$M_{max\ moment\ four\ trucks} = 714.1 \text{ ft} \cdot \text{kip}$$

$$S_{4\ truck\ external} := 428.9 \text{ in}^3$$

$$measured_strain_4 := 118.14$$

$$\epsilon_{4\ external} := \frac{M_{max\ moment\ four\ trucks} \cdot DF_{external}}{S_{4\ truck\ external} \cdot 29000 \cdot \text{ksi}} \cdot 10^6 = 309.34$$

$$K_b := 0.5$$

$$K_{a4} := \frac{\epsilon_{4\ external}}{measured_strain_4} - 1$$

$$K_4 := 1 + K_b \cdot K_{a4} = 2.32$$

Two trucks maximum moment

$$M_{max\ moment\ two\ trucks} = 435 \text{ ft} \cdot \text{kip}$$

$$S_{2\ truck\ external} := 428.9 \text{ in}^3$$

$$measured_strain_2 := 82.34$$

$$\epsilon_{2\ external} := \frac{M_{max\ moment\ two\ trucks} \cdot DF_{external}}{S_{2\ truck\ external} \cdot 29000 \cdot \text{ksi}} \cdot 10^6 = 188.44$$

$$K_{a2} := \frac{\epsilon_{2\ external}}{measured_strain_2} - 1 = 1.29$$

$$K_2 := 1 + K_b \cdot K_{a2} = 1.64$$

A.5 Windham No. 5298

A.5.1 Input Data, Experimental Configuration, and Experimental Data Collected

Table 144: Windham No. 5298 Bridge Input Data, Experimental Configuration, and Experimental Data Collected

| <i>File Contents</i> | <i>File Name</i> | <i>File Type</i> |
|--------------------------------------|--------------------------------|------------------|
| Bridge Geometry and Materials | Br5298_Geom.csv | CSV Format |
| Exterior Section Data | Br5298_Ext.csv | CSV Format |
| Interior Section Data | Br5298_Int.csv | CSV Format |
| Sensors | Br5298_Sensors.csv | CSV Format |
| Sensor Layout | Br5298_SensorLayout.csv | CSV Format |
| Truck Weight and Dimensions | Br5298_SensorLayout.mat | MATLAB Data File |
| Truck Starting Position | TestStart.m > Br5298_TestStart | MATLAB Data File |
| Truck Position Measurements | Br5298_Tk_Positions.mat | MATLAB Data File |
| Sensor Data | Br5298_1Tks_1Lns_1.xlsx | Microsoft Excel |
| | Br5298_2Tks_1Lns_1.xlsx | Microsoft Excel |
| | Br5298_2Tks_1Lns_3.xlsx | Microsoft Excel |
| | Br5298_2Tks_2Lns_1.xlsx | Microsoft Excel |
| | Br5298_4Tks_2Lns_2.xlsx | Microsoft Excel |
| Data Time Indices | Br3057_1Tks_1Lns_1_Time.csv | CSV Format |
| | Br3057_1UBT_1Lns_1_Time.csv | CSV Format |
| | Br3057_2Tks_1Lns_1_Time.csv | CSV Format |
| | Br3057_2Tks_1Lns_2_Time.csv | CSV Format |
| | Br3057_2Tks_2Lns_1_Time.csv | CSV Format |
| | Br3057_4Tks_2Lns_1_Time.csv | CSV Format |

A.5.2 Instrumentation




Figure 48: Windham No. 5298 sensor layout

A.5.3 Loading




Figure 49: Windham No. 5298 Truck T01-164 loading




Figure 50: Windham No. 5298 Truck T01-197 loading




Figure 51: Windham No. 5298 Truck T01-247 loading




Figure 52: Windham No. 5298 Truck T01-259 loading

A.5.4 Representative Data Plots




Figure 53: Windham No. 5298 - 2 trucks 2 lanes test 1 strains




Figure 54: Windham No. 5298 - 2 trucks 2 lanes test 1 shear slip




Figure 55: Windham No. 5298 - 4 trucks 2 lanes test 2 strains




Figure 56: Windham No. 5298 - 4 trucks 2 lanes test 2 shear slip

A.5.5 Rating Factor Calculations

Figure 57: Windham No. 5298 Calculations

Bridge #5298 Windham ME
Route Windham Center Road
Crossing Pleasant River

Prepared By: Mahmood J. Abraheemi
Checked By: SMT
Date : 201611-03


| <p>YearBuilt: 1950</p> <p>Table 6A.5.2.1-1—Minimum Compressive Strength of Concrete by Year of Construction</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>Year of Construction</th> <th>Compressive Strength, f'_c, ksi</th> </tr> </thead> <tbody> <tr> <td>Prior to 1959</td> <td>2.5</td> </tr> <tr> <td>1959 and Later</td> <td>3.0</td> </tr> </tbody> </table> <p>$f'_c := 2.5 \text{ ksi}$</p> <p>$\gamma_c := 150 \text{ pcf}$</p> <p>$\gamma_{c_mod} := 145 \text{ pcf}$</p> <p>LRFD Design Eq. 54.2.4.1</p> $E_c := 33000 \cdot \gamma_{c_mod}^{1.5} \cdot \sqrt{f'_c}$ <p>$E_c := 2875.9 \text{ ksi}$</p> | Year of Construction | Compressive Strength, f'_c , ksi | Prior to 1959 | 2.5 | 1959 and Later | 3.0 | <p>Table 6A.6.2.1-1—Minimum Mechanical Properties of Structural Steel by Year of Construction</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>Year of Construction</th> <th>Minimum Yield Point or Minimum Yield Strength, F_y, ksi</th> <th>Minimum Tensile Strength, F_u, ksi</th> </tr> </thead> <tbody> <tr> <td>Prior to 1905</td> <td>26</td> <td>52</td> </tr> <tr> <td>1905 to 1936</td> <td>30</td> <td>60</td> </tr> <tr> <td>1936 to 1963</td> <td>33</td> <td>66</td> </tr> <tr> <td>After 1963</td> <td>36</td> <td>66</td> </tr> </tbody> </table> <p>$f_y := 33 \text{ ksi}$</p> <p>$\gamma_s := 490 \text{ pcf}$</p> <p>$E_s := 29000 \text{ ksi}$</p> | Year of Construction | Minimum Yield Point or Minimum Yield Strength, F_y , ksi | Minimum Tensile Strength, F_u , ksi | Prior to 1905 | 26 | 52 | 1905 to 1936 | 30 | 60 | 1936 to 1963 | 33 | 66 | After 1963 | 36 | 66 |
|--|--|---------------------------------------|---------------|-----|----------------|-----|--|----------------------|--|---------------------------------------|---------------|----|----|--------------|----|----|--------------|----|----|------------|----|----|
| Year of Construction | Compressive Strength, f'_c , ksi | | | | | | | | | | | | | | | | | | | | | |
| Prior to 1959 | 2.5 | | | | | | | | | | | | | | | | | | | | | |
| 1959 and Later | 3.0 | | | | | | | | | | | | | | | | | | | | | |
| Year of Construction | Minimum Yield Point or Minimum Yield Strength, F_y , ksi | Minimum Tensile Strength, F_u , ksi | | | | | | | | | | | | | | | | | | | | |
| Prior to 1905 | 26 | 52 | | | | | | | | | | | | | | | | | | | | |
| 1905 to 1936 | 30 | 60 | | | | | | | | | | | | | | | | | | | | |
| 1936 to 1963 | 33 | 66 | | | | | | | | | | | | | | | | | | | | |
| After 1963 | 36 | 66 | | | | | | | | | | | | | | | | | | | | |

| | | |
|---------------------------|------------------------------|------------------------------------|
| Bridge Length | $L := 46 \text{ ft}$ | |
| Spacing between Girders | $S := 5.33 \text{ ft}$ | |
| Deck thickness | $t_s := 6.0 \text{ in}$ | |
| Wearing surface thickness | $t_{w.s.} := 9.0 \text{ in}$ | $\gamma_{w.s.} := 143 \text{ pcf}$ |

Bridge #5298 Windham ME
Route Windham Center Road
Crossing Pleasant River

Prepared By: Mahmood J. Abraheemi
Checked By: SMT
Date : 201611-03

Trucks Weight & Dimensions



Bridge #5298 Windham ME
Route Windham Center Road
Crossing Pleasant River

Prepared By: Mahmood J. Abraheemi
Checked By: SMT
Date : 201611-03

Loads on the Interior Girder

DeadLoad:

$M_{DC} := 190 \text{ ft} \cdot \text{kip}$ VHB report

$M_{DW} := 155 \text{ ft} \cdot \text{kip}$ VHB report

$d := 29.83 \text{ in}$ $b_f := 10.48 \text{ in}$

Live Load :

We use the average truck weight and dimensions in this calculation


| | Trucks Weight | | | |
|------------------|---------------|---------|---------|---------|
| | T01-197 | T01-247 | T01-164 | T01-259 |
| Front wheel | 15700 | 15200 | 14550 | 14800 |
| front rear wheel | 19450 | 19650 | 20100 | 19700 |
| Last Wheel | 19150 | 20600 | 21150 | 22400 |

Bridge #5298 Windham ME
Route Windham Center Road
Crossing Pleasant River

Prepared By: Mahmood J. Abraheemi
Checked By: SMT
Date : 201611-03

Trucks at Maximum Moment location:

d1 distance between front wheel and the support



$$R_b(d1) := \frac{(p1 \cdot d1) + (p2 \cdot (d1 + d3)) + (p3 \cdot (d1 + d2 + d3))}{L}$$

$$M(d1) := R_b(d1) \cdot (L - (d1 + d3)) - p3 \cdot (d2)$$

$$R_b(96 \text{ in}) = 25.776 \text{ kip}$$

$$M(96 \text{ in}) = 483.85 \text{ ft} \cdot \text{kip}$$


$$M_{\text{maxmomenttwo trucks}} := 483.85 \text{ (ft} \cdot \text{kip)}$$

Bridge #5298 Windham ME
Route Windham Center Road
Crossing Pleasant River

Prepared By: Mahmood J. Abraheemi
Checked By: SMT
Date : 201611-03

Trucks at Maximum Moment location:

d1 distance between front wheel and the support ; d4 distance between trucks



At Maximum Moment:

$$R_b(d1, d4) := \frac{p1 \cdot d1 + p2 \cdot (d1 + d3) + p3 \cdot (d1 + d3 + d2) + p3 \cdot (d1 + d3 + d2 + d4) + p2 \cdot (d1 + d3 + 2 \cdot d2 + d4)}{L}$$

$$M(d1, d4) := (R_b(d1, d4) \cdot (L - (d1 + d3 + d2))) - (p2 \cdot (d2 + d4)) - (p3 \cdot d4)$$

$$R_b(42 \text{ in}, 92 \text{ in}) = 49.279 \text{ kip}$$

$$M(42 \text{ in}, 92 \text{ in}) = 699.79 \text{ ft} \cdot \text{kip}$$

$$M_{\text{maxmomentfourtrucks}} := 700 \text{ (ft} \cdot \text{kip)}$$

$$V_{\text{moment}} := R_b(42 \text{ in}, 92 \text{ in}) = ? \text{ kip}$$

Bridge #5298 Windham ME
Route Windham Center Road
Crossing Pleasant River

Prepared By: Mahmood J. Abraheemi
Checked By: SMT
Date : 201611-03

Section Properties and Distribution Factors

| Girder Section Properties | | | | | |
|---------------------------|-------|-----------|---------------|--------------|------|
| component | width | thickness | modular ratio | transf. area | y |
| Slab | 69 | 9 | 10.00 | 62.1 | 34.8 |

Moment Distribution factors (Interior Girders)

VHB report

$$DF_{onelane} := 0.444$$

$$DF_{twolanes} := 0.574$$

Calculated Distribution factors based on actual measurements

$$DF_{onelane} = 0.404$$

$$DF_{twolanes} := 0.523$$

$$DF_{shear} := 0.652$$

Section Properties: Fully composite

$$y' := 28.1 \text{ in} \quad I := 13116 \cdot \text{in}^4 \quad S_{bot} := 466.1 \cdot \text{in}^3 \quad Q_{slab} := 416.5 \cdot \text{in}^3$$

Bridge #5298 Windham ME
Route Windham Center Road
Crossing Pleasant River

Prepared By: Mahmood J. Abraheemi
Checked By: SMT
Date : 201611-03

Maximum Live Load Moment calculation in each load case for the interior girder

Two trucks in two lanes

$$Mt_{0.5dtwo\ trucks} := DF_{two\ lanes} \cdot M_{0.5dtwo\ trucks} = 73 \text{ ft} \cdot \text{kip}$$

$$Mt_{1.0dtwo\ trucks} := DF_{two\ lanes} \cdot M_{1.0dtwo\ trucks} = 93 \text{ ft} \cdot \text{kip}$$

$$Mt_{1.5dtwo\ trucks} := DF_{two\ lanes} \cdot M_{1.5dtwo\ trucks} = 112 \text{ ft} \cdot \text{kip}$$

$$Mt_{2.0dtwo\ trucks} := DF_{two\ lanes} \cdot M_{2.0dtwo\ trucks} = 130 \text{ ft} \cdot \text{kip}$$

$$Mt_{max\ moment\ two\ trucks} := DF_{two\ lanes} \cdot M_{max\ moment\ two\ trucks} = 253 \text{ ft} \cdot \text{kip}$$

Four trucks in two lanes

$$Mt_{2.0d\ four\ trucks} := DF_{two\ lanes} \cdot M_{2.0d\ four\ trucks}$$

$$Mt_{3.0d\ four\ trucks} := DF_{two\ lanes} \cdot M_{3.0d\ four\ trucks}$$

$$Mt_{max\ moment\ four\ trucks} := DF_{two\ lanes} \cdot M_{max\ moment\ four\ trucks} = 366 \text{ ft} \cdot \text{kip}$$

Actual section Response

| Four Trucks | | | | | |
|-------------|--------------|------------|----------|----------|----------|
| Position | LV4521 | B3076 | B3075 | B3811 | LV4523 |
| Max Mom | -0.00208445 | -78.423732 | -26.3542 | 44.29619 | -4E-05 |
| 4.0d | -0.00323712 | -74.50521 | -16.4794 | 62.01858 | -1E-05 |
| 3.0d | -0.003866164 | -69.951864 | -12.9873 | 67.6924 | 5.82E-06 |
| 2.0d | -0.004086198 | -60.897547 | -9.78585 | 72.16478 | 1.94E-05 |

Bridge #5298 Windham ME
Route Windham Center Road
Crossing Pleasant River

Prepared By: Mahmood J. Abraheemi
Checked By: SMT
Date : 201611-03

Four Trucks

| | | |
|-------------------------------------|---------------------------------------|-----------------|
| $y'_{2.0d} := 29.4 \text{ in}$ | $S_{2.0d} := 466.1 \text{ in}^3$ | Fully composite |
| $y'_{3.0d} := 29.4 \text{ in}$ | $S_{3.0d} := 466.1 \text{ in}^3$ | Fully composite |
| $y'_{maxmoment} := 30.2 \text{ in}$ | $S_{maxmoment} := 466.1 \text{ in}^3$ | Fully composite |

$$M_{fourtrucks} := \begin{bmatrix} Mt_{2.0dfourtrucks} \\ Mt_{3.0dfourtrucks} \\ Mt_{maxmomentfourtrucks} \end{bmatrix}; \quad y_{fourtrucks} := \begin{bmatrix} y'_{2.0d} \\ y'_{3.0d} \\ y'_{maxmoment} \end{bmatrix}; \quad S_{fourtrucks} := \begin{bmatrix} S_{2.0d} \\ S_{3.0d} \\ S_{maxmoment} \end{bmatrix}$$

Strain based on actual response

$$\epsilon_{computed} := \begin{bmatrix} \frac{Mt_{2.0dfourtrucks}}{S_{2.0d} \cdot 29000 \text{ ksi}} \\ \frac{Mt_{3.0dfourtrucks}}{S_{3.0d} \cdot 29000 \text{ ksi}} \\ \frac{Mt_{maxmomentfourtrucks}}{S_{maxmoment} \cdot 29000 \text{ ksi}} \end{bmatrix} \cdot 10^6 = \begin{bmatrix} 297.097 \\ 317.338 \\ 325.015 \end{bmatrix}$$

$$\frac{Mt_{maxmomentfourtrucks}}{S_{maxmoment} \cdot 29000 \text{ ksi}} \cdot 10^6 = 325.015$$

$Kb := 0.5$

$$Ka := \frac{325.01}{154.9} - 1 = 1.098$$

$K := 1 + Kb \cdot Ka = 1.55$

Bridge #5298 Windham ME
Route Windham Center Road
Crossing Pleasant River

Prepared By: Mahmood J. Abraheemi
Checked By: SMT
Date : 201611-03

Two Trucks

$$\begin{array}{ll}
 y'_{0.5d} := 30.2 \text{ in} & S_{0.5d} := 466.1 \text{ in}^3 \\
 y'_{1.0d} := 30.2 \text{ in} & S_{1.0d} := 466.1 \text{ in}^3 \\
 y'_{2.0d} := 30.7 \text{ in} & S_{2.0d} := 466.1 \text{ in}^3 \\
 y'_{3.0d} := 30.2 \text{ in} & S_{3.0d} := 466.1 \text{ in}^3 \\
 y'_{\text{maxmoment}} := 31.1 \text{ in} & S_{\text{maxmoment}} := 466.1 \text{ in}^3
 \end{array}$$

$$M_{\text{twotrucks}} := \begin{bmatrix} Mt_{0.5dtwotrucks} \\ Mt_{1.0dtwotrucks} \\ Mt_{2.0dtwotrucks} \\ Mt_{\text{maxmomenttwotrucks}} \end{bmatrix} \quad y_{\text{twotrucks}} := \begin{bmatrix} y'_{0.5d} \\ y'_{1.0d} \\ y'_{2.0d} \\ y'_{\text{maxmoment}} \end{bmatrix} \quad S_{\text{twotrucks1}} := \begin{bmatrix} S_{0.5d} \\ S_{1.0d} \\ S_{2.0d} \\ S_{\text{maxmoment}} \end{bmatrix}$$

Strain based on actual response

$$\epsilon_{\text{computed}} := \begin{bmatrix} \frac{Mt_{0.5dtwotrucks}}{S_{0.5d} \cdot 29000 \text{ ksi}} \\ \frac{Mt_{1.0dtwotrucks}}{S_{1.0d} \cdot 29000 \text{ ksi}} \\ \frac{Mt_{2.0dtwotrucks}}{S_{2.0d} \cdot 29000 \text{ ksi}} \\ \frac{Mt_{\text{maxmomenttwotrucks}}}{S_{\text{maxmoment}} \cdot 29000 \text{ ksi}} \end{bmatrix} \cdot 10^6 = \begin{bmatrix} 64.539 \\ 82.647 \\ 115.009 \\ 224.655 \end{bmatrix}$$

$$\frac{Mt_{\text{maxmomenttwotrucks}}}{S_{\text{maxmoment}} \cdot 29000 \text{ ksi}} \cdot 10^6 = 224.655$$

$$Kb := 0.5$$

$$Ka := \frac{224.65}{108.15} - 1 = 1.077$$

$K := 1 + Kb \cdot Ka = 1.54$

Bridge #5298 Windham ME
Route Windham Center Road
Crossing Pleasant River

Prepared By: Mahmood J. Abraheemi
Checked By: SMT
Date : 201611-03

Shear Flow Calculation

Four Trucks maximum moment

maximum shearforce $V_{moment} = 49.279 \text{ kip}$

$$\tau := \frac{V_{moment} \cdot DF_{shear} \cdot Q_{slab}}{I \cdot b_f} = 97.4 \text{ psi} \quad \text{Fully composite}$$

Four Trucks maximum shear

maximum shearforce $V_{shear} = 59.738 \text{ kip}$

$$\tau := \frac{V_{shear} \cdot DF_{shear} \cdot Q_{slab}}{I \cdot b_f} = 118 \text{ psi} \quad \text{Fully composite}$$

Two Trucks maximum shear

maximum shearforce $V_{shear2t} = 38.204 \text{ kip}$

$$\tau := \frac{V_{shear2t} \cdot DF_{shear} \cdot Q_{slab}}{I \cdot b_f} = 75.475 \text{ psi} \quad \text{Fully composite}$$

Bridge #5298 Windham ME
Route Windham Center Road
Crossing Pleasant River

Prepared By: Mahmood J. Abraheemi
Checked By: SMT
Date : 201611-03

Calculation of Actual Distribution Factors

| | | | | |
|---------------------|-------------|-----------------|--|--|
| Moment of Inertia = | 23760.663 | in ⁴ | | |
| S_bottom = | 706.8 | in ³ | | |
| Mmidspac | 210.2980214 | | | |
| Mt | 210.2980214 | | | |

Four Trucks maxmoment DF analysis

Total_moment := 727 ft·kip

Girder Actual_DF AASHTO_DF

| <i>Girder</i> | <i>Actual_DF</i> | <i>AASHTO_DF</i> |
|---------------|------------------|------------------|
| "girder1" | 0.518 | 0.431 |
| "girder2" | 0.285 | 0.523 |
| "girder3" | 0.480 | 0.523 |
| "girder4" | 0.136 | 0.523 |
| "girder5" | 0.579 | 0.431 |

Two Trucks max moment DF analysis

Total_moment := 519 ft·kip

Girder Actual_DF AASHTO_DF

| <i>Girder</i> | <i>Actual_DF</i> | <i>AASHTO_DF</i> |
|---------------|------------------|------------------|
| "girder1" | 0.479 | 0.431 |
| "girder2" | 0.309 | 0.523 |
| "girder3" | 0.470 | 0.523 |
| "girder4" | 0.155 | 0.523 |
| "girder5" | 0.588 | 0.431 |

Bridge #5298 Windham ME
Route Windham Center Road
Crossing Pleasant River

Prepared By: Mahmood J. Abraheemi
Checked By: SMT
Date : 201611-03

$$DF_{external} := 0.431$$

Four trucks maximum moment

$$M_{maxmomentfourtrucks} = 700 \text{ ft} \cdot \text{kip}$$

$$S_{4trucksexternal} := 617.6 \text{ in}^3$$

$$measured_strain_4 := 125.97$$

$$\epsilon_{4external} := \frac{M_{maxmomentfourtrucks} \cdot DF_{external}}{S_{4trucksexternal} \cdot 29000 \cdot \text{ksi}} \cdot 10^6 = 202.14$$

$$K_b := 0.5$$

$$K_{a4} := \frac{\epsilon_{4external}}{measured_strain_4} - 1$$

$$K_4 := 1 + K_b \cdot K_{a4} = 1.302$$

Two trucks maximum moment

$$M_{maxmomenttwo trucks} = 483.85 \text{ ft} \cdot \text{kip}$$

$$S_{2trucksexternal} := 640.8 \text{ in}^3$$

$$measured_strain_2 := 80.13$$

$$\epsilon_{2external} := \frac{M_{maxmomenttwo trucks} \cdot DF_{external}}{S_{2trucksexternal} \cdot 29000 \cdot \text{ksi}} \cdot 10^6 = 134.663$$

$$K_{a2} := \frac{\epsilon_{2external}}{measured_strain_2} - 1 = 0.681$$

$$K_2 := 1 + K_b \cdot K_{a2} = 1.34$$

A.6 Buckfield No. 5452

A.6.1 Input Data, Experimental Configuration, and Experimental Data Collected

Table 15: Buckfield No. 5452 Bridge Input Data, Experimental Configuration, and Experimental Data Collected

| <i>File Contents</i> | <i>File Name</i> | <i>File Type</i> |
|--------------------------------------|--------------------------------|------------------|
| Bridge Geometry and Materials | Br5452_Geom.csv | CSV Format |
| Exterior Section Data | Br5452_Ext.csv | CSV Format |
| Interior Section Data | Br5452_Int.csv | CSV Format |
| Sensors | Br5452_Sensors.csv | CSV Format |
| Sensor Layout | Br5452_SensorLayout.csv | CSV Format |
| Truck Weight and Dimensions | Br5452_SensorLayout.mat | MATLAB Data File |
| Truck Starting Position | TestStart.m > Br5452_TestStart | MATLAB Data File |
| Truck Position Measurements | Br5452_Tk_Positions.mat | MATLAB Data File |
| Sensor Data | Br5452_1Tks_1Lns_1.xlsx | Microsoft Excel |
| | Br5452_2Tks_1Lns_1.xlsx | Microsoft Excel |
| | Br5452_2Tks_2Lns_1.xlsx | Microsoft Excel |
| | Br5452_4Tks_2Lns_1.xlsx | Microsoft Excel |
| Data Time Indices | Br5452_1Tks_1Lns_1_Time.csv | CSV Format |
| | Br5452_2Tks_1Lns_1_Time.csv | CSV Format |
| | Br5452_2Tks_1Lns_1_Time.csv | CSV Format |
| | Br5452_4Tks_2Lns_1_Time.csv | CSV Format |

A.6.2 Instrumentation




Figure 58: Buckfield No. 5452 sensor layout

A.6.3 Loading




Figure 59: Buckfield No. 5452 Truck T01-129 loading




Figure 60: Buckfield No. 5452 Truck T01-220 loading




Figure 61: Buckfield No. 5452 Truck T01-246 loading




Figure 62: Buckfield No. 5452 Truck T01-273 loading

A.6.4 Representative Data Plots




Figure 63: Buckfield No. 5425 - 4 trucks 2 lanes test 1 strains




Figure 64: Buckfield No. 5425 - 4 trucks 2 lanes test 1 shear slip

A.6.5 Rating Factor Calculations

Figure 65: Buckfield No. 5452 Calculations

Bridge#5452Buckfield ME
North Buckfield Road
Over NEZNSCOT River

Prepared By: Mahmood J. Abraheemi
Checked By: SMT
Date : 201611-14

| Year of Construction | Compressive Strength, f'_c , ksi |
|----------------------|------------------------------------|
| Prior to 1959 | 2.5 |
| 1959 and Later | 3.0 |

$f'_c := 2.5 \text{ ksi}$

| Year of Construction | Minimum Yield Point or Minimum Yield Strength, F_y , ksi | Minimum Tensile Strength, F_u , ksi |
|----------------------|--|---------------------------------------|
| Prior to 1905 | 26 | 52 |
| 1905 to 1936 | 30 | 60 |
| 1936 to 1963 | 33 | 66 |
| After 1963 | 36 | 66 |

$f_y := 33 \text{ ksi}$

$\gamma_c := 150 \text{ pcf}$ $\gamma_s := 490 \text{ pcf}$

$\gamma_{c_mod} := 145 \text{ pcf}$ $E_s := 29000 \text{ ksi}$

LRFD Design
Eq. 54.2.4-1

$$E_c := 33000 \cdot \gamma_{c_mod}^{1.5} \cdot \sqrt{f'_c}$$

$E_c := 2875.9 \text{ ksi}$

Bridge Length $L := 42.5 \text{ ft}$

Spacing between Girders $S := 5.75 \text{ ft}$


Deck thickness $t_s := 6 \text{ in}$

Wearing surface thickness $t_{w.s.} := 6 \text{ in}$ $\gamma_{w.s.} := 152 \text{ pcf}$ VHB Report

Bridge#5452BuckfieldME
North Buckfield Road
Over NEZNSCOT River

Prepared By: Mahmood J. Abraheemi
Checked By: SMT
Date : 201611-14

Trucks Weight & Dimensions



Bridge#5452BuckfieldME
North Buckfield Road
Over NEZNSCOT River

Prepared By: Mahmood J. Abraheemi
Checked By: SMT
Date : 201611-14

Loads on the Interior Girder

DeadLoad:

$M_{DC} := 156.47 \text{ ft} \cdot \text{kip}$ VHB report

$M_{DW} := 75.5 \text{ ft} \cdot \text{kip}$ VHB report

$d := 27.09 \text{ in}$ $b_f := 10.015 \text{ in}$

Live Load :

We use the average truck weight and dimensions in this calculation

| | Trucks Weight | | | |
|------------------|---------------|---------|---------|---------|
| | T01-220 | T01-129 | T01-248 | T01-273 |
| Front wheel | 13400 | 14500 | 14350 | 14700 |
| front rear wheel | 18750 | 21350 | 19400 | 19300 |
| Last Wheel | 18150 | 19700 | 18200 | 18800 |

Bridge#5452BuckfieldME
 North Buckfield Road
 Over NEZNSCOT River

Prepared By: Mahmood J. Abraheemi
 Checked By: SMT
 Date : 201611-14


Live Load Analysis

Two trucks in two lanes

$p3 := 18.5 \text{ kip}$ $p2 := 19.4 \text{ kip}$ $p1 := 14.5 \text{ kip}$ page #3 average axle weight

$d2$: distance between rear wheels $d2 := 5 \text{ ft}$
 $d3$ distance between front wheel and front rear wheel $d3 := 16 \text{ ft}$

Trucks at shear locations:



$$R_b(d1) := \frac{p2 \cdot d1 + p3 \cdot (d1 + d2)}{L}$$

$$M(d1) := R_b(d1) \cdot (L - (d1 + d2))$$

At 0.5 d from support

$$d1 := 0.5 \cdot d$$

$$M(d1) = 115.772 \text{ ft} \cdot \text{kip}$$

$$M_{0.5dtwotrucks} := M(d1) = 115.772 \text{ kip} \cdot \text{ft}$$

At 1.0 d from support

$$d1 := 1.0 \cdot d$$

$$M(d1) = 147.653 \text{ ft} \cdot \text{kip}$$

$$M_{1.0dtwotrucks} := M(d1) = 147.653 \text{ kip} \cdot \text{ft}$$

At 1.5 d from support

$$d1 := 1.5 \cdot d$$

$$M(d1) = 177.262 \text{ ft} \cdot \text{kip}$$

$$M_{1.5dtwotrucks} := M(d1) = 177.262 \text{ kip} \cdot \text{ft}$$

At 2.0 d from support

$$d1 := 2.0 \cdot d$$

$$M(d1) = 204.599 \text{ ft} \cdot \text{kip}$$


$$M_{2.0dtwotrucks} := M(d1) = 204.599 \text{ kip} \cdot \text{ft}$$

Bridge#5452BuckfieldME
North Buckfield Road
Over NEZNSCOT River

Prepared By: Mahmood J. Abraheemi
Checked By: SMT
Date : 201611-14

Trucks at Maximum Moment location:

d1 distance between front wheel and the support



$$R_b(d1) := \frac{(p1 \cdot d1) + (p2 \cdot (d1 + d3)) + (p3 \cdot (d1 + d2 + d3))}{L}$$

$$M(d1) := R_b(d1) \cdot (L - (d1 + d3)) - p3 \cdot (d2)$$

$$R_b(108 \text{ in}) = 27.541 \text{ kip}$$

$$M(108 \text{ in}) = 389.471 \text{ ft} \cdot \text{kip}$$


$$M_{\text{maxmomenttwo trucks}} := M(108 \text{ in}) = 389.471 \text{ ft} \cdot \text{kip}$$

Bridge#5452BuckfieldME
North Buckfield Road
Over NEZNSCOT River

Prepared By: Mahmood J. Abraheemi
Checked By: SMT
Date : 201611-14

Trucks at Maximum Moment location:

d1 distance between front wheel and the support ; d4 distance between trucks



At Maximum Moment:

$$R_b(d1, d4) := \frac{p1 \cdot d1 + p2 \cdot (d1 + d3) + p3 \cdot (d1 + d3 + d2) + p3 \cdot (d1 + d3 + d2 + d4) + p2 \cdot (d1 + d3 + 2 \cdot d2 + d4)}{L}$$

$$M(d1, d4) := (R_b(d1, d4) \cdot (L - (d1 + d3 + d2))) - (p2 \cdot (d2 + d4)) - (p3 \cdot d4)$$

$$R_b(7 \text{ in}, 85 \text{ in}) = 44.694 \text{ kip}$$

$$M(7 \text{ in}, 85 \text{ in}) = 596.541 \text{ ft} \cdot \text{kip}$$

$$M_{\text{maxmomentfourtrucks}} := 596.541 \text{ (ft} \cdot \text{kip)}$$

$$V_{\text{moment}} := R_b(7 \text{ in}, 85 \text{ in}) = 44.694 \text{ kip}$$

Bridge#5452BuckfieldME
North Buckfield Road
Over NEZNSCOT River

Prepared By: Mahmood J. Abraheemi
Checked By: SMT
Date : 201611-14

Section Properties and Distribution Factors

| Interior Girder Section Properties | | | | | |
|------------------------------------|-------|-----------|---------------|--------------|------|
| component | width | thickness | modular ratio | transf. area | y |
| Slab | 69 | 9 | 10.00 | 62.1 | 33.6 |

Moment Distribution factors (Interior Girders)

VHB report

$$DF_{onelane} = 0.403$$

$$DF_{twolanes} = 0.518$$

Calculated Distribution factors based on actual measurements

$$DF_{onelane} := 0.413$$

$$DF_{twolanes} := 0.53$$

$$DF_{shear} := 0.652$$

Section Properties: Fully composite

$$y' := 27.2 \text{ in} \quad I := 12078 \cdot \text{in}^4 \quad S_{bot} := 444.4 \cdot \text{in}^3 \quad Q_{slab} := 405.2 \cdot \text{in}^3$$

Bridge#5452BuckfieldME
North Buckfield Road
Over NEZNSCOT River

Prepared By: Mahmood J. Abraheemi
Checked By: SMT
Date : 201611-14

Maximum Live Load Moment calculation in each loadcase for the interior girder

Four trucks in two lanes

$$M_{t_{0.5fourtrucks}} := DF_{twolanes} \cdot M_{0.5fourtrucks} = 67.572 \text{ ft} \cdot \text{kip}$$

$$M_{t_{1.0fourtrucks}} := DF_{twolanes} \cdot M_{1.0fourtrucks} = 90.544 \text{ ft} \cdot \text{kip}$$

$$M_{t_{1.5fourtrucks}} := DF_{twolanes} \cdot M_{1.5fourtrucks} = 113.516 \text{ ft} \cdot \text{kip}$$

$$M_{t_{2.0fourtrucks}} := DF_{twolanes} \cdot M_{2.0fourtrucks} = 136.489 \text{ ft} \cdot \text{kip}$$

$$M_{t_{maxmomentfourtrucks}} := DF_{twolanes} \cdot M_{maxmomentfourtrucks} = 309 \text{ ft} \cdot \text{kip}$$

Actual section Response

| | | | |
|-------------------|---------------------|-------------|----------------|
| | y_bar = | 17.8 | in from bottom |
| | Moment of Inertia = | 5726.910814 | in^4 |
| | S_bottom = | 321.0 | in^3 |
| | Q_slab = | 127.7 | in^3 |
| Max moment | | | |

Bridge#5452BuckfieldME
North Buckfield Road
Over NEZNSCOT River

Prepared By: Mahmood J. Abraheemi
Checked By: SMT
Date : 201611-14

Four Trucks

Look at the critical girder the interior girder

| | | |
|-------------------------------------|---------------------------------------|-------------------|
| $y'_{0.5d} := 21.2 \text{ in}$ | $S_{0.5d} := 374.7 \text{ in}^3$ | Partial composite |
| $y'_{1.0d} := 17.3 \text{ in}$ | $S_{1.0d} := 310.6 \text{ in}^3$ | Partial composite |
| $y'_{1.5d} := 20 \text{ in}$ | $S_{1.5d} := 357.7 \text{ in}^3$ | Partial composite |
| $y'_{2.0d} := 17.8 \text{ in}$ | $S_{2.0d} := 321 \text{ in}^3$ | Partial composite |
| $y'_{maxmoment} := 18.4 \text{ in}$ | $S_{maxmoment} := 331.5 \text{ in}^3$ | Partial composite |

$$M_{fourtrucks} := \begin{bmatrix} Mt_{0.5fourtrucks} \\ Mt_{1.0fourtrucks} \\ Mt_{1.5fourtrucks} \\ Mt_{2.0fourtrucks} \\ Mt_{maxmomentfourtrucks} \end{bmatrix}; \quad y_{fourtrucks} := \begin{bmatrix} y'_{0.5d} \\ y'_{1.0d} \\ y'_{1.5d} \\ y'_{2.0d} \\ y'_{maxmoment} \end{bmatrix}; \quad S_{fourtrucks} := \begin{bmatrix} S_{0.5d} \\ S_{1.0d} \\ S_{1.5d} \\ S_{2.0d} \\ S_{maxmoment} \end{bmatrix}$$

Strain based on actual response

$$\epsilon_{computed} := \begin{bmatrix} \frac{Mt_{0.5fourtrucks}}{S_{0.5d} \cdot 29000 \text{ ksi}} \\ \frac{Mt_{1.0fourtrucks}}{S_{1.0d} \cdot 29000 \text{ ksi}} \\ \frac{Mt_{1.5fourtrucks}}{S_{1.5d} \cdot 29000 \text{ ksi}} \\ \frac{Mt_{2.0fourtrucks}}{S_{2.0d} \cdot 29000 \text{ ksi}} \\ \frac{Mt_{maxmomentfourtrucks}}{S_{maxmoment} \cdot 29000 \text{ ksi}} \end{bmatrix} \cdot 10^6 = \begin{bmatrix} 74.622 \\ 120.626 \\ 131.318 \\ 175.944 \\ 394.653 \end{bmatrix}$$

$$\frac{Mt_{maxmomentfourtrucks}}{S_{maxmoment} \cdot 29000 \text{ ksi}} \cdot 10^6 = 394.653$$

$$Kb := 0.5$$

$$Ka := \frac{394.65}{166.85} - 1 = 1.365$$

$K := 1 + Kb \cdot Ka = 1.68$

$$Kb := 1.0$$

$$Ka := \frac{394.65}{301.33} - 1 = ?$$

$$K := 1 + Kb \cdot Ka = ?$$

Bridge#5452BuckfieldME
North Buckfield Road
Over NEZNSCOT River

Prepared By: Mahmood J. Abraheemi
Checked By: SMT
Date : 201611-14

Shear Flow Calculation

Four Trucks maximum shear

maximum shearforce $V_{shear} = 38.4 \text{ kip}$ $Q_{shear} := 127.7 \cdot \text{in}^3$ $I_{shear} := 5727 \text{ in}^4$

$$\tau := \frac{V_{shear} \cdot DF_{shear} \cdot Q_{shear}}{I_{shear} \cdot b_f} = 55.743 \text{ psi} \quad \text{Actual shear flow}$$

$$\tau := \frac{V_{shear} \cdot DF_{shear} \cdot Q_{slab}}{I \cdot b_f} = 83.87 \text{ psi} \quad \text{Shear flow if fully composite}$$

Four Trucks maximum moment

maximum shearforce $V_{moment} := 44.69 \text{ kip}$ $Q_{moment} := 144.9 \text{ in}^3$ $I_{moment} := 6107 \cdot \text{in}^4$

$$\tau := \frac{V_{moment} \cdot DF_{shear} \cdot Q_{moment}}{I_{moment} \cdot b_f} = 69.032 \text{ psi} \quad \text{Actual shear flow}$$

$$\tau := \frac{V_{moment} \cdot DF_{shear} \cdot Q_{slab}}{I \cdot b_f} = 97.607 \text{ psi} \quad \text{Shear flow if fully composite}$$

Bridge#5452BuckfieldME
North Buckfield Road
Over NEZNSCOT River

Prepared By: Mahmood J. Abraheemi
Checked By: SMT
Date : 201611-14

$$DF_{external} := 0.44$$

Four trucks maximum moment

$$M_{max\ moment\ four\ trucks} = 596.541 \text{ ft} \cdot \text{kip}$$

$$S_{A\ truck\ external} := 294.2 \text{ in}^3$$

$$measured_strain_4 := 186.48$$

$$\epsilon_{4\ external} := \frac{M_{max\ moment\ four\ trucks} \cdot DF_{external}}{S_{A\ truck\ external} \cdot 29000 \cdot \text{ksi}} \cdot 10^6 = 369.176$$

$$K_b := 0.5$$

$$K_{a4} := \frac{\epsilon_{4\ external}}{measured_strain_4} - 1$$

$$K_4 := 1 + K_b \cdot K_{a4} = 1.49$$