

SANFORD DOWNTOWN RAISE GRANT IMPROVEMENT PROJECTS

Ernie Martin MaineDOT Senior Project Manager


Ethan Flynn, P.E. VHB Project Engineer





PROJECT COMPONENTS

- Main Street (Downtown)
- Cottage Street (Route 202)
- Mousam Promenade (William Oscar Emery Drive, Riverside Ave.)
- Park and Ride





MEETING AGENDA





Sanford Downtown, Raise Grant Improvement Project

Final Public Meeting Wednesday, September 11th, 2024 6:00pm-8:30 pm City Council Chambers, 919 Main Street, Sanford, ME 04037

Agenda

- 1) Welcome, Steve Buck, Sanford City Manager
- 2) Introductions and Project Descriptions, Ernie Martin, MaineDOT Project Manager
- 3) Project Improvements, Design Overviews
 - Sanford Downtown- VHB
 - Cottage Street-VHB
 - William Oscar Emery Drive Trail- Gorrill Palmer
 - Park & Ride Facility- Gorrill Palmer
- 4) Right of Way Presentation, Brian Sanderson, MaineDOT
- 5) Project Timeline & Communications, Ernie Martin, MaineDOT
 - Project Schedule
 - Outstanding items
- 6) Questions/answers/thoughts:
 - Ground rules- in council chambers please raise your hand, when called upon, please stand up and state your name and who you are representing. If you're attending on Zoom raise your hand in the chat and we will call upon you. One person at a time.



INTRODUCTIONS OF PROJECT DESIGN TEAMS & AGENDA

City of Sanford

- ➤ Matt Hill, City Engineer
- Matt Provencher, Assistant City Engineer


VHB

- ➤Tony Grande,
- **≻**Ethan Flynn

Gorrill-Palmer

- ➤ Don Ettinger
- ► Jared Winchenbach


LOCATION MAP







DOWNTOWN IMPROVEMENTS OVERVIEW







HIGHWAY OVERVIEW: EMERY ST - ROBERTS ST

-2.0%

NORMAL





5' LOAM AND SEED

AS DIRECTED (TYP.)

-5" LOAM AND SEED

AS DIRECTED (TYP.)

VARIES



(TYP.)

10° AGGREGATE SUBBASE COURSE - GRAVEL (TYP.) VARIES

AGGREGATE SUBBASE

COURSE - GRAVEL (TYP.)










HIGHWAY OVERVIEW: ROBERT ST – ROUTE 202


















HIGHWAY OVERVIEW: WASINGTON ST & RIVER ST












N


HIGHWAY OVERVIEW: SCHOOL ST







INTERSECTION OVERVIEW: MAIN/WASHINGTON/SCHOOL








INTERSECTION OVERVIEW: WASHINGTON/RIVER/HIGH








BRIDGE OVERVIEW: MOUSAM RIVER BRIDGES







COTTAGE STREET RECONSTRUCTION OVERVIEW








HIGHWAY OVERVIEW: RIVER ST – NORTH AVE










HIGHWAY OVERVIEW: NORTH AVE – PROJECT LIMITS









INTERSECTION OVERVIEW: WINTER/RIVER/COTTAGE










INTERSECTION OVERVIEW: BROOK/COTTAGE











DRAINAGE IMPROVEMENTS OVERVIEW:





CONSTRUCTION PHASING

- Step 1 Cottage St. (Green)
 - 1-way EB from River from River St to June St
 - Will require a WB detour
 - May require short-term closures for utilities (~1 day)
- Step 2 Downtown Improvements (Blue)
 - Until bump-outs are constructed shifted 2-way traffic is possible with loss of parking adjacent to the work area.
 - Evaluating 1-way roadways with detours
- •Step 3 Riverside Ave. & William Oscar Emery Dr. (Red)
 - Will be constructed with alternating 1-way closure
- Park and Ride (Yellow)
 - Has a flexible schedule
 - Will be done concurrently with one of the previous steps





WIN 25335.00







Public Meeting September 11, 2024


Matthew E. Hill, P.E. — Sanford,
Director of Public Works/City Engineer

Ernie Martin – Maine DOT, Project Manager

Jared S. Winchenbach, P.E. — Gorrill Palmer, Project Manager

SANFORD, RIVERSIDE AVE & WILLIAM OSCAR EMERY DRIVE





This is an aerial view of Sanford Maine. The project includes Riverside Ave (red section) and William Oscar Emery Drive (green section). Both are located near Number One Pond.

PROJECT LOCATION
















EXISTING CONDITIONS






- Roadway reconstruction.
- New sidewalks & multi-use pathway.
- New curbing & onstreet parking.
- Drainage improvements.
- Driveway connections.
- Intersection improvements.

WASHINGTON STREET TO WINTER STREET

RIVERSIDE AVE IMPROVEMENTS





- Roadway reconstruction.
- New sidewalks & multi-use pathway.
- New curbing.
- Drainage improvements.
- Driveway connections.
- Intersection improvements.

WINTER STREET TO PLEASANT AVE

RIVERSIDE AVE IMPROVEMENTS






- Roadway reconstruction.
- New sidewalks & multi-use pathway.
- New curbing & onstreet parking.
- Drainage improvements.
- Driveway connections.
- Intersection improvements.

PLEASANT AVE TO SUMMER STREET






- Roadway reconstruction.
- New sidewalks & multi-use pathway.
- New curbing & onstreet parking.
- Drainage improvements.
- Driveway connections.
- Intersection improvements.

SUMMER STREET TO GOWEN PARK DRIVE






- Roadway rehabilitation.
- New sidewalks & multi-use pathway.
- New curbing & onstreet parking.
- Drainage improvements.
- Large culvert replacement.
- Intersection improvements.

GOWEN PARK DRIVE TO ARMORY






- Roadway rehabilitation.
- New sidewalks & multi-use pathway.
- New curbing & onstreet parking.
- Drainage improvements.
- Driveway connections.
- Intersection improvements.

ARMORY TO RIVER STREET





-PROFILE GRADE


-2.0%*

** CONCRETE SIDEWALKS SHALL

4" HOT MIX ASPHALT (SEE SP 403)


-18" AGGREGATE SUBBASE COURSE - GRAVEL TYPE "D"

FULL DEPTH RECONSTRUCTION



TYPICAL SECTIONS

- Reconstruction & rehabilitation.
- Pavement & gravel depths.
- Cross slopes.
- Cross section widths.
- Material types.



(SEE SP 403)

- 12" AGGREGATE SUBBASE COURSE - GRAVEL TYPE "

RIVERSIDE & WILLIAM OSCAR **EMERY**



2" HOT MIX ASPHALT (SEE SP 403) WITH 12" AGGREGATE SUBBASE COURSE - GRAVEL TYPE "D"

4 FIBER REINFORCED CONCRETE SIDEWALK (SEE FIBER REINFORCED CONCRETE SIDEWALK DETAIL)** WITH 10 AGGREGATE SUBBASE

COURSE - GRAVEL TYPE "D"





MATCH LINE LEGO PERMANENTE DE SI AND PERMANENT DE SI AND PERMANEN

LANDSCAPING DESIGN

- Material types.
- Planting locations.
- Amenities.



RIVERSIDE & WILLIAM OSCAR EMERY



WIN 25335.00







Public Meeting September 11, 2024

Matthew E. Hill, P.E. — Sanford,
Director of Public Works/City Engineer

Ernie Martin – Maine DOT, Project Manager


Jared S. Winchenbach, P.E. — Gorrill Palmer, Project Manager

SANFORD, RIVERSIDE AVE & WILLIAM OSCAR EMERY DRIVE



WIN 26306.00







Public Meeting September 11, 2024

Matthew E. Hill, P.E. — Sanford,
Director of Public Works/City Engineer

Ernie Martin – Maine DOT, Project Manager

Jared S. Winchenbach, P.E. — Gorrill Palmer, Project Manager

SANFORD, EMERSON STREET PARKING FACILITY





This is an aerial view of Sanford Maine. The project is located on Emerson Street near Main Street and the Cumberland Farms gas station & store.

PROJECT LOCATION
















EXISTING CONDITIONS






DESCRIPTION OF WORK

- Paved parking lot with 85 parking spaces.
- New sidewalks in the facility and along Emerson Street.
- Access from Emerson St& Cumberland Farms.
- Transit stop with bus shelter.
- Drainage improvements.
- Lighting, landscaping & fencing improvements.






DESCRIPTION OF WORK

- Proposed grading plan.
- Proposed drainage improvements.






TYPICAL SECTIONS

- Pavement & gravel depths.
- Cross slopes.
- Cross section widths.
- Material types.







LANDSCAPING DESIGN

- Material types.
- Planting locations.
- Fencing requirements.







LIGHTING DESIGN


- Pole locations.
- Material types.
- Cutoff fixtures.





WIN 26306.00







Public Meeting September 11, 2024

Matthew E. Hill, P.E. — Sanford,
Director of Public Works/City Engineer

Ernie Martin – Maine DOT, Project Manager

Jared S. Winchenbach, P.E. — Gorrill Palmer, Project Manager

SANFORD, EMERSON STREET PARKING FACILITY



PROJECT TIMELINE & COMMUNICATIONS

- Public Meeting Tonight 9/11/24
- Right of way process has begun
 - Final Mapping
 - Appraisals
 - Negotiations
- Construction Phasing Public Meeting, Spring/Summer 2025'
- Project Plans, Specs & Estimate- November 2025'
- Project advertise- December 25'/January 2026'
- Bid Openings- January 2026'
- Project award- February 2026
- Construction Begin- March/April 2026
- Construction Complete- Fall 2028/Spring 2029



PROJECT CONSTRUCTION FUNDING

Federal RAISE Grant Funding Sources:

Federal Funding, State Funding, City of Sanford Funding and some Federal Flexible Funding for total project cost of \$31,000,000.



QUESTIONS/ANSWERS/THOUGHTS

Ground rules- in council chambers please raise your hand, when called upon, please stand up and state your name and who you are representing. If you're attending on Zoom raise your hand in the chat and we will call upon you. One person at a time.

