

SNOW FENCE NOTES

1. Chain-Link fence shall conform to Section 710.03 and Section 607. The size of wire mesh (fabric) shall be 1" by 1".

2. Post and rail pipe shall be hot-dip galvanized steel. All pipe shall be schedule 40, standard weight. Nominal pipe sizes are shown.

3. Rail may be field cut (sawn) to fit post spacing. Repair galvanizing on cut edges in accordance with ASTM A780. The thickness of the repair coating must be equal to or greater than the original coating thickness.

4. Payment for modified base plate will be incidental to related Contract items.