

UNDERDRAIN NOTES

1. *The maximum vertical measurement of depth for payment of Structural Rock Excavation will be to a horizontal plane located 12 inches below the bottom of the invert of the pipe for Underdrain Type "B" and Underdrain Type "C".*
2. *The material for Elbows, Tees, & Wyes for Underdrain Types "B" and "C" shall be at least as thick as the largest size pipe being connected.*
3. *The invert elevation of Underdrain Type "B" outlets shall be a minimum of 6 inches above the flow line of a ditch or the original ground.*
4. *Width of the trench for underdrain outlet will be the same as the underdrain trench.*
5. *No allowance for payment will be made for excavating or material excavated beyond the horizontal dimensions shown for Types "B" or "C" Underdrain.*
6. *In "Box Sections" the edge of the trench shall be in line with the edge of box section.*
7. *Type B and Type C materials shall meet the requirements of Standard Specification 703.22.*

UNDERDRAIN NOTES

605(02)

Revised June 16, 2022