



- (A) 2H:IV for culverts less than 60" diameter. 1.75H:IV for culverts 60" diameter or greater.
- (B) 24" for culverts less than 60" diameter. 36" for culverts 60" diameter or greater.
- (C) Dimensions will vary by location. Refer to Best Management Practices for Erosion and Sediment Control - Energy Dissipators for additional requirements.
- (D) Slopes within the dimensions of the culvert end treatment and any additional slopes steeper than 2H:IV shall be riprapped. Slopes steeper than 2H:IV shall be discussed with the Geotechnical Engineer.

## ROADWAY CULVERT END SLOPE TREATMENT

802(05)

Revised November 1, 2024