Label Town and PIN

FEDERAL PROJECT

BIDDING INSTRUCTIONS

FOR ALL PROJECTS:

- 1. Use pen and ink to complete all paper Bids.
- 2. As a minimum, the following must be received prior to the time of Bid opening:

For a Paper Bid:

a) a copy of the Notice to Contractors, b) the completed Acknowledgement of Bid Amendments form, c) the completed Schedule of Items, d) two copies of the completed and signed Contract Offer, Agreement & Award form, e) a Bid Guaranty, and f) any other certifications or Bid requirements listed in the Bid Documents as due by Bid opening.

For an Electronic Bid:

- a) a completed Bid using Expedite® software and submitted via the Bid ExpressTM webbased service, b) a Bid Guaranty (as described below) or a faxed copy of a Bid Bond (with original to be delivered within 72 hours), and c) any other certifications or Bid requirements listed in the Bid Documents as due by Bid opening.
- 3. Include prices for all required items in the Schedule of Items. ("Zero is not considered a Bid price.")
- 4. Include a Bid Guaranty. Acceptable forms are:
 - a. a properly completed and signed Bid Bond on the Department's prescribed form (or on a form that does not contain any significant variations from the Department's form as determined by the Department) for 5% of the Bid Amount or
 - b. an Official Bank Check, Cashier's Check, Certified Check, U.S. Postal Money Order or Negotiable Certificate of Deposit in the amount stated in the Notice to Contractors.
- 5. If a paper Bid is to be sent, Federal Express overnight delivery is suggested as the package is delivered directly to the DOT Headquarters Building located at 16 Child Street in Augusta. Other means, such as U.S. Postal Service's Express Mail has proven not to be reliable.

IN ADDITION, FOR FEDERAL AID PROJECTS:

6. Complete the DBE Proposed Utilization form in the proper amounts, and deliver to the Civil Rights Office, or fax to (207)624-3431 by 4:30 PM on bid opening day.

If you need further information regarding Bid preparation, call the DOT Contracts Section at (207)624-3410.

For complete bidding requirements, refer to Section 102 of the Maine Department of Transportation, Standard Specifications, Revision of December 2002.

NOTICE

The Maine Department of Transportation is attempting to improve the way Bid Amendments/Addendums are handled, and allow for an electronic downloading of bid packages from our website, while continuing to maintain a planholders list.

Prospective bidders, subcontractors or suppliers who wish to download a copy of the bid package and receive a courtesy notification of project specific bid amendments, must provide an email address to Diane Barnes or Mike Babb at the MDOT Contracts mailbox at: MDOT.contracts@maine.gov. Each bid package will require a separate request.

Additionally, interested parties will be responsible for reviewing and retrieving the Bid Amendments from our web site, and acknowledging receipt and incorporating those Bid Amendments in their bids using the Acknowledgement of Bid Amendment Form.

The downloading of bid packages from the MDOT website is <u>not</u> the same as providing an electronic bid to the Department. Electronic bids must be submitted via http://www.BIDX.com. For information on electronic bidding contact Larry Childs at Larry.Childs@maine.gov.

NOTICE

For security and other reasons, all Bid Packages which are mailed, shall be provided in double (one envelope inside the other) envelopes. The *Inner Envelope* shall have the following information provided on it:

Bid Enclosed - Do Not Open

PIN:

Town:

Date of Bid Opening:

Name of Contractor with mailing address and telephone number:

In Addition to the usual address information, the *Outer Envelope* should have written or typed on it:

Double Envelope: Bid Enclosed

PIN:

Town:

Date of Bid Opening:

Name of Contractor:

This should not be much of a change for those of you who use Federal Express or similar services.

Hand-carried Bids may be in one envelope as before, and should be marked with the following infrormation:

Bid Enclosed: Do Not Open

PIN:

Town:

Name of Contractor:

STATE OF MAINE DEPARTMENT OF TRANSPORTATION

Bid Guaranty-Bid Bond Form

KNOW ALL MEN BY THESE PRESE	ENTS THAT	
, of th	ne City/Town of	and State of
as Principal, and		as Surety, a
Corporation duly organized under the law	s of the State of	and having a usual place of
Business in	and hereby held a	nd firmly bound unto the Treasurer of
the State of Maine in the sum of	,for pay	yment which Principal and Surety bind
themselves, their heirs, executers, adminis		
The condition of this obligation is that the	Principal has submitte	ed to the Maine Department of
Transportation, hereafter Department, a c	ertain bid, attached her	reto and incorporated as a
part herein, to enter into a written contrac	t for the construction o	of
	and if the	Department shall accept said bid
and the Principal shall execute and delive	r a contract in the form	attached hereto (properly
completed in accordance with said bid) ar	nd shall furnish bonds t	for this faithful performance of
said contract, and for the payment of all p	ersons performing labor	or or furnishing material in
connection therewith, and shall in all other	er respects perform the	agreement created by the
acceptance of said bid, then this obligation	n shall be null and voic	d; otherwise it shall remain in full
force, and effect.		
Signe	ed and sealed this	day of20_
WITNESS:	P	PRINCIPAL:
	P	Ву
	B	Ву:
		By:
WITNESS	S	SURETY:
	P	Зу:
		Name of Local Agency:

NOTICE

Bidders:

Please use the attached "Request for Information" form when faxing questions and comments concerning specific Contracts that have been Advertised for Bid. Include additional numbered pages as required. Questions are to be faxed to the number listed in the Notice to Contractors. This is the only allowable mechanism for answering Project specific questions. Maine DOT will not be bound to any answers to Project specific questions received during the Bidding phase through other processes.

State of Maine Department of Transportation

REQUEST FOR INFORMATION

Date _		Time	
Information Requested:	PIN:	Town(s):	
·			
- 			
Request by:		Phone: ()	
Bid Date:		Fax: ()	
		the number listed in the Not	
	RFI received:		
Response:			
Resnance Ry		Date:	

NOTICE

Disadvantaged Business Enterprise Proposed Utilization

The Apparent Low Bidder must submit the <u>Disadvantaged</u> Business Enterprise Proposed Utilization form by close of Business (4:30 P.M.) on Bid day.

The <u>Contractor's Disadvantaged Business Enterprise Proposed</u> <u>Utilization Plan</u> form contains additional information that is required by USDOT.

The <u>Contractor's Disadvantaged Business Enterprise Proposed</u> <u>Utilization Plan</u> form must be used.

A copy of the new <u>Contractor's Disadvantaged Business</u> <u>Enterprise Proposed Utilization Plan</u> and instructions for completing it are attached.

Note: Questions about DBE firms, or to obtain a printed copy of the DBE Directory, contact the Civil Rights Office at (207) 624-3066.

MDOTs DBE Directory of Certified firms can also be obtained at www.maine.gov/mdot/disadvantaged-business-enterprises/dbe-home.php

INSTRUCTIONS FOR PREPARING THE CONTRACTOR'S DISADVANTAGED BUSINESS ENTERPRISE UTILIZATION PLAN

The Contractor Shall:

- 1. Submit a completed <u>Contractor's Disadvantaged Business</u> <u>Enterprise Utilization Plan</u> to the Contract's Engineer by 4:30 P.M. on the Bid day.
- 2. Extend equal opportunity to MDOT certified DBE firms (as listed in MDOT's DBE Directory of Certified Businesses) in the selection and utilization of Subcontractors and Suppliers.

SPECIFIC INSTRUCTIONS FOR COMPLETING THE FORM:

Insert Contractor name, the name of the person(s) preparing the form, and that person(s) telephone and fax number.

Provide total Bid price, Federal Project Identification Number, and location of the Project work.

In the columns, name each DBE firm to be used, provide the Unit or Item cost of the Work/Product to be provided by the DBE firm, give a brief description of the Work, and the dollar value of the Work.

If no DBE firm is to be utilized, the Contractor must document the reason(s) why no DBE firms are being used. Specific supporting evidence of good faith efforts taken by Contractors to solicit DBE Bidders must be attached. This evidence, as a minimum, includes phone logs, e-mail and/or mail DBE solicitation records, and the documented results of these solicitations.

NOTICE

Maine Department of Transportation Disadvantaged Business Enterprise Program

Notice is hereby given that in accordance with US DOT regulation 49 CFR Part 26, the Maine Department of Transportation has established a DBE Program for disadvantaged business participation in the federal-aid construction program; MaineDOT contracts covered by the program include consulting, construction, supplies, manufacturing, and service contracts.

For FFY 2008 (October 1, 2007 through September 30, 2008), MaineDOT has established a DBE participation goal of 4.5% to be achieved through race/gender neutral and race/gender conscious means.

Interested parties may view MaineDOT's DBE goal setting methodology for the next 30 days during normal business hours (8-4, M-F) at the Maine Department of Transportation, Civil Rights Office, 16 State House Station, Augusta ME 04333-0016. Appointments may be scheduled by telephone at (207) 624-3519. The goal setting methodology is also available for viewing on the MaineDOT website: http://www.maine.gov/mdot/disadvantaged-business-enterprises/dbe-home.php.

Public comment will be accepted for 45 days following the last date of publication. The public comment period will be complete on August 28th, 2007. The goal will be submitted for approval to the FHWA on August 1st, 2007 with an update based upon public comment sent to FHWA on August 30th.


Comments on the goal will be accepted for 45 days from the date of this notice. Written comments should be addressed to Jackie LaPerriere, Maine Department of Transportation, Civil Rights Office, 16 State House Station, Augusta, Maine 04333-0016 or by e-mail at: jackie.laperriere@maine.gov.

Several interested stakeholders will be notified directly by e-mail of the goal publication, including Maine SBA, Associated Constructors of Maine, and ACEC, and Maine DBEs.

	_ Ori	ginal Su	bmission				Page	01
	_ Re	vision#						
			Maine		TOR'S DBE/SUBO UTILIZATION FO		CTOR	
	Low Bidder must furnish this form to Contracts Section Bid Opening day.							
Contractor: Telephone: E							Ext	
Prep	pared l	by:				Fax:		
BID	PRICI	E: \$		BIJ	D DATE:/			
					PROJECT LOC			
			TOTAL DRE	0/ DADTICI	PATION FOR THIS S	I IDMISSIO	N T	
W	D	Non		m Name	Unit/Item Cost		Description of	Actual \$
vv B E•	B E•	DBE	F II	III Ivaine	Unit/Item Cost	UIIII #	Work & Item Number	Value
		-			+			
			 		+			
							Total >	
Contractors must make a good faith effort to include <u>Certified</u> DBE firms in all aspects of the project. If no DBE firms are to be part of this project, a detailed explanation is required. Attach supporting evidence to the maximum participation of DBEs on this project. This is a requirement. This evidence must include name of firm(s) contacted, date contacted, and outcome of solicitation.								
Г	Equa	al Opport	tunity Use:					
	Form	n received	d:/	_ Verified by:				
		Accept	ed	_ Rejected				
	cc: [] Contra	icts Other	:				

- WBEs are non-minority women owned firms certified by MaineDOT
- DBEs are male and minority owned firms certified by MaineDOT

For a complete list of certified firms go to http://www.maine.gov/mdot



MaineDOT's CIVIL RIGHTS OFFICE

To search for a specific work item, click on the binoculars, type in the word you want to search for and click on find. To go to the next selected item, click on the binoculars with the arrow.

MAINE DEPARTMENT OF TRANSPORTATION

CERTIFIED DISADVANTAGED AND WOMEN BUSINESS ENTERPRISE

DECEMBER 2005

Information is updated on an ongoing basis and can be retrieved by visiting our Website:

www.maine.gov/mdot/disadvantaged-business-enterprises/dbe-home.php

Vendor Registration

Prospective Bidders must register as a vendor with the Department of Administrative & Financial Services if the vendor is awarded a contract. Vendors will not be able to receive payment without first being registered. Vendors/Contractors will find information and register through the following link –

http://www.maine.gov/purchases/vendorinfo/vss.htm

STATE OF MAINE DEPARTMENT OF TRANSPORTATION NOTICE TO CONTRACTORS

Sealed Bids addressed to the Maine Department of Transportation, Augusta, Maine 04333 and endorsed on the wrapper "Bids for Concrete Rubblization, Hot Mix Asphalt Overlay, Pavement Milling, Drainage and Safety Improvements in the towns of Brunswick, Topsham, Bowdoin, Bowdoinham, Richmond and the city of Gardiner" will be received from contractors at the Reception Desk, Maine DOT Building, Child Street, Augusta, Maine, until 11:00 o'clock A.M. (prevailing time) on April 23, 2008, and at that time and place publicly opened and read. Bids will be accepted from contractors prequalified by the Department of Transportation for Highway Construction and Paving Projects. All other Bids may be rejected. We now accept electronic bids for those bid packages posted on the bidx.com website. Electronic bids do not have to be accompanied by paper bids. Please note: the Department will accept a facsimile of the bid bond; however, the original bid bond must then be received at the MDOT Contract Section within 72 hours of the bid opening. Until further notice, dual bids (one paper, one electronic) will be accepted, with the paper copy taking precedence.

Description: Maine Federal Aid Project No. IM-1511(400)E, PIN 15114.00.

Location: The section of highway under construction in Kennebec, Sagadahoc and Cumberland Counties Project No. IM-1511(400)E is located on Interstate 295 southbound, beginning 0.20 mi south of the Durham Road Overpass and extending northerly 21.80 mi. to 0.03 mi. south of the Exit 49 off ramp.

Outline of Work: Concrete Rubblization, Hot Mix Asphalt Overlay, Pavement Milling, Drainage and Safety Improvements; and other incidental work.

For general information regarding Bidding and Contracting procedures, contact Scott Bickford at (207)624-3410. Our webpage at http://www.maine.gov/mdot/contractor-consultant-information/contractor_cons.php contains a copy of the schedule of items, Plan Holders List, written portions of bid amendments (not drawings), and bid results. For Project-specific information fax all questions to **James Andrews** at (207)624-3431. Questions received after 12:00 noon of Monday prior to bid date will not be answered. Bidders shall not contact any other Departmental staff for clarification of Contract provisions, and the Department will not be responsible for any interpretations so obtained. Hearing impaired persons may call the Telecommunication Device for the Deaf at 888-516-9364.

Plans, specifications and bid forms may be seen at the Maine DOT Building in Augusta, Maine. They may be purchased from the Department between the hours of 8:00 a.m. to 4:30 p.m. by cash, credit card (Visa/Mastercard) or check payable to Treasurer, State of Maine sent to Maine Department of Transportation, Attn.: Mailroom, 16 State House Station, Augusta, Maine 04333-0016. They also may be purchased by telephone at (207) 624-3536 between the hours of 8:00 a.m. to 4:30 p.m. Full size plans \$45.00 (\$49.50 by mail) Half size plans \$22.50 (\$25.50 by mail), Bid Book \$10 (\$13 by mail), Single Sheets \$2, payment in advance, all non-refundable.


Each Bid must be made upon blank forms provided by the Department and must be accompanied by a bid bond at 5% of the bid amount or an official bank check, cashier's check, certified check, certificate of deposit, or United States postal money order in the amount of \$700,000 payable to Treasurer, State of Maine as a Bid guarantee. A Contract Performance Surety Bond and a Contract Payment Surety Bond, each in the amount of 100 percent of the Contract price, will be required of the successful Bidder.

This Contract is subject to all applicable Federal Laws. This contract is subject to compliance with the Disadvantaged Business Enterprise program requirements as set forth by the Maine Department of Transportation.

All work shall be governed by "State of Maine, Department of Transportation, Standard Specifications, Revision of December 2002", price \$10 [\$13 by mail], and Standard Details, Revision of December 2002, price \$20 [\$25 by mail]. Standard Detail updates can be found at http://www.maine.gov/mdot/contractor-consultant-information/contractor_cons.php

The right is hereby reserved to the MDOT to reject any or all bids.

Augusta, Maine April 2, 2008



JOHN E. DORITY CHIEF ENGINEER

SPECIAL PROVISION 102.7.3 ACKNOWLEDGMENT OF BID AMENDMENTS

With this form, the Bidder acknowledges its responsibility to check for all Amendments to the Bid Package. For each Project under Advertisement, Amendments are located at http://www.maine.gov/mdot/comprehensive-list-projects/project-information.php It is the responsibility of the Bidder to determine if there are Amendments to the Project, to download them, to incorporate them into their Bid Package, and to reference the Amendment number and the date on the form below. The Maine DOT will not post Bid Amendments any later than noon the day before Bid opening without individually notifying all the planholders.

Amendment Number	Date

The Contractor, for itself, its successors and assigns, hereby acknowledges that it has received all of the above referenced Amendments to the Bid Package.

	CONTRACTOR
Date	Signature of authorized representative
	(Name and Title Printed)

Page 1 of 1

BID

DATE OF OPENING: CALL ORDER:

CONTRACT ID : 015114.00

PROJECTS

IM-1511(400)E

COUNTY : SAGADAHOC

PAGE: 1 DATE: 080331

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015114.00 PROJECT(S): IM-1511(400)E

CONTRA	ACTOR :			
LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY		BID AMOUNT
	 	AND UNITS	DOLLARS CTS	DOLLARS CTS
SECTIO	ON 0001 REHAB			
0010	201.11 CLEARING 	3.000 AC		
	201.23 REMOVING SINGLE TREE TOP ONLY 	 20.000 EA		
0030	201.24 REMOVING STUMP 	20.000 EA		
	202.11 REMOVING PORTLAND CEMENT CONCRETE PAVEMENT	245000.000 SY		
	202.126 REMOVE EXISTING CONCRETE SLAB TO FULL DEPTH	27500.000		
	202.127 REMOVE EXISTING BITUMINOUS PAVEMENT 	 LUMP 	 LUMP 	
	202.202 REMOVING PAVEMENT SURFACE 	 212600.000 SY		
0080	202.205 RUMBLE STRIPS - SHOULDER 	 226900.000 LF		
0090	203.20 COMMON EXCAVATION	4500.000 CY		
0100	203.24 COMMON BORROW 	 2000.000 CY		

PAGE:

080331

SCHEDULE OF ITEMS

DATE: REVISED:

CONTRACT ID: 015114.00 PROJECT(S): IM-1511(400)E

LINE	I .		APPROX.	UNIT PR	ICE	BID AMO	TUUC
NO	DESCRIPTION		QUANTITY AND UNITS	DOLLARS	CTS	DOLLARS	CTS
0110	203.242 DIRTY BORROW	CY	1500.000			 	
0120	203.25 GRANULAR BORROW 	CY	2000.000			 	
0130	204.201 ADD SHOULDER AGGREGATE TO EXISTING SHOULDER	 SY	181300.000			 	
0140	205.512 WIDENING OF EXISTING SHOULDER 	 SY	7500.000				
0150	211.21 INSLOPE REHABILITATION 	 LF	243210.000				
0160	304.13 DENSE GRADED CRUSHED AGGREGATE SUBBASE	 CY	8500.000 				
	307.32 FULL DEPTH RECYCLED PAVEMENT(UNTREATED MAINELINE TRAVELWAY)	 SY	30000.000				
0180	311.36 FULL DEPTH CONCRETE RUBBLIZATION 	SY	245000.000			 	
	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE 	 T	17000.000			 	
	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT 	 T	33000.000	 		 	
	403.2102 9.5 MM ASPHALT RICH BASE MIXTURE	 T	4000.000			 	

SCHEDULE OF ITEMS

PAGE:

080331

REVISED:

CONTRACT ID: 015114.00 PROJECT(S): IM-1511(400)E

CONTRA	ACTOR:					
LINE	!	APPROX.	UNIT PRICE		BID AMO	UNT
		AND UNITS	DOLLARS	CTS	DOLLARS	CTS
0220	403.211 HOT MIX ASPHALT (SHIMMING) 	 5500.000 T		 		
0230	403.213 HOT MIX ASPHALT 12.5 MM HMA BASE 	 52000.000 T		 		
0240	403.2131 12.5 MM POLYMER MODIFIED HMA BASE 	 33000.000 T		 		
0250	403.2132 12.5 MM ASPHALT RICH BASE MIXTURE 	 36000.000 T		 		
0260	403.325 HIGH PERFORMANCE RUBBERIZED ASPHALT 	 550.000 T		 		
0270	409.15 BITUMINOUS TACK COAT - APPLIED 	 35000.000 G		 		
0280	411.10 UNTREATED AGGREGATE SURFACE COURSE (TRUCK MEASURE)	 15000.000 CY		 		
0290	424.3331 ASPHALT LOW MODULUS CRACK SEALER, APPLIED	 10000.000 LB		 		
0300	424.3333 LOW MODULUS JOINT SEALER, APPLIED 	 460000.000 LF		 		
0310	429.32 SELF ADHESIVE ASPHALTIC MEMBRANE 	 32400.000 SF		 		
0320	502.29 STRUCTURAL CONCRETE WEARING SURFACE ON BRIDGES	 LUMP 	 LUMP 	 		

PAGE: 080331

REVISED:

SCHEDULE OF ITEMS

CONTRACT ID: 015114.00 PROJECT(S): IM-1511(400)E

CONTRACTOR :	:
--------------	---

CONTRA	ACIOR:						
LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS		UNIT PR	ICE	BID AMOUNT	
	DESCRIPTION			 DOLLARS	CTS	DOLLARS	CTS
0330	502.31 STRUCTURAL CONCRETE APPROACH SLABS 	 LUMP 		LUMP			
0340	504.069 CONCRETE PIPE TIES 	 32. EA	000				
0350	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE (150 SY)	 LUMP 		 LUMP 			
0360	512.082 FRENCH DRAINS 	 775. EA	000				
0370	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	 LUMP 		LUMP			
0380	518.39 REPAIRING GRANITE CURB BEDDING MORTAR 	 130. LF	000			 	
0390	518.50 REPAIR OF UPWARD FACING SURFACES - TO REINFORCING STEEL < 7.9 IN.	300.	000		 		
0400	518.51 REPAIR OF UPWARD FACING SURFACES - BELOW REINFORCING STEEL < 7.9 IN.	 200. SF	000				
0410	518.60 REPAIR OF VERTICAL SURFACES < 7.9 IN.	 50. SF	000				
0420	518.61 REPAIR OF VERTICAL SURFACES > 7.9 IN.	 10. CY	000	 			
							

PAGE: 5 DATE: 080331

REVISED:

SCHEDULE OF ITEMS

CONTRACT ID: 015114.00 PROJECT(S): IM-1511(400)E

CONTRA	CONTRACTOR :							
LINE NO	!	APPROX.	UNIT PRICE		BID AMOUNT			
NO	DESCRIPTION	AND UNITS	DOLLARS	CTS	DOLLARS	CTS		
	520.241 BRIDGE JOINT MODIFICATION TYPE 1 	3.000 EA						
0440	520.242 BRIDGE JOINT MODIFICATION TYPE 2 	 5.000 EA						
	520.243 BRIDGE JOINT MODIFICATION TYPE 3 	 2.000 EA			 			
	526.301 TEMPORARY CONCRETE BARRIER TYPE I (1800 LF)	 LUMP 	 LUMP 		 			
	526.34 PERMANENT CONCRETE TRANSITION BARRIER	 20.000 EA			 			
	527.301 ENERGY ABSORBING SYSTEM (C-A-T)	 1.000 EA			 			
	527.34 WORK ZONE CRASH CUSHIONS 	3.000 UN						
	603.15 12 INCH CULVERT PIPE OPTION I 	 12.000 LF						
	603.16 15 INCH CULVERT PIPE OPTION I 	300.000 LF			 			
	603.195 24 INCH REINFORCED CONCRETE PIPE CLASS III	 8.000 LF						
	603.245 54 INCH REINFORCED CONCRETE PIPE CLASS III	 8.000 LF	 					

SCHEDULE OF ITEMS

PAGE: 080331 REVISED:

CONTRACT ID: 015114.00 PROJECT(S): IM-1511(400)E

CONTRA	ACTOR:			
LINE NO	:	APPROX.	UNIT PRICE 	
		AND UNITS	DOLLARS CTS	S DOLLARS CTS
	603.7424 REMOVE & RELAY 24 INCH CONCRETE PIPE 	 40.000 LF		
	603.743 REMOVE & RELAY 30 INCH CONCRETE PIPE 	 16.000 LF		
0560	603.7436 REMOVE & RELAY 36 INCH CONCRETE PIPE 	 24.000 LF		
0570	603.7454 REMOVE & RELAY 54 INCH CONCRETE PIPE	 8.000 LF		
0580	603.746 REMOVE & RELAY 60 INCH CONCRETE PIPE 	 24.000 LF		
0590	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE 	 10.000 EA		
	605.09 6 INCH UNDERDRAIN TYPE B 	 5000.000 LF		
	605.10 6 INCH UNDERDRAIN OUTLET 	 500.000 LF		
0620	606.1721 BRIDGE TRANSITION - TYPE 1 	 20.000 EA		
0630	606.178 GUARDRAIL BEAM 	 3500.000 LF		
0640	606.24 GUARDRAIL TYPE 3D - SINGLE RAIL 	 39950.000 LF		

PAGE:

REVISED:

080331

SCHEDULE OF ITEMS

CONTRACT ID: 015114.00 PROJECT(S): IM-1511(400)E

	ACTOR :						
LINE NO	TTEM DESCRIPTION	APPROX. QUANTITY		UNIT PR	ICE	BID AMOUNT	
110	BESCRIFTION		AND UNITS	DOLLARS	CTS	DOLLARS	CTS
0650	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	 EA	36.000				
0660	606.352 REFLECTORIZED BEAM GUARDRAIL DELINEATORS	 EA	50.000				
0670	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	 EA	123.000			 	
	606.356 UNDERDRAIN DELINEATOR POST 	 EA	75.000			 	
	606.3581 GUARDRAIL, MODIFY EXISTING TO TYPE 3D	 LF	4912.500			 	
0700	606.367 REPLACE UNUSABLE EXISTING GUARDRAIL POSTS 	 EA	100.000			 	
0710	606.48 SINGLE GALVANIZED STEEL POST 	 EA	200.000			 	
0720	606.64 GUARDRAIL THRIE BEAM - DOUBLE RAIL 	 LF	2675.000			 	
	606.65 GUARDRAIL THRIE BEAM - SINGLE RAIL 	 LF	337.500			 	
	606.70 TRANSITION SECTION THRIE BEAM 	 EA	4.000			 	
0750	606.754 WIDEN SHOULDER FOR GUARDRAIL 350 FLARED TERMINAL	 EA	46.000				

PAGE: DATE:

080331

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015114.00 PROJECT(S): IM-1511(400)E

CONTRA	ACTOR:			
LINE NO	!	APPROX. QUANTITY	UNIT PRICE	BID AMOUNT
		AND UNITS	DOLLARS CTS	DOLLARS CTS
0760	606.79 GUARDRAIL 350 FLARED TERMINAL 	 46.000 EA		
0770	606.792 GUARDRAIL 350 MEDIAN TERMINAL SYSTEM 	 1.000 EA		
0780	609.40 RESET CURB TYPE 5 	4250.000 LF		
0790	610.08 PLAIN RIPRAP 	 150.000 CY		
0800	612.06 BITUMINOUS SEALING - BLACK 	 1000.000 SY		
0810	613.319 EROSION CONTROL BLANKET 	 8000.000 SY		
0820	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY 	 2100.000 UN		
0830	618.1411 SEEDING METHOD NUMBER 3 - PLAN QUANTITY	 425.000 UN		
0840	619.1201 MULCH - PLAN QUANTITY 	 2525.000 UN		
0850	619.1401 EROSION CONTROL MIX 	4000.000 CY		
0860	620.58 EROSION CONTROL GEOTEXTILE 	 1000.000 SY		

PAGE: DATE:

REVISED:

080331

SCHEDULE OF ITEMS

CONTRACT ID: 015114.00 PROJECT(S): IM-1511(400)E

LINE DESCRIPTION	CONTRA	ACIOR:						
AND UNITS DOLLARS CTS DOLLARS CTS		!	!		UNIT PRICE		BID AMOUNT	
0870 GEOGRID		 	 		DOLLARS	CTS	DOLLARS	CTS
0880 627.18 12	0870	!		3500.000				
0880 PAVEMENT MARKING		 	SY	 				
0890 627.72 6 INCH WHITE 249800.000	0880	:		8600.000 				
0890 PAVEMENT MARKING LINE 249800.000		 	LF 	 	 -			
0900	0890	!		249800.000				
0900 PAVEMENT MARKING LINE		 	LF 	 	 	 		
0910 627.75 WHITE OR YELLOW 1525.000	0900	!		138800.000				
0910 PAVEMENT AND CURB SF 1525.000		 	LF 	 	 	 	·	 - -
	0910	PAVEMENT AND CURB	 SF	1525.000				
0920 PAINTED PAVEMENT MARKING 507000.000			- - -		 	<u>-</u>		- -
0930 STRAIGHT TIME 180.000	0920	PAINTED PAVEMENT MARKING	:	507000.000				
HR	0020			100 000				
0940 (INCLUDING OPERATOR) 100.000	0930		HR	180.000				
HR	0940	!	: :					
0950 (INCLUDING OPERATOR) 100.000	0,540							
HR	0950			100 000				
0960 EXCAVATOR (INCLUDING 160.000			HR					
OPERATOR)	0960			160.000				
0970 EXCAVATOR (INCLUDING 100.000			HR					
	0970	· ·		100.000				
		<u>:</u>	HR		 			

PAGE: DATE: REVISED:

10 080331

SCHEDULE OF ITEMS

CONTRACT ID: 015114.00

PROJECT(S): IM-1511(400)E

	ACTOR:				
LINE NO	ITEM DESCRIPTION	APPROX.	 UNIT PRICE 	BID AMOUNT	
		AND UNITS	DOLLARS CTS	DOLLARS CTS	
!	631.132 SMALL BULLDOZER (INCLUDING OPERATOR)	 160.000 HR			
	631.14 GRADER (INCLUDING OPERATOR)	120.000 120.000	<u></u> 		
1000	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR)	 50.000 HR			
	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	 240.000 HR			
	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	 100.000 HR			
	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	 50.000 HR			
1040	631.52 SIGN CREW	 300.000 HR			
	645.306 FLEXIBLE REFLECTORIZED DELINEATOR	 750.000 EA			
	652.30 FLASHING ARROW BOARD	 3.000 EA			
1070	652.33 DRUM	 200.000 EA			
1080	652.34 CONE	 600.000 EA			

PAGE:

080331

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015114.00 PROJECT(S): IM-1511(400)E

LINE	!	APPROX.	· ·		BID AMOUNT	
NO	DESCRIPTION	QUANTITY AND UNITS	DOLLARS	CTS	DOLLARS	CTS
	652.35 CONSTRUCTION SIGNS	 1500.000 SF				
	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES 	 120.000 CD		 	 	
	652.41 PORTABLE - CHANGEABLE MESSAGE SIGN 	 8.000 EA		 	 	
	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	 LUMP 	 LUMP			
1130	659.10 MOBILIZATION 	 LUMP	 LUMP			
	660.21 ON-THE-JOB TRAINING (BID)	 3000.000 HR		 	 	
	 SECTION 0001 TOTAL		 			
	 TOTAL BID		 			

CONTRACT AGREEMENT, OFFER & AWARD

AGREEMENT made on the date last signed below, by and between the State of Maine, acting through and by its Department of Transportation (Department), an agency of state government with its principal administrative offices located at Child Street, Augusta, Maine, with a mailing address at 16 State House Station, Augusta, Maine 04333-0016, and a corporation or other legal entity organized under the laws of the State of _______, with its principal place of business located at _______

The Department and the Contractor, in consideration of the mutual promises set forth in this Agreement (the "Contract"), hereby agree as follows:

A. The Work.

The Contractor agrees to complete all Work as specified or indicated in the Contract including Extra Work in conformity with the Contract, **Project No. IM-1511(400)E**, **PIN No. 15114.00**, for the Concrete Rubblization, Hot Mix Asphalt Overlay, Pavement Milling, Drainage and Safety Improvements in the towns Brunswick, Bowdoin, Bowdoinham, Richmond, Topsham and the city of Gardiner, Counties of Kennebec, Sagadahoc, and Cumberland Maine. The Work includes construction, maintenance during construction, warranty as provided in the Contract, and other incidental work.

The Contractor shall be responsible for furnishing all supervision, labor, equipment, tools supplies, permanent materials and temporary materials required to perform the Work including construction quality control including inspection, testing and documentation, all required documentation at the conclusion of the project, warranting its work and performing all other work indicated in the Contract.

The Department shall have the right to alter the nature and extent of the Work as provided in the Contract; payment to be made as provided in the same.

B. Time.

The Contractor agrees to complete all Work, except warranty work, on or before **October 18, 2008.** Further, the Department may deduct from moneys otherwise due the Contractor, not as a penalty, but as Liquidated Damages in accordance with Sections 107.7 and 107.8 of the State of Maine Department of Transportation Standard Specifications, Revision of December 2002 and related Special Provisions.

C. Price.

The quantities given	in the Schedule of Items of the Bid Package will be used as the
basis for determining	the original Contract amount and for determining the amounts of
the required Perform of this offer is	ance Surety Bond and Payment Surety Bond, and that the amount
<u>\$</u>	Performance Bond and Payment Bond each being
$1\overline{00}\%$ of the amount	of this Contract.

D. Contract.

This Contract, which may be amended, modified, or supplemented in writing only, consists of the Contract documents as defined in the Plans, Standard Specifications, Revision of December 2002, Standard Details Revision of December 2002 as updated through advertisement, Supplemental Specifications, Special Provisions, Contract Agreement; and Contract Bonds. It is agreed and understood that this Contract will be governed by the documents listed above.

E. Certifications.

By signing below, the Contractor hereby certifies that to the best of the Contractor's knowledge and belief:

- 1. All of the statements, representations, covenants, and/or certifications required or set forth in the Bid and the Bid Documents, including those in the Federal Contract Provisions Supplement, and the Contract are still complete and accurate as of the date of this Agreement.
- 2. The Contractor knows of no legal, contractual, or financial impediment to entering into this Contract.
- 3. The person signing below is legally authorized by the Contractor to sign this Contract on behalf of the Contractor and to legally bind the Contractor to the terms of the Contract.

F. Offer.

The undersigned, having carefully examined the site of work, the Plans, Standard Specifications Revision of December 2002, Standard Details Revision of December 2002 as updated through advertisement, Supplemental Specifications, Special Provisions, Contract Agreement; and Contract Bonds contained herein for construction of: Project No. IM-1511(400)E, PIN No. 15114.00, for the Concrete Rubblization, Hot Mix Asphalt Overlay, Pavement Milling, Drainage and Safety Improvements in the towns Brunswick, Bowdoin, Bowdoinham, Richmond, Topsham and the city of Gardiner, Counties of Kennebec, Sagadahoc, and Cumberland, State of Maine, on which bids will be received until the time specified in the "Notice to Contractors" do(es) hereby bid and offer to enter into this contract to supply all the materials, tools, equipment and labor to construct the whole of the Work in strict accordance with the terms and conditions of this Contract at the unit prices in the attached "Schedule of Items".

The Offeror agrees to perform the work required at the price specified above and in accordance with the bids provided in the attached "Schedule of Items" in strict accordance with the terms of this solicitation, and to provide the appropriate insurance and bonds if this offer is accepted by the Government in writing.

As Offeror also agrees:

First: To do any extra work, not covered by the attached "Schedule of Items", which may be ordered by the Resident, and to accept as full compensation the amount determined upon a "Force Account" basis as provided in the Standard Specifications, Revision of December 2002, and as addressed in the contract documents.

Second: That the bid bond at 5% of the bid amount or the official bank check, cashier's check, certificate of deposit or U. S. Postal Money Order in the amount given in the "Notice to Contractors", payable to the Treasurer of the State of Maine and accompanying this bid, shall be forfeited, as liquidated damages, if in case this bid is accepted, and the undersigned shall fail to abide by the terms and conditions of the offer and fail to furnish satisfactory insurance and Contract bonds under the conditions stipulated in the Specifications within 15 days of notice of intent to award the contract.

Third: To begin the Work as stated in Section 107.2 of the Standard Specifications Revision of December 2002 and complete the Work within the time limits given in the Special Provisions of this Contract.

Fourth: The Contractor will be bound to the Disadvantaged Business Enterprise (DBE) Requirements contained in the attached Notice (Additional Instructions to Bidders) and submit a completed Contractor's Disadvantaged Business Enterprise Utilization Plan by 4:30pm on the day of bid opening to the Contracts Engineer.

Fifth: That this offer shall remain open for 30 calendar days after the date of opening of bids.

Sixth: The Bidder hereby certifies, to the best of its knowledge and belief that: the Bidder has not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of competitive bidding in connection with its bid, and its subsequent contract with the Department.

IN WITNESS WHEREOF, the Contractor, for itself, its successors and assigns, hereby execute two duplicate originals of this Agreement and thereby binds itself to all covenants, terms, and obligations contained in the Contract Documents.

		CONTRACTOR
Date		(Signature of Legally Authorized Representative of the Contractor)
	Witness	(Name and Title Printed)
G.	Award.	
	Your offer is hereby accepted. documents referenced herein.	This award consummates the Contract, and the
		MAINE DEPARTMENT OF TRANSPORTATION
	Date	By: David A. Cole, Commissioner
	Witness	

CONTRACT AGREEMENT, OFFER & AWARD

AGREEMENT made on the date last signed below, by and between the State of Maine, acting through and by its Department of Transportation (Department), an agency of state government with its principal administrative offices located at Child Street, Augusta, Maine, with a mailing address at 16 State House Station, Augusta, Maine 04333-0016, and a corporation or other legal entity organized under the laws of the State of _______, with its principal place of business located at _______

The Department and the Contractor, in consideration of the mutual promises set forth in this Agreement (the "Contract"), hereby agree as follows:

A. The Work.

The Contractor agrees to complete all Work as specified or indicated in the Contract including Extra Work in conformity with the Contract, **Project No. IM-1511(400)E**, **PIN No. 15114.00**, for the Concrete Rubblization, Hot Mix Asphalt Overlay, Pavement Milling, Drainage and Safety Improvements in the towns Brunswick, Bowdoin, Bowdoinham, Richmond, Topsham and the city of Gardiner, Counties of Kennebec, Sagadahoc, and Cumberland Maine. The Work includes construction, maintenance during construction, warranty as provided in the Contract, and other incidental work.

The Contractor shall be responsible for furnishing all supervision, labor, equipment, tools supplies, permanent materials and temporary materials required to perform the Work including construction quality control including inspection, testing and documentation, all required documentation at the conclusion of the project, warranting its work and performing all other work indicated in the Contract.

The Department shall have the right to alter the nature and extent of the Work as provided in the Contract; payment to be made as provided in the same.

B. Time.

The Contractor agrees to complete all Work, except warranty work, on or before **October 18, 2008.** Further, the Department may deduct from moneys otherwise due the Contractor, not as a penalty, but as Liquidated Damages in accordance with Sections 107.7 and 107.8 of the State of Maine Department of Transportation Standard Specifications, Revision of December 2002 and related Special Provisions.

C. Price.

The quantities give	en in the Schedule of Items of the Bid Package will be used as the
basis for determini	ng the original Contract amount and for determining the amounts of
the required Performs of this offer is	mance Surety Bond and Payment Surety Bond, and that the amount
\$	Performance Bond and Payment Bond each being
$1\overline{00}\%$ of the amount	t of this Contract.

D. Contract.

This Contract, which may be amended, modified, or supplemented in writing only, consists of the Contract documents as defined in the Plans, Standard Specifications, Revision of December 2002, Standard Details Revision of December 2002 as updated through advertisement, Supplemental Specifications, Special Provisions, Contract Agreement; and Contract Bonds. It is agreed and understood that this Contract will be governed by the documents listed above.

E. Certifications.

By signing below, the Contractor hereby certifies that to the best of the Contractor's knowledge and belief:

- 1. All of the statements, representations, covenants, and/or certifications required or set forth in the Bid and the Bid Documents, including those in the Federal Contract Provisions Supplement, and the Contract are still complete and accurate as of the date of this Agreement.
- 2. The Contractor knows of no legal, contractual, or financial impediment to entering into this Contract.
- 3. The person signing below is legally authorized by the Contractor to sign this Contract on behalf of the Contractor and to legally bind the Contractor to the terms of the Contract.

F. Offer.

The undersigned, having carefully examined the site of work, the Plans, Standard Specifications Revision of December 2002, Standard Details Revision of December 2002 as updated through advertisement, Supplemental Specifications, Special Provisions, Contract Agreement; and Contract Bonds contained herein for construction of: Project No. IM-1511(400)E, PIN No. 15114.00, for the Concrete Rubblization, Hot Mix Asphalt Overlay, Pavement Milling, Drainage and Safety Improvements in the towns Brunswick, Bowdoin, Bowdoinham, Richmond, Topsham and the city of Gardiner, Counties of Kennebec, Sagadahoc, and Cumberland, State of Maine, on which bids will be received until the time specified in the "Notice to Contractors" do(es) hereby bid and offer to enter into this contract to supply all the materials, tools, equipment and labor to construct the whole of the Work in strict accordance with the terms and conditions of this Contract at the unit prices in the attached "Schedule of Items".

The Offeror agrees to perform the work required at the price specified above and in accordance with the bids provided in the attached "Schedule of Items" in strict accordance with the terms of this solicitation, and to provide the appropriate insurance and bonds if this offer is accepted by the Government in writing.

As Offeror also agrees:

First: To do any extra work, not covered by the attached "Schedule of Items", which may be ordered by the Resident, and to accept as full compensation the amount determined upon a "Force Account" basis as provided in the Standard Specifications, Revision of December 2002, and as addressed in the contract documents.

Second: That the bid bond at 5% of the bid amount or the official bank check, cashier's check, certificate of deposit or U. S. Postal Money Order in the amount given in the "Notice to Contractors", payable to the Treasurer of the State of Maine and accompanying this bid, shall be forfeited, as liquidated damages, if in case this bid is accepted, and the undersigned shall fail to abide by the terms and conditions of the offer and fail to furnish satisfactory insurance and Contract bonds under the conditions stipulated in the Specifications within 15 days of notice of intent to award the contract.

Third: To begin the Work as stated in Section 107.2 of the Standard Specifications Revision of December 2002 and complete the Work within the time limits given in the Special Provisions of this Contract.

Fourth: The Contractor will be bound to the Disadvantaged Business Enterprise (DBE) Requirements contained in the attached Notice (Additional Instructions to Bidders) and submit a completed Contractor's Disadvantaged Business Enterprise Utilization Plan by 4:30pm on the day of bid opening to the Contracts Engineer.

Fifth: That this offer shall remain open for 30 calendar days after the date of opening of bids.

Sixth: The Bidder hereby certifies, to the best of its knowledge and belief that: the Bidder has not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of competitive bidding in connection with its bid, and its subsequent contract with the Department.

IN WITNESS WHEREOF, the Contractor, for itself, its successors and assigns, hereby execute two duplicate originals of this Agreement and thereby binds itself to all covenants, terms, and obligations contained in the Contract Documents.

		CONTRACTOR
Date		(Signature of Legally Authorized Representative of the Contractor)
	Witness	(Name and Title Printed)
G.	Award.	
	Your offer is hereby accepted. documents referenced herein.	This award consummates the Contract, and the
		MAINE DEPARTMENT OF TRANSPORTATION
	Date	By: David A. Cole, Commissioner
	Witness	

CONTRACT AGREEMENT, OFFER & AWARD

gove Wint 0016	, <u> </u>
	poration or other legal entity organized under the laws of the state of Maine, with its ipal place of business located at(address of the firm bidding the job)
princ	ipai place of business located at
The Agre	Department and the Contractor, in consideration of the mutual promises set forth in this ement (the "Contract"), hereby agree as follows:
A.	The Work.
	The Contractor agrees to complete all Work as specified or indicated in the Contract virtualing Extra Work in conformity with the Contract, PIN No. 1224.00
	the Hot Mix Asphalt Overlay in the town city of West Eastport , County of
	town city of West Eastport , County of Washington , Maine. The Work includes construction, maintenance during
	construction, wateranty as provided in the Contract, and other incidental work.
	The Contractor shall be responsible for furnishing all supervision, labor, equipment,
	tools supplies, permanent materials and temporary materials required to perform the
	Work including construction quality control including inspection, testing and documentation, all required documentation at the conclusion of the project, warranting
	its work and performing all other work indicated in the Contract.
	The Department shall have the right to alter the nature and extent of the Work as provided in the Contract; payment to be made as provided in the same.
В.	Time.
	The Contractor agrees to complete all Work, except warranty work, on or before November 15, 2003. Further, the Department may deduct from moneys otherwise due the Contractor, not as a penalty, but as Liquidated Damages in accordance with Sections 107.7 and 107.8 of the State of Maine Department of Transportation Standard Specifications, Revision of December 2002.

C. Price.

The quantities given in the Schedule of Items of the Bid Package will be used as the basis for determining the original Contract amount and for determining the amounts of the required Performance Surety Bond and Payment Surety Bond, and that the amount of this offer is (Place bid here in alphabetical form such as One Hundred and

Two dollars and 10 cents)

Performance

Bond and Payment Bond each being 100% of the amount of this Contract.

\$ (repeat bid here in numerical terms, such as \$102.10)

D. Contract.

This Contract, which may be amended, modified, or supplemented in writing only, consists of the Contract documents as defined in the Plans, Standard Specifications, Revision of December 2002, Standard Detalls Revision of December 2002, Supplemental Specifications, Special Provisions, Contract Agreement; and Contract Bonds. It is agreed and understood that this Contract will be governed by the documents listed above.

E. Certifications.

By signing below, the Contractor hereby certifies that to the best of the Contractor's knowledge and belief:

- 1. All of the statements representations, covenants, and/or certifications required or set forth in the Bid and the Bid Documents, including those in Appendix A to Division 100 of the Standard Specifications Revision of December 2002 (Federal Contract Provisions Supplement), and the Contract are still complete and accurate as of the date of this Agreement.
- 2. The Contractor knows of no legal, contractual, or financial impediment to entering into this Contract.
- 3. The person signing below is legally authorized by the Contractor to sign this Contract on behalf of the Contractor and to legally bind the Contractor to the terms of the Contract.

F. Offer.

The undersigned, having carefully examined the site of work, the Plans, Standard Specifications, Revision of December 2002, Standard Details Revision of December 2002, Supplemental Specifications, Special Provisions, Contract Agreement; and Contract Bonds contained herein for construction of:

PIN 1234.00 West Eastport, Hot Mix Asphalt Overlay

State of Maine, on which bids will be received until the time specified in the "Notice to Contractors" do(es) hereby bid and offer to enter into this contract to supply all the materials, tools, equipment and labor to construct the whole of the Work in strict accordance with the terms and conditions of this Contract at the unit prices in the attached "Schedule of Items".

The Offeror agrees to perform the work required at the price specified above and in accordance with the bids provided in the attached "Schedule of Items" in strict accordance with the terms of this solicitation, and to provide the appropriate insurance and bonds if this offer is accepted by the Government in writing.

As Offeror also agrees

First. To do any extra work, not covered by the attached "Schedule of Items", which may be ordered by the Resident, and to accept as full compensation the amount determined upon a "Force Account" basis as provided in the Standard Specifications, Revision of December 2002, and as addressed in the contract documents.

Second: That the bid bond at 5% of the bid amount or the official bank check, cashier's check, certificate of deposit or U. S. Postal Money Order in the amount given in the "Notice to Contractors", payable to the Treasurer of the State of Maine and accompanying this bid, shall be forfeited, as liquidated damages, if in case this bid is accepted, and the undersigned shall fail to abide by the terms and conditions of the offer and fail to furnish satisfactory insurance and Contract bonds under the conditions stipulated in the Specifications within 15 days of notice of intent to award the contract.

Third: To begin the Work on the date specified in the Engineer's "Notice to Commence Work" as stated in Section 107.2 of the Standard Specifications Revision of 2002 and complete the Work within the time limits given in the Special Provisions of this Contract.

Fourth: The Contractor will be bound to the Disadvantaged Business Enterprise (DBE) Requirements contained in the attached Notice (Additional Instructions to Bidders) and submit a completed Contractor's Disadvantaged Business Enterprise Utilization Plan by 4:30pm on the day of bid opening to the Contracts Engineer.

Fifth: That this offer shall remain open for 30 calendar days after the date of opening of bids.

Sixth: The Bidder hereby certifies, to the best of its knowledge and belief that: the Bidder has not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of competitive bidding in connection with its bid, and its subsequent contract with the Department.

execute two duplicate originals of this A terms, and obligations contained in the Co	CONTRACTOR (Sign Here) (Signature of Legally Authorized Representative of the Contractor)
G. Award. Your offer is hereby accepted.	(Print Name Here) (Name and Titlé Printed) This award consummates the Contract, and the
documents referenced herein.	MAINE DEPARTMENT OF TRANSPORTATION
Date	By: David A. Cole, Commissioner
(Witness)	

BOND #	
--------	--

CONTRACT PERFORMANCE BOND

(Surety Company Form)

KNOW ALL MEN BY THESE PRESENT	S: That	
and the State of		
and		
a corporation duly organized under the law usual place of business		=
as Surety, are held and firmly bound unto		
of		
to be paid said Treasurer of the State of payment well and truly to be made, Prince executors and administrators, successors presents.	Maine or his successors in o cipal and Surety bind themsel	ffice, for which ves, their heirs,
The condition of this obligation is such the Contract to construct Project Numpromptly and obligation shall be null and void; otherwise	faithfully performs the Cor	Municipality of atract, then this
The Surety hereby waives notice of any alt of Maine.	eration or extension of time m	ade by the State
Signed and sealed this	day of	20
WITNESSES:	SIGNATURES: CONTRACTOR:	
Signature		
Print Name Legibly	Print Name LegiblySURETY:	
Signature		
Print Name Legibly	Print Name Legibly	
SURETY ADDRESS:	NAME OF LOCAL AGENC	CY:
	ADDRESS	
TELEPHONE		

BOND #		
--------	--	--

CONTRACT PAYMENT BOND

(Surety Company Form)

and the State of	KNOW ALL MEN BY THESE PRES	SENTS: That		
a corporation duly organized under the laws of the State of	and the	e State of		, as principal,
as Surety, are held and firmly bound unto the Treasurer of the State of Maine for the us and benefit of claimants as herein below defined, in the sum of and 00/100 Dollars (\$ for the payment whereof Principal and Surety bind themselves, their heirs, executors an administrators, successors and assigns, jointly and severally by these presents. The condition of this obligation is such that if the Principal designated as Contractor is the Contract to construct Project Number in the Municipality of promptly satisfies all claims and demands incurred for a labor and material, used or required by him in connection with the work contemplated be said Contract, and fully reimburses the obligee for all outlay and expense which the obligee may incur in making good any default of said Principal, then this obligation shale be null and void; otherwise it shall remain in full force and effect. A claimant is defined as one having a direct contract with the Principal or with Subcontractor of the Principal for labor, material or both, used or reasonably required for use in the performance of the contract. Signed and sealed this day of	anda corporation duly organized under the	ne laws of the Stat	e of	and having a
and benefit of claimants as herein below defined, in the sum of and 00/100 Dollars (\$ for the payment whereof Principal and Surety bind themselves, their heirs, executors an administrators, successors and assigns, jointly and severally by these presents. The condition of this obligation is such that if the Principal designated as Contractor is the Contract to construct Project Number in the Municipality of promptly satisfies all claims and demands incurred for a labor and material, used or required by him in connection with the work contemplated be said Contract, and fully reimburses the obligee for all outlay and expense which the obligee may incur in making good any default of said Principal, then this obligation shalbe null and void; otherwise it shall remain in full force and effect. A claimant is defined as one having a direct contract with the Principal or with Subcontractor of the Principal for labor, material or both, used or reasonably required for use in the performance of the contract. Signed and sealed this				
for the payment whereof Principal and Surety bind themselves, their heirs, executors an administrators, successors and assigns, jointly and severally by these presents. The condition of this obligation is such that if the Principal designated as Contractor is the Contract to construct Project Number in the Municipality of promptly satisfies all claims and demands incurred for a labor and material, used or required by him in connection with the work contemplated be said Contract, and fully reimburses the obligee for all outlay and expense which the obligee may incur in making good any default of said Principal, then this obligation shabe null and void; otherwise it shall remain in full force and effect. A claimant is defined as one having a direct contract with the Principal or with Subcontractor of the Principal for labor, material or both, used or reasonably required for use in the performance of the contract. Signed and sealed this				
administrators, successors and assigns, jointly and severally by these presents. The condition of this obligation is such that if the Principal designated as Contractor is the Contract to construct Project Number in the Municipality of promptly satisfies all claims and demands incurred for a labor and material, used or required by him in connection with the work contemplated be said Contract, and fully reimburses the obligee for all outlay and expense which the obligee may incur in making good any default of said Principal, then this obligation shalbe null and void; otherwise it shall remain in full force and effect. A claimant is defined as one having a direct contract with the Principal or with Subcontractor of the Principal for labor, material or both, used or reasonably required for use in the performance of the contract. Signed and sealed this				
the Contract to construct Project Number in the Municipality of promptly satisfies all claims and demands incurred for a labor and material, used or required by him in connection with the work contemplated by said Contract, and fully reimburses the obligee for all outlay and expense which the obligee may incur in making good any default of said Principal, then this obligation shabe null and void; otherwise it shall remain in full force and effect. A claimant is defined as one having a direct contract with the Principal or with Subcontractor of the Principal for labor, material or both, used or reasonably required for use in the performance of the contract. Signed and sealed this		=		
Signed and sealed this day of	the Contract to construct Project	Number	in aims and der on with the wall outlay and Principal, then and effect.	the Municipality of mands incurred for all work contemplated by d expense which the n this obligation shall Principal or with a
WITNESS: SIGNATURES: CONTRACTOR: Signature Print Name Legibly SURETY: Signature Print Name Legibly Print Name Legibly Print Name Legibly	use in the performance of the contract	t.		
WITNESS: SIGNATURES: CONTRACTOR: Signature Print Name Legibly SURETY: Signature Print Name Legibly Print Name Legibly Print Name Legibly	Signed and sealed this	day of		20
Signature. Print Name Legibly Print Name Legibly SURETY: Signature. Print Name Legibly Print Name Legibly	_	SIGNATU	RES:	,
Print Name Legibly Print Name Legibly SURETY: Signature Print Name Legibly Print Name Legibly Print Name Legibly	Signature			
Print Name Legibly Print Name Legibly		Print Nam	e Legibly	
Print Name Legibly Print Name Legibly	Signature			
	_		e Legibly	
	SURETY ADDRESS:	NAME OF		
TELEPHONEviii				

SPECIAL PROVISION PARTNERING

The successful bidder will have the opportunity to enter into a cooperative partnership agreement with the State Department of Transportation for the contract. The objective of this agreement is the effective completion of the work on time and to the standard of quality that will be a source of pride to both the State and the Contractor. The partnering agreement will not affect the terms of the contract. It is intended only to establish an environment of cooperation between the partnering agreement is accepted.

- 1. Contractor shall select and provide a third-party facilitator to conduct the team building workshop for the Contractor and Department personnel. Facilitator selection shall require Department concurrence. The cost for the facilitator and his associated expenses will be shared equally by the Department on the next monthly estimate, following receipt of invoice(s) from the Contractor, on an extra work basis.
- 2. Contractor and Department will exchange lists of the key personnel to be participants in the workshop. The list will contain the name and job title of each person, a contact phone number, and the address for job related correspondence.
- 3. The Contractor shall select the location and make all arrangements for space as required by facilitator, and for any meals required. This cost to be shared equally.
- 4. A working arrangement for the partnership will be agreed upon in writing at the workshop. The arrangement will set out the mutually recognized goals and expectation of the parties.
- 5. The Contractor and the Department agree to make an effort to maintain identified key personnel assigned to the work for its duration. A timely notice by each shall be given if changes by either must be made.
- 6. Project issues shall be processed in the manner agreed upon by the parties during the orientation.
- 7. Follow-up workshops may be held periodically throughout the duration of the contract as agreed by the Contractor and the Department.
- 8. The Partnering Agreement is not intended to be a legal document. Failure by either party to follow the process identified will not be grounds for any claim under the contract.
- 9. ARE YOU INTERESTED IN THIS OPPORTUNITY? YES _____ NO ____

1 of 1 29

General Decision Number: ME080009 02/08/2008 ME9

Superseded General Decision Number: ME20070009

State: Maine

Construction Type: Highway

Counties: Aroostook, Franklin, Hancock, Kennebec, Knox, Lincoln, Oxford, Piscataquis, Sagadahoc, Somerset, Waldo and

York Counties in Maine.

HIGHWAY CONSTRUCTION PROJECTS excluding major bridging (for example: bascule, suspension and spandrel arch bridges; those bridging waters presently navigating or to be navigatable; and those involving marine construction in any degree); tunnels, building structures in rest area projects and railroad construction.

Modification Number Publication Date 0 02/08/2008

* ENGI0004-015 04/01/2007

	Rates	Fringes
Power equipment operators: Pavers	.\$ 17.58	8.30 8.30
SUME2000-008 10/24/2000		
	Rates	Fringes
Carpenter	.\$ 11.60	1.51
Ironworkers: Structural	.\$ 12.03	1.58
Laborers: Drillers Flaggers Guardrail Installers Landscape Line Stripper Pipelayers Rakers Sign Erectors Unskilled Wheelman	.\$ 6.00 .\$ 7.92 .\$ 7.87 .\$ 8.69 .\$ 9.21 .\$ 9.00 .\$ 10.00 .\$ 8.66	2.50 .16 .23 2.31 1.51 1.38 .43
Power equipment operators: Backhoes	.\$ 12.33 .\$ 14.06 .\$ 12.38 .\$ 13.06	2.05 2.88 1.75 2.48 3.73 2.87

Mechanics\$	13.18	2.57
Truck drivers:		
Dump\$	9.35	3.10
Tri axle\$	8.70	1.18
Two axle\$	8.56	2.19

WELDERS - Receive rate prescribed for craft performing operation to which welding is incidental.

Unlisted classifications needed for work not included within the scope of the classifications listed may be added after award only as provided in the labor standards contract clauses (29CFR 5.5 (a) (1) (ii)).

In the listing above, the "SU" designation means that rates listed under the identifier do not reflect collectively bargained wage and fringe benefit rates. Other designations indicate unions whose rates have been determined to be prevailing.

WAGE DETERMINATION APPEALS PROCESS

- 1.) Has there been an initial decision in the matter? This can be:
- * an existing published wage determination
- * a survey underlying a wage determination
- * a Wage and Hour Division letter setting forth a position on a wage determination matter
- * a conformance (additional classification and rate) ruling

On survey related matters, initial contact, including requests for summaries of surveys, should be with the Wage and Hour Regional Office for the area in which the survey was conducted because those Regional Offices have responsibility for the Davis-Bacon survey program. If the response from this initial contact is not satisfactory, then the process described in 2.) and 3.) should be followed.

With regard to any other matter not yet ripe for the formal process described here, initial contact should be with the Branch of Construction Wage Determinations. Write to:

Branch of Construction Wage Determinations Wage and Hour Division U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

2.) If the answer to the question in 1.) is yes, then an interested party (those affected by the action) can request review and reconsideration from the Wage and Hour Administrator (See 29 CFR Part 1.8 and 29 CFR Part 7). Write to:

Wage and Hour Administrator U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

The request should be accompanied by a full statement of the interested party's position and by any information (wage payment data, project description, area practice material, etc.) that the requestor considers relevant to the issue.

3.) If the decision of the Administrator is not favorable, an interested party may appeal directly to the Administrative Review Board (formerly the Wage Appeals Board). Write to:

Administrative Review Board U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

4.) All decisions by the Administrative Review Board are final.

END OF GENERAL DECISION

Town: Gardiner-Bowdoinham, I-295 SB Project: IM 1511(400)E, Pin 15114.00

Date: March 24, 2008

SPECIAL PROVISIONS SECTION 104 UTILITIES

MEETING

A Preconstruction Utility Conference, as defined in Subsection 104.4.6 of the Standard Specifications **is** required.

GENERAL

Utilities have been notified and will be furnished a project specification book. If utility relocations, though unexpected, become necessary, they will be scheduled in compliance with Section 104.4.6 of the Standard Specifications and will be done by the utilities in conjunction with the work by the Contractor.

Utility/Railroad	Aerial	Underground
Time Warner Cable	X	
Central Maine Power Company	X	
Verizon	X	
MaineCom Services	X	
Cobbosseecontee Telephone Company	X	
MDOT		X
Maine Natural Gas		X
Maritimes Northeast Pipeline		X

Temporary utility adjustments are **not** anticipated. If temporary relocation becomes necessary, sufficient time will need to be allowed prior to the construction for all required temporary relocation. If the **Contractor** feels temporary relocation is necessary they must notify the **Department** of their concerns prior to construction.

Any times and dates mentioned are estimates only and are dependent upon favorable weather, working conditions, and freedom from emergencies. The **Contractor** shall have no claim against the Department if they are exceeded.

Page 1 of 4 33

Town: **Gardiner, I-295 SB**Project: **IM 1592(900)E, I-295 SB**

Date: **February 14, 2008**

In all cases, the utilities shall be notified, by the **Contractor**, well in advance (three weeks) before work in any area is to commence.

Special note to Contractor and the Utilities: The Contractor shall plan and schedule his work in such a manner that the utilities that are located on this project will not be harmed, damaged or impacted in any way. The Contractor and Utility will coordinate and communicate their work plans in an effort not to interfere with each other's progress or the completion of the project.

Aerial

Several utilities have aerial wires crossings over I-295. These locations are at every bridge location that side roads either cross over or under I-295 and at all exits. No relocation or involvement of any kind is anticipated by the aerial utilities as part of this project but the contractor should be aware of these lines when using machines that are over legal heights.

CMP has a major high volt power line that crosses the project at mile marker 34.0. The contractor is once again advised to use caution when working in that area with over height machines.

Underground

Unless otherwise specified, any underground utility facilities indicated in these project documents represent approximate locations gathered from available information. The Department cannot certify the level of accuracy of this data. The contractor is required to notify the underground utility involved for more accurate layout of their facility.

Maine Department of Transportation

The Maine Department of Transportation has underground facilities in the form of highway lighting in and around Exits 31, 37, 43 and 49. Although no conflicts are anticipated, if the scope of the work changes to include subsurface work in the area of the lighting, the contractor shall contact Ron Cote at 624-3602 for location and marking of the facilities. There is also remote traffic warning speed signs on the shoulder of the project. Should any subsurface work be necessary in the vicinity of these sites, the contractor shall contact Debbie Morgan at 624-3606 for location and marking of the facilities. The contractor shall provide at least a five (5) working day notice before commencing any work in these areas.

Town: **Gardiner, I-295 SB**Project: **IM 1592(900)E, I-295 SB**

Date: **February 14, 2008**

Maine Natural Gas

Maine Natural Gas has a 6 inch poly gas main that crosses the project in the area of the Cathance River. Not knowing which machines the contractor will choose to accomplish the rubblization, Maine Natural Gas requests:

- 1. Through a utility coordination meeting, prior to the start of construction, Maine Natural Gas (MNG) is made aware of the schedule for the work in the vicinity of their pipe. The purpose will be so they can leak survey the area before and after the rubblizing occurs.
- 2. MNG will be notified well in advance (three weeks) if the equipment selected is other than the Antigo MHB (maximum lift: 60", maximum hammer weight: 2,000 pounds) or the Resonant Machines RHB. MNG feels other equipment warrants more analysis and would want to know the hammer size, weight, drop height, and frequency.

If it is determined that the rubblization process is having potential damage in any way, to Maine Natural Gas pipe, the contractor shall remove the slab by excavation method and be paid under item 202.126. The project Resident will determine the distance either side of Maine Natural Gas pipe for excavation removal, if that should be the case, with the help of the representative from Maine Natural Gas. That representative will be Gary Kenny and he can be reached at 207-729-0420, ext. 103.

Maritimes Northeast Pipeline

M&N Pipeline operates a 30" high pressure gas main that crosses the project at mile marker 42.8 approximately. (Line is well marked with yellow markers) Although the pipe has sufficient cover, Maritimes Northeast requires being able to definitively determine stress levels induced by the equipment used by the contractor. At this time, not knowing exactly which machines will be used, M&N Pipeline will need sufficient time to analyze the specs of the machines used. M&N Pipeline will require the same notification that Maine Natural Gas is requiring.

Regardless of what machines used, Maritimes Northeast will require concrete removal by excavation for at least 10 feet either side of their pipe line. The Resident and M&N Pipeline will give the contractor guidance if more than 20 feet is required. The contact for Maritimes Northeast is Don Thompson at 737-8249.

Town: Gardiner, I-295 SB
Project: IM 1592(900)E, I-295 SB
Date: February 14, 2008

DIG SAFE

The Contractor shall be responsible for determining the presence of underground utility facilities prior to commencing any excavation work and shall notify utilities of proposed excavation in accordance with M.R.S.A. Title 23 §3360-A, Maine "Dig Safe" System.

MAINTAINING UTILITY LOCATION MARKINGS

The Contractor will be responsible for maintaining the buried utility location markings following the initial locating by the appropriate utility or their designated representative.

THE CONTRACTOR SHALL PLAN AND CONDUCT HIS WORK ACCORDINGLY.

The following utilities are known to have facilities in the area of this project:

Central Maine Power Company	Gary Crabtree	791-8025
Verizon	Andrea Hanson	442-8018
Maritimes Northeast Pipeline	Don Thompson	737-8249
Maine Natural Gas	Gary Kenny	729-0420
State of Maine	Ron Cote	624-3602
	Debbie Morgan (Traffic)	624-3606
Time Warner Cable	Don Johnson	253-2291
Maine Com Services	Mark Curtis	441-9532
Cobbosseecontee Telephone Company	Benjie Ladabour	634-7300

IM-1511(400)E Pin 15114.00 Gardiner-Brunswick I-295 Southbound

SPECIAL PROVISION SECTION 104.4.2 Preconstruction Meeting

A preconstruction meeting has been scheduled ahead of time for May 1, 2008 from 9:00 am to 12:00 pm and May 5, 2008 from 9:00 am to 12:00 pm. The meeting will be held in Augusta at a Maine DOT facility. These meetings are contingent upon the contractor submitting their performance and payment bonds, certificate of insurance and DBE Utilization form one week prior to these scheduled meetings.

If there is a period of time between the award and preconstruction meetings, the Maine DOT is willing to hold a meeting to discuss traffic control in order to allow the contractor to work on signage of the project.

SPECIAL PROVISION 105 CONSTRUCTION AREA

A Construction Area located in the **Towns of Brunswick, Topsham, Bowdoin, Bowdoinham, Richmond and City of Gardiner** has been established by the Maine Department of Transportation (MDOT) in accordance with provisions of 29-A § 2382 Maine Revised Statutes Annotated (MRSA).

- (a) The section of highway under construction in Kennebec, Sagadahoc and Cumberland Counties, Project No. IM-1511(400)E is located on Interstate I-295 southbound, beginning 0.20 mi south of the Durham Road Overpass and extending northerly 21.80 mi. to 0.03 mi. south of the Exit 49 off ramp.
- Per 29-A § 2382 (7) MRSA, the MDOT may "issue permits for stated periods of time for loads and equipment employed on public way construction projects, United States Government projects or construction of private ways, when within construction areas established by the Department of Transportation. The permit:
 - A. Must be procured from the municipal officers for a construction area within that municipality;
 - B. May require the contractor to be responsible for damage to ways used in the construction areas and may provide for:
 - (1) Withholding by the agency contracting the work of final payment under contract; or
 - (2) The furnishing of a bond by the contractor to guarantee suitable repair or payment of damages.

The suitability of repairs or the amount of damage is to be determined by the Department of Transportation on state-maintained ways and bridges, otherwise by the municipal officers;


- C. May be granted by the Department of Transportation or by the state engineer in charge of the construction contract; and
- D. For construction areas, carries no fee and does not come within the scope of this section."

The Municipal Officers for the **Towns of Brunswick, Topsham, Bowdoin, Bowdoinham, Richmond and City of Gardiner** agreed that an Overlimit Permit will be issued to the Contractor for the purpose of using loads and equipment on municipal ways in excess of the limits as specified in 29-A MRSA, on the municipal ways as described in the "Construction Area".


As noted above, a bond may be required by the municipality, the exact amount of said bond to be determined prior to use of any municipal way. The MDOT will assist in determining the bond amount if requested by the municipality.

The maximum speed limits for trucks on any town way will be 25 mph (40 km per hour) unless a higher legal limit is specifically agreed upon in writing by the Municipal Officers concerned.

IM-1511(400)E



LOCATION MAP



Scale in Miles

SPECIAL PROVISION 105 OVERLIMIT PERMITS

Title 29-A § 2382 MRSA Overlimit Movement Permits.

- **1. Overlimit movement permits issued by State.** The Secretary of State, acting under guidelines and advice of the Commissioner of Transportation, may grant permits to move nondivisible objects having a length, width, height or weight greater than specified in this Title over a way or bridge maintained by the Department of Transportation
- **2. Permit fee.** The Secretary of State, with the advice of the Commissioner of Transportation, may set the fee for single trip permits, at not less than \$6, nor more than \$30, based on weight, height, length and width. The Secretary of State may, by rule, implement fees that have been set by the Commissioner of Transportation for multiple trip, long-term overweight movement permits. Rules established pursuant to this section are routine technical rules pursuant to Title 5, chapter 375, subchapter II-A.
- **3. County and municipal permits.** A county commissioner or municipal officer may grant a permit, for a reasonable fee, for travel over a way or bridge maintained by that county or municipality
- **4. Permits for weight.** A vehicle granted a permit for excess weight must first be registered for the maximum gross vehicle weight allowed for that vehicle.
- **5. Special mobile equipment.** The Secretary of State may grant a permit, for no more than one year, to move pneumatic-tire equipment under its own power, including Class A and Class B special mobile equipment, over ways and bridges maintained by the Department of Transportation. The fee for that permit is \$15 for each 30-day period.
- **6. Scope of permit.** A permit is limited to the particular vehicle or object to be moved, the trailer or semitrailer hauling the overlimit object and particular ways and bridges.
- **7. Construction permits.** A permit for a stated period of time may be issued for loads and equipment employed on public way construction projects, United States Government projects or construction of private ways, when within construction areas established by the Department of Transportation. The permit:
 - A. Must be procured from the municipal officers for a construction area within that municipality;
 - B. May require the contractor to be responsible for damage to ways used in the construction areas and may provide for:
 - (1) Withholding by the agency contracting the work of final payment under contract; or

Page 1 of 3 40

(2) The furnishing of a bond by the contractor to guarantee suitable repair or payment of damages.

The suitability of repairs or the amount of damage is to be determined by the Department of Transportation on state-maintained ways and bridges, otherwise by the municipal officers;

- C. May be granted by the Department of Transportation or by the state engineer in charge of the construction contract; and
- D. For construction areas, carries no fee and does not come within the scope of this section.
- **8.** Gross vehicle weight permits. The following may grant permits to operate a vehicle having a gross vehicle weight exceeding the prescribed limit:
 - A. The Secretary of State, with the consent of the Department of Transportation, for state and state aid highways and bridges within city or compact village limits;
 - B. Municipal officers, for all other ways and bridges within that city and compact village limits; and
 - C. The county commissioners, for county roads and bridges located in unorganized territory.
- **9. Pilot vehicles.** The following restrictions apply to pilot vehicles.
 - A. Pilot vehicles required by a permit must be equipped with warning lights and signs as required by the Secretary of State with the advice of the Department of Transportation.
 - B. Warning lights may be operated and lettering on the signs may be visible on a pilot vehicle only while it is escorting a vehicle with a permit on a public way.

With the advice of the Commissioner of Transportation and the Chief of the State Police, the Secretary of State shall establish rules for the operation of pilot vehicles.

9-A. Police escort. A person may not operate a single vehicle or a combination of vehicles of 125 feet or more in length or 16 feet or more in width on a public way unless the vehicle or combination of vehicles is accompanied by a police escort. The Secretary of State, with the advice of the Commissioner of Transportation, may require a police escort for vehicles of lesser dimensions.

Page 2 of 3 41

- A. The Bureau of State Police shall establish a fee for state police escorts to defray the costs of providing a police escort. A county sheriff or municipal police department may establish a fee to defray the costs of providing police escorts.
- B. The Bureau of State Police shall provide a police escort if a request is made by a permittee. A county sheriff or municipal police department may refuse a permittee's request for a police escort.
- C. A vehicle or combination of vehicles for which a police escort is required must be accompanied by a state police escort when operating on the interstate highway system.
- 10. Taxes paid. A permit for a mobile home may not be granted unless the applicant provides reasonable assurance that all property taxes, sewage disposal charges and drain and sewer assessments applicable to the mobile home, including those for the current tax year, have been paid or that the mobile home is exempt from those taxes. A municipality may waive the requirement that those taxes be paid before the issuance of a permit if the mobile home is to be moved from one location in the municipality to another location in the same municipality for purposes not related to the sale of the mobile home.
- **11. Violation.** A person who moves an object over the public way in violation of this section commits a traffic infraction.

Section History:

```
PL 1993, Ch. 683, §A2 (NEW).
```

PL 1993, Ch. 683, §B5 (AFF).

PL 1997, Ch. 144, §1,2 (AMD).

PL 1999, Ch. 117, §2 (AMD).

PL 1999, Ch. 125, §1 (AMD).

PL 1999, Ch. 580, §13 (AMD).

PL 2001, Ch. 671, §30 (AMD).

PL 2003, Ch. 166, §13 (AMD).

PL 2003, Ch. 452, §Q73,74 (AMD).

PL 2003, Ch. 452, §X2 (AFF).

Page 3 of 3 42

SPECIAL PROVISION <u>SECTION 105</u> General Scope of Work (Limitations of Operations)

Contractor will be allowed to commence work and end work daily according to the Department of Marine Resources Sunrise/Sunset Table at the following Web address (http://www.maine.gov/dmr/sunrise_table.htm). Contractor will be allowed to enter roadway at Sunrise and must be off the roadway before Sunset. "Any work conducted outside these times will require that the contractor provide appropriate lighting and safety attire for their employees in compliance with the MUTCD."

SPECIAL PROVISION SECTION 105

General Scope of Work (Environmental Requirements)

In-Water work consists of any activity conducted below the normal high water mark of a river, steam, brook, lake, pond or "Coastal Wetland" areas that are subject to tidal action during the highest tide level for the year which an activity is proposed as identified in the tide tables published by the National Ocean Service. http://www.oceanservice.noaa.gov/ For the full definition of "Coastal Wetlands", please refer to 38 MRSA 480-B(2)

I. In-Water Work shall not be allowed between the dates of 10/2 and 5/31.

(In-Water work is allowed from 6/1 to 10/1.)

- II. In-Water work window applies to the following water bodies at the following station #'s:
 - 1. Station 767+60;
 - 2. Station 868+67
 - 3. Station 909+50
 - 4. Station 1091+22
 - 5. Station 1129+00.
- III. Special Conditions:
 - 1. In-Water work shall be conducted during low flows.
- IV. Approvals:
 - 1. Temporary Soil Erosion and Water Pollution Control Plan
- V. All activities are <u>prohibited</u> (including placement and removal of cofferdams unless otherwise permitted by Regulatory Agencies) below the normal high water mark if outside the prescribed in-water work window, except for the following:
 - 1. Work within a cofferdam constructed according to MaineDOT's Standard Specifications and in adherence with the contractors approved "Soil Erosion and Water Pollution Control Plan".
- VI. No work is allowed that completely blocks a river, stream, or brook without providing downstream flow.

NOTE: Regulatory Review and Approval is required to modify the existing In-Water work window. Procedure to modify the existing in-water work window can be found on the back of this document or the next page.

PROCEDURE FOR PROCESSING ANY IN-WATER WORK EXTENSION

MaineDOT will not incur any claims as a result of an In-Water modification being denied.

The following procedure will assist in processing a review by the Regulatory Agencies when the in-water work restrictions of a permit need modification:

- The Contractor shall submit to the MaineDOT Resident in writing the in-water work extension request. The written request shall be submitted in accordance with State of MaineDOT Standard Specification section 107.4 Scheduling of Work This is a change in the contract, and per MaineDOT Standard Specification section 109, a contract modification is required.
- 2. The Contractor's written request shall have the following items identified for the MaineDOT Environmental Office to evaluate adequate justification to continue forward with the modification of existing Contract Permit Conditions:
 - A) Description of the scope of In-Water work
 - B) Total number of working days requested to complete the scope of In-Water work
 - C) The reason(s) the In-Water work cannot be done in accordance with the Permit Conditions and/or Special Provision 105 Specification.
 - D) Benefit(s) to the MaineDOT for this change of Contract requirement
 - E) Photographs of the area of work described
- 3. MaineDOT is held harmless from claims and liability if the request to "Modify" the Contract Permit Conditions are denied.
 - Please Note: depending on the level of State and Federal Permitting required for the project, permit modification timeframes will vary depending on revised consultations and approvals. Timeframes will vary from project to project (even site to site on individual projects) and contractors will not count this review/modification "timeframe" as time lost from doing in-water work.
- 4. If the request is approved by the Regulatory Agencies, then a Contract Modification will be issued by the MaineDOT Resident indicating the monetary and time commitment this change has on the MaineDOT's contract.

SPECIAL PROVISION <u>SECTION 105</u> CONTROL OF WORK

(Cooperation Between Contractors)

It is hereby brought to the Contractor's attention that the Department has awarded or plans to award contracts adjacent to the limits of this contract, which may be in progress simultaneously.

The Contractor shall cooperate with other Contractors at all times and provide project access as necessary and as directed by the Resident.

1 of 1 46

SPECIAL PROVISION

(Work within limits of the Maine Turnpike)

105.5.1 General Requirements

This Subsection is amended by the addition of the following:

The installation of construction signs on the Maine Turnpike shall be approved in advance by the Maine Turnpike Authority. The Contractor shall submit plans illustrating construction details and proposed locations. Signs shall be located behind guardrail or outside of the roadside recovery area or shall be installed on break away supports.

Change of Direction

The Contractor will not be allowed to use the median openings or toll plazas on the Maine Turnpike to reverse direction.

107.4.2 Schedule of Work Required

This Subsection is amended by the addition of the following:

The Contractor shall submit a schedule that shows all work on the Maine Turnpike that is anticipated for the following week. This schedule shall be transmitted to the Resident Engineer by noon Thursday of the preceding week. The Resident Engineer shall transmit this information to the Maine Turnpike Authority.

The following Subsections are added:

107.4.6 Prosecution of Work

The installation of signs on the Maine Turnpike will require a shoulder closure in accordance with the MUTCD. Southbound shoulder closures are allowed Monday thru Friday from 7:00 am to 2:00 pm.

110.3.8 Administrative & General Provisions

A. Additional Insured

The Maine Turnpike Authority shall be named as an additional insured.

.

SPECIAL PROVISION SECTION 105 GENERAL SCOPE OF WORK (LIMITATIONS OF OPERATIONS)

Maine Turnpike toll plaza

Contractor vehicles used to install, maintain, and remove traffic control devices on the Maine Turnpike are granted free use of the Turnpike at the Interchange 103 (Gardiner I-295) toll plaza while completing the traffic control operation. All other vehicles shall pay the required toll. The placement of traffic control devices on the Maine Turnpike shall be coordinated in advance with the Maine Turnpike Authority.

The Contractor will not be allowed to use the median openings or the toll plaza on the Maine Turnpike to reverse direction unless the opening is located within a passing lane closures on both roadways.

The Contractor will not be allowed to change direction within the Toll Plaza area. The limits of this area extend from the terminals of the median guardrail north and south of the toll plaza. This may require NB traffic to use exit109 in Augusta to change direction.

The Contractor will be assessed a traffic control violation every time any employee of the Contractor, Subcontractor or Supplier is observed using a median opening or toll plaza area to change direction on the Maine Turnpike. The fine will be deducted from monies owed to the Contractor.

All work within 1500' of the toll plaza shall be coordinated with the Maine Turnpike Authority.

The Contractor will be required to keep a minimum of two lanes in each direction open to traffic at the toll plaza at all times. The Contractor will not be allowed to close any lane(s) at the toll plaza without prior notification to the Maine Turnpike.

Traffic Control devices shall have a minimum spacing of 40' within 300' of the plaza.

SPECIAL PROVISION SECTION 105 GENERAL SCOPE OF WORK (LIMITATIONS OF OPERATIONS)

- 1. The Interstate will be completely shut down to all traffic from Station 712+50 to 1661+00 (Northerly limits of the project) starting June 16, 2008 at 12:00 am to August 31, 2008 at 11:59 pm.
- 2. The completion date for 100% of all work excluding work on ramps and acceleration and deceleration lanes is August 31, 2008 at 11:59 pm. Work on Ramps may continue after this date with shoulder closures only; however, traffic must be able to utilize the ramps between the hours of 6:30 am and 7:00 pm. Ramps may be closed down between the hours of 7:00 pm to 6:30 am with 72 hours notice.
- 3. Interstate Crossovers will not be allowed to be utilized to change direction. Crossovers may be used for storage areas; however sufficient room will be left for the utilization of law enforcement vehicles.
- 4. Work performed prior to June 16, 2008 at 12:00 am will be required to be completed in lane closures not to exceed 3 miles in length and must have at least two miles between each closure.
- 5. The contractor will be allowed to work 24 hours a day, seven days a week and all Holidays.
- 6. Items 605.09 Type B underdrain and 512.082 French Drains shall be completed 5 calendar days prior to rubblizing the concrete pavement in any one area.
- 7. The HMA surface layer/course on mainline will be required to be completed during daylight hours.
- 8. All pipe and rental items shall be completed in an area prior to the contractor commencing placement of HMA surface in a given area.

IM-1511(400)E Pin 15114.00 Gardiner-Brunswick I-295 Southbound

SPECIAL PROVISION <u>SECTION 105</u> CONTROL OF WORK

(Cooperation with Municipalities)

It is hereby brought to the Contractor's attention that the Department has begun to organize an incident management team with all the surrounding municipalities. The contractor shall be an active participant on this team and attend, at a minimum, weekly meetings discussing the incident management plan and contractor's work schedule and truck hauling route.

The contractor is expected to cooperate with the surrounding communities and follow through with any reasonable requests.

1 of 1 49

SPECIAL PROVISION <u>SECTION 106</u> QUALITY

(Quality Level Analysis- Structural Concrete)

<u>106.7.1 Standard Deviation Method</u> Under H. Replace the Method A payfactor with the following;

"Method A: PF = [32.5 + (Quality Level * 0.75)] * 0.01"

Page 1 of 1 50

IM-1511(400)E Pin 15114.00 Gardiner-Brunswick I-295 Southbound

SPECIAL PROVISION <u>SECTION 107</u> TIME

(Scheduling of Work and Truck Hauling Routes)

<u>Description:</u> The Contractor shall submit, at the time of their bid, a schedule of work and proposed locations of Hot Mix Asphalt Plants and proposed haul route for major construction material (such as hot mix asphalt and gravel).

SPECIAL PROVISION <u>SECTION 107</u> TIME

(Scheduling of Work – Projected Payment Schedule)

<u>Description</u> The Contractor shall also provide the Department with a Quarterly Projected Payment Schedule that estimates the value of the Work as scheduled, including requests for payment of Delivered Materials. The Projected Payment Schedule must be in accordance with the Contractor's Schedule of Work and prices submitted by the Contractor's Bid. The Contractor shall submit the Projected Payment Schedule as a condition of Award.

IM-1511(400)E Pin 15114.00 Gardiner-Brunswick I-295 Southbound

SPECIAL PROVISION SECTION 107 PROSECUTION AND PROGRESS (CONTRACT TIME)

- 1. The contractor will be allowed to commence work anytime after the award of the contract provided that all applicable plans required under this contract have been submitted and approved and a preconstruction meeting has been held.
- 2. The completion date for 100% of all work excluding work on ramps and acceleration and deceleration lanes is August 31 at 11:59 pm. See Special Provision 108 for incentives and disincentives. If the contractor has not completed this work by Augusta 31, 2008 at 11:59 pm, the contractor will not be allowed to have any lane closures September 5, 6, 7, 2008 but will still be charged the disincentive.
- 3. The completion date for this contract is October 18, 2008. For every calendar day past this date that the contract is not complete, the contractor will be charged \$10,000 in liquidated damages.
- 4. From station 511+00 to 712+50 must be completed by June 15, 2008. For every calendar past this date, the contractor will be charged \$25,000 in liquidated damages.

SPECIAL PROVISION <u>SECTION 108</u> PAYMENT

(Incentive/Disincentive)

The Contractor must complete all work as described in Special Provision 107 – Contract Time - #2, by 11:59 P.M., August 31st, 2008.

The Contractor will be paid an incentive for early completion or charged a disincentive for late completion. The maximum incentive will be 20 days. There will be no maximum disincentive.

The amount of the incentive paid will be based on the following formula:

\$55,000 X [Calendar Days]^{1.2}

Calendar Days = August 31st, 2008 – Actual Completion Date

The amount of the disincentive charged will be based on the following formula:

\$55,000 X [Calendar Days]^{1.2}

Calendar Days = Actual Completion Date – August 31st, 2008

All incentives/disincentives will be rounded to the nearest \$1,000 increment. Calendar Days will be calculated to the whole day; rounded down for early completion and rounded up for late completion.

Example:

Calendar Days from August 31 st	Incentive/Disincentive
5	\$379,000
10	\$872,000
15	\$1,418,000
20	\$2,003,000

1 of 1 54

SPECIAL PROVISION <u>SECTION 202</u> REMOVING STRUCTURES AND OBSTRUCTIONS

(Shoulder Rumble Strip)

<u>Description</u> This work shall consist of milling a pattern onto highway shoulders at the spacing, offset, width, and depth shown on the plans. Rumble strips shall not be placed across ramp openings, crossover openings, or bridges.

CONSTRUCTION REQUIREMENTS

Removing Material The bituminous material shall be removed by a cold milling machine capable of removing the pavement to the required depth and width. The machine must be adjustable to grind or plane on various cross-slopes. Salvage and disposal of bituminous material shall be in accordance with Section 203.

Equipment The equipment shall be a cold milling machine or a cold planing machine specially manufactured for rumble strips. This machine shall be capable of cutting 1200 rumble strips per hour of operation. The Contractor will perform a test section prior to rumble strip installation and at any time as directed by the Resident. The test section will be done to ensure that the machine is capable of milling the rumble strips in accordance with these specifications and the plans.

Method of Measurement Rumble strips will be measured by the meter [foot] longitudinally along the edge of the travelway. For rumbled strips that are broken at regular intervals to permit emergency stopping on shoulders for motorcycles, the length measured for payment shall include the full running length including the regular breaks. Breaks in rumble strip installation for acceleration lanes, deceleration lanes, and crossovers will not be included in the length measured for payment.

<u>Basis of Payment</u> The accepted quantity of rumble strips will be paid for at the unit price bid per foot [meter] which price will be full compensation for removing and salvaging the bituminous material and for any labor, equipment, and incidentals needed to complete this work.


Payment will be made under:

Pay Item Pay Unit


202.205 Rumble Strip - Shoulder

Foot [Meter]

1 of 1 55



EDGE OF TRAVELED WAY -TRAVELED WAY SHOULDER



PROPOSED RUMBLE STRIP

BREAK DETAIL

NOTES:

- I. SHOULDER RUMBLE STRIPS SHALL BE PLACED ON THE MEDIAN AND OUTSIDE SHOULDER AS SHOWN IN THE ABOVE DETAIL.
- 2.ON THE OUTSIDE SHOULDER, THE RUMBLE STRIP PLACEMENT SHALL BE BROKEN FOR A DISTANCE OF 20 FT FOR EVERY 80 FT PLACED.

SPECIAL PROVISIONS <u>SECTION 202</u> REMOVING STRUCTURES AND OBSTRUCTIONS

(Removing Portland Cement Concrete Pavement)

Section <u>202-Removing Structures and Obstructions</u>, subsection <u>202.01 Description</u> and <u>202.04-Removing Pavement Surface</u> of the December 2002 Revision of the Standard Specifications, has been removed and replaced in it's entirety by the following:

<u>202.01 Description</u> This work shall consist of removing, grinding, milling the top 3 inches +- of the existing 9 inch +- thick Portland Cement Concrete Pavement and salvaging or disposing of the material removed.

202.04 Removing Portland Cement Concrete Pavement The equipment for removing the Portland Cement Concrete Pavement shall be a power operated milling machine or grinder capable of removing the Portland Cement Concrete Pavement to the required depth, transverse cross slope, and profile grade by the use of an automated grade and slope control system. The controls shall automatically increase or decrease the pavement removal depth as required, and readily maintain desired cross slope, to compensate for surface irregularities in the existing pavement course. The equipment shall be capable of accurately establishing profile grades by referencing from a fixed reference such as a grade wire, or from the existing pavement surface using a 30 foot (9m) minimum contact ski (floating beam), or 24 foot (8m) non-contact grade control beam.

The Contractor shall locate and remove all objects in the pavement through the work area that would be detrimental to the milling or grinding machine.

The finished milled surface will be inspected before being accepted, and any deviations in the profile exceeding 1 inch under a 16 foot string line or straightedge placed parallel to the centerline will be corrected. Any deviations in the cross-slope that exceed 3/4 inch under a 3 10 foot string line or straightedge placed transversely to centerline will be corrected. All corrections will be made with approved methods and materials. Any areas that require corrective measures will be subject to the same acceptance tolerances. Excess material that becomes bonded to the milled surface will be removed to the Resident's satisfaction before the area is accepted.

IM-1511(400)E PIN 15114.00 Gardiner-Brunswick I-295 Southbound

SPECIAL PROVISIONS <u>SECTION 202</u> REMOVING STRUCTURES AND OBSTRUCTIONS

(Removing Portland Cement Concrete Pavement)

Section <u>202-Removing Structures and Obstructions</u>, subsection <u>202.01 Description</u> of the December 2002 Revision of the Standard Specifications, has been removed and replaced in it's entirety by the following and additions made to subsection 202.08 Basis of Payment:

<u>202.01 Description</u> This work shall consist of removing Portland Cement Concrete Pavement Slabs and salvaging or disposing of the material removed. The existing slabs measure approximately 12 feet wide by 20 feet long by 9 inches in depth.

The contractor may, at their option, choose to rubblize the concrete prior to removing the slabs. If so, the contractor will be paid by the square yard.

202.08 Basis of Payment

<u>Pay Item</u> 202.126 Removing Existing Concrete Slab Full Depth Pay Unit Square Yard

SPECIAL PROVISION <u>SECTION 203</u> EXCAVATION AND EMBANKMENT

(Dirty Borrow)

<u>Description</u>: This work shall consist of furnishing and placing dirty borrow for seeding, in reasonably close conformity with the thicknesses called for on the plans or as authorized by the Resident.

<u>Materials</u>: Materials shall conform to the requirements specified in the following Sections of Division 700 – Materials:

Common Borrow 703.18 Humus 717.09

Dirty Borrow shall meet the requirements of Section 703.18 Common Borrow with the following addition and deletions: 703.18 Second sentence, delete the word peat.

Dirty Borrow shall contain no particles or fragments with a maximum dimension in excess of the compacted thickness of the layer being placed.

The granular material must have at least 20 percent, but not more than 50 percent, of the minus 25 mm [1 in] material passing the 75 micron [No. 200] mesh sieve.

The Dirty Borrow must have an organic humus content of 3% to 8% as determined by ignition test.

The Contractor may elect to manufacture Dirty Borrow from a combination of project materials that the contractor is entitled to use, combined with other suitable materials furnished by the Contractor.

CONSTRUCTION REQUIREMENTS

<u>Application of Dirty Borrow:</u> Dirty Borrow shall be spread evenly and uniformly on prepared areas in a thickness as shown on the plans.

<u>Method of Measurement:</u> Dirty Borrow will be measured by the cubic meter [cubic yard] complete in place after finishing to the required depth as shown on the plans or directed by the Resident. Lateral measurements will be parallel with the slope of the ground.

<u>Basis of Payment</u>: The accepted quantities of dirty borrow will be paid for at the contract unit price per cubic meter [cubic yard] complete in place.

Payment shall be full compensation for furnishing and placing the Dirty Borrow.

Payment will be made under:

Pay Item 203.242 Dirty Borrow

Pay Unit Cubic Meter [Cubic Yard]

SPECIAL PROVISION <u>SECTION 203</u> EXCAVATION AND EMBANKMENT (Dredge Materials)

<u>Description:</u> Dredge Material (See MaineDOT Standard Specifications § 101.2) is regulated as a Special Waste.

In accordance with CMR 418, one hundred cubic yards or less of Dredge Material Beneficially Used in the area adjacent to and draining into the dredged water body is exempt from Beneficial Use Permits. The I-295 highway improvement project includes work associated with the extension and/or enhancement of several culverts. It is anticipated that the work on these individual culverts will result in less than 100 cubic yards of Dredge Materials. In light of this, at each culvert work area all of the Dredge Materials excavated will be placed into onsite Beneficial Use.

CONSTRUCTION REQUIREMENTS

<u>Management:</u> The contractor shall Beneficially Use all Dredge Material excavated at the individual culvert sites in areas adjacent to and draining into the dredged water body. No more than 100-cubic yards of Dredge Material may be excavated at any of the individual culvert sites.

Basis of Payment: Payment for the Beneficial Use of Dredge Material will be incidental to the Contract Pay Items.

Payment shall be full compensation for excavation, dewatering, managing, transporting, and placement of the Dredge Materials.

SPECIAL PROVISION <u>SECTION 205</u> SHOULDER RECONSTRUCTION

The following additions are made to Section 204 Subsections 204.10 and 204.11 of the December 2002 revision of the Standard Specifications.

204.10 Method of Measurement:

The quantity of add shoulder aggregate measured for payment will be the number of square yards measured in place.

204.11 Basis of Payment:

Pay Item Pay Unit 204.201 Add Shoulder Aggregate to Existing Shoulder Square Yard

SPECIAL PROVISION <u>SECTION 204</u> ADD SHOULDER AGGREGATE

<u>Description</u>: This work shall consist of adding new aggregate to existing shoulders by furnishing, placing, grading, and compacting new shoulder aggregate to required grade.

MATERIALS

<u>Aggregates</u>: New shoulder aggregate shall be material meeting the requirements of Special Provision 304 Dense Graded Aggregate.

Salvaged concrete slabs may be crushed and used as dense grade aggregate. The crushed concrete material shall be free of all steel.

CONSTRUCTION REQUIREMENTS

Existing Shoulder: The existing bituminous pavement shall be removed from the shoulders under item 202.202 Remove Pavement Surface. The existing granular material shall be compacted with a minimum of one pass from a 10 ton vibratory soil compactor roller with a minimum width of 84 inches. New shoulder aggregate shall then be added to the existing shoulder to the widths and grades required by typical sections or as directed by the Department in the field.

New Aggregate: New shoulder aggregate shall be material meeting the requirements of Special Provision 304 Dense Graded Aggregate. New aggregate material shall then be shaped to the cross-slope and grades shown on the plans, typicals, or as directed by the Department. New aggregate shall then be compacted with a minimum 10 ton vibratory roller with a minimum width of 84 inches. The new aggregate shall then be compacted by making a minimum of four passes with the required roller with a pass being down and back. If the Department determines more compaction effort is needed, more passes will be required.

<u>Surface Tolerance</u>: The completed surface of the shoulder shall be shaped and maintained to a uniform machine finish.

Method of Measurement: Add Shoulder Aggregate will be measured by the square yard.

1 of 2

IM-1511(400)E Pin 15114.00 Gardiner-Brunswick I-295 Southbound

<u>Basis of Payment</u>: The accepted quantity of Add Shoulder Aggregate to existing shoulder will be paid for at the contract unit price per square yard. Payment will be full compensation for furnishing, placing, grading, and compacting new aggregate to the required depth and dimensions on the plans and typicals or as directed in the field by the Department.

Additional material required as a result of cross-slope variance of the pavement surface will not be paid for directly, but will be considered incidental to the contract unit price per square yard of existing shoulder.

Payment will be made under:

Pay Item Pay Unit

204.201 Add Shoulder Aggregate to Existing Shoulder

Square Yard

2 of 2

SPECIAL PROVISION <u>SECTION 205</u> SHOULDER RECONSTRUCTION

The following additions are made to Section 205 Subsections 205.06 and 205.11 of the December 2002 revision of the Standard Specifications.

205.06 Method of Measurement:

The quantity of widening of existing shoulders measured for payment will be the number of square yards [square meters] measured in place.

205.11 Basis of Payment:

Pay Item 205.512 Widening of Existing Shoulder Pay Unit Square Yard

SPECIAL PROVISION <u>SECTION 304 & 703</u> DENSE GRADED AGGREGATES

<u>703.06</u> Aggregates for Base and Subbase. Part "A" and "B" of this subsection is amended by the addition of the following:

Dense graded crushed aggregate base may be manufactured from ledge or natural aggregates and shall be obtained from a source approved by the Resident. When tested by the Los Angeles wear test, the percent loss shall not exceed 25. The material will be tested before being used and retested at intervals of approximately 25%, 50%, and 75% completion of the course.

Salvaged concrete slabs may be crushed and used as dense grade aggregate. The crushed concrete material shall be free of all steel.

At least 50 percent by weight of the material coarser than the No. 4 sieve shall have at least one fractured face.

The material shall meet the grading requirements of the following table:

Percentage by Weight Passing Square Mesh Sieves
100
90-100
75-100
50-80
30-60
15-40
0-6

If Dense graded aggregate is used, the top two inches in the subbase shall meet the requirements of <u>411.12 Crushed Stone Surface</u>. Payment to be considered incidental to item 304.10

Page 1 of 1 65

SPECIAL PROVISION <u>SECTION 311</u> FULL DEPTH CONCRETE RUBBLIZATION

<u>311.01</u> <u>Description</u> This work shall consist of pulverizing/rubblizing Portland cement concrete pavement full depth to provide a rubblized concrete base on which to pave. The contractor shall grade and compact this material to the lines, grades, and dimensions shown on the plans or established in the field by the Resident.

MATERIALS

311.02 Rubblized Material Rubblized material shall consist of the existing Portland cement concrete pavement being rubblized to a material where all particles are 6 inches or less in the largest dimension. The particle sizes shall be 2 inches or less at the surface of the rubblized base.

311.021 New Aggregate and Additional Recycled Material New aggregate shall meet the requirements of Standard Specification 411 and Special Provision 411 Aggregate for Untreated Surface Course. New aggregate if required will be measured and paid for under item 411.10.

Recycled pavement material salvaged from the project or from off-site stockpiles may be used when processed prior to use so that 100% of the material passes a ³/₄ inch square mesh sieve. Recycled material shall be conditionally accepted at the source by the Resident. It shall be free of winter sand, granular fill, construction debris, and other materials not generally considered bituminous pavement.

Recycled concrete pavement slabs salvaged from the project may be used when processed prior to use so that 100% of the material passes a ³/₄ inch square mesh sieve. Recycled material shall be conditionally accepted at the source by the Resident. It shall be free of winter sand, granular fill, steel, construction debris, and other materials not generally considered concrete pavement.

EQUIPMENT

311.03 Concrete Rubblizer Rubblizing shall be accomplished with a resonant breaker that breaks the PCC pavement into the required particle sizes without damaging the existing subbase material and without excessively displacing the rubblized material into the base or subgrade. The rubblization equipment shall be a self-contained, self-propelled unit utilizing resonant frequency to produce a low amplitude breaking force. The concrete rubblizing machine shall be specifically manufactured for full-depth concrete rubblizing work and capable of reducing the required existing materials to a size that will meet the requirements of subsection 311.02 Rubblized Material. The rubblizing machine shall be equipped with an approved watering system which shall be used as needed to suppress dust generated by the rubblizing operation.

66

<u>311.04 Health and Safety/Right-to-Know</u> Portland cement is considered a hazardous chemical under US OSHA Hazard Communication Rule 29 CFR 1910.120, therefore, all Contractors and Subcontractors are required to notify their workers of the potential health hazards associated with working with Portland cement.

In no area of the work site, where cement or cement-pavement-gravel combination is being applied, re-worked, rolled or graded, shall respirable dust be allowed to exceed the NIOSH [1974] established respirable dust standard (RDS) recommended exposure limit (REL) of 0.05 mg/m3 (for up to a 10 hour workday during a 40 hour work week).

The Contractor shall notify the Resident before commencing any work that involves Portland cement application, reclaiming, rolling, or grading.

The Contractor shall designate a Hazardous Waste Operations "Competent Person" to provide direct on-site supervision plus health and safety monitoring for work in the Portland cement impacted sections of the project. The Competent Person shall have certified training and experience in field implementation of the aforementioned regulations.

<u>Submittals</u> The Contractor shall submit a site specific Health and Safety Plan (HASP) to the Resident at least two weeks in advance of any Portland cement related work on the project.

Health and Safety Monitoring In any area of the project where Portland cement is being worked, the Contractor's designated Competent Person shall monitor the worker breathing zone for respirable dust. In the event the OSHA respirable dust REL is exceeded, the Contractor's Competent Person shall direct operations to cease. Operations will not recommence until the situation is corrected and respirable air returns to acceptable levels. The Contractor shall provide all required health and safety monitoring equipment.

- <u>311.05 Rollers</u> The full depth concrete rubblized material shall be rolled with a 10 ton vibratory steel roller and Type II 18 ton pneumatic tire roller. The 10 ton steel roller shall have a minimum contact area per foot of 17 in² and a minimum width of 84 inches. The pneumatic tire roller shall meet the requirements of Section 401.10 and the minimum allowable tire pressure shall be 85 psi.
- <u>311.08 Surface Tolerance</u> The completed surface of the Full Depth concrete rubblization shall be shaped and maintained to a tolerance of 1 inch above or below the required cross sectional template.
- 311.09 Full Depth Rubblizing Procedure The existing concrete pavement material shall pulverized/rubblized into a homogeneous mass passing the gradation as specified in section 311.02. Material found not to meet the gradation as specified in section 311.02 shall be required to be reprocessed by the rubblizer. The material shall then be shaped to the cross-slope and grade shown on the plans, typicals, or as directed by the Resident and meeting the tolerances of section 311.08. The rubblized concrete shall then be compacted using the rollers specified in section 311.05. Each roller shall make four passes with a pass being down and back. The 10 ton vibratory roller shall make the initial four passes and then the Type II 18 ton pneumatic tire roller shall make the final four passes. If the rubblized material still shows signs of movement or lack of compaction more passes will be required.

If at this time it is apparent that the existing sub-grade and sub-base has been damaged, the contractor shall excavate down to sub-grade and replace with 304.13 Dense Graded Crushed Aggregate Sub-base from sub-grade to finish grade of the rubblized Portland Cement Concrete Pavement. If the Department determines the damage was caused by the contractor and their operations, The Department will not reimburse the contractor for any expenses to correct any damages.

Any exposed steel shall be removed prior to placing the leveling course.

After compaction of the rubblized concrete material, the contractor shall place a leveling course of new aggregate as needed and directed by the department. The new aggregate shall meet the requirements of section 311.021 and shall be paid for under item 411.10. This course will then be required to be compacted by making as many passes as needed with a 10 ton vibratory roller to assure the Department that the material is properly compacted. The leveling course of new aggregate shall be fine-graded to \pm 3/8 in tolerance.

Sufficient water shall be added during the compaction process to aid in the compaction of both the rubblized concrete material and the leveling course of new aggregate.

The resultant material shall be graded and compacted to the cross-slope and profile shown on the plans or as directed by the Resident. The Contractor will also be responsible for reestablishing the existing profile grade as specified on the typical, in the plans, or as directed by the resident in the field. The department's intent of the new profile grade is to be 5" +-higher than the old profile grade (except for areas like bridges and overpasses where the grade must be adjusted or for areas where the department wishes to correct minor depressions).

QUALITY CONTROL

<u>311.10 Quality Control</u> The Contractor shall operate in accordance with the approved Quality Control Plan (QCP) to assure a product meeting the contract requirements. The QCP shall meet the requirements of Section 106.4 - Quality Control and this Section. The Contractor shall not begin recycling operations until the Department approves the QCP in writing.

Prior to performing any rubblizing, the Department and the Contractor shall hold a Prerubblization conference to discuss the rubblizing schedule, type and amount of equipment to be used, sequence of operations, and traffic control. A copy of the QC random numbers for test pit locations to be used on the project shall be provided to the Resident. All field supervisors including the responsible onsite supervisor for the rubblizing operation shall attend this meeting.

The QCP shall address any items that affect the quality of the Rubblizing Process including, but not limited to, the following:

A. Make and type of rollers including weight, weight per inch of steel wheels, and average contact pressure for pneumatic tired rollers.

- B. Rubblizing operations including type of equipment, speed of equipment, monitoring, methods to ensure that segregation is minimized, and procedures for grading and compacting operations.
- C. Method of grade checks.
- D. Name, responsibilities, and qualifications of the Responsible onsite Rubblizing Supervisor experienced and knowledgeable with the process.
- E. Access to operators manual on all equipment.

The Project Superintendent shall be named in the QCP, and the responsibilities for successful implementation of the QCP shall be outlined.

At the initiation of and during rubblizing, establish, demonstrate and document the capability of the equipment, including the machine's speed and impact frequency to achieve the required results.

At a minimum frequency of one every 1500 feet per lane, inspect the rubblized concrete pavement full depth to determine whether the gradation is being met and whether the reinforcement is de-bonded. The resident may increase or decrease the frequency of inspection depending upon how successful the previous results have been.

The completed rubblized surface shall have a uniform appearance without unbroken strips of pavement, exposed reinforcement steel, rubberized crack seal material, and excessive voids or cross slope issues.

<u>311.12 Method of Measurement</u> Full Depth Concrete Rubblization will be measured by square yard.

<u>311.13 Basis of Payment</u> The accepted quantity of Full Depth Concrete Rubblization will be paid for at the contract unit price per square yard, complete in-place which price will be full compensation for furnishing all equipment and labor for rubblizing, grading, compacting, and for all incidentals necessary to complete the work.

The addition of materials to restore profile grade and/or cross-slope in areas shown on the plans or described in the construction notes will be paid separately under designated pay items within the contract.

Payments will be made under:

Pay Item Pay Unit

311.36 Full Depth Concrete Rubblization Square Yard

Page 4 of 4 69

SPECIAL PROVISION <u>DIVISION 400</u> PAVEMENTS

SECTION 401 - HOT MIX ASPHALT PAVEMENT

401.01 Description The Contractor shall furnish and place one or more courses of Hot Mix Asphalt Pavement (HMA) on an approved base in accordance with the contract documents and in reasonably close conformity with the lines, grades, thickness, and typical cross sections shown on the plans or established by the Resident. The Department will accept this work under Quality Assurance provisions, in accordance with these specifications and the requirements of Section 106 – Quality, the provisions of AASHTO M 323 except where otherwise noted in sections 401 and 703 of these specifications, and the Maine DOT Policies and Procedures for HMA Sampling and Testing.

401.02 Materials Materials shall meet the requirements specified in Section 700 - Materials:

Asphalt Cement 702.01 Aggregates for HMA Pavement 703.07 HMA Mixture Composition 703.09

401.021 Recycled Asphalt Materials Recycled Asphalt Pavement (RAP) may be introduced into the mixture at percentages approved by the Department. If approved by the Department, the Contractor shall provide documentation stating the source, average residual asphalt content, and stockpile gradations showing RAP materials have been sized to meet the maximum aggregate size requirements of each mix designation. The Department will obtain samples for verification and approval prior to its use.

In the event that RAP source or properties change, the Contractor shall notify the Department of the change and submit new documentation stating the new source or properties a minimum of 72 hours prior to the change to allow for obtaining new samples and approval.

401.03 Composition of Mixtures The Contractor shall compose the Hot Mix Asphalt Pavement with aggregate, Performance Graded Asphalt Binder (PGAB), and mineral filler if required. HMA shall be designed and tested according to AASHTO T312 and the volumetric criteria in Table 1. The Contractor shall size, uniformly grade, and combine the aggregate fractions in proportions that provide a mixture meeting the grading requirements of the Job Mix Formula (JMF). The Contractor may use a maximum of 15% reclaimed asphalt pavement (RAP) in any base, binder, surface, or shim course. The Contractor may be allowed to use more than 15% RAP, up to a maximum of 25% RAP, in a base, binder, or shim course provided that PG 58-34 asphalt binder is used in the mixture.

The Contractor shall submit for Department approval a JMF to the Central Laboratory in Bangor for each mixture to be supplied. The Department may approve 1 active design per nominal maximum size, per traffic level, per plant, plus a 9.5mm "fine" mix @ 50 gyrations for shimming and where required, a non-RAP design for bridge decks. The Department shall then have 15 calendar days in which to process a new design before approval. The JMF shall establish a single percentage of aggregate passing each sieve size within the limits shown in section 703.09. The mixture shall be designed and produced, including all production tolerances, to comply with the allowable control points for the particular type of mixture as outlined in 703.09. The JMF shall state the original source, gradation, and percentage to be used of each portion of the aggregate and mineral filler if required. It shall also state the proposed PGAB content, the name and

location of the refiner, the supplier, the source of PGAB submitted for approval, the type of PGAB modification if applicable, and the location of the terminal if applicable.

In addition, the Contractor shall provide the following information with the proposed JMF:

Properly completed JMF indicating all mix properties (Gmm, VMA, VFB, etc.)

Stockpile Gradation Summary

Design Aggregate Structure Consensus Property Summary

Design Aggregate Structure Trial Blend Gradation Plots (0.45 power chart)

Trial Blend Test Results for at least three different asphalt contents

Specific Gravity and temperature/viscosity charts for the PGAB to be used

Recommended mixing and compaction temperatures from the PGAB supplier

Material Safety Data Sheets (MSDS) For PGAB

Asphalt Content vs. Air Voids trial blend curve

Test report for Contractor's Verification sample

At the time of JMF submittal, the Contractor shall identify and make available the stockpiles of all proposed aggregates at the plant site. There must be a minimum of 135 Mg [150 ton] for stone stockpiles, 70 Mg [75] ton] for sand stockpiles, and 45 Mg [50 ton] of blend sand before the Department will sample. The Department shall obtain samples for laboratory testing. The Contractor shall also make available to the Department the PGAB proposed for use in the mix in sufficient quantity to test the properties of the asphalt and to produce samples for testing of the mixture. Before the start of paving, the Contractor and the Department shall split a production sample for evaluation. The Contractor shall test its split of the sample and determine if the results meet the requirements of the Department's written policy for mix design verification (See Maine DOT Policies and Procedures for HMA Sampling and Testing available at the Central Laboratory in Bangor). If the results are found to be acceptable, the Contractor will forward their results to the Department's Lab, which will test the Department's split of the sample. The results of the two split samples will be compared and shared between the Department and the Contractor. If the Department finds the mixture acceptable, an approved JMF will be forwarded to the Contractor and paving may commence. The first day's production shall be monitored, and the approval may be withdrawn if the mixture exhibits undesirable characteristics such as checking. shoving or displacement. The Contractor shall be allowed to submit aim changes within 24 hours of receipt of the first Acceptance test result. Adjustments will be allowed of up to 2% on the percent passing the 2.36 mm sieve through the 0.075 mm and 3% on the percent passing the 4.75 mm or larger sieves. Adjustments will be allowed on the %PGAB of up to 0.2%. Adjustments will be allowed on GMM of up to 0.010.

The Contractor shall submit a new JMF for approval each time a change in material source or materials properties is proposed. The same approval process shall be followed. The cold feed percentage of any aggregate may be adjusted up to 10 percentage points from the amount listed on the JMF, however no aggregate listed on the JMF shall be eliminated. The cold feed percentage for RAP may be adjusted up to 5 percentage points from the amount listed on the JMF but shall not exceed the maximum allowable percentage for RAP for the specific application.

TABLE 1: VOLUMETRIC DESIGN CRITERIA

Design ESAL's	Required Density (Percent of G _{mm})		Voids in the Mineral Aggregate (VMA)(Minimum Percent) Nominal Maximum Aggregate Size (mm)			Voids Filled with Binder (VFB)	Fines/Eff.			
(Millions)	N _{initial}	N_{design}	N_{max}	25	19	12.5	9.5	4.75	(Minimum %)	Binder Ratio
< 0.3	<u>≤</u> 91.5								70-80	
0.3 to <3	<u>≤</u> 90.5								65-80	
3 to <10		96.0	<u><</u> 98.0	13.0	14.0	15.0	16.0	16.0		0.6-1.2
10 to <30	<u>≤</u> 89.0								65-80*	
≥ 30										

^{*}For 9.5 mm nominal maximum aggregate size mixtures, the maximum VFB is 82.

^{*}For 4.75 mm nominal maximum aggregate size mixtures, the maximum VFB is 84.

<u>401.04 Temperature Requirements</u> After the JMF is established, the temperatures of the mixture shall conform to the following tolerances:

```
In the truck at the mixing plant – allowable range 135° to 163°C [275 to 325°F]
At the Paver – allowable range 135° to 163°C [275 to 325°F]
```

The JMF and the mix subsequently produced shall meet the requirements of Tables 1 and Section 703.07.

401.05 Performance Graded Asphalt Binder Unless otherwise noted in Special Provision 403 - Hot Bituminous Pavement, PGAB shall be 64-28, except that for mixtures containing greater than 15% but no more than 25% RAP the PGAB shall be PG 58-34. The PGAB shall meet the applicable requirements of AASHTO M320 - Standard Specification for PGAB. The Contractor shall provide the Department with an approved copy of the Quality Control Plan for PGAB in accordance with AASHTO R 26 Certifying Suppliers of PGAB.

401.06 Weather and Seasonal Limitations The State is divided into two paving zones as follows:

- <u>a. Zone 1</u> Areas north of US Route 2 from Gilead to Bangor and north of Route 9 from Bangor to Calais.
- b. Zone 2 Areas south of Zone 1 including the US Route 2 and Route 9 boundaries.

The Contractor may place Hot Mix Asphalt Pavement for use other than a traveled way wearing course in either Zone between the dates of April 15th and November 15th, provided that the air temperature as determined by an approved thermometer (placed in the shade at the paving location) is 4°C [40°F] or higher and the area to be paved is not frozen. The Contractor may place Hot Mix Asphalt Pavement as traveled way wearing course in Zone 1 between the dates of May 1st and the Saturday following October 1st and in Zone 2 between the dates of April 15th and the Saturday following October 15th, provided the air temperature determined as above is 10°C [50°F] or higher. For the purposes of this Section, the traveled way includes truck lanes, ramps, approach roads and auxiliary lanes. The atmospheric temperature for all courses on bridge decks shall be 10°C [50°F] or higher.

Hot Mix Asphalt Pavement used for curb, driveways, sidewalks, islands, or other incidentals is not subject to seasonal limitations, except that conditions shall be satisfactory for proper handling and finishing of the mixture. Unless otherwise specified, the Contractor shall not place Hot Mix Asphalt Pavement on a wet or frozen surface and the air temperature shall be 4°C [40°F] or higher.

On all sections of overlay with wearing courses less than 25 mm [1 in] thick, the wearing course for the travelway and adjacent shoulders shall be placed between the dates of May 15th and the Saturday following September 15th.

On all sections of overlay with wearing courses less than 1 inch thick, the wearing course for the travelway and adjacent shoulders shall be placed between the dates of June 1st and the Saturday following September 1st if the work is to be performed, either by contract requirement, or Contractor option, during conditions defined as "night work".

401.07 Hot Mix Asphalt Plant

401.071 General Requirements HMA plants shall conform to AASHTO M156.

<u>a. Truck Scales</u> When the hot mix asphalt is to be weighed on scales meeting the requirements of Section 108 - Payment, the scales shall be inspected and sealed by the State Sealer as often as the Department deems necessary to verify their accuracy.

Plant scales shall be checked prior to the start of the paving season, and each time a plant is moved to a new location. Subsequent checks will be made as determined by the Resident. The Contractor will have at least ten 20 Kg [50 pound] masses for scale testing.

401.072 Automation of Batching Batch plants shall be automated for weighing, recycling, and monitoring the system. In the case of a malfunction of the printing system, the requirements of Section 401.074 c. of this specification will apply.

The batch plant shall accurately proportion the various materials in the proper order by weight. The entire batching and mixing cycle shall be continuous and shall not require any manual operations. The batch plant shall use auxiliary interlock circuits to trigger an audible alarm whenever an error exceeding the acceptable tolerance occurs. Along with the alarm, the printer shall print an asterisk on the delivery slip in the same row containing the out-of-tolerance weight. The automatic proportioning system shall be capable of consistently delivering material within the full range of batch sizes. When RAP is being used, the plant must be capable of automatically compensating for the moisture content of the RAP.

All plants shall be equipped with an approved digital recording device. The delivery slip load ticket shall contain information required under Section 108.1.3 - Provisions Relating to Certain Measurements, Mass and paragraphs a, b, and c of Section 401.073

401.073 Automatic Ticket Printer System on Automatic HMA Plant An approved automatic ticket printer system shall be used with all approved automatic HMA plants. The requirements for delivery slips for payment of materials measured by weight, as given in the following Sections, shall be waived: 108.1.3 a., 108.1.3 b., 108.1.3 c., and 108.1.3 d. The automatic printed ticket will be considered as the Weight Certificate.

The requirements of Section 108.1.3 f. - Delivery Slips, shall be met by the weigh slip or ticket, printed by the automatic system, which accompanies each truckload, except for the following changes:

- a. The quantity information required shall be individual weights of each batch or total net weight of each truckload.
- b. Signatures (legible initials acceptable) of Weighmaster (required only in the event of a malfunction as described in 401.074 c.).
- c. The MDOT designation for the JMF.

<u>401.074 Weight Checks on Automatic HMA Plant</u> At least twice during each 5 days of production either of the following checks will be performed:

- a. A loaded truck may be intercepted and weighed on a platform scale that has been sealed by the State Sealer of Weights and Measures within the past 12 months. Whenever the discrepancy in net weights is greater than 1.0%, but does not exceed 1.5%, the plant inspector will notify the producer to take corrective action; payment will still be governed by the printed ticket. The producer will be allowed a period of two days to make any needed repairs to the plant and/or platform scales so that the discrepancy in net weights between the two is less than 1.0%. If the discrepancy exceeds 1.5%, the plant will be allowed to operate as long as payment is determined by truck platform scale net weight. Effective corrective action shall be taken within two working days.
- b. Where platform scales are not readily available, a check will be made to verify the accuracy and sensitivity of each scale within the normal weighing range and to assure that the interlocking devices and automatic printer system are functioning properly.

c. In the event of a malfunction of the automatic printer system, production may be continued without the use of platform truck scales for a period not to exceed the next two working days, providing total weights of each batch are recorded on weight tickets and certified by a Licensed Public Weighmaster.

<u>401.08 Hauling Equipment</u> Trucks for hauling Hot Mix Asphalt Pavement shall have tight, clean, and smooth metal dump bodies, which have been thinly coated with a small amount of approved release agent to prevent the mixture from adhering to the bodies.

All truck dump bodies shall have a cover of canvas or other water repellent material capable of heat retention, which completely covers the mixture. The cover shall be securely fastened on the truck, unless unloading.

All truck bodies shall have an opening on both sides, which will accommodate a thermometer stem. The opening shall be located near the midpoint of the body, at least 300 mm [12 in] above the bed.

<u>401.09 Pavers</u> Pavers shall be self-contained, self-propelled units with an activated screed (heated if necessary) capable of placing courses of Hot Mix Asphalt Pavement in full lane widths on the main line, shoulder or similar construction.

On projects with no price adjustment for smoothness, pavers shall be of sufficient class and size to place Hot Mix Asphalt Pavement over the full width of the mainline travel way with a 3 m [10 ft] minimum main screed with activated extensions.

The Contractor shall place Hot Mix Asphalt Pavement on the main line with a paver using an automatic grade and slope controlled screed, unless otherwise authorized by the Department. The controls shall automatically adjust the screed and increase or decrease the layer thickness to compensate for irregularities in the preceding course. The controls shall maintain the proper transverse slope and be readily adjustable so that transitions and superelevated curves can be properly paved. The controls shall operate from a fixed or moving reference such as a grade wire or ski type device (floating beam) with a minimum length of 10 m [30 ft], a non-contact grade control with a minimum span of 7.3 m [24 ft], except that a 12 m [40 ft] reference shall be used on Expressway projects.

The Contractor shall operate the paver in such a manner as to produce a visually uniform surface texture and a thickness within the requirements of Section 401.101 - Surface Tolerances. The paver shall have a receiving hopper with sufficient capacity for a uniform spreading operation and a distribution system to place the mixture uniformly, without segregation in front of the screed. The screed assembly shall produce a finished surface of the required evenness and texture without tearing, shoving, or gouging the mixture. Pavers with extendible screeds shall have auger extensions and tunnel extenders as per the manufacturer's recommendations, a copy of which shall be available if requested.

The Contractor shall have the paver at the project site sufficiently before the start of paving operations to be inspected and approved by the Department. The Contractor shall repair or replace any paver found worn or defective, either before or during placement, to the satisfaction of the Department. Pavers that produce an unevenly textured or non-uniform mat will be repaired or replaced before continuing to place HMA on MDOT projects. On a daily basis, the Contractor shall perform nuclear density testing across the mat being placed, at 300 mm [12 in] intervals. If the values vary by more than 2.0% from the mean, the Contractor shall make adjustments until the inconsistencies are remedied.

Failure to replace or repair defective placement equipment may result in a letter of suspension of work and notification of a quality control violation resulting in possible monetary penalties as governed by Section 106 - Quality

401.10 Rollers Rollers shall be static steel, pneumatic tire, or approved vibrator type. Rollers shall be in good mechanical condition, capable of starting and stopping smoothly, and be free from backlash when reversing direction. Rollers shall be equipped and operated in such a way as to prevent the picking up of hot mixed material by the roller surface. The use of rollers, which result in crushing of the aggregate or in displacement of the HMA will not be permitted. Any Hot Mix Asphalt Pavement that becomes loose, broken, contaminated, shows an excess or deficiency of Performance Graded Asphalt Binder, or is in any other way defective shall be removed and replaced at no additional cost with fresh Hot Mix Asphalt Pavement, which shall be immediately compacted to conform to the adjacent area.

The type of rollers to be used and their relative position in the compaction sequence shall generally be the Contractor's option, provided specification densities are attained and with the following requirements:

- a. On variable-depth courses, the first lift of pavement over gravel, reclaimed pavement, an irregular surface, or on bridges, at least one roller shall be 14.5 Mg [16 ton] pneumatic-tired. Unless otherwise allowed by the Resident, pneumatic-tired rollers shall be equipped with skirting to minimize the pickup of HMA materials from the paved surface. When required by the Resident, the roller shall be ballasted to 18.1 Mg [20 ton].
- b. Compaction with a vibratory or steel wheel roller shall precede pneumatic-tired rolling, unless otherwise authorized by the Department.
- c. Vibratory rollers shall not be operated in the vibratory mode when checking or cracking of the mat occurs, or on bridge decks.
- d. Any method, which results in cracking or checking of the mat, will be discontinued and corrective action taken.

The maximum operating speed for a steel wheel or pneumatic roller shall not exceed the manufacturer's recommendations, a copy of which shall be available if requested.

- 401.101 Surface Tolerances The Department will check surface tolerance utilizing the following methods:
 - a.) A 5 m [16 ft] straightedge or string line placed directly on the surface, parallel to the centerline of pavement.
 - b.) A 3 m [10 ft] straightedge or string line placed directly on the surface, transverse to the centerline of pavement.

The Contractor shall correct variations exceeding 6 mm [¼ in] by removing defective work and replacing it with new material as directed by the Department. The Contractor shall furnish a 10 foot straightedge for the Departments use.

<u>401.11 Preparation of Existing Surface</u> The Contractor shall thoroughly clean the surface upon which Hot Mix Asphalt Pavement is to be placed of all objectionable material. When the surface of the existing base or pavement is irregular, the Contractor shall bring it to uniform grade and cross section. All surfaces shall have a tack coat applied prior to placing any new HMA course. Tack coat shall conform to the requirements of Section 409 – Bituminous Tack Coat, Section 702 – Bituminous Material, and all applicable sections of the contract.

401.12 Hot Mix Asphalt Documentation The Contractor and the Department shall agree on the amount of Hot Mix Asphalt Pavement that has been placed each day.

<u>401.13 Preparation of Aggregates</u> The Contractor shall dry and heat the aggregates for the HMA to the required temperature. The Contractor shall properly adjust flames to avoid physical damage to the aggregate and to avoid depositing soot on the aggregate.

<u>401.14 Mixing</u> The Contractor shall combine the dried aggregate in the mixer in the amount of each fraction of aggregate required to meet the JMF. The Contractor shall measure the amount of PGAB and introduce it into the mixer in the amount specified by the JMF.

The Contractor shall produce the HMA at the temperature established by the JMF.

The Contractor shall dry the aggregate sufficiently so that the HMA will not flush, foam excessively, or displace excessively under the action of the rollers. The Contractor shall introduce the aggregate into the mixer at a temperature of not more than 14°C [25°F] above the temperature at which the viscosity of the PGAB being used is 0.150 Pa·s.

The Contractor shall store and introduce into the mixer the Performance Graded Asphalt Binder at a uniformly maintained temperature at which the viscosity of the PGAB is between 0.150 Pa·s and 0.300 Pa·s. The aggregate shall be coated completely and uniformly with a thorough distribution of the PGAB. The Contractor shall determine the wet mixing time for each plant and for each type of aggregate used.

<u>401.15 Spreading and Finishing</u> On areas where irregularities or unavoidable obstacles make the use of mechanical spreading and finishing equipment impracticable, the Contractor shall spread, rake, and lute the HMA with hand tools to provide the required compacted thickness.

On roads opened to two-way traffic, the Contractor shall place each course over the full width of the traveled way section being paved that day, unless otherwise noted by the Department in Section 403 - Hot Bituminous Pavement

<u>401.16 Compaction</u> Immediately after the Hot Mix Asphalt Pavement has been spread, struck off, and any surface irregularities adjusted, the Contractor shall thoroughly and uniformly compact the HMA by rolling.

The Contractor shall roll the surface when the mixture is in the proper condition and when the rolling does not cause undue displacement, cracking, or shoving. The Contractor shall prevent adhesion of the HMA to the rollers or vibrating compactors without the use of fuel oil or other petroleum based release agents.

The Contractor shall immediately correct any displacement occurring as a result of the reversing of the direction of a roller or from other causes to the satisfaction of the Department. Any operation other than placement of variable depth shim course that results in breakdown of the aggregate shall be discontinued. Any new pavement that shows obvious cracking, checking, or displacement shall be removed and replaced for the full lane width as directed by the Resident at no cost to the Department.

Along forms, curbs, headers, walls, and other places not accessible to the rollers, the Contractor shall thoroughly compact the HMA with mechanical vibrating compactors. The Contractor shall only use hand tamping in areas inaccessible to all other compaction equipment. On depressed areas, the Contractor may use a trench roller or cleated compression strips under a roller to transmit compression to the depressed area.

Any HMA that becomes unacceptable due to cooling, cracking, checking, segregation or deformation as a result of an interruption in mix delivery shall be removed and replaced, with material that meets contract specifications at no cost to the Department.

<u>401.17 Joints</u> The Contractor shall construct wearing course transverse joints in such a manner that minimum tolerances shown in Section 401.101 - Surface Tolerances are met when measured with a straightedge.

The paver shall always maintain a uniform head of HMA during the joint construction. The HMA shall be free of segregation and meet temperature requirements outlined in section 401.04. Transverse joints of the wearing course shall be straight and neatly trimmed. The Contractor may form a vertical face exposing the full depth of the course by inserting a header, by breaking the bond with the underlying course, or by cutting back with hand tools. The Department may allow feathered or "lap" joints on lower courses or when matching existing low type pavements.

Longitudinal joints shall be constructed in a manner that will best ensure joint integrity. Methods or activities that prove detrimental to the construction of sound longitudinal joints will be discontinued.

The Contractor shall apply a coating of emulsified asphalt immediately before paving all joints to the vertical face and 75 mm [3 in] of the adjacent portion of any pavement being overlaid except those formed by pavers operating in echelon. The Contractor shall use an approved spray apparatus designed for covering a narrow surface. The Department may approve application by a brush for small surfaces, or in the event of a malfunction of the spray apparatus, but for a period of not more than one working day.

Where pavement under this contract joins an existing pavement or when the Department directs, the Contractor shall cut the existing pavement along a smooth line, producing a neat, even, vertical joint. The Department will not permit broken or raveled edges. The cost of all work necessary for the preparation of joints is incidental to related contract pay items.

401.18 Quality Control Method A, B & C The Contractor shall operate in accordance with the approved Quality Control Plan (QCP) to assure a product meeting the contract requirements. The QCP shall meet the requirements of Section 106.6 - Acceptance and this Section. The Contractor shall not begin paving operations until the Department approves the QCP in writing.

Prior to placing any mix, the Department and the Contractor shall hold a Pre-paving conference to discuss the paving schedule, source of mix, type and amount of equipment to be used, sequence of paving pattern, rate of mix supply, random sampling, project lots and sublots and traffic control. A copy of the QC random numbers to be used on the project shall be provided to The Resident. The Departments' random numbers for Acceptance testing shall be generated and on file with the Resident and the Project Manager. All field and plant supervisors including the responsible onsite paving supervisor shall attend this meeting.

The QCP shall address any items that affect the quality of the Hot Mix Asphalt Pavement including, but not limited to, the following:

- a. JMF(s)
- b. Hot mix asphalt plant details
- c. Stockpile Management (to include provisions for a minimum 2 day stockpile)
- d. Make and type of paver(s)
- e. Make and type of rollers including weight, weight per inch of steel wheels, and average contact pressure for pneumatic tired rollers
- f. Name of QCP Administrator, and certification number
- g. Name of Process Control Technician(s) and certification number(s)
- h. Name of Quality Control Technicians(s) and certification number(s)
- i. Mixing & transportation including process for ensuring that truck bodies are clean and free of debris or contamination that could adversely affect the finished pavement
- j. Testing Plan

- k. Laydown operations including longitudinal joint construction, procedures for avoiding paving in inclement weather, type of release agent to be used on trucks tools and rollers, compaction of shoulders, tacking of all joints, methods to ensure that segregation is minimized, procedures to determine the maximum rolling and paving speeds based on best engineering practices as well as past experience in achieving the best possible smoothness of the pavement
- 1. Examples of Quality Control forms including a daily plant report and a daily paving report
- m. Silo management and details (can show storage for use on project of up to 36 hours)
- n. Provisions for varying mix temperature due to extraordinary conditions
- o. Name and responsibilities of the Responsible onsite Paving Supervisor
- p. Method for calibration/verification of Density Gauge
- q. A note that all testing will be done in accordance with AASHTO and the Maine DOT Policies and Procedures for HMA Sampling and Testing.
- r. A note detailing conditions under which the percent of RAP will vary from that specified on the JMF
- s. A note detailing when production will be halted due to QC testing results.

The QCP shall include the following technicians together with these minimum requirements:

- a. QCP Administrator A qualified individual shall administer the QCP. The QCP Administrator must be a full-time employee of or a consultant engaged by the Contractor or paving subcontractor. The QCP Administrator shall have full authority to institute any and all actions necessary for the successful operation of the QCP. The QCP Administrator (or its designee in the QCP Administrator's absence) shall be available to communicate with the Department at all times. The QCP Administrator shall be certified as a Quality Assurance Technologist certified by the New England Transportation Technician Certification Program (NETTCP).
- b. Process Control Technician(s) (PCT) shall utilize test results and other quality control practices to assure the quality of aggregates and other mix components and control proportioning to meet the JMF(s). The PCT shall inspect all equipment used in mixing to assure it is operating properly and that mixing conforms to the mix design(s) and other Contract requirements. The QCP shall detail how these duties and responsibilities are to be accomplished and documented, and whether more than one PCT is required. The Plan shall include the criteria to be utilized by the PCT to correct or reject unsatisfactory materials. The PCT shall be certified as a Plant Technician by the NETTCP.
- c. Quality Control Technician(s) (QCT) shall perform and utilize quality control tests at the job site to assure that delivered materials meet the requirements of the JMF(s). The QCT shall inspect all equipment utilized in transporting, laydown, and compacting to assure it is operating properly and that all laydown and compaction conform to the Contract requirements. The QCP shall detail how these duties and responsibilities are to be accomplished and documented, and whether more than one QCT is required. The QCP shall include the criteria utilized by the QCT to correct or reject unsatisfactory materials. The QCT shall be certified as a Paving Inspector by the NETTCP.

The QCP shall detail the coordination of the activities of the Plan Administrator, the PCT and the QCT. The Project Superintendent shall be named in the QCP, and the responsibilities for successful implementation of the QCP shall be outlined.

The Contractor shall sample, test, and evaluate Hot Mix Asphalt Pavement in accordance with the following minimum frequencies:

TABLE 2: MINIMUM QUALITY CONTROL FREQUENCIES

Test or Action	Frequency	Test Method
Temperature of mix	6 per day at street and plant	-
Temperature of mat	4 per day	-
%TMD (Surface)	1 per 115 Mg [125 ton]	ASTM D2950
	(As noted in QC Plan)	
%TMD (Base)	1 per 225 Mg [250 ton]	AASHTO T269
	(As noted in QC Plan)	
Fines / Effective Binder	1 per 450 Mg [500 ton]	AASHTO T 312*
Gradation	1 per 450 Mg [500 ton]	AASHTO T30
PGAB content	1 per 460 Mg [500 ton]	AASHTO T164
		or T308
Voids at N _{design}	1 per 450 Mg [500 ton]	AASHTO T 312*
Voids in Mineral Aggregate at	1 per 450 Mg [500 ton]	AASHTO T 312*
N _{design}		
Rice Specific Gravity	1 per 450 Mg [500 ton]	AASHTO T209
Coarse Aggregate Angularity	1 per 4500 Mg [5000 ton]	ASTM D5821
Flat and Elongated Particles	1 Per 4500 Mg [5000 ton]	ASTM D4791
Fine Aggregate Angularity	1 Per 4500 Mg [5000 ton]	AASHTO T304

^{*}Method A and B only.

The Contractor may utilize innovative equipment or techniques not addressed by the Contract documents to produce or monitor the production of the mix, subject to approval by the Department.

The Contractor shall submit all Hot Mix Asphalt Pavement plant test reports, inspection reports and updated pay factors in writing, signed by the appropriate technician and present them to the Department by 1:00 P.M. on the next working day, except when otherwise noted in the QCP due to local restrictions. The Contractor shall also retain splits of the previous 5 QC tests, with QC results enclosed for random selection and testing by The Department during QA inspections of the HMA production facility. Test results of splits that do not meet the Dispute Resolution Variance Limits in Table 10 shall trigger an investigation by the MDOT Independent Assurance Unit, and may result in that lab losing NETTCP certification and the ability to request a dispute [Section 401.223 - Process for Dispute Resolution (Methods A, B and C only)].

The Contractor shall make density test results, including randomly sampled densities, available to the Department onsite. Summaries of each day's results, including a daily paving report, shall be recorded and signed by the QCT and presented to the Department by 1:00 p.m. the next working day.

The Contractor shall have a testing lab at the plant site, equipped with all testing equipment necessary to complete the tests in Table 2. The Contractor shall locate an approved SHRP Gyratory Compactor at the plant testing lab or within 30 minutes of the plant site.

The Contractor shall fill all holes in the pavement resulting from cutting cores by the Contractor or the Department with a properly compacted, acceptable mixture no later than the following working day. Before filling, the Contractor shall carefully clean the holes and apply a coating of emulsified asphalt. On surface courses, cores shall not be cut except for Verification of the Nuclear Density Gauge, at a rate not to exceed 3 per day or 2 per 900 Mg [1000 ton] placed.

The Contractor shall monitor plant production using running average of three control charts as specified in Section 106 - Quality. Control limits shall be as noted in Table 3 below. The UCL and LCL, shall not exceed the allowable control points for the particular type of mixture as outlined in Table 1 of section 703.09

TABLE 3: Control Limits

Property	UCL and LCL
Passing 4.75 mm and larger sieves	Target +/-4.0
Passing 2.36 mm sieve	Target +/-2.5
Passing .075 mm sieve	Target +/-1.2
PGAB Content*	Target +/-0.3
Voids in the Mineral Aggregate	LCL = LSL + 0.2
% Voids at N _{design}	JMF Target +/-1.3

^{*}Based on AASHTO T 308

The Contractor shall cease paving operations whenever one of the following occurs on a lot in progress:

- a. Methods A and B: The Pay Factor for VMA, Voids @ N_d, Percent PGAB, composite gradation, VFB, fines to effective binder or density using all Acceptance or all Quality Control tests for the current lot is less than 0.85. Method C: The Pay Factor for VMA, Voids @ N_d, Percent PGAB, percent passing the nominal maximum sieve, percent passing 2.36 mm sieve, percent passing 0.300 mm sieve or percent passing 0.075 mm sieve using all Acceptance or all available Quality Control tests for the current lot is less than 0.85.
- b. The Coarse Aggregate Angularity or Fine Aggregate Angularity value falls below the requirements of Table 3: Aggregate Consensus Properties Criteria for the design traffic level.
- c. Each of the first 2 control tests for a Method A or B_lot_fall outside the upper or lower limits for VMA, Voids @ Nd, or Percent PGAB; or under Method C, each of the first 2 control tests for the lot fall outside the upper or lower limits for the individual gradation sieve sizes as required in Table 3, or Percent PGAB.
- d. The Flat and Elongated Particles value exceeds 10% by ASTM D4791.
- e. There is any visible damage to the aggregate due to over-densification other than on variable depth shim courses.
- f. The Contractor fails to follow the approved QCP.
- g. The Contractor's control chart shows the process to be out of control (defined as a single point outside of the control limits on the running average of three chart.) on any property listed in Table 3: Control Limits.

Paving operations shall not resume until the Contactor and the Department determines that material meeting the Contract requirements will be produced. The Department will consider corrective action acceptable if the pay factor for the failing property increases, based on samples already in transit, or a verification sample is tested and the property falls within the specification limits.

The Department retains the exclusive right, with the exception of the first day's production of a new JMF, to determine whether the resumption of production involves a significant change to the production process. If the Department so determines, then the current lot will be terminated, a pay factor established, and a new lot will begin.

401.19 Quality Control Method D For Items covered under Method D, the Contractor shall submit a modified QC Plan detailing, how the mix is to be placed, what equipment is to be used, and what HMA plant is to be used. All mix designs (JMF) shall be approved and verified by MDOT prior to use. Certified QC personnel shall not be required. The Contractor shall certify the mix and the test results for each item by a Certificate of Compliance.

401.20 Acceptance Method A, B & C These methods utilizes Quality Level Analysis and pay factor specifications.

For Hot Mix Asphalt Pavement designated for acceptance under Quality Assurance provisions, the Department will sample once per sublot on a statistically random basis, test, and evaluate in accordance with the following Acceptance Criteria:

PROPERTIES	POINT OF	TEST METHOD
	SAMPLING	
Gradation	Paver Hopper	AASHTO T30
PGAB Content	Paver Hopper	AASHTO T308
%TMD	Mat behind all Rollers	AASHTO T269
(Surface)		
%TMD (Base	Mat behind all Rollers	AASHTO T269
or Binder)		
Air Voids at N _d	Paver Hopper	AASHTO T 312
%VMA at N _d	Paver Hopper	AASHTO T 312
Fines to	Paver Hopper	AASHTO T 312
Effective Binder		
%VFB	Paver Hopper	AASHTO T 312

TABLE 4: ACCEPTANCE CRITERIA

On the first day of production in the current calendar year, or the first day of production of a new JMF the Department will take three random samples, which will be used to calculate the quality level of the in-place material in the event the lot is terminated prematurely. Only one of the three will be tested, the other two will be held onsite until at least three random samples have been taken, at which time the other two will be discarded.

<u>Lot Size</u> For purposes of evaluating all acceptance test properties, a lot shall consist of the total quantity represented by each item listed under the lot size heading.

If the Department terminates a Lot prematurely, the samples from the first day's production will be used to calculate a volumetric pay factor, and a minimum of three cores will be used for a density pay factor, if applicable, for quantities placed to date.

<u>Sublot size</u> - Refer to section 401.201, 401.202, and 401.203 for minimum size and number of sublots. The quantity represented by each sample will constitute a sublot.

If there is less than one-half of a sublot remaining at the end, then it shall be combined with the previous sublot. If there is more than one-half sublot remaining at the end, then it shall constitute the last sublot and shall be represented by test results. If it becomes apparent partway through a Lot that, due to an underrun, there will be insufficient mix quantity to obtain the minimum number of sublots needed, the Resident may adjust the size of the remaining sublots and select new sample locations based on the estimated quantity of material remaining in the Lot.

Acceptance Testing The Department will obtain samples of Hot Mix Asphalt Pavement in conformance with AASHTO T168 Sampling Bituminous Paving Mixtures, and the Maine DOT Policies and Procedures for HMA Sampling and Testing, which will then be transported by the Contractor to the designated MDOT Laboratory within 48 hours (except when otherwise noted in the project specific QCP due to local restrictions), as directed by MDOT in approved transport containers to be provided by the Department, unless otherwise directed by the Resident. The Department will take the sample randomly within each sublot. Target values shall be as specified in the JMF. The Department will use Table 5 for calculating pay factors for gradation, PGAB Content, Air Voids at N_{design}, VMA, Fines to Effective Binder and VFB. The Department will withhold reporting of the test results for the Acceptance sample until 7:00 AM, on the second working day of receipt of the sample, or after receipt of the Contractors results of the Acceptance sample split. Upon conclusion of each lot, where there is a minimum of four sublots, results shall be examined for statistical outliers, as stated in Section 106.7.2 - Statistical Outliers.

<u>Isolated Areas</u> During the course of inspection, should it appear that there is an isolated area that is not representative of the lot based on a lack of observed compactive effort, excessive segregation or any other questionable practice, that area may be isolated and tested separately. An area so isolated that has a calculated pay factor below 0.80, based on three random tests shall be removed and replaced at the expense of the Contractor for the full lane width and a length not to be less than 50 m [150 ft].

Pavement Density The Department will measure pavement density using core samples tested according to AASHTO T-166. The Department will randomly determine core locations. The Contractor shall cut 6 inch diameter cores at no additional cost to the Department by the end of the working day following the day the pavement is placed, and immediately give them to the Department. The cores will be placed in a transport container provided by the Department and transported by the Contractor to the designated MDOT Lab as directed by the Department. Pre-testing of the cores will not be allowed. At the time of sampling, the Contractor and the Department shall mutually determine if a core is damaged. If it is determined that the core(s) is damaged, the Contractor shall cut new core(s) at the same offset and within 1 m [3 ft] of the initial sample. At the time the core is cut, the Contractor and the Department will mutually determine if saw cutting of the core is needed, and will mark the core at the point where sawing is needed. The core may be saw cut by the Contractor in the Department's presence onsite, or in an MDOT Lab by The Department, without disturbing the layer being tested to remove lower layers of Hot Mix Asphalt Pavement, gravel, or RAP. No recuts are allowed at a test location after the core has been tested. Upon conclusion of each lot, density results shall be examined for statistical outliers as stated in Section 106.7.2.

On all sections of overlay with wearing courses designed to be 19 mm [3/4 in] or less in thickness, there shall be no pay adjustment for density otherwise noted in Section 403 - Hot Bituminous Pavement. For overlays designed to be 19 mm [3/4 in] or less in thickness, density shall be obtained by the same rolling train and methods as used on mainline travelway surface courses with a pay adjustments for density, unless otherwise directed by the Department.

There shall be no pay adjustment for density on shoulders unless otherwise noted in Section 403 - Hot Bituminous Pavement. Density for shoulders shall be obtained by the same rolling train and methods as used on mainline travelway, unless otherwise directed by the Department. Efforts to obtain optimum compaction will not be waived by the Department unless it is apparent during construction that local conditions make densification to this point detrimental to the finished pavement surface course.

401.201 Method A Lot Size will be the entire production per JMF for the project, or if so agreed at the Prepaving Conference, equal lots of up to 4050 Mg [4500 tons], with unanticipated over-runs of up to 1350 Mg [1500 ton] rolled into the last lot. Sublot sizes shall be 675 Mg [750 ton] for mixture properties, 450 Mg [500 ton] for base or binder densities and 225 Mg [250 ton] for surface densities. The minimum number of sublots for mixture properties shall be 4, and the minimum number of sublots for density shall be five.

TABLE 5: METHOD A ACCEPTANCE LIMITS

Property	USL and LSL
Passing 4.75 mm and larger sieves	Target +/-7%
Passing 2.36 mm to 1.18 mm sieves	Target +/-4%
Passing 0.60 mm	Target +/-3%
Passing 0.30 mm to 0.075 mm sieve	Target +/-2%
PGAB Content	Target +/-0.4%
Air Voids	4.0% +/-1.5%
Fines to Effective Binder	0.6 to 1.2
Voids in the Mineral Aggregate	LSL Only from Table 1
Voids Filled with Binder	Table 1 values plus a 4%
	production tolerance for USL only
% TMD (In place density)	95.0% +/- 2.5%

401.202 Method B Lot Size will be the entire production per JMF for the project and shall be divided into 3 equal sublots for Mixture Properties and 3 equal sublots for density.

TABLE 6: METHOD B ACCEPTANCE LIMITS

111525 0, 1/1511105	THE ELIVITY
Property	USL and LSL
Percent Passing 4.75 mm and larger sieves	Target +/-7
Percent Passing 2.36 mm to 1.18 mm sieves	Target +/-5
Percent Passing 0.60 mm	Target +/-4
Percent Passing 0.30 mm to 0.075 mm sieve	Target +/-3
PGAB Content	Target +/-0.5
Air Voids	4.0% +/-2.0
Fines to Effective Binder	0.6 to 1.4
Voids in the Mineral Aggregate LSL from Table 1	
Voids Filled with Binder	Table 1 plus a 4% production tolerance for USL.
% TMD (In-place Density) 95.0% +/- 2.5%	

401.203 Testing Method C Lot Size will be the entire production per JMF for the project, or if so agreed at the Pre-paving Conference, equal lots of up to 4050 Mg [4500 tons], with unanticipated over-runs of up to 1350 Mg [1500 ton] rolled into the last lot. Sublot sizes shall be 675 Mg [750 ton] for mixture properties, 450 Mg [500 ton] for base or binder densities and 225 Mg [250 ton] for surface densities. The minimum number of sublots for mixture properties shall be 4, and the minimum number of sublots for density shall be five.

TABLE 7: METHOD C ACCEPTANCE LIMITS

Property	USL and LSL
Passing 4.75 mm and larger sieves	Target +/-7%
Passing 2.36 mm to 1.18 mm sieves	Target +/-4%
Passing 0.60 mm	Target +/-3%
Passing 0.30 mm to 0.075 mm sieve	Target +/-2%
PGAB Content	Target +/-0.4%
Air Voids	4.0% +/-1.5%
Fines to Effective Binder	0.6 to 1.2
Voids in the Mineral Aggregate	LSL Only from Table 1
Voids Filled with Binder	Table 1 values plus a 4% production
	tolerance for USL only
% TMD (In place density)	95.0% +/- 2.5%

401.204 Testing Method D For hot mix asphalt items designated as Method D in Section 403 - Hot Bituminous Pavement, one sample will be taken from the paver hopper or the truck body per 225 Mg [250 ton] per pay item. The mix will be tested for gradation and PGAB content. Disputes will not be allowed. If the mix is within the tolerances listed in Table 8: Method D Acceptance Limits, the Department will pay the contract unit price. If the test results for each 225 Mg [250 ton] increment are outside these limits, the following deductions (Table 8b) shall apply to the HMA quantity represented by the test.

TABLE 8: METHOD D ACCEPTANCE LIMITS

Property	USL and LSL
Percent Passing 4.75 mm and larger sieves	Target +/-7
Percent Passing 2.36 mm to 1.18 mm sieves	Target +/-5
Percent Passing 0.60 mm	Target +/-4
Percent Passing 0.30 mm to 0.075 mm sieve	Target +/-3
PGAB Content	Target +/-0.5
% TMD (In-place Density)	95.0% +/- 2.5%

TABLE 8b Method "D" Price Adjustments

PGAB Content	-5%
2.36 mm sieve	-2%
0.30 mm sieve	-1%
0.075 mm sieve	-2%
Density	-10%*

^{*}Only applies when called for in Section 403 - Hot Bituminous Pavement. Contractor shall cut two 150 mm [6 in] cores, which shall be tested for percent TMD per AASHTO T-269. If the average for the two tests falls below 92.5% the disincentive shall apply.

<u>401.21 Method of Measurement</u> The Department will measure Hot Mix Asphalt Pavement by the Mg [ton] in accordance with Section 108.1 - Measurement of Quantities for Payment.

<u>401.22 Basis of Payment</u> The Department will pay for the work, in place and accepted, in accordance with the applicable sections of this Section, for each type of HMA specified.

The Department will pay for the work specified in Section 401.11, for the HMA used, except that cleaning objectionable material from the pavement and furnishing and applying bituminous material to joints and contact surfaces is incidental.

Payment for this work under the appropriate pay items shall be full compensation for all labor, equipment, materials, and incidentals necessary to meet all related contract requirements, including design of the JMF, implementation of the QCP, obtaining core samples, transporting cores and samples, filling core holes, applying emulsified asphalt to joints, and providing testing facilities and equipment.

The Department will make a pay adjustment for quality as specified below.

<u>401.221 Pay Adjustment</u> The Department will sample, test, and evaluate Hot Mix Asphalt Pavement in accordance with Section 106 - Quality and Section 401.20 - Acceptance, of this Specification.

<u>401.222 Pay Factor (PF)</u> The Department will use the following criteria for pay adjustment using the pay adjustment factors under Section 106.7 - Quality Level Analysis:

<u>Density</u> If the pay factor for Density falls below 0.80 for Method A or C or 0.86 for Method B, all of the cores will be randomly recut by Sublot. A new pay factor will be calculated that combines all initial and retest results. If the resulting pay factor is below 0.80 for Method A or C or below 0.86 for Method B, the entire Lot shall be removed and replaced with material meeting the specifications at no additional cost to the Department, except that the Department may, when it appears that there is a distinct pattern of defective material, isolate any defective material by investigating each mix sample sublot and require removal of defective mix sample sublots only, leaving any acceptable material in place if it is found to be free of defective material. Pay factors equal to or greater than the reject level will be paid accordingly.

<u>Gradation</u> For HMA evaluated under Acceptance Method A or B, the Department will determine a composite pay factor (CPF) using applicable price adjustment factors "f" from Table 9: Table of Gradation Composite "f" Factors, and Acceptance limits from Table 5: Method A Acceptance Limits, for Method A or Table 6: Method B Acceptance Limits, for Method B. The Department will not make price adjustments for gradation on Methods A and B, but will monitor them as shutdown criteria.

TABLE 9: TABLE OF GRADATION COMPOSITE " f " FACTORS (Methods A and B)

	,		"f" Fact	or	
Constituent		19 mm	12.5 mm	9.5 mm	4.75 mm
	25 mm	-	-	-	-
	19 mm	4	-	-	-
	12.5 mm		4	4	-
	9.50 mm				4
Gradation	2.36 mm	6	6	6	8
	1.18 mm				
	0.60 mm	2	2	2	2
	0.30 mm	2	2	2	2
	0.075 mm	6	6	6	8

For HMA evaluated under Acceptance Method C, the Department will determine a pay factor using acceptance limits from Table 7: Method C Acceptance Limits.

<u>VMA</u>, <u>Air Voids</u>, <u>VFB</u> and <u>Fines to Effective Binder</u> The Department will determine a pay factor (PF) using the applicable Acceptance Limits.

The following variables will be used for pay adjustment:

PA = Pay Adjustment

Q = Quantity represented by PF in Mg [ton]

P = Contract price per Mg [ton]

PF = Pay Factor

Pay Adjustment Method A

The Department will use the following criteria for pay adjustment: density, Performance Graded Asphalt Binder content, voids $@N_d$, VMA, VFB, F/B_{eff}, and the screen sizes listed in Table 9 for the type of HMA represented in the JMF. If any pay factor for any single property or composite gradation falls below 0.85, the Contractor shall shut down the HMA plant. If any single pay factor for PGAB Content, VMA, or Air Voids falls below 0.80, then the composite pay factor for PGAB Content, VMA, and Air Voids shall be 0.55.

<u>Density</u>: For mixes having a density requirement, the Department will determine a pay factor using Table 5: Method A Acceptance Limits:

$$PA = (density PF- 1.0)(Q)(P)x0.50$$

<u>PGAB Content, VMA and Air Voids</u>: The Department will determine a pay adjustment using Table 5: Method A Acceptance Limits as follows:

$$PA = (voids @ N_d PF- 1.0)(Q)(P)x0.20 + (VMA @ N_d PF- 1.0)(Q)(P)x0.20 + (PGAB PF- 1.0)(Q)(P)x0.10$$

<u>VFB and Fines to Effective Binder</u> The Department will determine a pay factor (PF) using Table 5: Method A Acceptance Limits. The Department will not make price adjustments for VFB or Fines to Effective Binder, but will monitor them as shutdown criteria.

Pay Adjustment Method B

The Department will use the following criteria for pay adjustment: density, Performance Graded Asphalt Binder content, voids @N_d, VMA, VFB, F/B_{eff}, and the screen sizes listed in Table 9 for the type of HMA represented in the JMF. If any pay factor for any single property or composite gradation falls below 0.90, the Contractor shall shut down the HMA plant. If any single pay factor for PGAB Content, VMA, or Air Voids falls below 0.86, then the composite pay factor for PGAB Content, VMA, and Air Voids shall be 0.70.

<u>Density</u>: For mixes having a density requirement, the Department will determine a pay factor using Table 6: Method B Acceptance Limits:

$$PA = (density PF - 1.0)(Q)(P)x0.50$$

<u>PGAB Content, VMA and Air Voids</u>: The Department will determine a pay adjustment using Table 6: Method B Acceptance Limits as follows:

$$PA = (voids @ N_d PF- 1.0)(Q)(P)x0.20 + (VMA @ N_d PF- 1.0)(Q)(P)x0.20 + (PGAB PF- 1.0)(Q)(P)x0.10$$

<u>VFB and Fines to Effective Binder</u> The Department will determine a pay factor (PF) using Table 6: Method B Acceptance Limits. The Department will not make price adjustments for VFB or Fines to Effective Binder, but will monitor them as shutdown criteria.

Pay Adjustment Method C

The Department will use density, Performance Graded Asphalt Binder content, and the screen sizes listed in Table 7 for the type of HMA represented in the JMF. If any pay factor for any single property falls below 0.85, the Contractor shall shut down the HMA plant. If the PGAB content falls below 0.80, then the PGAB pay factor shall be 0.55. If the percent passing the nominal maximum sieve, the 2.36 mm sieve, the 0.300 mm sieve or the 0.075 mm sieve for Method C falls below 0.80, then the composite pay factor for the four sieves shall be 0.55.

<u>Density</u>: For mixes having a density requirement, the Department will determine a pay factor using Table 7: Method C Acceptance Limits:

$$PA = (density PF- 1.0)(Q)(P)x0.50$$

<u>PGAB Content and Gradation</u> The Department will determine a pay factor using Table 7: Method C Acceptance Limits. The Department will calculate the price adjustment for Mixture Properties as follows:

PA = (% Passing Nom. Max PF-1.0)(Q)(P)X0.05+(% passing 2.36 mm PF-1.0)(Q)(P)X0.05+(% passing 0.30 mm PF-1.0)(Q)(P)X0.05+(% passing 0.075 mm PF-1.0)(Q)(P)X0.10+(PGAB PF-1.0)(Q)(P)X0.25

<u>VMA</u>, <u>Air Voids</u>, <u>VFB</u> and <u>Fines to Effective Binder</u> The Department will determine a pay factor (PF) using Table 7: Method C Acceptance Limits. The Department will not make price adjustments for VMA, Air Voids, VFB or Fines to Effective Binder, but will monitor them as shutdown criteria.

Pay Adjustment Method D

The Department will use density, Performance Graded Asphalt Binder content, and the screen sizes listed in Table 8b for the type of HMA represented in the JMF. If test results do not meet the Table 8 requirements, deducts as shown in Table 8b shall be applied to the quantity of mix represented by the test.

401.223 Process for Dispute Resolution (Methods A B & C only)

<u>a. Dispute Resolution sampling</u> At the time of Hot-Mix Asphalt sampling, the Department will obtain a split sample of each Acceptance test random sample for possible dispute resolution testing. The Contractor shall also obtain a split sample of the HMA at this same time. If the Contractor wishes to retain the option of requesting dispute testing of the initial Acceptance sample, the Contractor will test their split of the

Acceptance sample and shall report their results to the Resident, with a copy to the QA Engineer at the Central Laboratory in Bangor by 7:00 AM, on the second working day from time of QA sampling, otherwise dispute resolution will not be initiated. The Department's dispute resolution split sample will be properly labeled and stored for a period of not more than two weeks, or until the sample is tested.

- <u>b. Disputing Acceptance results</u> The Contractor may dispute the Department's Acceptance results and request (Methods A, B, & C) that the dispute resolution split sample be tested by notifying the Department's Resident and the QA Engineer at the Central Laboratory in Bangor in writing within two working days after receiving the results of the Acceptance test. The following shall be provided in the request:
 - Acceptance sample reference number
 - The specific test result(s) or property(ies) being disputed, and
 - The complete, signed report of the Contractor's testing (In a lab certified by the NETTCP and MDOT) of their split of the Acceptance sample indicating that the variances in Table10: Dispute Resolution Variance Limits, for the specific test result(s) or property(ies) were exceeded.
- c. Disputable items The Contractor may dispute any or all of the following test results when the difference between the Department's value and the Contractor's value for that test equals or exceeds the corresponding allowable variation in Table 10: Dispute Resolution Variance Limits, PGAB content, G_{mb} , and G_{mm} . In addition, if the allowable variation for these tests is not met or exceeded, the Contractor may dispute either or both of the following material properties provided the difference between results for them equals or exceeds the corresponding allowable variation in Table 10: Voids at N_{design} , and VMA. For Method C only, % passing may only be disputed on sieves which are used for price adjustments
- d. Outcome The value of any disputed result or property reported for the initial Acceptance sample shall stand if the value reported for the dispute resolution sample is <u>not</u> closer to the value the Contractor reported for their split sample than to the value reported for the initial Acceptance sample. If the value

reported for the dispute resolution falls precisely half-way between the other two values the value reported for the dispute resolution will replace the original acceptance value. Otherwise, the value reported for the dispute resolution sample will replace the value reported for the initial Acceptance sample, and will be used to re-calculate any other affected results or properties.

TABLE 10: DISPUTE RESOLUTION VARIANCE LIMITS

PGAB Content	+/-0.4%
G_{mb}	+/-0.030
G_{mm}	+/-0.020
Voids @ N _d	+/-0.8%
VMA	+/-0.8%
Passing 4.75 mm and larger sieves	+/- 4.0%
Passing 2.36 mm to 0.60 mm sieves	+/- 3.0%
Passing 0.30 mm to 0.15	+/- 2.0 %
0.075 mm sieve	+/- 1.0%

SECTION 402 - PAVEMENT SMOOTHNESS

<u>402.00 Smoothness Projects</u> Projects to have their pavement smoothness analyzed in accordance with this Specification will be so noted in Special Provision 403 - Bituminous Box

<u>402.01 Pavement Smoothness</u> The final pavement surface shall be evaluated for smoothness using a Class I or Class II profiler as defined by ASTM E950 (94). Smoothness measurements will be expressed in terms of the International Roughness Index (IRI) as defined by the World Bank, in units of inches/mile.

402.02 Lot Size Lot size for smoothness will be 1000 lane-meters [3000 lane-feet]. A sublot will consist of 20 lane-meters [50 lane-feet]. Partial lots will be included in the previous lot if less than one-half the size of a normal lot. If equal to or greater than one-half the normal lot size, it will be tested as a separate lot.

<u>402.03 Acceptance Testing</u> The Department will conduct Acceptance testing following completion of the surface course. Sections to be excluded from testing include the following:

Bridge decks and joints (no smoothness measurements will be taken within 30 m [100 ft] of bridge joints)

Acceleration and deceleration lanes

Shoulders and ramps

Side streets and roads

Within 30 m [100 ft] of transverse joints at the beginning and end of the project

Within 30 m [100 ft] of railroad crossings

Urban areas with speed limits of 50 kph [30 mph] or lower

Each lot shall have 2 measurements made in each wheel path. The average of the 4 measurements will determine the smoothness for that lot.

The smoothness measurements will be statistically evaluated for pay factors as described in Subsection 106.7 - Quality Level Analysis, using the specification limits shown below.

ACCEPTANCE LIMITS

Level	USL
I	1.10 m/km [70 in/mile]
II	1.25 m/km [80 in/mile]
III	1.40 m/km [90 in/mile]

Computation of Smoothness Pay Adjustment:

PA = (PF-1.0)(Q)(P)

where:

Q = Quantity of surface course in the Lot (excluding shoulders, side streets, bridge decks, ramps, acceleration and deceleration lanes)

PF = smoothness pay factor for the Lot

P = Contract unit price for surface pavement

PA = pay adjustment

402.04 Unacceptable Work In the event that any Lot is found to have a pay factor less than 0.80, the Contractor shall take whatever remedial action is required to correct the pavement surface in that Lot at no additional expense to the Department. Such remedial action may include but is not limited to removal and replacement of the unacceptable pavement. In the event remedial action is necessary, the Contractor shall

submit a written plan to the Resident outlining the scope of the remedial work. The Resident must approve this plan before the remedial work can begin. Following remedial work, the Lot shall be retested, and will be subject to the specification limits listed above. The resulting pay factor, if within the acceptable range, will be used in the final pay adjustment. The Contractor shall pay the cost of retesting the pavement following corrective action.

Localized surface tolerance defects will be subject to the provisions outlined in Section 401.101 Surface Tolerances

Payment will be made under:

Pay Item Pay Unit

402.10 Incentive/Disincentive - Pavement Smoothness Lump Sum

SECTION 403 - HOT BITUMINOUS PAVEMENT

<u>403.01 Description</u> This work shall consist of constructing one or more courses of bituminous pavement on an approved base in accordance with these specifications, and in reasonably close conformity with the lines, grades, thickness and typical cross sections shown on the plans or established.

The bituminous pavement shall be composed of a mixture of aggregate, filler if required, and bituminous material.

<u>403.02 General</u> The materials and their use shall conform to the requirements of Section 401 - Hot Mix Asphalt Pavement.

403.03 Construction The construction requirements shall be as specified in Section 401 - Hot Mix Asphalt Pavement.

In addition, hot bituminous pavement placed on bridges shall also conform to the following requirements.

- a. The mixture shall be composed of aggregate, PGAB and mineral filler but no recycled asphalt pavement and placed in courses as specified in the Special Provisions.
- b. The bottom course shall be placed with an approved rubber mounted bituminous paver of such type and operated in such a manner that the membrane waterproofing will not be damaged in any way.
- c. The top course shall not be placed until the bottom course has cooled sufficiently to provide stability.
- d. The Contractor will not be required to cut sample cores from the compacted pavement on the bridge deck.
- e. After the top course has been placed, the shoulder areas shall be sealed 1 meter [3 ft] wide with two applications of an emulsified bituminous sealer meeting the requirements of Section 702.12 Emulsified Bituminous Sealing Compound. The first application shall be pre-mixed with fine, sharp sand, similar to mortar sand, as needed to fill all voids in the mix in the area being sealed. The second application may be applied without sand. The sealer shall be carried to the curb at the gutter line in sufficient quantity to leave a bead or fillet of material at the face of the curb. The area to be sealed shall be clean, dry and the surface shall be at ambient temperature.
- f. The furnishing and applying of the required quantity of sealer for the bridge shoulder areas shall be incidental to placing the hot bituminous pavement.
- g. The atmospheric temperature for all courses on bridge decks shall be 10°C [50°F] or higher.

<u>403.04 Method of Measurement</u> Hot bituminous pavement will be measured as specified in Section 401.21-Method of Measurement.

<u>403.05 Basis of Payment</u> The accepted quantities of hot bituminous pavement will be paid for at the contract unit price per Megagram [ton] for the bituminous mixtures, including bituminous material complete in place.

Method A, Method B, Method C and Method D shall be used for acceptance as specified in Section 401 - Hot Mix Asphalt Pavements. (See Complementary Notes, Section 403 - Hot Bituminous Pavement, for Method location).

Payment will be made under:

<u>Pa</u>	ay Item	Pay Unit
403.102	Hot Mix Asphalt Pavement for Special Areas	MG [Ton]
403.206	Hot Mix Asphalt, 25 mm Nominal Maximum Size	MG [Ton]
403.207	Hot Mix Asphalt, 19.0 mm Nominal Maximum Size	MG [Ton]
403.208	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size	MG [Ton]
403.209	Hot Mix Asphalt, 9.5 mm Nominal Maximum Size	MG [Ton]
	(sidewalks, drives, islands & incidentals)	
403.210	Hot Mix Asphalt, 9.5 mm Nominal Maximum Size	MG [Ton]
403.211	Hot Mix Asphalt (shimming)	MG [Ton]
403.212	Hot Mix Asphalt, 4.75 mm Nominal Maximum Size	MG [Ton]
403.213	Hot Mix Asphalt, 12.5 mm	MG [Ton]
	Nominal Maximum Size, Base	

SPECIAL PROVISION <u>DIVISION 401</u> HOT MIX ASPHALT PAVEMENTS (Asphalt Rich Base Mixture)

The Special Provision 400 – Pavements; Section 401 – <u>Hot Mix Asphalt Pavements</u>; the following subsections

<u>Description</u> The Contractor shall furnish and place one or more courses of <u>Asphalt Rich Base Hot Mix Asphalt (ARBHMA)</u> on an approved base in accordance with the contract documents and in reasonably close conformity with the lines, grades, thickness, and typical cross sections shown on the plans or established by the Resident. The Department will accept this work under Quality Assurance provisions, in accordance with these specifications and the requirements of Section 106 – Quality, the provisions of AASHTO M 323 except where otherwise noted in sections 401 and 703 of these specifications, and the Maine DOT Policies and Procedures for HMA Sampling and Testing.

MATERIALS

401.02 Materials This section has been modified with the following revision:

The Asphalt Rich Base HMA shall be designed for an Air Void Target of 2.5 % at 50 Gyrations.

401.03 Composition of Mixtures This section has been modified with the following revision:

The Asphalt Rich Base HMA shall meet the following design criteria.

have been modified with the following:

DESIGN CRITERIA

Gradation	PGAB Content
9.5mm mixture	7.0 % minimum
12.5mm mixture	6.5 % minimum
19.0mm mixture	6.0 % minimum

The mixture shall meet the gradation requirements of a current MaineDOT approved <u>9.5mm</u>, <u>12.5mm</u>, or <u>19.0mm</u> 50 Gyration JMF, as required by the contract, and the minimum PGAB content noted above. The Acceptance Limit targets for gradation will be as specified on the JMF.

401.201 Method A Lot Size will be the entire production per JMF for the project, or if so agreed at the Prepaving Conference, equal lots of up to 4050 Mg [4500 tons], with unanticipated over-runs of up to 1350 Mg [1500 ton] rolled into the last lot. Sublot sizes shall be 675 Mg [750 ton] for mixture properties, 450 Mg [500 ton] for base or binder densities and 225 Mg [250 ton] for surface densities. The minimum number of sublots for mixture properties shall be 4, and the minimum number of sublots for density shall be five.

TABLE 5: METHOD A ACCEPTANCE LIMITS

Property	USL and LSL
Passing 4.75 mm and larger sieves	Target +/-7%
Passing 2.36 mm to 1.18 mm sieves	Target +/-4%
Passing 0.60 mm	Target +/-3%
Passing 0.30 mm to 0.075 mm sieve	Target +/-2%
PGAB Content	Target +/-0.4%
Air Voids	2.5 % +/-1.5%
Fines to Effective Binder	0.4 to 1.2
Voids in the Mineral Aggregate	LSL Only from Table 1
Voids Filled with Binder	Table 1 values plus a 8%
	production tolerance for USL only
% TMD (In place density)	96 .0% +/- 2.5%

Payment will be made under:

Pay Item	Pay Unit
403.2102 – 9.5mm Asphalt Rich Base HMA	Ton
403.2132 – 12.5mm Asphalt Rich Base HMA	Ton
403.2072 – 19.0mm Asphalt Rich Base HMA	Ton

SPECIAL PROVISION <u>SECTION 401</u> PLANT MIX PAVEMENTS - GENERAL

(Material Transfer Vehicle)

The hot bituminous mix shall be transferred to the paver for mainline on the **final two lifts/courses** of pavement by a material transfer vehicle (MTV) on main line paving.

The MTV shall operate as an independent unit not attached to the paver. It shall be a commercially manufactured unit specifically designed to transfer the hot mix from haul trucks to the paver without depositing the mix on the roadway.

Also required is a separate hopper with a capacity of 18 Mg [20 ton] that shall be inserted into the regular paver hopper.

The MTV or the hopper insert shall be designed so that the mix receives additional mixing action either in the MTV unit or the paver hopper.

The MTV and the hopper insert will not be paid for directly, but will be considered incidental to the related contract pay items.

1 of 1 93

SECTION 401 HOT MIX ASPHALT PAVEMENT

High Performance Rubberized Asphalt Pavement

The Special Provision 400 – Pavements; Section 401 – <u>Hot Mix Asphalt Pavements</u>; the following subsections have been modified with the following:

401.01 Description. The Contractor shall furnish and place one or more courses of High Performance Rubberized Asphalt Pavement surface, or base, in accordance with the contract documents and in reasonably close conformity with the lines, grades, thicknesses, and typical cross sections shown on the plans or established by the Resident. The Department will accept this work under Quality Assurance provisions, in accordance with these specifications and the requirements of Section 106 - Quality.

Rubber Modifier Additive 401.021 The High Performance Rubberized Asphalt Pavement shall be modified with a polymer modifier packaged in 10.1kg (22.5 pound) units in meltable polyethylene bags, with a minimum of 45 pounds of polymer modifier. The meltable bags can be tossed into the pug mill without opening, and will melt to disperse the additive through the normal mixing action of the pug mill. The exact rubber modifier content shall be determined by the mix design submitted by the Contractor and modifier supplier based on laboratory testing. The final blend will be in accordance with the rubber modifier manufacturer requirements and approved by the Engineer. The modifier shall be a concentrated thermoplastic virgin polymeric material that is waterproof, has a melting point of 250 degrees Fahrenheit and an embrittlement point of -34 degrees Fahrenheit.

<u>Or</u>

The granulated rubber shall be vulcanized rubber product from the ambient temperature processing of scrap, pneumatic tires. The granulated rubber shall meet the following gradations: No substitutions will be accepted.

Sieve Size	% Passing
2.00 mm, (#10)	100
1.18 mm, (#16)	90 - 100
0.60 mm, (#30)	25 - 75
0.18 mm, (#80)	0 - 20

The use of rubber of multiple types from multiple sources is acceptable provided that the overall blend of rubber meets the gradation requirements. The length of the individual rubber particles shall not exceed 3 mm, (1/8). The rubber shall be accepted by certification from the rubber supplier.

The percent of rubber shall be a minimum of 15% by weight of total asphalt-rubber mixture. The exact granulated rubber content shall be determined by the mix design submitted by the Contractor and granulated rubber supplier based on laboratory testing.

The temperature of the asphalt shall be between 177°C and 218°C, (350°F and 425°F), at the time of addition of the granulated reclaimed rubber. The asphalt and rubber shall be combined and mixed together in a blender unit and reacted for a minimum of one hour. The temperature of the asphalt-rubber mixture shall be above 163°C, (325°F), during the reaction period.

A mechanical blender for proper proportioning and thorough mixing of the asphalt-cement and granulated rubber is required. This unit shall be equipped with: an asphalt totaling meter (liters or gallons); a flow rate meter (liters per minute or gallons per minute); a positive displacement auger to feed the rubber properly to mixing chamber at the specified rate; and a static motionless mixer. Blender will have a separate asphalt cement feed pump and finished product pump to maximize production. Blender shall be capable of providing 100% proportional mix at any given time during the blending cycle and documentation from the manufacturer, supporting this, shall be submitted to the Maine DOT.

401.03 Composition of Mixtures; revised as follows:

The Contractor shall compose the High Performance Rubberized Asphalt Pavement with aggregate, Performance Graded Asphalt Binder (PGAB), mineral filler if required and crumb rubber concentrate. The final job mix design will be according to the crumb rubber modifier manufacturer's requirements and approved by the Department. The High Performance Rubberized Asphalt Pavement shall be designed and tested according to AASHTO T312 and the design criteria listed below. The Contractor shall size, uniformly grade, and combine the aggregate fractions in proportions that provide a mixture meeting the grading requirements of the Job Mix Formula (JMF).

Design Criteria

PGAB Content	6.5 – 8.0
Air Void	2.0 +/- 1.5%
Rubber Additive	3% - 5%

GRADATION REQUIREMENTS

Sieve Size	Percent Passing
12.5 mm	100
9.5 mm [3/8 inch]	75-100
4.75 mm [No. 4]	55-85
2.36 mm [No. 8]	48-65
1.18 mm [No. 16]	15-25
0.600 mm [No. 30]	10-18
0.300 mm [No. 50]	5-10
0.075 mm [No. 200]	2-6.0

The construction of a test strip will be required prior to production of the High Performance Rubberized Asphalt Pavement.

401.031 Test Strip A test strip shall be constructed prior to the placement of High Performance Rubberized Asphalt Pavement on the bridge decks. The test strip will be constructed offsite to establish the proper production, placement, and compaction procedures for this contract prior to full plant production.

The test strip is to be constructed off site, and shall consist of a 20 ton minimum quantity. The Contractor shall notify the Department within 48 hours prior to their intent to construct the strip. The Contractor shall provide the Department with two mix samples from the test strip produced material for mix verification. The samples shall be tested for asphalt content and gradation against the JMF and other contract requirements before further production. A minimum of three cores will be sampled from the test strip, and the average density of the three is required to be above the LSL of 93.0 %. If the average density of the three cores is less than the LSL of 93.0, the test strip will be rejected and a new test strip will be required before further production. There will be no separate payment for material placed in a offsite test strip, but shall be considered incidental to the 403.325 High Performance Rubberized Asphalt Pavement, 9.5 mm item.

Modified bituminous concrete surface course production will not resume unless the Department is confident material meeting the contract requirements can be produced.

401.04 Temperature Requirements This section has been modified with the addition of the following:

After the JMF is established, the temperatures of the mixture shall conform to the following tolerances:

At the Plant – Additive manufactures recommended mix temp. $\pm 10^{\circ}\text{C} [20^{\circ}\text{F}]$ At the Paver – Additive manufactures recommended compaction temp. $\pm 10^{\circ}\text{C} [20^{\circ}\text{F}]$

The JMF, and the mix subsequently produced, shall meet the requirements of the design criteria and Section 703.07. Under no circumstances will the Department accept HMA (unless the binder has been modified) that has been heated to temperatures exceeding the manufactures recommendations. The Department will have a full time inspector in the plant during all production of the High Performance Rubberized Asphalt Pavement. The Contractor shall notify the Department within 48 hours prior to producing the High Performance Rubberized Asphalt Pavement.

<u>401.05 Performance Graded Asphalt Binder</u> This section has been modified with the addition of the following:

Unless otherwise noted in Special Provision 403 - Hot Bituminous Pavement, the PGAB shall be 64-28, or <u>70-28</u>, except that for mixtures containing greater than 15% RAP the PGAB shall

be PG 58-34. The PGAB shall meet the applicable requirements of AASHTO M320 - Standard Specification for PGAB. The Contractor shall provide the Department with an approved copy of the Quality Control Plan for PGAB in accordance with AASHTO R 26-01 Certifying Suppliers of PGAB.

401.08 Hauling Equipment This section has been modified with the addition of the following:

All truck dump bodies shall have a cover of canvas or other water repellent material capable of heat retention, which completely covers the <u>entire mixture</u>. The cover shall be securely fastened on the loaded truck except when unloading.

401.10 Rollers This section has been modified with the addition of the following:

Full compaction of the High Performance Rubberized Asphalt Pavement is required and shall be achieved by utilizing steel double drum drive rollers used in the static mode. One roller will be required for break down, and one for finish rolling. A third roller, the same as the two being utilized to do the work, will be on the job to cover any breakdowns. The rollers' water system must be in reliable working order, and apply even water coverage to the asphalt mat. High Performance Rubberized Asphalt Pavement may be temperatures are higher than conventional mixes and require more water to keep the material from sticking to the steel rolls. Pneumatic rollers are not required on the High Performance Rubberized Asphalt Pavement.

The contractor may use other compaction means in areas where the specified roller train can't access. The use of an asphalt vibratory whacker may be allowed as long as it is in good working order and the watering system works reliably. Breakdown rolling will be done immediately behind the spreading operation. The finish roller will follow breakdown and used to remove imperfections in the mat. The rolling pattern will be straight with the paving direction, with minimal turning. The Department will work with the Contractor to control the rolling pattern and the frequency of passes in required. Any changes to the paving and rolling procedures must be approved by the Resident and included in a modified QCP.

If methods of compaction other than the conventional the rolling train is required, additional manpower shall be provided by the Contractor to ensure that the areas not accessible by rollers is compacted before the material cools below breakdown compaction temperatures. Areas found to be deficient due to lack of observed compactive effort, or tested to be below the minimum density requirement, will be corrected in accordance with this Special Provision's Section, 401.20 - Acceptance: Correction of Deficiencies.

<u>401.11 Preparation of Existing Surface</u> This section has been modified with the addition of the following:

(Deck Preparation) Following any required deck patching and prior to placement of the High Performance Rubberized Asphalt Pavement, the concrete deck shall be prepared as follows:

The work under this Item shall consist of cleaning the surface of the concrete deck to remove any milled material or debris which would reduce or prevent bonding, furnishing and applying Edge Sealer, Tack Coat, furnishing and placing on the cleaned and tack coated bridge deck, an impermeable hot-mix waterproofing asphalt course to the lines, grades, width and depth as indicated on the plans, and saw cutting and filling any construction joints with rubberized joint sealer, all in accordance with the specifications and as directed by the Engineer.

High Performance Rubberized Asphalt Pavement shall not be placed until the moisture content of the surface it is to be placed on is at or below 6%. The moisture content will be checked with a "Sovereign Potable Electronic Moisture master" meter or an approved equal. The moisture content shall be checked in a minimum of one location in each span. High Performance Rubberized Asphalt Pavement shall not be placed until the new concrete has been in place a minimum of 7 days. The entire deck shall be shot blasted to achieve an anchor profile which is clean of foreign materials, such as oil or grease, and any sharp protrusions removed and free of laitance. The Contractor shall have a copy of Technical Guideline No. 03732 (Guideline for Selecting and Specifying Concrete Surface Preparation for Sealers, Coatings, and Polymer Overlays) published by the International Concrete Repair Institute. The final concrete surface profile shall range between a CSP 1 and CSP 5 as defined by this guideline. Areas where rapid setting patching materials have been placed shall be cured for a minimum of 72 hours or longer when recommended by the product manufacturer prior to applying the High Performance Rubberized Asphalt Pavement. All surfaces shall then be swept and cleaned by brooms and compressed air as directed by the Resident before the modified bituminous concrete surface course is placed.

The deck must be clean and free of any loose debris and moisture. A 100-150 mm (4-6 inch) application of Edge Sealer, at a rate specified by the manufacturer, shall be used to seal all edges of the planned day's placement of the modified bituminous concrete surface course. Particular attention shall be given to vertical edges of headers, drains, scuppers, expansion joints or wherever compaction may be difficult to achieve. Where vertical edges exist, apply Edge Sealer 100-150 mm (4-6 inch) out from curb scuppers, joints, etc., on the horizontal and up to the top of the proposed finished surface grade. When practical, this should be done the day before or as early as possible to maximize drying time.

The Tack Coat shall be applied to the existing horizontal concrete bridge deck surfaces in a uniform coating at the rate specified by the manufacturer.

Butt joints made during paving operations must have Edge Sealer applied to the butt surface before the joining asphalt lift. Construction joints shall be saw cut to a 12.7 mm (½ inch) width and filled to within 3 mm (1/8 inch) of the surface with the rubberized asphalt joint sealer previously specified. Extreme care shall be taken so as not to overfill these sawed joints since excess joint sealer material will cause ripples in the surface course necessitating corrective work by the Contractor.

Edge Sealer shall be applied to all terminations of the paved asphalt, including curb lines and deck joints, as soon as possible after the pavement has cooled.

The Contractor shall thoroughly clean the surface of all objectionable material upon which modified bituminous concrete surface course is to be placed.

401.15 Spreading and Finishing This section has been modified with the addition of the following:

On areas where irregularities or unavoidable obstacles make the use of mechanical spreading and finishing equipment impracticable, the Contractor shall spread, rake, and lute the High Performance Rubberized Asphalt Pavement with hand tools to provide the required compacted thickness.

On roads opened to two-way traffic, the Contractor shall place each course over the full width of the traveled way section being paved that day, unless otherwise noted by the Department in Section 403 - Hot Bituminous Pavement.

All pavements shall be placed on surfaces that have been tack coated, if required, and allowed to cure for a minimum period of 40 minutes. An approved Tack Coat shall be applied to the existing concrete deck, and to the first layer of pavement in accordance with the manufacturer's recommendations if required. The film thickness of the tack coat shall be 0.04 to 0.15 gallons per square yard. The tack coat shall be allowed to break or dry prior to placement of the modified bituminous concrete surface course. A Tack Coat is not required between the pavement layers if the base and surface layers of pavement are placed the same working day, or unless the base layer surface becomes contaminated with materials that would reduce bond between layers.

The material shall be placed at temperatures specified by the manufacturer.

401.16 Compaction This section has been modified with the addition of the following:

Immediately after the High Performance Rubberized Asphalt Pavement has been spread, struck off, and any surface irregularities adjusted, the Contractor shall thoroughly and uniformly compact the modified bituminous concrete surface course by rolling.

The Contractor shall roll the surface when the mixture is in the proper condition and when the rolling does not cause undue displacement, cracking, or shoving. The Contractor shall prevent adhesion of the High Performance Rubberized Asphalt Pavement to the rollers or vibrating compactors without the use of fuel oil or other petroleum based release agents.

The Contractor shall immediately correct any displacement occurring as a result of the reversing of the direction of a roller or from other causes to the satisfaction of the Department. Any operation that results in breakdown of the aggregate shall be discontinued. Any new pavement that shows obvious cracking, checking, or displacement shall be removed and replaced for the full lane width as directed by the Resident at no cost to the Department.

Along forms, curbs, headers, walls, and other places not accessible to the rollers, the Contractor shall thoroughly compact the High Performance Rubberized Asphalt Pavement with mechanical vibrating compactors. The Contractor shall only use hand tamping in areas inaccessible to all

other compaction equipment. On depressed areas, the Contractor may use a trench roller or cleated compression strips under a roller to transmit compression to the depressed area. If methods of compaction other than the conventional the rolling train is required, additional manpower shall be provided by the Contractor to ensure that the areas not accessible by rollers is compacted before the material cools below breakdown compaction temperatures. Areas found to be deficient due to lack of observed compactive effort, or tested to be below the minimum density requirement, will be corrected in accordance with this Special Provision's Section, 401.20 - Acceptance: Correction of Deficiencies.

Any High Performance Rubberized Asphalt Pavement that becomes unacceptable due to cooling, cracking, checking, segregation or deformation as a result of an interruption in mix delivery shall be removed and replaced, with material that meets contract specifications at no cost to the Department.

401.17 Joints This section has been modified with the addition of the following:

The Contractor shall construct wearing course transverse joints in such a manner that minimum tolerances shown in Section 401.101 - Surface Tolerances are met when measured with a straightedge.

The paver shall always maintain a uniform head of High Performance Rubberized Asphalt Pavement during the joint construction. The High Performance Rubberized Asphalt Pavement shall be free of segregation and meet temperature requirements. Transverse joints of the wearing course shall be straight and neatly trimmed. The Contractor may form a vertical face exposing the full depth of the course by inserting a header, by breaking the bond with the underlying course, or by cutting back with hand tools.

Longitudinal joints shall be constructed in a manner that will best ensure joint integrity. Methods or activities that prove detrimental to the construction of sound longitudinal joints will be discontinued.

The edges of the pavement shall be sealed by applying Edge Sealer on all vertical faces which will be in contact with the High Performance Rubberized Asphalt Pavement. The material shall be applied so the entire edge of the layer, and a few inches onto the deck surface, is coated.

A Tack Coat shall be applied to the existing concrete deck, and the first layer of pavement in accordance with the manufacturer's recommendations. The film thickness of the tack coat shall be 0.04 to 0.15 gallons per square yard. The Tack Coat shall be allowed to break or dry prior to placement of the High Performance Rubberized Asphalt Pavement. A Tack Coat is not required between the pavement layers if the base and surface layers of pavement are placed the same working day, or unless the base layer surface becomes contaminated with materials that would reduce bond between layers.

The Contractor shall use an approved spray apparatus designed for covering a narrow surface. The Department may approve application by a brush for small surfaces, or in the event of a malfunction of the spray apparatus, but for a period of not more than one working day.

Where High Performance Rubberized Asphalt Pavement under this contract joins an existing pavement or when the Department-directs, the Contractor shall cut the existing pavement along a smooth line, producing a neat, even, vertical joint. The Department will not permit broken or raveled edges. The cost of all work necessary for the preparation of joints is incidental to related contract pay items.

The Contractor shall fill all holes in the pavement resulting from cutting cores acceptable mixture no later than the following working day. The Contractor shall carefully clean the holes and apply a coating of Edge sealer. On surface courses, cores shall not be cut except for Quality Assurance.

Contractor shall monitor plant production using running average of three control charts as specified in Section 106 - Quality. Control limits shall be as noted in Table 3 below.

The Resident may at any time, notwithstanding previous sampling and certification, notify and stop the Contractor, reject and require the Contractor to dispose of any batch of bituminous mix which is rendered unfit for use due to temperature, oxidation, contamination, segregation or incomplete coating of aggregate. Such rejection may be based on visual inspection alone.

401.20 Acceptance This section has been modified with the addition of the following:

Pavement Density The Department will High Performance Rubberized Asphalt Pavement density using core samples tested according to AASHTO T-166. The Department will randomly determine core locations. The Contractor shall cut 150 mm [6 in] diameter cores at no additional cost to the Department by the end of the working day following the day the pavement is placed, and immediately give them to the Department. The cores will be placed in a transport container provided by the Department and transported by the Contractor to the designated MDOT Lab as directed by the Department. Pre-testing of the cores will not be allowed. At the time of sampling, the Contractor and the Department shall mutually determine if a core is damaged. If it is determined that the core(s) is damaged, the Contractor shall cut new core(s) at the same offset and within 1 m [3 ft] of the initial sample. At the time the core is cut, the Contractor and the Department will mutually determine if saw cutting of the core is needed, and will mark the core at the point where sawing is needed. The core may be saw cut by the MaineDOT Lab, without disturbing the layer being tested to remove lower layers of Hot Mix Asphalt Pavement, gravel, or RAP. No recuts are allowed at a test location after the core has been tested. Upon conclusion of each lot, density results shall be examined for statistical outliers as stated in Section 106.7.2.

401.203 Acceptance Testing This section has been modified with the addition of the following:

Lot Size will be the entire production per JMF for the project, or if so agreed at the Pre-paving Conference, equal lots of up to 4050 Mg [4500 tons], with unanticipated over-runs of up to 1350 Mg [1500 ton] rolled into the last lot. Sublot sizes shall be 675 Mg [750 ton] for mixture properties, 450 Mg [500 ton] for base or binder densities and 225 Mg [250 ton] for surface

densities. The minimum number of sublots for mixture properties shall be 4, and the minimum number of sublots for density shall be five.

TABLE 7: ACCEPTANCE LIMITS

Property	USL and LSL
Passing 4.75 mm and larger sieves	Target +/-7%
Passing 2.36 mm to 1.18 mm sieves	Target +/-4%
Passing 0.60 mm	Target +/-3%
Passing 0.30 mm to 0.075 mm sieve	Target +/-2%
PGAB Content	Target +/-0.4%
Air Voids	2.0% +/-1.5%
Fines to Effective Binder	N/A
Voids in the Mineral Aggregate	N/A
Voids Filled with Binder	N/A
% TMD (In place density)	96.0% +/- 2.5%

<u>Correction of Deficiencies</u> In the event of any portions of pavement fails to comply with specified quality requirements, the Contractor shall replace or repair deficient pavements as directed by the Resident. Corrections shall be made as work progresses and not reserved for a separate operation at some later date.

- 1. For thickness deficiencies, the only acceptable repair methods are removal and replacement, or placement of an overlay layer. Corrective work shall begin and end at the repair, and feather edging will not be permitted.
- 2. Where more than 6 mm (¼ inch) above the required grade, correct deficiency by removal as necessary to comply with the specifications, except where an approved contour pattern satisfying riding quality and drainage as shown on the Contract Drawings has been established.
- 3. For deficiency in smoothness tolerance, correct any deficiency by means approved by the Resident and subject to all other provisions hereof. The area for correction of deficiencies in surface smoothness and surface grade tolerance shall be those areas, which fail to satisfy quality requirements. Existing pavement shall be removed as necessary to provide square joints for the full depth of the course.
- 4. For deficiency of in-place voids, remove and replace deficient pavement in accordance with all requirements specified herein. The area replaced for deficiency of in-place voids shall be the total area paved with-in the deficient paving lot. Existing pavement shall be removed as necessary to provide square joints for the full depth of the course.
- 5. For deficiency involving a porous surface in the mat at longitudinal joints, or at

construction joints, the surface shall be sealed with an asphalt filler/sealer material submitted to and approved by the Resident.

401.222 Pay Factor (PF) This section has been modified with the addition of the following:

The Department will use the following criteria for pay adjustment using the pay adjustment factors under Section 106.7 - Quality Level Analysis:

<u>Density</u> If the pay factor for Density falls below 0.80 all of the cores will be randomly recut by Sublot. A new pay factor will be calculated that combines all initial and retest results. If the resulting pay factor is below 0.80, the entire Lot shall be removed and replaced with material meeting the specifications at no additional cost to the Department, except that the Department may, when it appears that there is a distinct pattern of defective material, isolate any defective material by investigating each mix sample sublot and require removal of defective mix sample sublots only, leaving any acceptable material in place if it is found to be free of defective material. Pay factors equal to or greater than the reject level will be paid accordingly.

TABLE 9: TABLE OF GRADATION COMPOSITE " f " FACTORS (Methods A and B)

,			"f" Fact	or	
Cor	stituent	19 mm	12.5 mm	9.5 mm	4.75 mm
Gradation	25 mm	-	-	1	-
	19 mm	4	-	1	-
	12.5 mm		4	4	-
	9.50 mm				4
	2.36 mm	6	6	6	8
	1.18 mm				
	0.60 mm	2	2	2	2
	0.30 mm	2	2	2	2
	0.075 mm	6	6	6	8

For HMA evaluated under this specification, the Department will determine a pay factor using acceptance limits from Table 7: Acceptance Limits.

<u>VMA</u>, <u>Air Voids</u>, <u>VFB and Fines to Effective Binder</u> The Department will determine a pay factor (PF) using the applicable Acceptance Limits.

The following variables will be used for pay adjustment:

PA = Pay Adjustment

Q = Quantity represented by PF in Mg [ton]

P = Contract price per Mg [ton]

PF = Pay Factor

Pay Adjustment This section has been modified with the addition of the following:

The Department will use density, Performance Graded Asphalt Binder content, and the screen sizes listed in Table 7 for the type of HMA represented in the JMF. If any pay factor for any single property falls below 0.85, the Contractor shall shut down the HMA plant. If the PGAB content falls below 0.80, then the PGAB pay factor shall be 0.55. If the percent passing the nominal maximum sieve, the 2.36 mm sieve, the 0.300 mm sieve or the 0.075 mm sieve falls below 0.80, then the composite pay factor for the four sieves shall be 0.55.

Density: For mixes having a density requirement, the Department will determine a pay factor using Table 7: Acceptance Limits:

PA = (density PF-1.0)(Q)(P)x0.50

PGAB Content and Gradation The Department will determine a pay factor using Table 7: Acceptance Limits. The Department will calculate the price adjustment for Mixture Properties as follows:

> PA = (% Passing Nom. Max PF-1.0)(Q)(P)X0.05+(% passing 2.36 mm PF-1.0)(Q)(P)X0.05+(%passing 0.30 mm PF-1.0)(Q)(P)X0.05+(%passing 0.075 mm PF-1.0)(Q)(P)X0.10+(PGAB PF-1.0)(Q)(P)X0.25

VMA, Air Voids, VFB and Fines to Effective Binder The Department will determine a pay factor (PF) using Table 7: Acceptance Limits. The Department will not make price adjustments for VMA, Air Voids, VFB or Fines to Effective Binder, but will monitor them as shutdown criteria.

Method of Measurement. High Performance Rubberized Asphalt Pavement will be measured by the ton, complete and in place.

Basis of Payment. High Performance Rubberized Asphalt Payement (HPRA) will be paid for at the contract unit price per ton. Such payment shall be full compensation for obtaining and furnishing all aggregate, additives, and bituminous material including tack and edge sealer, for processing, heating, mixing, weighing, trucking, placing, and rolling; for furnishing the test strip, all labor, equipment, tools and all incidentals necessary to complete the work. Price adjustments will be made in accordance to the designated testing method.

Payment will be made under:

Pay Unit Pay Item

403.325 High Performance Rubberized Asphalt Pavement, 9.5 mm

Ton

SPECIAL PROVISION <u>SECTION 403</u> HOT BITUMINOUS PAVEMENT

The following additions are made to Section 403 Subsection 403.05 of the December 2002 revision of the Standard Specifications.

403.05 Basis of Payment:

Pay Item	Pay Unit
403.2081 12.5mm Polymer Modified Hot Mix Asphalt	Ton [Megagram]
403.2102 9.5mm Asphalt Rich Base Mixture	Ton [Megagram]
403.2131 12.5mm Polymer Modified HMA Base	Ton [Megagram]
403.2132 12.5mm Asphalt Rich Base Mixture	Ton [Megagram]

Brunswick - Gardiner IM-1511(400)E I - 295 Southbound 3 ½ inch Overlay Sections Highway Rehabilitation March 26, 2008

SPECIAL PROVISION SECTION 403 HOT MIX ASPHALT OVERLAY

Desc. of Course	Grad. Design	Item Number	Bit Cont. % of Mix	Total Thick	No. Of Layers	Comp. Notes
	Sta. 51	1+00 to 534+00	Travel and Pas	sing Lane witl	n Shoulder	
		2" Ex	<u>isting Pavemer</u>	<u>nt Mill</u>		
		3 1/23	' HMA Resurfa	acing_		
Wearing	12.5mm	403.2081	N/A	1 ½"	1	1,5,7,12,22
Base	12.5mm	403.2131	N/A	2"	1	1,5,7,12
		Sta. 511+00 t	o 534+00 10 fo	oot Shoulders		
		1 1/2"	' HMA Resurfa	acing_		
Wearing	12.5mm	403.208	N/A	1 1/2"	1	5,7,12
		<u>Mi</u>	<u>scellaneous Ar</u>	<u>eas</u>		
Shim	9.5 mm	403.211	N/A	variable	1	2,4,7,11

COMPLEMENTARY NOTES

- 1. The required PGAB for this mixture will meet a <u>PG 70-28</u> to <u>PG 76-28</u> grading. The use of Recycled Asphalt Pavement (RAP) <u>will not</u> be permitted in mixtures utilizing modified PGAB's.
- 2. The density requirements are waived.
- 4. The design traffic level for mix placed shall be 0.3 to <3 million ESALS. The design, verification, Quality Control, and Acceptance tests for this mix will be performed at 50 gyrations.
- 5. The aggregate qualities shall meet the design traffic level of 3 to <10 million ESALS for mix placed under this contract. The design, verification, Quality Control, and Acceptance tests for this mix will be performed at **75 gyrations**.
- 7. Section 106.6 Acceptance, (1) Method A.
- 11. The combined aggregate gradation required for this item shall be classified as a 9.5mm "**fine graded**" mixture, (using the Primary Control Sieve control point) as defined in 703.09.
- 12. The combined aggregate gradation required for this item shall be classified as a 12.5mm "**fine graded**" mixture (using the Primary Control Sieve control point) as defined in 703.09.
- 22. The final pavement surface shall be evaluated for smoothness in accordance with Special Provision section 402 Pavement Smoothness dated 3-12-08. Acceptance limits shall be as outlined under the **Level 1** classification.

Tack Coat

A tack coat of emulsified asphalt, RS-1 Item #409.15 shall be applied to any existing pavement at a rate of approximately 0.025 G/SY, and on milled pavement approximately 0.05 G/SY, prior to placing a new course. A fog coat of emulsified asphalt shall be applied between shim / intermediate course and the surface course, at a rate not to exceed 0.025 G/SY.

Tack used between layers of pavement will be paid for at the contract unit price for Item 409.15 Bituminous Tack Coat.

Page 1 of 1

Brunswick - Gardiner IM-1511(400)E I - 295 Southbound 4 inch Overlay Sections Highway Rehabilitation March 26, 2008

SPECIAL PROVISION SECTION 403 HOT MIX ASPHALT OVERLAY

Desc. of Course	Grad. Design	Item Number	Bit Cont. % of Mix	Total Thick	No. Of Layers	Comp. Notes	
	Sta. 534	4+00 to729+50 T	ravel and Pass	sing Lane with	Shoulder	_	
	,	4'']	HMA Resurfac	cing_	_		
Wearing	12.5mm	403.2081	N/A	1 1/2"	1	1,5,7,12,22	
Base	12.5mm	403.2131	N/A	1 ½"	1	1,5,7,12	
Base	9.5mm	403.2102	N/A	1"	1	4,7,11,19	
		Sta. 534+00 t	to729+50 10 fo	ot Shoulders			
		4"	HMA Resurfac	eing			
Wearing	12.5mm	403.208	N/A	2"	1	1,5,7,12,22	
Base	12.5mm	403.213	N/A	2"	1	1,5,7,12	
Miscellaneous Areas							
Shim	9.5 mm	403.211	N/A	variable	1	2,4,7,11	

COMPLEMENTARY NOTES

- 1. The required PGAB for this mixture will meet a <u>PG 70-28</u> to <u>PG 76-28</u> grading. The use of Recycled Asphalt Pavement (RAP) <u>will not</u> be permitted in mixtures utilizing modified PGAB's.
- 2. The density requirements are waived.
- 4. The design traffic level for mix placed shall be 0.3 to <3 million ESALS. The design, verification, Quality Control, and Acceptance tests for this mix will be performed at **50 gyrations.**
- 5. The aggregate qualities shall meet the design traffic level of 3 to <10 million ESALS for mix placed under this contract. The design, verification, Quality Control, and Acceptance tests for this mix will be performed at **75 gyrations**.
- 7. Section 106.6 Acceptance, (1) Method A.
- 11. The combined aggregate gradation required for this item shall be classified as a 9.5mm "**fine graded**" mixture, (using the Primary Control Sieve control point) as defined in 703.09.
- 12. The combined aggregate gradation required for this item shall be classified as a 12.5mm "**fine graded**" mixture (using the Primary Control Sieve control point) as defined in 703.09.
- 19. Refer to Special Provision 401 Asphalt Rich Base Mixture for project specifics.
- 22. The final pavement surface shall be evaluated for smoothness in accordance with Special Provision section 402 Pavement Smoothness dated 3-12-08. Acceptance limits shall be as outlined under the **Level 1** classification.

Tack Coat

A tack coat of emulsified asphalt, RS-1, Item #409.15 shall be applied to any existing pavement at a rate of approximately 0.025 G/SY, and on milled pavement approximately 0.05 G/SY, prior to placing a new course. A fog coat of emulsified asphalt shall be applied between shim / intermediate course and the surface course, at a rate not to exceed 0.025 G/SY.

Tack used between layers of pavement will be paid for at the contract unit price for Item 409.15 Bituminous Tack Coat.

Page 1 of 1 107

Brunswick - Gardiner IM-1511(400)E I - 295 Southbound 8 inch Overlay Section Highway Rehabilitation March 26, 2008

SPECIAL PROVISION SECTION 403 HOT MIX ASPHALT OVERLAY

Desc. of Course	Grad. Design	Item Number	Bit Cont. % of Mix	Total Thick	No. Of Layers	Comp. Notes
		Sta.	729+50 to 1661	<u>l+00</u>		
		8" HMA Pav	ement Reconsti	ruction Areas		
		Travo	el and Passing l	<u>Lanes</u>		
Wearing	12.5mm	403.2081	N/A	1 ½"	1	1,5,7,12,22
Wearing	12.5mm	403.2131	N/A	1 ½"	1	1,5,7,12
Base	12.5mm	403.213	N/A	2 ½"	1	1,5,7,13
Base	12.5mm	403.2132	N/A	2 ½"	1	4,7,13,19
		Sta.	729+50 to 1661	<u>1+00</u>		
		3" HMA I	Pavement Reco	nstruction		
		Passing Lane S	houlders and G	uardrail Are	<u>as</u>	
Wearing	12.5mm	403.2081	N/A	1 ½"	1	1,5,7,12
Base	12.5mm	403.2131	N/A	1 ½"	1	1,5,7,12
		Sta.	729+50 to 1661	L+ 00		· · · · · · · · · · · · · · · · · · ·
			Pavement Reco			
		Travel Lane Sl			as	
Wearing	12.5mm	403.208	N/A	1 1/2"	- 1	5,7,12
Base	12.5mm	403.213	N/A	1 ½"	1	5,7,12
			scellaneous Ar			
Shim	9.5 mm	403.211	N/A	variable	1	2,4,7,11

COMPLEMENTARY NOTES

- 1. The required PGAB for this mixture will meet a <u>PG 70-28</u> to <u>PG 76-28</u> grading. The use of Recycled Asphalt Pavement (RAP) will not be permitted in mixtures utilizing modified PGAB's.
- 2. The density requirements are waived.
- 4. The design traffic level for mix placed shall be 0.3 to <3 million ESALS. The design, verification, Quality Control, and Acceptance tests for this mix will be performed at **50 gyrations.**
- 5. The aggregate qualities shall meet the design traffic level of 3 to <10 million ESALS for mix placed under this contract. The design, verification, Quality Control, and Acceptance tests for this mix will be performed at **75 gyrations**.
- 7. Section 106.6 Acceptance, (1) Method A.
- 11. The combined aggregate gradation required for this item shall be classified as a 9.5mm "**fine graded**" mixture, (using the Primary Control Sieve control point) as defined in 703.09.
- 12. The combined aggregate gradation required for this item shall be classified as a 12.5mm "**fine graded**" mixture (using the Primary Control Sieve control point) as defined in 703.09.
- 13. The combined aggregate gradation required for this item shall be classified as a 12.5mm "**fine graded**" mixture, or a 19.0mm "**fine graded**" mixture (using the Primary Control Sieve control point) as defined in 703.09.

Page 1 of 2

Brunswick - Gardiner IM-1511(400)E I - 295 Southbound 8 inch Overlay Section Highway Rehabilitation March 26, 2008

- 19. Refer to Special Provision 401 Asphalt Rich Base Mixture for project specifics.
- 22. The final pavement surface shall be evaluated for smoothness in accordance with Special Provision section 402 Pavement Smoothness dated 3-12-08. Acceptance limits shall be as outlined under the **Level 1** classification.

Tack Coat

A tack coat of emulsified asphalt, RS-1 Item #409.15 shall be applied to any existing pavement at a rate of approximately 0.025 G/SY, and on milled pavement approximately 0.05 G/SY, prior to placing a new course. A fog coat of emulsified asphalt shall be applied between shim / intermediate course and the surface course, at a rate not to exceed 0.025 G/SY. Tack used between layers of pavement will be paid for at the contract unit price for Item 409.15 Bituminous Tack Coat.

Page 2 of 2

Brunswick - Gardiner IM-1511(400)E I - 295 Southbound 9 inch Overlay Section Highway Rehabilitation March 26, 2008

SPECIAL PROVISION SECTION 403 HOT MIX ASPHALT OVERLAY

Desc. of Course	Grad. Design	Item Number	Bit Cont. % of Mix	Total Thick	No. Of Layers	Comp. Notes	
		9" HMA Pavo	ement Reconsti	ruction Areas			
		Trave	el and Passing l	<u>Lanes</u>			
Wearing	12.5mm	403.2081	N/A	1 1/2"	1	1,5,7,12,22	
Wearing	12.5mm	403.2131	N/A	1 ½"	1	1,5,7,12	
Base	12.5mm	403.213	N/A	3"	1	1,5,7,13	
Base	12.5mm	403.2132	N/A	3"	1	4,7,13,19	
		<u>3" HMA I</u>	Pavement Reco	nstruction			
		Passing Lane S	houlders and G		<u>as</u>		
Wearing	12.5mm	403.2081	N/A	1 ½"	1	1,5,7,12	
Base	12.5mm	403.2131	N/A	1 ½"	1	1,5,7,12	
		<u>3" HMA I</u>	Pavement Reco	<u>nstruction</u>			
		Travel Lane Sl	noulders and G	uardrail Area	as		
Wearing	12.5mm	403.208	N/A	1 ½"	- 1	5,7,12	
Base	12.5mm	403.213	N/A	1 ½"	1	5,7,12	
Miscellaneous Areas							
Shim	9.5 mm	403.211	N/A	variable	1	2,4,7,11	

COMPLEMENTARY NOTES

- 1. The required PGAB for this mixture will meet a <u>PG 70-28</u> to <u>PG 76-28</u> grading. The use of Recycled Asphalt Pavement (RAP) <u>will not</u> be permitted in mixtures utilizing modified PGAB's.
- 2. The density requirements are waived.
- 4. The design traffic level for mix placed shall be 0.3 to <3 million ESALS. The design, verification, Quality Control, and Acceptance tests for this mix will be performed at **50 gyrations.**
- 5. The aggregate qualities shall meet the design traffic level of 3 to <10 million ESALS for mix placed under this contract. The design, verification, Quality Control, and Acceptance tests for this mix will be performed at **75 gyrations**.
- 7. Section 106.6 Acceptance, (1) Method A.
- 11. The combined aggregate gradation required for this item shall be classified as a 9.5mm "**fine graded**" mixture, (using the Primary Control Sieve control point) as defined in 703.09.
- 12. The combined aggregate gradation required for this item shall be classified as a 12.5mm "**fine graded**" mixture (using the Primary Control Sieve control point) as defined in 703.09.
- 13. The combined aggregate gradation required for this item shall be classified as a 12.5mm "**fine graded**" mixture, or a 19.0mm "**fine graded**" mixture (using the Primary Control Sieve control point) as defined in 703.09.
- 19. Refer to Special Provision 401 Asphalt Rich Base Mixture for project specifics.
- 22. The final pavement surface shall be evaluated for smoothness in accordance with Special Provision section 402 Pavement Smoothness dated 3-12-08. Acceptance limits shall be as outlined under the **Level 1** classification.

Page 1 of 2

Brunswick - Gardiner IM-1511(400)E I - 295 Southbound 9 inch Overlay Section Highway Rehabilitation March 26, 2008

Tack Coat

A tack coat of emulsified asphalt, RS-1, Item #409.15 shall be applied to any existing pavement at a rate of approximately 0.025 G/SY, and on milled pavement approximately 0.05 G/SY, prior to placing a new course. A fog coat of emulsified asphalt shall be applied between shim / intermediate course and the surface course, at a rate not to exceed 0.025 G/SY. Tack used between layers of pavement will be paid for at the contract unit price for Item 409.15 Bituminous Tack Coat.

Page 2 of 2

Brunswick - Gardiner IM-1511(400)E I - 295 Southbound Bridge Decks Highway Rehabilitation March 26, 2008

SPECIAL PROVISION SECTION 403 HOT MIX ASPHALT OVERLAY

Desc. of Course	Grad. Design	Item Number	Bit Cont. % of Mix	Total Thick	No. Of Layers	Comp. Notes	
		2" HMA	Mill and 2 ¼" R	esurface			
		Trave	el and Passing L	<u>anes</u>			
		Maine C	entral Railroad	Bridge			
Wearing	12.5 mm	403.2131	N/A	2 1/4"	1/more	5,7,11	
		2" HMA	Mill and 2 1/4" R	<u>esurface</u>			
		Trave	el and Passing L	anes			
		Ol	d Lewiston Roa	<u>d</u>			
Wearing	9.5 mm	403.325	N/A	2 1/4"	1/more	5,7,11,23	
		2" HMA	Mill and 2 ¼" R	<u>esurface</u>			
		Trave	el and Passing L	<u>anes</u>			
Maine Central Railroad Bridge							
Wearing	9.5 mm	403.325	N/A	2 1/4"	1/more	5,7,11,23	
Miscellaneous Areas							
Shim	9.5 mm	403.211	N/A	variable	1	2,4,7,11	

COMPLEMENTARY NOTES

- 2. The density requirements are waived.
- 4. The design traffic level for mix placed shall be 0.3 to <3 million ESALS. The design, verification, Quality Control, and Acceptance tests for this mix will be performed at **50 gyrations.**
- 5. The aggregate qualities shall meet the design traffic level of 3 to <10 million ESALS for mix placed under this contract. The design, verification, Quality Control, and Acceptance tests for this mix will be performed at <u>75 gyrations</u>.
- 7. Section 106.6 Acceptance, (1) Method A.
- 11. The combined aggregate gradation required for this item shall be classified as a 9.5mm "**fine graded**" mixture, (using the Primary Control Sieve control point) as defined in 703.09.
- 23. Refer to Special Provision 401 High Performance Rubberized Hot Mix Asphalt for project specifics.

Tack Coat

A tack coat of emulsified asphalt, RS-1, Item #409.15 shall be applied to any existing pavement at a rate of approximately 0.025 G/SY, and on milled pavement approximately 0.05 G/SY, prior to placing a new course. A tack coat of emulsified asphalt, **SS-1**, Item #409.15 shall be applied to any PCC pavement at a rate of approximately 0.025 G/SY. A fog coat of emulsified asphalt, RS-1, shall be applied between shim / intermediate course and the surface course, at a rate not to exceed 0.025 G/SY.

Tack used between layers of pavement will be paid for at the contract unit price for Item 409.15 Bituminous Tack Coat.

Page 1 of 1 112

Brunswick - Gardiner IM-1511(400)E I - 295 Southbound On and Offramps Highway Rehabilitation March 26, 2008

SPECIAL PROVISION SECTION 403 HOT MIX ASPHALT OVERLAY

Desc. of Course	Grad. Design	Item Number	Bit Cont. % of Mix	Total Thick	No. Of Layers	Comp. Notes
			Exit 28 Offram			
***	10.5		<u> Iainline Mill &</u>		4	5 7 10
Wearing	12.5mm	403.208	N/A	2"	1	5,7,12
Base	12.5mm	403.213	N/A	2"	<u> </u>	5,7,12
			Exit 28 Offram			
			Bridgedeck Re			
<u>Wearing</u>	12.5mm	403.208	N/A	1 ½"	1	5,7,12
			t 31 and 43 Rar			
			eclaim, 4" HM			
			nline and Shou		_	
Wearing	12.5mm	403.208	N/A	2"	1	5,7,12
Base	12.5mm	403.213	N/A	2"	1	5,7,12
			Exit 49 Onramı			
			<u>ill & Fill Full V</u>			
			nline and Shou			
Wearing	12.5mm	403.208	N/A	2"	1	5,7,12
Base	12.5mm	403.213	N/A	2"	1	5,7,12
		Evit 3	37 On and Offr	amne		
			/2" HMA Overl			
			nline and Shou			
Wearing	12.5mm	403.208	N/A	1 ½"	1	5,7,12
Shim	9.5mm	403.211	N/A	variable		2,4,7,11
SIIIII	J.J111111		and Miscellane		<u> </u>	۷,٦,/,11
Shim	9.5 mm	403.211	N/A	variable	1	2,4,7,11

COMPLEMENTARY NOTES

- 2. The density requirements are waived.
- 4. The design traffic level for mix placed shall be 0.3 to <3 million ESALS. The design, verification, Quality Control, and Acceptance tests for this mix will be performed at **50 gyrations.**
- 5. The aggregate qualities shall meet the design traffic level of 3 to <10 million ESALS for mix placed under this contract. The design, verification, Quality Control, and Acceptance tests for this mix will be performed at **75 gyrations**.
- 7. Section 106.6 Acceptance, (1) Method A.
- 11. The combined aggregate gradation required for this item shall be classified as a 9.5mm "fine graded" mixture, (using the Primary Control Sieve control point) as defined in 703.09.

Page 1 of 2 113

Brunswick - Gardiner IM-1511(400)E I - 295 Southbound On and Offramps Highway Rehabilitation March 26, 2008

12. The combined aggregate gradation required for this item shall be classified as a 12.5mm "fine graded" mixture (using the Primary Control Sieve control point) as defined in 703.09.

Tack Coat

A tack coat of emulsified asphalt, **RS-1**, Item #409.15 shall be applied to any existing pavement at a rate of approximately 0.025 G/SY, and on milled pavement approximately 0.05 G/SY, prior to placing a new course. A tack coat of emulsified asphalt, **SS-1**, Item #409.15 shall be applied to any PCC pavement at a rate of approximately 0.025 G/SY. A fog coat of emulsified asphalt, RS-1, shall be applied between shim / intermediate course and the surface course, at a rate not to exceed 0.025 G/SY.

Tack used between layers of pavement will be paid for at the contract unit price for Item 409.15 Bituminous Tack Coat.

Page 2 of 2

SPECIAL PROVISION <u>SECTION 424</u> LOW MODULUS CRACK SEALER

<u>Description</u> This work shall consist of the furnishing and placement of crack sealing material in the cracks of existing bituminous concrete pavement in accordance with these Special Provisions. Placement shall consist of: 1) crack cleaning and drying, 2) material preparation and application, 3) material finishing and shaping and 4) barrier material and application.

<u>Materials</u> low modulus crack sealant material shall conform to ASTM D-3405 and the following specification.

Cone Penetration 90 - 150

Flow @ 60°C [140°F] < 3.0mm [1/8 in]

Bond, non-immersed Three 12.7mm [½ in] specimens pass 3

cycles @ 200% extension @ -29°C [-20°F]

Resilience, % 60 min

Asphalt Compatibility, ASTM D5329 pass*

The contractor shall provide the Resident or authorized representative with a copy of the material manufacturer's recommendations pertaining to heating, application, and reheating prior to the beginning of operations or the changing of materials.

CONSTRUCTION REQUIREMENTS

<u>Weather</u> Low Modulus Crack Sealer shall not be applied on a wet surface, after sunset or before sunrise, or when the atmospheric temperature is below 10°C [50°F] in a shaded area at the job site, or when weather conditions are otherwise unfavorable to proper construction procedures.

<u>Equipment</u> Equipment used in the performance of the work shall be subject to the Resident's or authorized representative's approval and shall be maintained in a satisfactory working condition at all times.

(a) <u>Air Compressor</u>: Air compressors shall be portable and capable of furnishing not less than 3 m³ [4 yd³] of air per minute at not less than 620 kPa [90 psi] pressure at the nozzle. The compressor shall be equipped with traps that will maintain the compressed air free of oil and water.

^{*} There shall be no failure in adhesion, formation of any oily exudate at the interface between the sealant and asphaltic concrete or other deleterious effects on the asphaltic concrete or sealant when tested at 60°C [140°F].

- (b) <u>Sweeper</u>: Manually operated, gas powered air-broom or self-propelled sweeper designed especially for use in cleaning pavements shall be used to remove debris, dirt, and dust from the cracks.
- (c) <u>Hot Air Lance</u>: Should operate with propane and compressed air in combination at 1100°C 1650°C [2000°F 3000°F], exit air heated at 310 m/s [1000 ft/s]. The lance should draw propane from no smaller than a 45 Kg [100 lb] tank using separate hoses for propane and air draw. The hoses shall be wrapped together with reflectorized wrap to keep them together and to protect workers in low light situations.
- (d) <u>Hand Tools</u>: Shall consist of V-shaped squeegee, brooms, shovels, metal bars with chisel shaped ends, and any other tools which may be satisfactorily used to accomplish this work.
- (e) Melting Kettle: The unit used to melt the joint sealing compound shall be a double boiler, indirect fired type. The space between inner and outer shells shall be filled with a suitable heat transfer oil or substitute having a flash point of not less than 320°C [608°F]. The kettle shall be equipped with a satisfactory means of agitating and mixing the joint sealer at all times. This may be accomplished by continuous stirring with mechanically operated paddles and/or a continuous circulating gear pump attached to the heating unit. The kettle must be equipped with thermostatic control calibrated between 94°C [200°F] and 290°C [550°F].
- (f) <u>Application Wand</u>: The application wand shall apply a controlled flow of material via an insulated or heated hose. The nozzle shall distribute the material as called for in this specification. A pressure regulator shall be provided to regulate pressure at the nozzle. A bypass line into the holding tank is required for use when the nozzle is shut off.

Preparation All cracks greater than 5 mm [¼ in] shall be blown free of loose material, dirt, vegetation, and other debris by high pressure air. Material removed from the crack shall be removed from the pavement surface by means of a power sweeper or appropriate hand tools as required. Cracks showing evidence of vegetation after being blown out shall be additionally cleaned by appropriate hand tools and additionally blown out. All cracks must be blown and heated via the hot air lance 10 minutes prior to the crack being sealed. Distance between the hot air lance and the crack sealing unit should be no more than 15 m [50 ft] to eliminate reinvasion of water, debris, and other incompressibles. All debris, vegetation, and water shall be removed to enhance adhesion of the crack sealing material. THIS WORK SHALL NOT BE DONE IN INCLEMENT WEATHER.

<u>Preparation and Placement of Sealer</u> The low modulus crack sealer material shall be heated and applied at the temperature specified by the manufacturer and approved by the Resident or authorized representative. Any material that has been heated above the manufacturer's specification shall not be used. Material that is reheated or held at temperature for an extended period of time may be used as allowed by the manufacturer's specification and approval of the Resident or authorized representative. The Contractor shall provide the Resident or authorized representative with a suitable device for verifying the sealant temperature in the kettle and at the application site.

Any over application or spills are to be removed to the satisfaction of the Resident or authorized representative. Any sealed areas with damaged or contaminated sealer or visible voids are to be removed, prepared and resealed.

Sealer shall be delivered to the crack while the cracks are still hot from the hot air lance preparation through a pressure hose line and applicator shoe. The shoe width and the sealer overbanding area shall vary from 50 mm - 100 mm [2 in - 4 in] depending on the severity of the cracks. The applicator shall be followed by a V-shaped squeegee to minimize the thickness of the overband. Any loose material on the surface or in the crack, which may contaminate the crack sealer or impede bonding of the sealant to the pavement, is to be removed by hand tools prior to crack filling. No crack filling material shall be applied in a crack that is wet or where frost, snow, or ice is present. The ambient air temperature must be 10°C [50°F] or higher.

If the sealed area is to be opened to traffic immediately, a barrier material such as Glenzoil or an equivalent approved by the Resident shall be provided by the Contractor and shall be applied to the crack sealer to prevent pickup as directed by the Resident or authorized representative.

<u>Quality of Work</u> Excess of spilled sealer shall be removed from the pavement by approved methods and discarded. Any quality of Work determined to be below normal acceptable standards will not be accepted, and will be corrected and/or replaced as directed by the Resident or authorized representative.

Method of Measurement Asphalt Low Modulus Crack Sealer will be measured by the kilogram (pound) of sealant used. The manufacturer's weights of the sealant will be accepted as the basis for measurement.

<u>Basis of Payment</u>. The accepted quantity of Low Modulus Crack Sealer will be paid for at the contract unit price per kilogram [pound] complete in place. This price shall be full compensation for furnishing and placing crack sealer, including cleaning cracks and furnishing and placing barrier materials if necessary.

Payment will be made under:

Pay Item Pay Unit

424.3331 Low Modulus Crack Sealer, Applied Kilogram [Pound]

Page 3 of 3

SPECIAL PROVISION <u>SECTION 424</u> LOW MODULUS JOINT SEALER

<u>Description</u> This work shall consist of furnishing all labor, equipment and materials necessary to clean and seal longitudinal and transverse joints that result in the construction of bituminous concrete pavement courses. This material is to be thoroughly applied to the joints during the construction of bituminous pavement courses, to seal the construction joint from deterioration due to the elements, and to adhere the joint materials together.

<u>Materials</u> Asphalt Low Modulus Joint Sealer shall be a modified asphalt and rubber compound designed for sealing and improving the strength and performance of the base asphalt cement and shall conform to ASTM D-3405 and the following specification.

Cone Penetration 90 - 150

Flow @ 60°C [140°F] < 3.0mm [? in]

Bond, non-immersed Three 12.7mm [½ in] specimens pass 3

cycles @ 200% extension @ -29°C [-20°F]

Resilience, % 60 min

Asphalt Compatibility, ASTM D5329 pass*

The contractor shall provide the Resident or authorized representative with a copy of the material manufacturer's recommendations pertaining to heating, application, and reheating prior to the beginning of operations or the changing of materials

CONSTRUCTION REQUIREMENTS

<u>Weather</u> Low modulus joint sealer shall not be applied on a wet surface, or when the atmospheric temperature is below 10°C [50°F] in a shaded area at the job site, or when weather conditions are otherwise unfavorable to proper construction procedures. An atmospheric temperature of 2°C [36°F] and rising will be permitted on intermediate and base courses, with the time and weather constraints remaining.

<u>Preparation and Placement</u> This work shall be constructed using a low modulus joint sealer. The sealer shall be heated and applied at a temperature between 170°C - 200°C [340°F - 390°F] or as specified by the manufacturer and approved by the Resident. Sealer shall be delivered to

^{*} There shall be no failure in adhesion, formation of any oily exudate at the interface between the sealant and asphaltic concrete or other deleterious effects on the asphaltic concrete or sealant when tested at 60°C [140°F].

the joint through a pressure hose line and applicator shoe. The shoe width and the sealer overbanding area shall vary from 35 mm - 40 mm [1 3/8 in - 1 ½ in] depending on the joint height variability. The sealer shall be applied at a rate that produces a coating thickness of 3 mm [? in], typical. The material shall not be applied more than 12 hours prior to the placement of any pavement course, and subject to approval by the Resident.

<u>Preparations of Joints</u> All joints shall be swept or blown free of loose material, dirt, and other debris. Material removed from the joint shall be removed from the pavement surface by means of a power sweeper or appropriate hand tools as required. Joints shall additionally be cleaned by appropriate hand tools if contaminants remain on the face. All debris and water shall be removed to enhance adhesion of the joint sealing material. THIS WORK SHALL NOT BE DONE IN INCLEMENT WEATHER.

<u>Equipment</u> Equipment used in the performance of the work shall be subject to the Resident's approval and shall be maintained in a satisfactory working condition at all times.

- (a) <u>Sweeper</u>: The sweeper shall be a manually operated, gas powered air-broom, or self-propelled sweeper designed especially for use in cleaning pavements shall be used to remove all debris, dirt, and dust from the joints.
- (b) Melting Kettle: The unit used to melt the joint sealing compound shall be a double boiler, indirect fired type. The space between inner and outer shells shall be filled with a suitable heat transfer oil or substitute having a flash point of not less than 320°C [608°F]. The kettle shall be equipped with a satisfactory means of agitating and mixing the joint sealer at all times. This may be accomplished by continuous stirring with mechanically operated paddles and/or a continuous circulating gear pump attached to the heating unit. The kettle must be equipped with thermostatic control calibrated between 94°C [170°F] and 290°C [525°F].

Quality of Work Excess sealer shall be removed from the pavement by approved methods and discarded. Any quality of Work determined to be below normal acceptable standards will not be accepted, and will be corrected and/or replaced as directed by the Resident.

Method of Measurement Low modulus joint sealer will be measured by the meter [foot] applied.

<u>Basis of Payment</u> The accepted quantity of Low modulus joint sealer will be paid for at the contract unit price per meter [foot] complete in place, which price shall be full compensation for furnishing and placing sealer, including all cleaning of joints, and furnishing and placing all materials necessary to perform the work.

Payment will be made under:

Pay Item Pay Unit

424.3333 Low Modulus Joint Sealer, Applied Meter [Foot]

Page 2 of 2

SPECIAL PROVISION <u>SECTION 411</u> UNTREATED AGGREGATE SURFACE COURSE

The following changes and additions are made to Subsection 411.02.

411.02 Aggregate:

Aggregates for untreated aggregate surface course shall conform to the requirements of section 703.12.

Recycled pavement material salvaged from the project or from off-site stockpiles may be used when processed prior to use so that 100% of the material passes a ³/₄ inch square mesh sieve. Recycled material shall be conditionally accepted at the source by the Resident. It shall be free of winter sand, granular fill, construction debris, and other materials not generally considered bituminous pavement.

Recycled concrete pavement slabs salvaged from the project may be used when processed prior to use so that 100% of the material passes a ¾ inch square mesh sieve. Recycled material shall be conditionally accepted at the source by the Resident. It shall be free of winter sand, granular fill, steel, construction debris, and other materials not generally considered concrete pavement.

The following additions are made to subsection 411.04 Compaction.

411.04 Compaction:

Compaction shall be obtained by using a minimum 10 ton steel vibratory roller with a minimum width of 84 inches.

SPECIAL PROVISION <u>SECTION 429</u> PAVEMENT REINFORCING SYSTEM

(Self-Adhesive Pavement Composite Membrane)

<u>Description</u> This work shall consist of furnishing and installing a reinforced high density crack reduction interlayer membrane on existing pavement joints in accordance with these specifications and as shown on the plans.

Materials - Membrane The membrane shall be:

- 1) PavePrep SA[®], as manufactured by Pavetech International, 105 May Drive, Harrison, Ohio 45030. The local distributor is May Corporation, 32 Edgewater Road, Falmouth, ME 04105, Tel. 207-781-4110.
- 2) Pro-Guard[®], as manufactured by Amoco Fabrics and Fibers Company, 260 The Bluffs, Austell, GA 30168, Tel. 770-944-4569. The local distributor is A.H. Harris and Sons, Inc., Augusta, ME, Tel. 207-622-0821.
- 3) or an Approved Equal.

<u>Equipment</u> The equipment for installation shall be capable of meeting the provisions of the Construction Requirements of this Specification. Where required, cutting of the membrane shall be done with utility knives or other approved methods. Material shall be rolled with a static drum or hand type roller to ensure adequate adhesion.

CONSTRUCTION REQUIREMENTS

<u>Surface Preparation</u> The membrane shall be applied between the Hot Mix Asphalt (HMA) base course and binder course. The area being repaired shall first be cleaned by sweeping or with compressed air and maintained free of accumulation of debris such as dirt, dust, gravel, grass, and other material. Non-compressible objects shall be removed from the pavement joints prior to repair.

The membrane shall not be installed unless both ambient and pavement temperatures are 20° C [70°F] or above. The pavement surface to be treated must be dry. Installation of the membrane shall be delayed a minimum of 24 hours following rain.

A self-adhesive membrane shall be used. Installation shall be done in accordance with the manufacturer's recommendations.

Material Placement The membrane shall be unrolled and cut with a utility knife to follow the path of the joint. The attached film shall be removed as recommended by the manufacturer. The membrane shall be centered over the joint or crack pattern. The membrane shall be cut to length allowing a minimum of 125 mm [5 in] overlap at each end of the joint or crack pattern. Membrane seams, if allowed, shall have a minimum 50 mm [2 in] overlap. The membrane shall be installed straight and free of wrinkles with no curled or uplifted edges.

Page 1 of 2

<u>General</u> The roadway may be open to traffic after the application of the membrane and before paving if recommended by the manufacturer and if approved by the Resident.

Paving operations can begin only when the membrane is thoroughly bonded to the existing surface. All edges of the membrane must be securely bonded to the pavement surface.

A paving tack coat of PGAB 64-28 or product recommended by the manufacturer shall be applied in accordance with manufacturer's recommendations.

The membrane shall be12'-6" wide.

Removal and replacement of unsatisfactory membrane, and all membrane that is damaged by traffic and construction operations, as determined by the Resident is the responsibility of the contractor.

In hot weather, "dusting" or "sanding" may be necessary over newly applied membrane to prevent traffic pick-up of the material.

Storage of the membrane shall be in dry covered conditions. Pallets shall not be stacked. Boxes shall be stored upright and at a temperature below 43°C [110°F].

<u>Method of Measurement</u> The membrane system shall be measured by the square meter [square foot] in place.

<u>Basis of Payment</u> The accepted quantity of self-adhesive asphalt membrane will be paid for at the contract unit price per square meter (m²). Payment will be full compensation for furnishing and placing the membrane and for all labor and other incidentals necessary to complete the work.

Payment shall be made under:

Pay Items		Pay Unit
429.32	Self-Adhesive Asphaltic Membrane	square meter (square foot)

Page 2 of 2

SPECIAL PROVISION <u>SECTION 502</u> STRUCTURAL CONCRETE

(QC/QA Acceptance Methods)

CLASS OF	ITEM	DESCRIPTION		METHOD
CONCRETE	NUMBER			
LP	502.29	Structural Concrete Wearing Surface	\$450	A
A	502.31	Structural Concrete Approach Slabs	-	C
A	518.50	Repair of Upward facing Surfaces to	-	C
		reinforcing steel		
A	518.51	Repair of Upward facing Surfaces to below	-	C
		reinforcing steel		
A	518.60	Repair of Vertical Surfaces < 7.9 in.	-	C
A	518.61	Repair of Vertical Surfaces > 7.9 in.	-	С
LP	520.241	Bridge Joint Modification Type 1	\$450	A
LP	520.242	Bridge Joint Modification Type 2	\$450	A
LP	520.243	Bridge Joint Modification Type 3	\$450	A
LP	526.34	Permanent Concrete Transition Barrier	\$450	A

P values listed above reflect the price per cubic (yd³) for all pay adjustment purposes.

_

Page 1 of 1 123

SPECIAL PROVISION <u>SECTION 502</u> STRUCTURAL CONCRETE (Quality Level Analysis)

502.01 Description In second sentence, replace "...METHOD B Small Qunatity Product Verification..." with "...METHOD B Statistical Acceptance..."

502.05 Composition and Proportioning Delete Table 1 and replace with the following;

Concrete	Compressive Strength		Perme	Entrained Air		Notes	
CLASS			(COUL				
	(1	PSI)		(%)			
	LSL	USL	LSL	USL	LSL	USL	
S	2,900	N/A	N/A	N/A	6.0	8.5	1, 5
A	4,350			2,400	6.0	8.5	1,2,5,6
P					5 ½	7 ½	1,2,3,4,5
LP	5,075			2,000	6.0	8.5	1,2,5,6
Fill	2,900	N/A	N/A	N/A	N/A	N/A	6

TABLE 1- Methods A and B

502.503 Delete and replace with the following;

"502.0503 Quality Assurance METHOD B The Department will determine the acceptability of the concrete through a quality assurance program.

The Department will take Quality Assurance samples a minimum of once per sublot on a statistically random basis. Quality Assurance tests will include compressive strength, air content and permeability.

Concrete sampling for quality assurance tests will be taken at the discharge point, with pumped concrete sampling taken at the discharge end of the pump line.

Lot Size A lot size shall consist of the total quantity represented by each class of concrete in the Contract, except in the case when the same class of concrete is paid for under both lump sum items and unit price items in the Contract; in this case, the lump sum item quantities shall comprise 1 lot and the unit price item quantities shall comprise a separate lot. A lot shall consist of a minimum of 3 and a maximum of 10 sublots. If a lot is comprised of more than 10 sublots, sized in accordance with Table #3, then this quantity shall be divided equally into 2, or more, lots such that there is a minimum of 3 and a maximum of 10 sublots per lot. If there is insufficient quantity in a lot to meet the recommended minimum sublot size, then the lot shall be divided into 3 equal sublots.

Page 1 of 4

<u>Sublot Size, General</u> The size of each sublot shall be determined in accordance with Table #3. The Resident may vary sublot sizes based on placement sizes and sequence.

Sublot Size, Unit Price Items Sublot sizes will initially be determined from estimated quantities. When the actual final quantity of concrete is determined: If there is less than one-half the estimated sublot quantity in the remaining quantity, then this quantity shall be combined with the previous sublot, and no further Acceptance testing will be performed; if there is more than one-half the estimated sublot quantity in the remaining quantity, then this quantity shall constitute the last sublot and shall be represented by Acceptance test results. If it becomes apparent part way through a lot that, due to an underrun in quantity, there will be an insufficient quantity of concrete to comprise three sublots, then the Resident may adjust the sizes of the remaining sublots and select new sample locations based on the revised estimated quantity of concrete remaining in the lot.

<u>Sublot Size, Lump Sum Items</u> Each lot shall be divided into sublots of equal size, based on the estimated quantity of concrete.

TABLE 3

٠	Quantity m ³ [cy]	Recommended Sublot Size m ³ [cy]				
Ī	0-400 [0-500]	40 [50]				
ſ	401-800 [501-1000]	60 [75]				
ſ	801-1600 [1001-2000]	80 [100]				
ſ	1601 [2001]or greater	200 [250]				

Determination of the concrete cover over reinforcing steel for structural concrete shall be made prior to concrete being placed in the forms. Bar supports, chairs, slab bolsters, and side form spacers shall meet the requirements of Concrete Reinforcing Steel Institute (CRSI) Manual of Standard Practice, Chapter 3 Section 2.5 Class 1, Section 2.6 Class 1A, or Section 4. All supports shall meet the requirements for type and spacing as stated in the CRSI Manual of Standard Practice, Chapter 3. Concrete will not be placed until the placing of the reinforcing steel and supports have been approved by the Resident. If the Contractor fails to secure Department approval prior to placement, the Contractor's failure shall be cause for removal and replacement at the Contractor's expense. The Contractor shall notify the Resident, at least 48 hours prior to the placement, when the reinforcing steel will be ready for checking. Sufficient time must be allowed for the checking process and any needed repairs.

Evaluation of materials will be made using the specification limits in Table 1.

Compressive strength tests will be completed by the Department in accordance with AASHTO-T22 at \geq 28 days, except that no slump will be taken. The average of two

Page 2 of 4 125

concrete cylinders per sublot will constitute a test result and this average will be used to determine the compressive strength for pay adjustment computations.

Testing for Entrained Air in concrete, at the rate of one test per sublot, shall be in accordance with AASHTO T152.

Rapid Chloride Permeability test specimens will be completed by the Resident in accordance with AASHTO T-277 at an age \geq 56 days. Two 100 mm x 200 mm [4 in x 8 in] cylinders will be taken per sublot placed.

Surface Tolerance, Alignment and Trueness, Plumb and Batter, and Finish will be measured as described in Section 502.0502.

<u>Rejection by Resident</u> For an individual sublot with a calculated pay factor of less than 0.80, the Department will, at its sole discretion:

- <u>A.</u> Require the Contractor to remove and replace the entire affected placement with concrete meeting the Contract requirements at no additional expense to the Department, or
- <u>B.</u> Accept the material, at a reduced payment as determined by the Department. (See also Section 502.191)

For a lot in progress, the Contractor shall discontinue operations whenever one or more of the following occurs:

- <u>A.</u> The pay factor for any property drops below 1.00 and the Contractor is taking no corrective action
- <u>B.</u> The pay factor for any property is less than 0.90
- C. The Contractor fails to follow the QC Plan"
- <u>502.18 Method of Measurement</u> Under Section E. make the following change from "....Method A, and under Section 502.19..." to "...Method A, Section 502.0503- Quality Assurance Method B, and under Section 502.19..."
- 502.19 Basis of Payment Modify the first sentence of the seventh paragraph from "...accepted under Method A." to "...accepted under Method A and Method B."
- 502.191 Pay Adjustment for Compressive Strength Add the following as the second sentence to the first paragraph; "Pay factors (PF) for pay adjustments for compressive strength will be determined using the Quality Level Analysis as specified in Section 106."

Page 3 of 4 126

<u>502.192 Pay Adjustment for Chloride Permeability</u> Delete and replace with the following:

"Pay factors (PF) for pay adjustments for Chloride Permeability will be determined using the Quality Level Analysis as specified in Section 106.

Values greater than 4000 coulombs shall be subject to rejection and replacement at no additional cost to the Department."

502.193 Pay Adjustment for Air Content Delete and replace with the following;

"Pay factors (PF) for pay adjustments for air content will be determined using the Quality Level Analysis as specified in Section 106."

Add the following Section;

"502.195 Pay Adjustments for Compressive Strength, Chloride Permeability and Air Content The Composite Pay Factor (CPF) for each lot of concrete shall be computed as follows:

The pay adjustment for each lot of concrete shall be computed as follows:

Lot Pay Adjustment = $P \times CPF \times Lot Size$

There will be no positive pay adjustments for Method B Concrete."

Page 4 of 4

SPECIAL PROVISION <u>SECTION 504</u> CONCRETE PIPE TIES

<u>Description</u> This work shall consist of furnishing and installing concrete pipe ties in conformance with the Standard Details.

Materials All materials shall meet the requirements shown in the Standard Details.

Method of Measurement Concrete pipe ties shall be measured per each.

<u>Basis of Payment</u> The accepted quantity of concrete pipe ties will be paid for at the contract unit price per each. Such payment will be full compensation for furnishing, installing, and all other necessary incidentals for satisfactory completion of the work. Any grout or mortar necessary to repair chipping shall be incidental to the installation of the pipe ties.

Pay Item Pay Unit

504.069 Concrete Pipe Ties

Each

1 of 1

SPECIAL PROVISION <u>SECTION 512</u> FRENCH DRAINS

The f	followi	ng chan	iges and	additions	are mad	de to S	ubsection	512.04.	512.	.05.
			500 0000	*************	****	· · ·		· · · ·	,	

512.04 Method of Measurement:

French Drains will be measured as one each per location.

512.05 Basis of Payment:

French Drains will be paid for as one each for each location. Payment will be full compensation for excavating and disposing of existing material, furnishing and placing stone, furnishing and installing geotextile, re-grading in-slopes and all other incidentals to complete the work according to the typical/detail in the plans.

Pay Item Pay Unit 512.082 French Drains Each

IM-1511(400)E PIN 15114.00 Gardiner- Brunswick I-295 Southbound March 27, 2008 Supersedes December 2, 1991

SPECIAL PROVISION SECTION 518

REHABILITATION OF STRUCTURAL CONCRETE BRIDGE DECKS (Repairing Granite Curb Bedding Mortar)

<u>Description</u> This work shall consist of the removal and replacement of existing deteriorated granite curb bedding mortar as shown on the plans and as directed by the Resident.

<u>Materials</u> Mortar shall be an approved epoxy resin mortar or an approved polymer modified cementitious repair mortar.

<u>Construction Requirements</u> After the existing wearing surface is removed, the Resident will designate areas where the existing granite bedding mortar is to be repaired.

In areas designated to be repaired, the existing granite bedding mortar shall be removed under the curb to a depth of 25 mm [1 in] from the face of curb. The mortar shall be replaced with new mortar and finished with a 45° bevel at the face of curb. The mortar shall be proportioned, mixed, and applied in accordance with the Manufacturer's recommendations.

Method of Measurement Repairing Granite Curb Bedding Mortar will be measured for payment by the meter [foot], complete and accepted.

<u>Basis of Payment</u> Repairing Granite Curb Bedding Mortar will be paid for at the contract unit price, which will include all materials, labor, equipment, and incidentals necessary to complete the work including removal of existing mortar.

Payment will be made under:

Pay Item Pay Unit

518.39 Repairing Granite Curb Bedding Mortar

Meter [Foot]

IM-1511(400)E PIN 15114.00 Gardiner- Brunswick I-295 Southbound March 27, 2008

SPECIAL PROVISION <u>SECTION 520</u> EXPANSION DEVICES (Bridge Joint Modifications)

<u>Description</u> This work shall consist of removal, adjustment, modification, and replacement of bridge joints, as indicated on the Plans, and in accordance with the specifications.

<u>Materials</u> All structural concrete removed shall be replaced with Class LP concrete, per Section 502. A bonding agent from the Departments Qualified Products List (QPL) shall be used for bonding fresh concrete or patching material to existing hardened concrete.

The Elastomeric Concrete shall be one of the products listed on the Maine Department of Transportations Qualified Products List for Bridge Expansion Joints Systems. A manufacturer representative shall be on-site at the start of this work to ensure an acceptable installation.

The Joint and Seals, as required, shall be new material as indicated on the plans and shall meet the material, fabrication, and construction requirements of Section 520 - Expansion Devices - Non-Modular.

<u>Construction Requirements</u> The removal, adjustments, modifications and replacement of bridge joints shall be done in a manner to accommodate maintenance of traffic requirements, as approved by the Resident.

The Contractor shall install the joints or joint systems according to the manufacturer's recommendations.

The Contractor shall saw-cut a neat line for the substrate blockout per the dimensions indicated on the plans and standard details. The Contractor shall sand blast the substrate, blow it clean with dry oil-free compressed air, and thoroughly dry the substrate prior to placing joint material. Care shall be taken where reinforcing steel is uncovered not to damage the steel or its bond to the surrounding concrete. All existing reinforcing steel exposed by the joint and concrete removal shall be cleaned by sandblasting, or by other means approved by the Resident.

Page 1 of 2

IM-1511(400)E PIN 15114.00 Gardiner- Brunswick I-295 Southbound March 27, 2008

<u>Method of Measurement</u> Bridge joint modifications will be measured by each unit, complete in place and accepted for the type(s) identified on the Plans.

<u>Basis of Payment</u> The accepted quantity of bridge joint modifications will be paid for at the contract unit price each, which payment will be full compensation for all materials (including, but not limited to the following; elastomeric concrete, joint steel, joint seal, concrete, and reinforcing steel). Payment will also be full compensation labor, equipment, and incidentals necessary to complete the work, including removing and replacing structural concrete, adjusting and cleaning existing joint materials and reinforcing steel, and fabricating and installing new joint material and new seals, as required.

Payment will be made under:

<u>Pay Item</u>	Pay Unit
520.241 Bridge Joint Modifications- Type 1	Each
520.242 Bridge Joint Modifications- Type 2	Each
520.243 Bridge Joint Modifications- Type 3	Each

Page 2 of 2

SPECIAL PROVISION <u>SECTION 526</u> CONCRETE BARRIER (Temporary Concrete Barrier)

 $\underline{\text{Materials}}$ The connecting pin shall be 1 $\frac{1}{8}$ " in [28.58 mm] in diameter with a nut and washer connection.

Page 1 of 1 133

SPECIAL PROVISION <u>SECTION 527</u> ENERGY ABSORBING UNIT

(C-A-T System)

<u>Description</u> This work consists of furnishing and installing a C-A-T crash cushion as a permanent energy absorbing system in accordance with these specifications at location(s) shown on the plans or established by the Resident.

<u>Materials</u> The energy absorbing system shall be the C-A-T System as manufactured by Syro Steel Company of Girard, Ohio as approved and crash tested by the Federal Highway Administration.

<u>Replacement Parts</u> The Contractor shall provide a complete spare set of all above ground parts for each energy absorption system installed. All spare sets will be delivered to the local Division Office.

<u>Installation</u> A set of installation drawings will be provided to the Resident for the system installed. The system shall be installed in accordance with the manufacturer's recommendations and the installation drawings.

<u>Method of Measurement</u> Energy absorbing system will be measured by each unit, complete in place and accepted.

<u>Basis of Payment</u> The accepted quantity of energy absorbing system will be paid for at the contract unit price which shall include a complete spare set of all above ground parts for each energy absorbing system installed, the tail end length required and all incidentals necessary.

Payment will be made under:

Pay Item Pay Unit

527.301 Energy Absorbing System (C-A-T) Each

Page 1 of 1 134

SPECIAL PROVISION SECTION 605 UNDERDRAINS

The following changes and additions are made to Section 605.

605.02 Materials


Backfill material for Underdrain Type B shall meet the following:

Siev Designa Metric U	· -	Percentage by Weight Passing Square Mesh Sieves
25.0 mm	1 in	100
19.0 mm	³ / ₄ in	90-100
9.5 mm	³ / ₈ in	0-75
4.75 mm	No. 4	0-25
2.00 mm	No. 10	0-5

605.03 General:

Underdrain pipe for underdrain, type B shall consist of one of the following:

Corrugated Polyethylene Pipe for Underdrain (Smoothlined) Polyvinylchloride (PVC) Perforated Pipe



NOTES:

- I. EDGEDRAIN OUTLETS SHALL BE INSTALLED ONE PER EVERY 250 FT OF EDGEDRAIN.
 THE OUTLETS SHALL HAVE A MINIMUM SLOPE OF 1.0%. PIPE USED FOR OUTLETS
 SHALL BE NON-PERFORATED AND WILL BE PAID FOR UNDER ITEM 605.10.
- 2.THE MATERIAL FOR ELBOWS, TEES, AND WYES FOR EDGE DRAIN SHALL BE AT LEAST AS THICK AS THE LARGEST SIZE PIPE BEING CONNECTED.
- 3.THE INVERT ELEVATION OF EDGEDRAIN OUTLETS SHALL BE AT LEAST 6 INCHES ABOVE THE FLOW LINE OF A DITCH OR THE ORIGINAL GROUND.
- 4.NO ALLOWANCE FOR PAYMENT WILL BE MADE FOR EXCAVATING OR MATERIAL EXCAVATED BEYOND THE HORIZONTAL DIMENSIONS SHOWN FOR EDGEDRAIN.
- 5.EDGEDRAIN SHALL MEET ALL THE REQUIREMENTS OF STANDARD SPECIFICATION 605 AS WELL AS THE ADDITIONAL REQUIREMENTS OF SPECIAL PROVISION 605 OF THE CONTRACT. EDGEDRAIN SHALL BE PAID FOR UNDER ITEM 605.09, EDGEDRAIN OUTLETS SHALL BE PAID FOR UNDER ITEM 605.10.

136

SPECIAL PROVISION <u>SECTION 606</u> GUARDRAIL

<u>606.01 Description</u> This work shall consist of furnishing and installing guardrail components in accordance with these specifications and in reasonably close conformity with the lines and grades shown on the plans or as established. The types of guardrail are designated as follows:

Type 3-Galvanized steel "w" beam, wood posts or galvanized steel posts.

Type 3a-Galvanized steel "w" beam, wood posts, wood or composite offset blocks.

Type 3aa-Corrosion resistant steel "w" beam, wood posts, wood or composite offset blocks.

Type 3b-Galvanized steel "w" beam, galvanized steel posts, galvanized steel offset blocks.

Type 3c-Galvanized steel "w" beam, wood posts or galvanized steel posts, wood or composite offset blocks.

Type 3d-Galvanized steel "w" beam, galvanized steel posts, wood or composite offset blocks.

Thrie Beam-Galvanized steel thrie beam, wood posts or galvanized steel posts, wood or composite offset blocks.

Median barriers shall consist of two beams of the above types, mounted on single posts. Except for thrie beam, median barriers may include rub rails when called for.

Bridge mounted guardrail shall consist of furnishing all labor, materials, and equipment necessary to install guardrail as shown on the plans. This work shall also include drilling for and installation of offset blocks if specified, and incidental hardware necessary for satisfactory completion of the work.

Remove and Reset and Remove, Modify, and Reset guardrail shall consist of removing the existing designated guardrail and resetting in a new location as shown on the plans or directed by the Resident. Remove, Modify, and Reset guardrail and Modify guardrail include the following guardrail modifications: Removing plate washers at all posts, except at anchorage assemblies as noted on the Standard Details, Adding offset blocks, and other modifications as listed in the Construction Notes or General Notes. Modifications shall conform to the guardrail Standard Details.

Bridge Connection shall consist of the installation and attachment of beam guardrail to the existing bridge. This work shall consist of constructing a concrete end post or modifying an existing endpost as required, furnishing, and installing a terminal connector, necessary hardware, and incidentals required to complete the work as shown on the plans. Bridge Transition shall consist of a bridge connection and furnishing and installing guardrail components as shown in the Standard Details.

<u>606.02 Materials</u> Materials shall meet the requirements specified in the following Sections of Division 700 - Materials:

Timber Preservative	708.05
Metal Beam Rail	710.04
Guardrail Posts	710.07
Guardrail Hardware	710.08

Guardrail components shall meet the applicable standards of "A Guide to Standardized Highway Barrier Hardware" prepared and approved by the AASHTO-AGC-ARTBA Joint Cooperative Committee, Task Force 13 Report.

Posts for underdrain delineators shall be "U" channel steel, 2.44m [8 ft] long, 3.72 kg/m [2 ½ lb/ft] minimum and have 9.5 mm [3/8 in] round holes, 25 mm [1 in] center to center for a minimum distance of 610 mm [2 ft] from the top of the post.

Reflectorized Flexible Guardrail Markers shall be mounted on all guardrails. A marker shall be mounted onto guardrail posts at the flared end treatment's terminal and its tangent point, both at the leading and trailing ends of each run of guardrail. The marker's flexible posts shall be grey with either silver-white or yellow reflectors (to match the edge line striping) at the tangents, red at leading ends, and green at trailing ends. Whenever the end treatment is not flared, markers will only be required at the end treatment's terminal. These shall be red or green as appropriate. Markers shall be installed on the protected side of guardrail posts unless otherwise approved by the Resident. Reflectorized flexible guardrail markers shall be from the Maine DOT's Approved Product List of Guardrail Material. The marker shall be grey, flexible, durable, and of a non-discoloring material to which 75 mm [3 in] by 225 mm [9 in] reflectors shall be applied, and capable of recovering from repeated impacts. Reflective material shall meet the requirements of Section 719.01 for ASTM D 4956 Type III reflective sheeting. The marker shall be secured to the guardrail post with two fasteners, as shown in the Standard Details.

Reflectorized beam guardrail ("butterfly"-type) delineators shall be mounted on all "w"-beam guardrail. The delineators shall be mounted within the guardrail beam at guardrail posts. Delineators shall be fabricated from high-impact, ultraviolet & weather resistant thermoplastic. Reflectorized beam guardrail delineators shall be placed at approximately 20 m [62.5 ft] intervals or every tenth post on tangents and at approximately 10 m [31.25 ft] intervals or every fifth post on curves. Exact locations of the delineators shall be as directed by the Resident. On divided highways, the left hand delineators shall be yellow and the right hand delineators shall be silver/white. On two directional highways, the right hand side shall be silver/white and no reflectorized delineator used on the left. All reflectors shall have reflective sheeting applied to only one side of the delineator facing the direction of traffic as shown in the Standard Detail 606(07). Reflectorized sheeting for guardrail delineators shall meet the requirements of Section 719.01.

Single wood post shall be of cedar, white oak, or tamarack, well seasoned, straight, and sound and have been cut from live trees. The outer and inner bark shall be removed and all knots trimmed flush with the surface of the post. Posts shall be uniform taper and free of kinks and bends.

Single steel post shall conform to the requirements of Section 710.07 b.

Single steel pipe post shall be galvanized, seamless steel pipe conforming to the requirements of ASTM A120, Schedule No. 40, Standard Weight.

Acceptable multiple mailbox assemblies shall be listed on the Department's Approved Products List and shall be NCHRP 350 tested and approved.

The Guardrail 350 Flared Terminal shall be a terminal with a 1.2 m [4 ft] offset as shown in the Manufacturer's installation instructions.

Existing materials damaged or lost during adjusting, removing and resetting, or removing, modifying, and resetting, shall be replaced by the Contractor without additional compensation. Existing guardrail posts and guardrail beams found to be unfit for reuse shall be replaced when directed by the Resident.

606.03 Posts Posts for guardrail shall be set plumb in holes or they may be driven if suitable driving equipment is used to prevent battering and distorting the post. When posts are driven through pavement, the damaged area around the post shall be repaired with approved bituminous patching. Damage to lighting and signal conduit and conductors shall be repaired by the Contractor.

When set in holes, posts shall be on a stable foundation and the space around the posts, backfilled in layers with suitable material, thoroughly tamped.

The reflectorized flexible guardrail markers shall be set plumb with the reflective surface facing the oncoming traffic. Markers shall be installed on the protected side of guardrail posts. Markers, which become bent or otherwise damaged, shall be removed and replaced with new markers.

Single wood posts shall be set plumb in holes and backfilled in layers with suitable material, thoroughly tamped. The Resident will designate the elevation and shape of the top. The posts, that are not pressure treated, shall be painted two coats of good quality oil base exterior house paint.

Single steel posts shall be set plumb in holes as specified for single wood posts or they may be driven if suitable driving equipment is used to prevent battering and distorting the post.

Additional bolt holes required in existing posts shall be drilled or punched, but the size of the holes shall not exceed the dimensions given in the Standard Details. Metal around the holes shall be thoroughly cleaned and painted with two coats of approved aluminum rust resistant paint. Holes shall not be burned.

606.04 Rails Brackets and fittings shall be placed and fastened as shown on the plans. Rail beams shall be erected and aligned to provide a smooth, continuous barrier. Beams shall be lapped with the exposed end away from approaching traffic.

End assemblies shall be installed as shown on the plans and shall be securely attached to the rail section and end post.

All bolts shall be of sufficient length to extend beyond the nuts but not more than 13 mm [$\frac{1}{2}$ in]. Nuts shall be drawn tight.

Additional bolt holes required in existing beams shall be drilled or punched, but the size of the holes shall not exceed the dimensions given in the Standard Details. Metal around the holes shall be thoroughly cleaned and painted with two coats of approved aluminum rust resistant paint. Holes shall not be burned.

<u>606.045 Offset Blocks</u> The same offset block material is to be provided for the entire project unless otherwise specified.

<u>606.05 Shoulder Widening</u> At designated locations the existing shoulder of the roadway shall be widened as shown on the plans. All grading, paving, seeding, and other necessary work shall be in accordance with the Specifications for the type work being done.

606.06 Mail Box Post Single wood post shall be installed at the designated location for the support of the mailbox. The multiple mailbox assemblies shall be installed at the designated location in accordance with the Standard Details and as recommended by the Manufacturer. Attachment of the mailbox to the post will be the responsibility of the home or business owner.

<u>606.07 Abraded Surfaces</u> All galvanized surfaces of new guardrail and posts, which have been abraded so that the base metal is exposed, and the threaded portions of all fittings and fasteners and cut ends of bolts shall be cleaned and painted with two coats of approved rust resistant paint.

<u>606.08 Method of Measurement</u> Guardrail will be measured by the meter [linear foot] from center to center of end posts along the gradient of the rail except where end connections are made to masonry or steel structures, in which case measurement will be as shown on the plans.

Terminal section, low volume end, NCHRP 350 end treatments, reflectorized flexible guardrail marker, terminal end, bridge transition, bridge connection, multiple mailbox post, and single post will be measured by each unit of the kind specified and installed.

Widened shoulder will be measured as a unit of grading within the limits shown on the plans.

Excavation in solid rock for placement of posts will be measured by the cubic meter [cubic yard] determined from the actual depth of the hole and a hypothetical circle diameter of 600 mm [2 ft].

606.09 Basis of Payment The accepted quantities of guardrail will be paid for at the contract unit price per meter [linear foot] for the type specified, complete in place. Reflectorized beam guardrail ("butterfly"-type) delineators will not be paid for directly, but will be considered incidental to guardrail items. Terminal section, buffer end, NCHRP 350 end treatment, bridge connection, single post and reflectorized flexible guardrail markers will be paid for at the contract unit price each for the kind specified complete in place.

NCHRP 350 end treatments and low volume guardrail ends will be paid for at the contract price each, complete in place which price shall be full payment for furnishing and installing all components including the terminal section, posts, offset blocks, "w" beam, cable foundation posts, plates and for all incidentals necessary to complete the installation within the limits as shown on the Standard Details or the Manufacturer's installation instructions. Each end treatment will be clearly marked with the manufacturers name and model number to facilitate any future needed repair. Such payment shall also be full compensation for furnishing all material, excavating, backfilling holes, assembling, and all incidentals necessary to complete the work, except that for excavation for posts or anchorages in solid ledge rock, payment will be made under Pay Item 206.07. Type III Retroreflective Adhesive Sheeting

shall be applied to the approach buffer end sections and sized to substantially cover the end section. On all roadways, the ends shall be marked with alternating black and retroreflective yellow stripes. The stripes shall be 75 mm [3 in] wide and sloped down at an angle of 45 degrees toward the side on which traffic is to pass the end section. Guardrail 350 flared terminal shall also include a set of installation drawings supplied to the Resident.

Anchorages to bridge end posts will be part of the bridge work. Connections thereto will be considered included in the unit bid price for guardrail.

Guardrail to be placed on a radius of curvature of 45 m [150 ft] or less will be paid for under the designated radius pay item for the type guardrail being placed.

Widened shoulder will be paid for at the contract unit price each complete in place and will be full compensation for furnishing and placing, grading and compaction of aggregate subbase and any required fill material.

Adjust guardrail will be paid for at the contract unit price per meter and will be full compensation for adjusting to grade. Payment shall also include adjusting terminal end treatments where required.

Modify guardrail will be paid for at the contract unit price per meter and will be full compensation for furnishing and installing offset blocks, additional posts, and other specified modifications; removing, modifying, installing, and adjusting to grade existing posts and beams; removing plate washers and backup plates, and all incidentals necessary to complete the work. Payment shall also include removing and resetting terminal ends where required.

Remove and Reset guardrail will be paid for at the contract unit price per meter and will be full compensation for removing, transporting, storing, reassembling all parts, necessary cutting, furnishing new parts when necessary, reinstalling at the new location, and all other incidentals necessary to complete the work. Payment shall also include removing and resetting terminal ends when required. No payment will be made for guardrail removed, but not reset and all costs for such removal shall be considered incidental to the various contract pay items.

Remove, Modify, and Reset guardrail will be paid for at the contract unit price per meter and will be full compensation for the requirements listed in Modify guardrail and Remove and Reset guardrail.

Bridge Connections will be paid for at the contract unit price each. Payment shall include, attaching the connection to the endpost including furnishing and placing concrete and reinforcing steel necessary to construct new endposts if required, furnishing and installing the terminal connector, and all miscellaneous hardware, labor, equipment, and incidentals necessary to complete the work.

Bridge Transitions will be paid for at the contract unit price each. Payment shall include furnishing and installing the thrie beam or "w"-beam terminal connector, doubled beam section, and transition section, where called for, posts, hardware, precast concrete transition curb, and any other necessary materials and labor, including the bridge connection as stated in the previous paragraph.

Payment will be made under:

	Pay Item	Pay Unit
606.15	Guardrail Type 3a-Single Rail	meter [Linear Foot]
606.151	Guardrail Type 3aa-Single Rail	meter [Linear Foot]
606.17	Guardrail Type 3b-Single Rail	meter [Linear Foot]
606.1721	Bridge Transition - Type I	Each
606.1722	Bridge Transition - Type II	Each
606.1731	Bridge Connection - Type I	Each
606.1732	Bridge Connection - Type II	Each
606.178	Guardrail Beam	meter [Linear foot]
606.18	Guardrail Type 3b - Double Rail	meter [Linear foot]
606.19	Guardrail Type 3a - 4.5 m [15 ft] radius and less	meter [Linear Foot]
606.191	Guardrail Type 3aa - 4.5 m [15 ft] radius and less	meter [Linear Foot]
606.20	Guardrail Type 3a - over 4.5 m [15 ft] radius	meter [Linear Foot]
606.201	Guardrail Type 3aa - over 4.5 m [15 ft] radius	meter [Linear Foot]
606.21	Guardrail Type 3b - 4.5 m [15 ft] radius and less	meter [Linear Foot]
606.22	Guardrail Type 3b - over 4.5 m [15 ft] radius	meter [Linear Foot]
606.23	Guardrail Type 3c - Single Rail	meter [Linear Foot]
606.2301	Guardrail Type 3c - Double Rail	meter [Linear Foot]
606.231	Guardrail Type 3c - 4.5 m [15 ft] radius and less	meter [Linear Foot]
606.232	Guardrail Type 3c - over 4.5 m [15 ft] radius	meter [Linear Foot]
606.24	Guardrail Type 3d - Single Rail	meter [Linear Foot]
606.2401	Guardrail Type 3d - Double Rail	meter [Linear Foot]
606.241	Guardrail Type 3d - 4.5 m [15 ft] radius and less	meter [Linear Foot]
606.242	Guardrail Type 3d - over 4.5 m [15 feet] radius	meter [Linear Foot]
606.25	Terminal Connector	Each
606.257	Terminal Connector - Thrie Beam	Each
606.265	Terminal End-Single Rail - Galvanized Steel	Each
606.266	Terminal End-Single Rail - Corrosion Resistant Steel	Each
606.275	Terminal End-Double Rail - Galvanized Steel	Each
606.276	Terminal End-Double Rail - Corrosion Resistant Steel	Each
606.353	Reflectorized Flexible Guardrail Marker	Each
606.354	Remove and Reset Reflectorized Flexible Guardrail Marke	r Each
606.356	Underdrain Delineator Post	Each
606.358	Guardrail, Modify, Type 3b to 3c	meter [Linear Foot]
606.3581	Guardrail, Modify Existing to Type 3d	meter [Linear Foot]
606.362	Guardrail, Adjust	meter [Linear Foot]
606.365	Guardrail, Remove, Modify, and Reset, Type 3b to 3c	meter [Linear Foot]
606.3651	Guardrail, Remove, Modify, and Reset Existing to Type 3d	l meter [Linear Foot]
606.366	Guardrail, Removed and Reset, Type 3c	meter [Linear Foot]
606.367	Replace Unusable Existing Guardrail Posts	Each
606.47	Single Wood Post	Each
606.48	Single Galvanized Steel Post	Each
606.50	Single Steel Pipe Post	Each

Page 6 of 7


606.51	Multiple Mailbox Support	Each
606.55	Guardrail Type 3 - Single Rail	meter [Linear Foot]
606.551	Guardrail Type 3 - Single Rail with Rub Rail	meter [Linear Foot]
606.56	Guardrail Type 3 - Double Rail	meter [Linear Foot]
606.561	Guardrail Type 3 - Double Rail with Rub Rail	meter [Linear Foot]
606.568	Guardrail, Modify Type 3c -Double Rail	meter [Linear Foot]
606.59	Guardrail Type 3 - 4.5 m [15 ft] radius and less	meter [Linear Foot]
606.60	Guardrail Type 3 - over 4.5 m [15 ft] radius	meter [Linear Foot]
606.63	Thrie Beam Rail Beam	meter [Linear Foot]
606.64	Guardrail Thrie Beam - Double Rail	meter [Linear Foot]
606.65	Guardrail Thrie Beam - Single Rail	meter [Linear Foot]
606.66	Terminal End Thrie Beam	Each
606.70	Transition Section - Thrie Beam	Each
606.71	Guardrail Thrie Beam - 4.5 m [15 ft] radius and less	meter [Linear Foot]
606.72	Guardrail Thrie Beam - over 4.5 m [15 ft] radius	meter [Linear Foot]
606.73	Guardrail Thrie Beam - Single Rail Bridge Mounted	meter [Linear Foot]
606.74	Guardrail Type 3 - Single Rail Bridge Mounted	meter [Linear Foot]
606.753	Widen Shoulder for Low Volume Guardrail End - Type 3	Each
606.754	Widen Shoulder for Guardrail 350 Flared Terminal	Each
606.78	Low Volume Guardrail End - Type 3	Each
606.79	Guardrail 350 Flared Terminal	Each

Page 7 of 7

I. Reflectorized Flexible Guardrail Markers shall be from Maine DOT's Approved Product List of Guardrail Material.

2. Installation:

- a. Each bolt-hole diameter shall be the bolt diameter + $\frac{1}{16}$ ".
- b. Wood post attachment attach marker with 2, 5/16" diameter zinc-coated lag bolts, having 2" of embedment into wood post.
- c. Steel post attachment attach marker with 2, $\frac{1}{4}$ " diameter zinc-coated bolt, washer and nut assemblies, having $\frac{1}{2}$ " of bolt extension behind steel post.
- d. When provided by the marker manufacturer, a stiffening pipe shall be inserted into the base of the marker prior to drilling bolt holes and shall remain in-place.



SPECIAL PROVISION <u>SECTION 620</u> REINFORCEMENT GEOGRID

Description

This work shall consist of furnishing and installing reinforcement geogrid in accordance with these specifications and in reasonably close conformity with the lines, grades, and dimensions shown on the plans or as directed by the Resident.

Material

Geogrids shall consist of a regular network of integrally connected polymeric tensile elements with aperture geometry sufficient to permit significant mechanical interlock with the surrounding soil, aggregate or other material. The geogrid structure shall be dimensionally stable to retain its geometry under construction stresses and shall have high resistance to damage during construction, ultraviolet degradation, and all forms of chemical and biological degradation encountered in the soil being reinforced.

The reinforcement geogrid shall meet or exceed the Minimum Average Roll Values (MARV) of the properties in Table 1.

Acceptable manufacturers for reinforcement geogrids must be approved by the Resident.

Table 1. - Physical Property Requirements (Biaxial Reinforcement Geogrid)

Reinforcement Geogrid	Test Method	Minimum Average Roll Value
Mechanical Property		$(MARV)^1$
Tensile Modulus at 5% Strain MD	ASTM D-6637	236.0 kN/m (16,000 lb/ft)
Tensile Modulus at 5% Strain XD	ASTM D-6637	396.0 kN/m (26,500 lb/ft)
Rib Junction Strength	GRI-GG2	14.6 kN/m (1000 lb/ft) in both
		directions
Aperture Openings		Between 19.0 and 75.0 mm
		(0.75 and 3 inches)
Percent Open Area		50 to 80%

Values are minimum average roll values determined in accordance with ASTM D-4759.

Certification

Prior to construction the Contractor shall submit to the Resident the Manufacturer's certification that the geogrid supplied has been evaluated in full compliance with this Specification and is fit for long-term, critical soil reinforcement applications. The Contractor's submittal package shall include, but not be limited to, actual tests for tension/creep, durability/aging, construction damage, and quality control tensile testing.

Delivery, Storage and Handling

The Contractor shall check the reinforcing geogrid upon delivery to ensure that the proper material has been received. Each geogrid roll shall be shipped in a protective bag and clearly

marked with roll number, lot number, geogrid style and principle strength direction. During all periods of shipment and storage, the geogrid shall be protected from temperatures greater than 60°C (140°F) and all deleterious materials that might otherwise become affixed to the geogrid and affect its performance. The manufacturer's recommendations shall be followed with regard to protection from direct sunlight. The geogrid shall be stored off the ground in a clean, dry environment out of the pathway of construction equipment.

Construction Requirements

Reinforcement geogrid shall be installed, in accordance with the manufacturer's recommendations, to the proper elevation and alignment, as shown on the plans or as directed by the Resident.

- 1. The geogrid shall be laid at the proper elevation and alignment as shown on the plans. The Contractor shall verify correct orientation of the geogrid. Geogrid may be temporarily secured in-place with staples, pins, sand bags or backfill as required by fill properties, fill placement procedures, or weather conditions, or as directed by the Resident.
- 2. Reinforcement geogrid shall be oriented such that the roll length runs parallel to the construction centerline.
- 3. Adjacent rolls of reinforcement geogrid shall be overlapped a minimum of 300 mm (1 foot).
- 4. Lengths of reinforcement geogrid shall be continuous, splicing along the length will not be allowed.
- 5. Seams along adjacent lengths of reinforcement geogrid shall be tied together with hog rings or cable ties every 1.2 to 1.8 meters (4 to 6 feet).
- 6. The reinforcement geogrid shall be anchored at each end, and pulled taut, to reduce any considerable slack, as directed by the Resident.
- 7. Fill shall not be dumped directly onto the Reinforcement Geogrid or Reinforcement Geotextile. It shall be dumped at the edge of Reinforcement Geogrid/Reinforcement Geotextile or on a previous course of fill with a minimum compacted depth of 200 mm (8 inches).
- 8. The geogrid shall be covered with fill materials within 5 days of placement to protect against unnecessary exposure.
- 9. Fill may then be pushed onto the reinforcement geogrid using a track mounted bulldozer. At no time shall construction equipment be allowed directly onto the reinforcement geogrid. Track mounted equipment shall be allowed on previous courses of fill with a minimum compacted depth of 200 mm (8 inches). Smooth drum roller compaction equipment shall be allowed on previous courses of fill with a minimum compacted depth of 200 mm (8 inches) and spread fill with a minimum depth of 300 mm (12 inches), loose measure. At no time shall rubber tired or sheeps-foot rollers be allowed onto the reinforced fill. Turning of vehicles should be kept to a

minimum to prevent tracks from displacing the fill and damaging the geogrid. Sudden breaking and sharp turning shall be avoided. Equipment speeds over 15 MPH shall not be allowed.

- 10. Placement, spreading, and compaction of soil on top of the reinforcement geogrid shall advance from one end of the reinforcement geogrid and move towards the other. Care shall be taken to minimize the development of wrinkles and to ensure that the reinforcement geogrid doesn't move from its position during fill placement. Limited stacking may the permitted, as directed by the Resident.
- 11. Fill shall be compacted as specified in (1) the Standard Specifications or (2) to at least 90 percent of the maximum dry density determined in accordance with AASHTO T-180, whichever is greater. Density testing shall be made at a minimum frequency of one (1) test per lift or as otherwise specified in the Standard Specifications.
- 12. During construction the surface of the fill shall be kept approximately horizontal. Fill shall be graded away from the slope crest and rolled at the end of each work day to prevent ponding of water on surface of the reinforced soil mass.
- 13. Any geogrid damage shall be repaired or replaced in accordance with the manufacturer's recommendations. The Contractor, at no additional cost to the Department, shall replace any geogrid damaged during installation.
- 14. Rutting may develop within the initial granular lift but rut depths should not exceed 75 mm (3 inches). It may be necessary to decrease the size and/or weight of the construction equipment or increase the thickness of the granular lift if rut depths of 75 mm (3 inches) or less cannot be maintained.
- 15. All rutting formed during construction shall be filled with new base material. In no case shall rutting be filled by blading down

Method of Measurement

Reinforcement Geogrid measurement will be by the square yard of material installed. Incidental overlaps for connections, splices, etc. are not included in the pay item.

Basis of Payment

Reinforcement geogrid placement will be paid for at the Contract unit price per square yard which shall be full compensation for all off-loading, inspection, storage, labor, materials, equipment, tools and any incidentals to complete the installation.

Pay Item	Description	Pay Unit
620.65	Reinforcement Geogrid	Square Meter (Square Yard)

SPECIAL PROVISION <u>SECTION 627</u> PAVEMENT MARKINGS

The following additions are made to Section 627 Subsection 627.10 of the December 2002 revision of the Standard Specifications.

627.10 Basis of Payment:

<u>Pay Item</u>	Pay Unit
627.72 6 Inch White Pavement Marking Line	Linear Foot [Meter]
627.74 6 Inch Yellow Pavement Marking Line	Linear Foot [Meter]
627.781 Temporary 6 Inch Painted Pavement	Linear Foot [Meter]
Painted Marking Line, White or Yellow	

SPECIAL PROVISION <u>SECTION 631</u> EQUIPMENT RENTAL EQUIPMENT REQUIREMENTS

The following are added to Subsection 631.01, 631.02 and 631.08.

631.01 Description

This item is to be used in areas not accessible with other equipment and will only be used when authorized by the Resident.

631.02 General

<u>Equipment</u> <u>Description</u> <u>Minimum Size</u>

Mini-All Purpose Excavator Track mounted 89 hp [66.1 kW]

Operating Weight Bucket Range

27,100 lbs. [12,300 kg] .5 -.98 Cu. Yd. [.38 - .75 Cu. M]

631.08 Basis of Payment

Payment will be made under:

<u>Pay Item</u> <u>Pay Unit</u>

631. 122 Mini – All Purpose Excavator (including Operator) Hour

Page 1 of 1 149

IM-1511(400)E Pin 15114.00 Gardiner-Brunswick I-295 Southbound

SPECIAL PROVISION <u>SECTION 631</u> EQUIPMENT RENTAL SIGN CREW

The following are added to Subsection 631.01, 631.02 and 631.08. 631.01 Description

This item is to be used to modify detour signs and locations when emergencies arise or when Maine DOT is unreachable. This item may be used at any time due to emergency situations and must be available on short notice if needed. It is the intent of the Department that the "Sign Crew" item be a separate crew and equipment from what is being used by the contractor for item 652.36. The contractor may be allowed to use crew and equipment that is being used for item 652.36 on a limited basis if approved in advance by the Resident.

631.02 General

Equipment

A sign crew shall consist of a minimum of 2 laborers and 1 truck capable of carrying at least four signs (4'x 4' in size) including all hardware and equipment necessary to install and remove them as needed.

631.08 Basis of Payment

Payment will be made under:

Pay Item Pay Unit

631.52 Sign Crew Hour

SPECIAL PROVISION <u>SECTION 645</u> HIGHWAY SIGNING

(Flexible Reflectorized Delineator)

<u>Description</u> This work shall consist of furnishing and installing flexible reflectorized delineators in accordance with the Manufacturer's recommendations in reasonably close conformity with the plans and specifications.

Materials Flexible reflectorized delineators shall be one of the following:

Manufacturer Model

Safe-Hit Corp. Safe-Hit Co-extruded Type SH248GP3

Safe-Hit Co-extruded Type SH254GP3

Safe-Hit Co-extruded Type SH348GP3

Construction Requirements Flexible delineators shall be installed in accordance with Section 645.062 Installation of Delineators, except that the mounted height of the delineator shall be 1200 mm [4 ft] above the edge of shoulder.

<u>Method of Measurement</u> Flexible reflectorized delineators will be measured by the number of units complete in place.

<u>Basis of Payment</u> The accepted reflectorized delineators will be paid for at the contract unit price each. Such payment will be full compensation for furnishing and installing the delineator and all associated hardware complete in place.

Payment will be made under:

Pay Item Pay Unit

645.306 Flexible Reflectorized Delineator

Each

SPECIAL PROVISION SECTION 652 MAINTENANCE OF TRAFFIC Construction Sign Sheeting Material

Super high intensity fluorescent retroreflective sheeting, ASTM D 4956 - Type VII, Type VIII, or Type IX (prismatic), is required for all construction signs.

Page 1 of 1 152

SPECIAL PROVISION <u>SECTION 652</u> MAINTENANCE OF TRAFFIC

Approaches. Approach signing for the work on the Interstate shall include the following

signs

Road Work 3 Miles Road Work 500 Feet
Road Work 2 Miles Road Work Next x Miles

Road Work 1 Mile End Road Work

Work Areas Interstate. At the work sites, signs, flashing arrow boards and channeling devices as shown on the Work Zone Signing details shall be used as directed by the Resident.

Signs Include:

Right or Left Lane Closed 2 Miles

Lane Ends 1 mile Merge Right or Left Now

Right or Left Lane Closed 1/2 Mile

Speed Limit 55* (Existing speed limit signs will be covered when in use)

Fines Doubled* 1

Work Zone 1

Do Not Pass*

Right/Left Merge Symbol (W 4-2)

End Work Zone

Resume Speed

Exit (green with white legend and border)

Road Work Ahead

Merging Traffic Symbol (At on-ramp in right lane closure)

Stop Ahead (At on-ramp in right lane closure)

Single Lane Ahead (At on-ramp in left lane closure)

Stop (At on-ramp in right lane closure)

Directional Arrows (At on-ramp in right lane closure)

Bump

Trucks Entering

Left Turning Trucks with 500 Feet Advisory Plate

Flagger Sign

Caution Rumble Strip

Ramp Closed

- * White with black legend and border
- ¹ In addition to work zone package these signs will also be required at the end of any on ramps that are within the lane closure

The above lists of Approach signs and Work Area signs are representative of the contract requirements. Other sign legends may be required.

General Requirements-Interstate.

There shall be no diverting of traffic between northbound and southbound lanes.

The Contractor shall provide a minimum traveled way width of 14 Feet through an expressway lane closure.

The maximum length of lane closure shall be 3 miles in length.

Lane closures shall not be set up until work in the area is to be performed and must be removed when no work is being performed.

Lane closures shall be separated by at least 2 miles.

All construction work shall be confined to the lane closed to traffic.

Slow moving construction equipment may travel the closed lane for short distances.

All trucking shall be done in the lane open to traffic.

No equipment or vehicles of the Contractor, his Subcontractor or employees engaged in work on this contract, shall be parked or stopped on lanes carrying traffic, or on lanes or shoulders adjacent to lanes carrying traffic, at any time.

The Contractor shall keep all paved areas of the roadway as clear as possible at all times. The Contractor's men and equipment shall avoid crossing traffic lanes whenever possible.

Road Work Ahead signs shall be used on roads adjacent to the interstate when the Contractor is working on or near an on-ramp or when the on-ramp enters a lane closure area.

Existing pavement markings at centerline in the taper to the lane closure shall be removed or painted over with an approved paint beginning at the first drum in the taper in overnight lane closures.

A temporary pavement marking line, or at the Contractor's option temporary approved raised pavement markers, shall be placed from the existing lane edge line through the length of the taper in overnight lane closures. Temporary painted lines shall only be used where the pavement is to be overlaid. Temporary plastic lines or raised pavement markers shall be used on pavement that it not to be overlaid. Removing existing pavement markings and **installing and removing raised pavement markers in lane closure tapers** shall be incidental to item 652.36. Placing all other temporary pavement marking lines or markers will be paid under Item 627.781 Temporary 6 Inch Painted Pavement Marking Line, White or Yellow.

12:1 paved tapers shall be placed at all Ramps to be used by traffic immediately following paving.

Interstate crossovers will not be used to reverse direction. They may be used as storage areas as long as sufficient room is left for the utilization of law enforcement.

The Contractor, his Subcontractor or employees shall conduct all work in a safe and professional manner as it relates to the traveling public (i.e. not adversely disrupting the flow of traffic in an unsafe manner when exiting or entering a lane closure or crossover, negative verbal or physical gestures).

The Interstate will be completely shut down to all southbound traffic from Station 712+50 to 1661+00 (Northerly limits of the project) starting June 16 at 12:00 am to August 31 at 11:59 pm. The Maine DOT will have a detour in place prior to June 15, 2008, including a temporary on ramp for southbound traffic at station 710+50 +-. The Maine DOT will be responsible for all signs, installation, adjusting and maintenance of the detour.

The contractor will be responsible closing down all on and off ramps including signs, drums, barricades, installation, and maintenance and ensuring the public has no access to I-295 southbound.

Devices used to close the ramps shall be placed so that vehicles will not be able to physically drive between the devices.

Channelization. Channelization devices shall include the following:

Flashing Arrow Boards

Vertical Panel Markers

Drums (The contractor shall place 3 drums across a closed lane every 1500')

Cones

Temporary Raised Pavement Markers

Channelization devices shall be installed and maintained at the spacing determined by the MUTCD to delineate travel lanes through the project. Vertical Panel markers shall be placed 2 feet from the outside edge of the shoulder on the passing lane at 600 feet intervals when the travel lane is closed in overnight lane closures. The vertical panel marker size shall be 12 inches x 24 inches. When directed by the Engineer, drums or other channelization devices shall be placed in the closed lane at a maximum—spacing of 2 x speed limit.

<u>Temporary Centerline or Edge Line</u>. A temporary painted centerline and edge line shall be marked each day on all new pavement to be used by traffic. The temporary line shall conform to the standard marking patterns used for permanent markings and will be paid for under Section 627. Failure to apply a temporary line daily will result in suspension of paving until temporary markings are applied to all previously placed pavement.


<u>Roadside Recovery Area.</u> The Contractor shall not store material nor park equipment within 15 feet of the edge of the established travel lanes.

No long term storage of equipment or material will be allowed within 30 feet of the edge of the established travel lanes. Short term storage of equipment or material less than 30 feet from the edge of the established travel lanes must be approved by the Department and shall be clearly marked by **drums and cones**. Short term storage shall be defined as less than 12 hours. No equipment or material will be allowed within 30 feet of the edge of the established travel lanes at night.

Vehicles shall not be parked in the median, except at crossovers. Crossovers shall not be blocked from the normal use of maintenance or State Police Forces. Equipment parked in crossovers shall be well delineated with **drums**.

<u>Speed Limits in Work Zones</u>. The Contractor shall sign all approved reduced speed limits on construction project according to APM #431 - A Policy on the Establishment of Speed Limits in Work Zones.

WORK ZONE SIGNING



RESUME SPEED

TRAFF I C

FLOW


RESUME SPEED

END WORK ZONE

110 FEET FEET. **OF** \sim AGE SHALL BE SPACED AT A DISTANCE OF ACROSS THE CLOSED LANE EVERY 1500 SHALL BE SPACED AT 55 FEET APART. IZING DEVICES ITH 3 DEVICES IN THE TAPER CHANNEL I APART WI DEVICES

4

RAMPS - LEFT LANE CLOSED



SPECIAL PROVISION SECTION 652 MAINTENANCE OF TRAFFIC

(Traffic Control)

Failure by the contractor to follow the Contracts 652 Special Provisions and Standard Specification and/or The Manual on Uniform Traffic Control Devices (MUTCD) and/or The Contractors own Traffic Control Plan will result in a violation letter and result in a reduction in payment as shown in the schedule below. The Departments Resident or any other representative of The Department reserves the right to suspend the work at any time and request a meeting to discuss violations and remedies. The Department shall not be held responsible for any delay in the work due to any suspension under this item. Any reduction in payment under this Special Provision will be in addition to forfeiting payment of maintenance of traffic control devices for that day.

ORIGINAL CONTRACT AMOUNT

from	Up to and	Amount of Penalty
More Than	Including	Damages per Violation
\$0	\$100,000	\$250
\$100,000	\$300,000	\$500
\$300,000	\$500,000	\$750
\$500,000	\$1,000,000	\$1,500
\$1,000,000	\$2,000,000	\$2,500
\$2,000,000	\$4,000,000	\$5,000
\$4,000,000	and more	\$10,000

SPECIAL PROVISION SECTION 652- PORTABLE DYNAMIC MESSAGE SIGN

<u>Description</u> This work consists of furnishing seven (7) new, trailer-mounted portable dynamic message signs (signs) and providing sign-related testing, up to 20 hours of class room training, spare parts, control software, 12-months of technical assistance, and warranty.

General

<u>Project Summary</u> The signs will be installed by others on gravel pads next to freeways. The manufacturer shall deliver the signs to the Maine Department of Transportation's (the Department's) Fairfield facility (10 Mountain Avenue, Fairfield, ME, near the I-95/Rt. 201 interchange). There, the manufacturer shall test each sign (and certain spare parts) in the presence of Department personnel and the installation contractor. The manufacturer shall also train the installation contractor's staff and Department personnel in the proper installation and set-up of the signs.

The signs will be installed near Portland and Bangor. When the first sign is installed, the sign manufacturer shall supervise the installation contractor's work and shall conduct additional training, if needed, to ensure that the trainees are competent to install the remaining signs.

The manufacturer shall install sign control software on computers supplied by the Department, test the software, and train Department personnel in its use.

<u>Manufacturer Qualifications</u> The sign must be made by a manufacturer meeting the following qualifications:

- Little risk of financial problems that could impair the manufacturer's ability to provide warranty service, technical support, and spare parts over the next year.
- A record of satisfied customers for products equivalent to those to be furnished under this contract.
- Ability to produce products in compliance with the National Transportation Communications for ITS Protocol (NTCIP).

Required Submittals Five copies of the following items shall be submitted.

- <u>a.</u> With the bid The bid will not be deemed acceptable unless these items demonstrate that the manufacturer meets the requirements of the above.
 - 1. Dunn & Bradstreet's "Comprehensive Insight Plus" report on the manufacturer's financial condition. If the manufacturer is a subsidiary, provide the report for the parent.

Page 1 of 21

- 2. Names, titles, and telephone numbers of individuals at five or more transportation agencies that have purchased the manufacturer's trailer-mounted LED signs with NTCIP-enabled central control software. Do not include customers who have had the products less than six months.
- 3. Letter from an independent testing agency certifying that the manufacturer's signs are compliant with NTCIP 1203. The signs and software subjected to the independent test need not be identical to those proposed for this project.
- <u>b. Prior to shipping any signs</u> Each of these items must be revised until found acceptable by the Department.
- 1. Shop drawings and descriptive literature demonstrating that the signs meet these specifications.
- 2. Test report and certification by an independent testing agency that the sign meets the environmental requirements of NEMA TS 4, <u>Hardware Standards for Dynamic Message Signs (DMS) with NTCIP Requirements</u>. The test must have been performed on sample components that are essentially identical to those provided in this project.
- 3. Certification by an independent testing agency or a professional engineer registered in Maine that the sign meets the structural integrity requirements of NEMA TS 4. The certification need only cover those aspects of structural integrity for which TS 4 requires certification.
- 4. Calculations demonstrating that the sign meets the battery capacity and solar recharging requirements of below, as well as the recharging requirement of Paragraph 3.3.5.3 of NEMA TS 4. For solar recharging, take into account the azimuth and tilt of the panels as they will be mounted. If these cannot be aimed, assume the panels are facing north.
 - 5. A user manual for the central software.
 - 6. A manual or manuals for the installation, operation, and maintenance of the signs.
- 7. A proposed plan for testing the signs, software, and spare parts at the time of delivery.
- 8. Resumes demonstrating the qualifications of the individuals who will train the installation contractor and Department staff.
- 9. An outline of the proposed training activities with the estimated duration of each activity.

c. With the Signs

Page 2 of 21 163

- 1. A CD containing the management information bases (MIBs) and electronic copies of the manuals and drawings provided earlier. The MIBs shall be ASCII files in Abstract Syntax Notation 1 (ASN.1) format. The supported range shall be indicated in ASN.1 format in the SYNTAX field of the associated OBJECT TYPE macro for devices that do not support the full range of any object within a standard MIB module. The manuals and drawings shall be in Acrobat or Word. The manufacturer shall allow the use of this documentation by any party authorized by the Department for systems integration purposes.
- 2. Warranty covering the signs for the manufacturer's standard warranty period, but not less than one year.

<u>Conformance Testing of Display</u> The manufacturer is not required to provide independent certification that the display meets the requirements in Section 5 of NEMA TS 4. However if, after inspecting the signs, the Department believes that the display properties do not fully comply with TS 4 and these specifications, then the manufacturer must either remedy the defects or present third party certification that the signs are in compliance.

<u>Portable Sign</u> The sign shall consist of an all-LED (light emitting diode) matrix message board, support post, power system, and a controller assembly, all mounted on a heavy duty, towable trailer. The sign shall conform to NEMA TS 4, except for requirements of NEMA TS 4 that conflict with the requirements in this specification.

General

- <u>a. Finish</u> All exterior surfaces except the sign face shall be cleaned, primed and finished with two coats of Highway Safety Orange. An exception is the border around the display, which shall be black. The finish shall be either polyester powdercoat or baked enamel.
- <u>b. Wiring</u> All wiring shall be inaccessible to vandals. Connections to power and telephone service supplied by others shall be via wires enclosed in liquid-tight flexible metal conduit, so the sign must have provision for connecting such conduit to the sign.
- c. <u>Labeling</u> All terminals and connections shall be clearly labeled. Labels shall be permanent, waterproof and machine-printed.

Message Board

<u>a. Dimensions</u> The display shall be a matrix of LED pixels approximately six feet high by 12 feet wide. Center-to-center pixel spacing shall be the same horizontally and vertically and shall be 2.6 inches or less. If the spacing is 2.6 inches, the display shall be at least 50 pixels wide and 27 pixels high. If the spacing is less, the number of pixels shall be

Page 3 of 21 164

proportionally larger. The sign shall be capable of displaying three lines of 18" high characters.

- <u>b. Finish</u> The inside of the display enclosure shall be painted black to facilitate heat dissipation.
- c. Display Modules The display shall be composed of at least ten display modules that can quickly be replaced in the field. They must be designed so they cannot warp.
- <u>d. Glazing</u> If the display modules are not weatherproof, they shall be protected by a watertight sheet of UV-protected acrylic or polycarbonate.
- <u>e. LEDs</u> The LEDs shall be amber and have a viewing angle of 30 degrees in the horizontal plane. That is, brightness at 15 degrees off axis shall be at least 50 percent of the on-axis brightness.
- <u>f. Enclosure</u> The enclosure shall be made of aluminum with aluminum and/or stainless steel fasteners.
- g. Brightness When all pixels are illuminated at maximum brightness, the display shall have an on-axis luminance intensity of at least 3,720 candelas per square meter. The sign shall have an automatic intensity control feature in order to keep the LED lamp matrix intensity constant with a reduction in voltage.
- <u>h. Sighting Device</u> The housing shall include a sighting device to facilitate proper directional alignment of the message board.

<u>Support Post</u> The message board shall be mounted on a mast that is raised and lowered by an electrically powered hydraulic pump (with attached fluid reservoir).

- <u>a. Backup Pump</u> The hydraulic system shall include an auxiliary manual pump with release for emergency use.
- <u>b</u>, <u>Rotation</u> When fully raised in the display position, the message board shall be able to rotate so the sign can be aimed at traffic.
- <u>c. Locking Mechanisms</u> The sign's rotation-locking device shall be independent from the sign's raise/lower-locking device
 - <u>d. Protection</u> The hydraulic system shall be inside a locked housing.

<u>Power System</u> The sign shall be powered by batteries that are recharged by 120 volt AC power when available and by solar power at other times.

Page 4 of 21 165

- <u>a. Batteries</u> The batteries must be available from multiple manufacturers. The number and type of batteries shall be sufficient to operate a full display of characters for 30 continuous days with no recharging.
- <u>b. Recharging</u> During recharging of low batteries from 120-volt power, the sign shall operate normally.

Power control circuitry shall protect the batteries from overcharging by the 120-volt and solar chargers. It shall also protect the all components from damage in the event of a short circuit, overload, or similar problem. It shall disconnect the load from the batteries when further discharging could damage the batteries.

The battery charger shall include an ammeter for monitoring the charging process, as well as a display of the battery voltage.

- c. Automatic Sensing of 120-Volt Power The system shall automatically switch between solar and 120-volt power (when available) for battery charging with no operator intervention.
- d. Operation without Batteries If the batteries have been disconnected, the sign and controller shall operate using 120 VAC.
- <u>e. Solar Recharging</u> Under average conditions for Bangor in winter, the solar charging system shall produce more power in a 24 hour period than the sign needs to display a 3-line message continuously for 24 hours.

Controller Assembly

- <u>a. Control Architecture</u> The sign shall support both types of control architecture described in Section 8.10 of TS 4. The controller shall be able to store at least 30 messages in non-volatile memory.
- <u>b. Fonts</u> Section 5.6 of TS 4 does not apply to this sign. The controller shall be capable of storing at least four fonts in memory and shall be shipped with at least two fonts in memory. The user shall be able to create at least two additional fonts, download them to the controller, and store them there.

Both fonts shall be 18 inches high. One shall be comparable to that shown in Figure 7-1 of Federal Highway Administration publication # FHWA-TS-90-043. The other shall be a similar, compressed font. Both fonts shall include:

- All upper case letters,
- The following punctuation marks . , / ? ': and ".
- All numerals 0 to 9,
- The following special characters #& * +< >←→↑↓ トスピリ

Page 5 of 21

166

c. Alarms The sign controller shall automatically notify the central sign control computer when the batteries are low.

<u>Communication</u> Section 8.7 of TS 4 does not apply to this sign. All communication with the sign controller shall use the latest recommended NTCIP standards at the time of bidding.

- a. Communication Ports The controller shall have at least two communication ports that can be used for remote control. The controller shall accept commands via either port and respond via the same port that received the command, so that each port automatically functions as a backup communication link for the other port and include cell phone modems for AT&T, GPS and web server service
 - One port shall be equipped with an internal modem and shall communicate over a
 dial-up telephone line, which may be a cellular connection. It shall operate in
 accordance with the latest version of NTCIP 2103, <u>Point-to-Point Protocol over RS-232 Subnetwork Profile</u>. All Challenge Handshake Authentication Protocol (CHAP)
 secrets shall be user configurable via the CHAP Secret Table.
 - The other port shall be an RJ-45 Ethernet port, which may be used for a wireless data communication service. The Ethernet port shall also be suitable for connecting a notebook computer for local control and maintenance. It shall operate in accordance with the latest version of NTCIP 2104, <u>Ethernet Subnetwork Profile</u>. The medium shall be 10Base-T.

<u>b. Cellular Antenna</u> An antenna suitable for cellular telephone or data service shall be installed on top of the message board. Install the antenna in a way that does not permit water to enter the message board. A 50 Ohm coaxial cable, 100 percent shielded and designed for outdoor use, shall run from the antenna to the controller compartment. The cable may not pass through the top of the compartment and the hole where the cable enters must be sealed watertight. Immediately upon entering the controller compartment, the cable shall terminate on a grounded lightning protector. The antenna shall be omnidirectional, designed for both the 806-894 MHz range and the 1850-1990 MHz range. It shall have a built-in ground plane and vertical polarization. The antenna gain shall be at least 5 dBi.

c. Information Level Standards

<u>1. Global Objects</u>. The sign shall support the following objects defined in NTCIP 1201, Global Object Definitions:

- All objects in the Global Configuration Node.
- The following objects in the Global Time Management Node: globalTime; globalDaylightSaving; maxTimeBaseScheduleEntries; timeBaseScheduleTable; maxDayPlans; maxDayPlanEvents; timeBaseDayPlanTable.
- All objects in the Report Parameters Node.

Page 6 of 21 167

The module table required by Clause 2.2.3 of NTCIP 1201 shall contain at least one row with module Type equal to 3 (software).

2. Dynamic Message Sign Objects At least the following objects, if defined in NTCIP 1203

- Sign Configuration and Capability Objects
 - dmsSignAccess
 - dmsSignType
 - dmsSignHeight
 - dmsSignWidth
 - dmsSignTechnology
 - vmsCharacterHeightPixels
 - vmsCharacterWidthPixels
 - vmsSignHeightPixels
 - vmsSignWidthPixels
 - vmsHorizontalPitch
 - vmsVerticalPitch
 - vmsMaxNumberPages
 - vmsMaxMultiStringLength
- ♦ Font Objects
 - numFonts
 - fontTable and subsidiary objects
 - maxFontCharacters
 - characterTable and subsidiary objects
 - fontMaxCharacterSize
- MULTI Configuration Objects
 - defaultFlashOn
 - defaultFlashOff
 - defaultFont
 - defaultJustificationLine
 - defaultJustificationPage
 - defaultPageOnTime
 - defaultPageOffTime
 - defaultCharacterSet
 - dmsColorScheme
 - dmsSupportedMultiTags

Page 7 of 21

- Message Objects
 - messageIDCode
 - messageActivationCode
 - dmsNumPermanentMsg
 - dmsNumChangeableMsg
 - dmsMaxChangeableMsg
 - dmsFreeChangeableMemory
 - dmsNumVolatileMsg
 - dmsMaxVolatileMsg
 - dmsFreeVolatileMemory
 - dmsMessageTable and subsidiary objects
 - dmsValidateMessageError
- ◆ Sign Control Objects
 - dmsControlMode
 - dmsSWReset
 - dmsActivateMessage
 - dmsMessageTimeRemaining
 - dmsMsgTableSource
 - dmsMsgRequesterID
 - dmsMsgSourceMode
 - dmsShortPowerRecoveryMessage
 - dmsLongPowerRecoveryMessage
 - dmsShortPowerLossTime
 - dmsResetMessage
 - dmsCommunicationLossMessage
 - dmsTimeCommLoss
 - dmsPowerLossMessage
 - dmsEdDurationMessage
 - dmsActivateMsgError
 - dmsMultiSyntaxError
 - dmsMultiSyntaxErrorPosition
 - dmsMultiOtherErrorDescription
 - dmsActivateMessageState
- Brightness Objects
 - dmsIllumControl
 - dmsIllumMaxPhotocellLevel

Page 8 of 21 169

- dmsIllumPhotocellLevelStatus
- dmsIllumManLevel
- dmsIllumBrightnessValues
- dmsIllumBrightnessValuesError
- dmsIllumLightOutputStatus
- Scheduling Action Objects
 - numActionTableEntries
 - dmsActionTable and subsidiary objects
- Sign Status Objects, to the extent supported by the sign hardware.
 - statMultiFieldRows
 - statMultiFieldTable and subsidiary objects
 - watchdogFailureCount
 - dmsStatDoorOpen
 - shortErrorStatus
 - controllerErrorStatus
 - dmsPowerStatusMap
 - dmsPowerNumRows
 - dmsPowerStatusTable and subsidiary objects
 - fanFailures
 - pixelFailureTableNumRows
 - pixelFailureTable and subsidiary objects
 - pixelTestActivation
 - dmsPixelStatusTable and subsidiary objects
 - dmsPixelFailureTestRows
 - dmsPixelFailuresMessageRows
 - dmsLightSensorStatusMap
 - dmsLightSensorNumRows
 - dmsLightSensorStatusTable and subsidiary objects
 - dmsTepSensorStatusMap
 - dmsTemSensorNumRows
 - dmsTempSensorStatusTable and subsidiary objects
 - powerSource
 - tempMinAmbient
 - temptMaxAmbient
 - tempMinSignHousing
 - tempMaxSignHousing

Page 9 of 21 170

- tempSensorWarningMap
- tempSensorCriticalTempMap
- Graphic Definition Objects
 - dmsGraphicMaxEntries
 - dmsGraphicNumEntries
 - dmsGraphicVertSpacing
 - dmsGraphicHorzSpacing
 - dmsGraphicMaxSize
 - availableGraphicMemory
 - dmsGraphicBlockSize
 - dmsGraphicTable and subsidiary Objects
 - dmsGraphicsBitmapTable and subsidiary objects

Any mandatory objects that are required by NTCIP1203 but that are missing from the above list shall also be supported.

<u>3. Object Range Requirements</u> Every object required by these specifications shall have full standardized object range support except:

OBJECT	MINIMUM PROJECT REQUIREMENTS
Max Time Base Schedule Entries	28
Max Day Plans	14
Max Day Plan Events	12
Max Event Log Configurations	50
Event Configuration Mode	2, 3, and 4
Max Event Log Size	200
Max Event Classes	16
Max Group Address	1
Number Fonts	4
Max. Font Characters	100
Number Action Table Entries	Equal to message capacity of sign
Number of User-Define Events	0
Number of External Devices	0

Number of Brightness Levels	16 or more

- d. Blanking Displaying a blank sign shall be achieved in the same way that any message is displayed (i.e., by using an object that has a syntax of either MessageActivationCode or MessageIDCode). However, a new memory type, dmsMessageMemoryType equal to 'blank (7)', shall be created to support this operation. It shall function as follows: The dmsMessageNumber for this memory type shall be reflective of the run time priority and shall be between 1 and 255, inclusive. The CRC for this memory type shall be 0x00 00 and the normal CRC algorithm shall not be applied to blank messages. The dmsMessageMultiString shall be an octet string of length 0. The activate priority for any MessageActivationCode using this type of memory shall be used as the actual activation priority.
- e. Mark Up Language for Transportation Information (MULTI) The software shall implement the following tags (opening and closing where defined) of MULTI as defined in NTCIP 1203.
 - Fields for 12 hour time, day of month, month, four digit year, and current speed in mph.
 - Flash
 - Font
 - Justification Line
 - Justification Page
 - Moving Text
 - New Line
 - New Page
 - Page Time
 - Hexadecimal Character
- f. Other NTCIP Standards All communication shall conform to NTCIP 2202, <u>Internet (TCP/IP and UDP/IP) Transport Protocol</u>; NTCIP 1102, <u>Octet Encoding Rules (OER) Base Profile</u>; and NTCIP 1103, <u>Transportation Management Protocols</u>. Communication with the signs shall use SNMP only.

Trailer

- a. Hitch The trailer shall have a fixed height, two-inch ball hitch.
- b. <u>Dimensions</u> The trailer shall be no more than 20 feet (6 m) long with the tongue in place, and no more than eight feet (2.5 m) wide.

- c. <u>Tongue</u> The tongue shall be removable. No tools shall be required for removal or remounting of the tongue. It shall not be necessary to disconnect any hydraulic brake lines to effect complete removal, and it shall not be necessary to bleed the brake system upon reinstallation of the tongue.
 - d. Safety Chains Both the tongue and coupler shall have safety chains attached.
- <u>e. Compartments</u> The trailer shall have lockable, weatherproof compartments for the controller and batteries. The battery compartment shall be centrally positioned to promote stability of the trailer
- <u>f. Leveling Jacks</u> The trailer chassis shall have at each corner a leveling jack affixed in such a manner that the jacks may be readily placed and locked in a horizontal position for traveling without the use of any tools.
- g. Conspicuity Material The face of the trailer shall be delineated on a permanent basis by affixing retro-reflective material, known as conspicuity material, in a continuous line as seen by oncoming drivers."

Miscellaneous Requirements

- <u>a. Radar-Ready</u> The sign shall be fully capable of having an on-board Doppler radar speed detector installed, such that the speed of approaching vehicles can be displayed on the sign.
- <u>b. Grounding</u> All electrical systems, surge protectors, antenna grounds, and the trailer shall connect to a common ground that also connects to a grounding lug on the outside of the trailer. Label the lug "EARTH GROUND".

<u>Control Software</u> The software is to enable traffic management staff to control and monitor the signs. It is also to enable a maintenance technician at a sign to exercise all sign features, examine event logs, and run diagnostic tests. It is expected that the software will be the DMS manufacturer's standard product, with minimal customization. The software for use by maintenance technicians need not be identical to that used by the traffic management staff, although it must have equivalent capabilities.

The manufacturer is to install the software on six of the Department's existing computers and provide the Department with the right and means to install the same software on at least ten other computers.

It is expected that this software will be used to control additional portable and permanent dynamic message signs that the Department will buy.

<u>Computer Compatibility</u> Three of the computers will be stationary desktop computers with Intel Pentium IV (1.8 GHz) processors and the other three will be notebook computers with Intel

Pentium M (1.5 GHz) processors. All will have Windows XP operating systems (with Service Pack 2), 512 MB or more of memory, a 20 GB hard drive, and an internal V.34 modem. The software shall work with these computers.

The manufacturer shall visit four Department facilities to install this software. The main control computer, a desktop, will be in the radio room at the Department's Augusta Headquarters. Backup control computers will be in the regional offices in Portland and Bangor. The three notebook computers will be at the Fairfield facility when the signs are tested. Addresses for the Departments Augusta, Portland, and Bangor office locations are as follows:

Augusta: Maine Department of Transportation

Child Street

Augusta, Maine 04333

Portland: Maine Department of Transportation

Region 1 Office Pleasant Hill Road

Scarborough, Maine 04070

Bangor: Maine Department of Transportation

Region 4 Office Hogan Road

Bangor, Maine 04401

<u>Password Protection</u> Only users, who have proper authorization, as indicated by their passwords, shall be able to undertake the following actions:

- Place equipment on standby.
- Change sign messages, blank signs, and change message priority.
- Replace or delete messages stored in a DMS controller's memory.
- Display test patterns on a sign.
- Change or delete the sign computer's schedule.

- Modify the message library on the sign computer's hard disk.
- Change sign configuration parameters.
- Delete the event log.
- View passwords.
- Change passwords and privileges.

Each user shall have a different password. Users may be granted or denied permission to use each protected command independently. Via an encrypted lookup table, the computer shall determine which of the protected commands a user may use.

The software shall ask the user for his password at the time the protected command is entered. The computer shall not carry out these commands unless the user has the proper privileges.

Off Line Status A user shall be able to take a sign off line, causing it to be ignored by the sign computer. This will be used when a malfunctioning sign is generating an excessive number of alarms. When a user attempts to control an off line sign, a message shall appear on his screen informing him that the sign is out of service. When a user takes a sign off line, the software shall ask the user to type in a comment of up to 100 characters explaining the action. The comment field may be left blank. The computer shall also record the user's name, based on his password, and include the name and comment in the failure report described below.

Message Library The sign computer shall store a library of at least 999 messages on its hard disk. In addition to the message text, the file shall contain all the MULTI control codes needed for a sign to properly display the message

When adding a message to the library, a user shall specify the message name. If a message with the same name already exists in the library, the software shall notify the user and give him the options of replacing the existing file or selecting a new name for the message he has just created. A user shall also be able to delete library messages from within the program. The program shall ask the user to confirm each message deletion before actually deleting the file.

If the user is seeking a message to display, the software shall present a list so that the user can choose one. When the user makes his selection, the software shall display the entire message, exactly as it would appear on a sign, and shall ask the user to confirm that this is the message desired. The user shall then be able to post the message on one or more signs, edit the message, or do nothing with it.

<u>Sign Control</u> Future signs may have different line lengths and heights (measured in pixels) than the signs provided in this project, and may have more or fewer lines. The software shall display messages as a matrix of dots that replicate the way the message will actually appear on a selected sign. The presentation should be based on the assigned font and the height and width (in pixels) of the display, as stored in a data base maintained by the sign computer. This type of display will be used during message creation and editing, as well as when displaying to a user the message currently on a sign. If the user is displaying a message from the library or creating a message without specifying what sign it will go on, the display shall be based on the characteristics of the signs provided in this project.

Upon creating or revising a message, the user shall be able to save it in the message library on the sign computer's hard disk or send it directly to one or more DMS controllers for storage or display.

When a user sends a message to one or more signs, the sign computer shall automatically check to be sure that the message will fit on the sign. This checking shall take into account the selected fonts and the size of the sign's display. If the message won't fit, the computer shall alert the user and not post the message.

If a user chooses to send the same message to multiple signs, the software shall present the user with a list of all signs, so that the user can check off which signs the new message goes to. The screen shall also give the user a choice of "All Signs". The list shall identify signs by roadway and milepost. Using a single command, the user shall be able to cause the message to be stored in all the signs he specified, replacing those previously stored in the controllers. Similarly, the user shall be able to use a single command to have all the selected signs display the same message, or the same message number.

In addition to entering commands for immediate execution, a user may store commands in the sign computer for future execution. For example, the user may want to conduct a pixel test of every sign each night at 3:00 AM. A user shall be able to quickly and easily create, modify, suspend, or cancel a schedule of commands for the sign computer to issue to specified DMS controllers. The user shall be able to specify the same action at the same time for multiple signs, in the same way as was described in the preceding paragraph. A user shall also be able to schedule the printing of sign-related reports. A user shall not be able to schedule any command that he does not have the privilege to execute directly. The schedule shall show the name of the user who scheduled each command, based on his password. Actions that would be recorded in the event log if a user commanded them directly shall also be logged when they result from a scheduled command. The record shall include the user's name and an indication that the command was scheduled.

The software shall provide a single command that not only transmits a message to a sign (after confirming that it fits) but also causes the sign to immediately display that message on the sign (after confirming that the transmission was error free).

Status Monitoring The sign computer shall maintain an event log file on its hard disk with a record for each appearance or disappearance of an alarm from a sign. The file shall be in ASCII format with fixed-length fields separated by spaces, suitable for transfer to spreadsheet and data base management software. The record shall include the date, time, sign ID, and nature of the change. If the alarm indicates a change in the sign display, the log shall include the exact text of the message, the device from which it was commanded, and, if commanded via the sign computer, the name of the person posting the message, based on his password. The log file shall include this same information each time a message is downloaded to a sign's memory from the sign computer.

The log shall also record each time a user at the sign computer does the following:

- Changes the priority of a message.
- Changes the schedule.
- Changes a message in the library on the computer's hard disk.

The record shall include the user's name based on his password.

The log shall also record the beginning and end of communication failures. The sign computer shall deem a communication failure to have occurred if it does not get an error-free response to two consecutive commands to a controller. The computer shall deem a controller recovered if it responds properly to a command.

<u>Reports</u> The system shall provide the following reports to the user's screen, a disk file named by the user, or to the printer, as specified by the user:

- Equipment Failures. Lists each sign that is currently malfunctioning, along with the time and date of failure and a phrase indicating the nature of the problem. Also lists each DMS controller that is off line, along with the date and time it was taken off line, the comment written by the user who took it off line, and the user's name based on his password.
- <u>Sign System Configuration</u>. Lists the current values of all configuration parameters stored in the sign computer, clearly labeled. It includes such things as communication address. It does not include operating parameters stored in the DMS controllers.
- <u>Individual Sign Configuration</u>. Lists the current values of all changeable parameters stored in a DMS controller, clearly labeled. It includes such things as temperature thresholds. This report shall cover all signs, or a particular sign, as specified by the user. The information displayed shall be uploaded from the DMS controllers at the time the report is requested. If the sign computer is unable to upload the data from a particular sign, it shall use the corresponding data on its hard disk, but shall indicate in the report that the data is from the hard disk and may not be current.

- <u>Current Sign Status</u>. Lists sign location, text of message currently displayed, the priority value of the message, storage location of the message in the sign's memory, entity that caused the message to be displayed, and controller status (failed, working, or off line) for each sign in the system. This report shall cover all signs, or a particular sign, as specified by the user.
- Event Log. Lists all information in the control computer's event log file, with each field clearly labeled. The user shall be able to specify that only events between certain times, or pertaining to a certain sign, or pertaining to a certain type of event, or any combination of the foregoing, shall be included in the report. Events shall be listed chronologically.
- Message Library. Lists the text of each frame of each message in the message library, along with the duration for which the frame is displayed. Also lists the message's file name and latest revision date. Each frame shall be displayed in the report in the same way it would appear on a sign, with regard to text centering, bolding, and justification. Flashing text shall be underlined. Messages shall be grouped by subdirectory, and a user shall be able to specify that only certain subdirectories be included.
- <u>Sign Computer's Schedule</u>. Lists all information in the sign computer's schedule, clearly labeled. The user shall be able to specify that only events between certain times, or pertaining to a certain sign, or pertaining to a certain type of event, or any combination of the foregoing, shall be included in the report. Events shall be listed chronologically.
- <u>Sign Memory</u>. Lists sign ID and location and the text of each message stored in the sign. The message portion of the report shall indicate the message's memory location number and shall display the text of each frame of the message, along with the duration for which the frame is displayed. Each frame shall be displayed in the report in the same way it would appear on a sign, with regard to text centering, bolding, and justification. Flashing text shall be underlined. All information shall be clearly labeled. The user shall be able to specify that the report cover only a particular sign, or all signs. The information displayed shall be uploaded from the DMS controllers at the time the report is requested. If the sign computer is unable to upload the data from a particular sign, it shall use the corresponding data on its hard disk, but shall indicate in the report that the data is from the hard disk and may not be current.
- <u>Bad Pixel Maps</u>. Consist of a matrix display indicating which display elements of a sign have failed, according to the DMS controller. The user shall be able to specify that the report cover only a particular sign or all signs with display problems. If the user specifies all signs with display problems, the report will cover all signs whose controllers are currently reporting malfunctioning drivers or display elements.

The time and date for which the information is current shall appear on every page of each printed report. All pages shall be numbered.

<u>Alarms</u> The sign computer shall issue alarms by beeping and displaying a message clearly identifying the problem in a prominent box that pops up on the user's screen. The box shall disappear when the user clicks on it and the beeping shall stop. If the alarm is of the type called "recurring", the beeping and screen message recur every 15 minutes as long as the condition persists. The sign computer shall issue a single alarm for the following situations:

- A new sign failure.
- The sign computer is unable to change a sign's display as scheduled because the currently displayed message has a higher priority.

A sign computer shall issue a recurring alarm if its hard disk is over 90 percent full.

<u>User Interface</u> The user shall enter commands by selecting from menus. The user shall make selections from menus and from lists of signs, messages, and options using a mouse. The interface shall be easy to use, minimizing memorization and opportunities for errors. The interface shall automatically check commands for out-of-range values and other errors. When it checks an error, it shall beep, reject the command or data, and provide the user with a clear explanation.

The software shall have the complete text of the software operator's manual stored on disk, readily available to the user.

<u>Communication Interface</u> The software shall be capable of contacting signs by dial-up telephone and over an Ethernet network. It shall use the appropriate communication method for each sign, based on information stored in the computer's database. If a sign is connected to both telephone and Ethernet networks, the software shall use the dial-up link as a backup when the Ethernet network is not successful.

Spare Parts Provide the following spare parts:

- Display modules: 20 percent of the total provided.
- Controllers: two.
- Display power supplies: ten percent of total provided.
- Other circuit boards used in the sign, if not covered by the previous items: one of each type.
- Surge protectors: two of each type.
- Battery charging unit: one.
- Battery: one

<u>Testing</u>. The manufacturer shall test the signs, software, and spare parts. The manufacturer shall develop the test procedures and revise them as necessary to meet the Engineer's approval. Prior to the testing, the manufacturer shall deliver all signs and spare parts to the Department's

Fairfield facility, shall successfully install the software on the Department's computers, shall conduct all the tests in the test plans, and shall correct any deficiencies found.

When the manufacturer is confident that the signs, software, and parts will pass the test, he shall arrange for the Department's representative's to witness the testing. He shall contact the Engineer at least two weeks in advance of the proposed testing date and shall arrange for testing to begin at a mutually convenient time. All testing will be done on the same day (or two days, if necessary) at the Department's Fairfield facility. The installation contractor may witness this testing if he or she chooses. The manufacturer shall provide all materials and equipment needed for testing and shall prepare a written report of the test results.

<u>Sign Testing</u> The test procedure shall be designed to uncover manufacturing defects and shipping damage of all types. The test shall include a visual inspection of the sign. Among the aspects that must be tested are the following:

- All diagnostic routines provided by the manufacturer.
- Proper operation of every pixel, including uniform brightness at all brightness levels and proper current consumption.
- Proper wiring of the display modules, checked by displaying a text message that identifies the modules' proper row and column positions.
- Appropriate display brightness for day and night conditions, and brightness when the sun at its worst condition for the location.
- Proper aiming of the display modules.
- Proper entry of messages into memory.
- Proper operation of sign monitoring.
- Proper operation of sensors for alarm conditions.
- Correct wiring of sensors and alarms to the controller's inputs.
- Proper remote access and control using the central and laptop software provided in this project.

<u>Software Testing</u> The purpose of the sign computer software test is to demonstrate that the software operates reliably and is in full compliance with the specifications. The manufacturer shall conduct the tests following the approved test plan but, if practical, shall also perform any supplemental tests requested by the Department's representatives at the time of testing. To be accepted, the software must pass all the tests.

The test plan shall test every interface, feature, and function of the software, including features present but not required by these specifications. The testing shall demonstrate that the software deals appropriately with communication errors and operator errors. The testing shall confirm that the signs can be monitored and controlled from each of the Department's computers on which software was installed.

Spare Parts Testing Test the parts by substituting them into a working sign.

Training

<u>General</u> Within two weeks of successful completion of testing, the manufacturer shall train the Department's operations and maintenance staff at the Fairfield facility. All the signs will still be at that facility for use during training.

In the training, each trainee shall receive copies of the appropriate manuals. The training shall be conducted in such a way as to familiarize the trainees with the manuals (and any other handouts provided) so that the trainees are able to make efficient use of those materials after the training. All course material, in reproducible form, shall be delivered to the Engineer immediately following course completion.

The manufacturer shall provide all tools and instruments needed for the training.

<u>Installation Training</u> The class will consist of up to 15 people, some from the Department and others from the contractor who is to install the signs. It shall cover proper towing and positioning of the sign, leveling, removing the tongue, raising and lowering the message board, aiming the message board, aiming the solar panels, connections to communication and power, and all other setup activities. It shall last four hours.

<u>Maintenance Training</u> The maintenance training shall be provided for 12 hours for at least ten maintenance technicians with electronics backgrounds. These trainees will also attend the training session for sign operators, so material in that class need not be repeated in the maintenance training. The training shall include theory of operation, circuit description, field adjustments, preventive maintenance procedures, troubleshooting, operation of diagnostic and configuration software, use of the event log, and repair of components.

In addition to classroom training, it shall include "hands on" training using the signs provided in this project. That training shall include use of the control panels (if provided), control of the signs using the Department's notebook computers, display module replacement, controller replacement, battery replacement, and troubleshooting. Spare parts furnished under this contract may be used for the replacement activities. Each trainee shall use the Department's laptop software to run all the diagnostic messages, create a message, schedule the message, and adjust the sign's brightness. Each shall use the sign controller's front panel to run stored messages and determine the sign's current status.

Operator Training The training shall be provided for a minimum of four hours for at least ten engineering and operations personnel. The training shall include a complete demonstration of the operation and capabilities of the signs and software, as well as opportunities for the trainees to create and store messages, post messages, and schedule messages.

<u>Technical Support</u> Phone numbers provided for technical support must be attended by a person who can answer questions or promptly find the answer to questions. An answering machine or answering service does not constitute technical support. The telephone support required by these specifications shall be provided at least eight hours a day on all work days.

On-Site Support The manufacturer shall have a representative present when the installation contractor installs the first sign. The representative shall observe the installation, provide additional training to the contractor as required, and ensure that the sign is installed correctly. If the manufacturer's representative is not confident that the contractor can install the remaining signs without assistance, the representative shall immediately notify the Engineer.

<u>Telephone Support During Installation</u> The manufacturer shall provide telephone support to the installation contractor during installation. This support shall be available until all the signs have been installed.

<u>Telephone Support for Operation and Maintenance</u> The manufacturer shall provide telephone support to the Department's operations and maintenance staff for a period of one year following the acceptance of the signs.

Method of Measurement Portable Dynamic Message Signs will be measured by lump sum.

Basis of Payment The accepted portable dynamic message signs will be paid for at the lump sum price. Such price will be full compensation for furnishing and testing the seven (8) signs, as well as all sign-related documentation. Control software, spare parts, training and technical support as described within this Special Provision will be included in the lump sum price for the Portable Dynamic Message Signs. The contractor will deliver to the Maine DOT five message boards. The Maine DOT will retain complete ownership of the Five message boards.

Payment will be made under:

Pay item	<u>Item</u>	Pay Unit
652.41	Portable Dynamic Message Sign	Each

Town:Gardiner-Brunswick PIN:#15114.00 DATE:3-17-08

SPECIAL PROVISION SECTION 656

Temporary Soil Erosion and Water Pollution Control

The following is added to Section 656 regarding Project Specific Information and Requirements. All references to the Maine Department of Transportation Best Management Practices for Erosion and Sedimentation Control (a.k.a. Best Management Practices manual or BMP Manual) are a reference to the latest revision of said manual. The latest version is dated "February 2008" (available at http://www.maine.gov/mdot/environmental-office-homepage/surface-water-resources.php.) Procedures specified shall be according to the BMP Manual unless stated otherwise.

Any and all references to "bark mulch" or "composted bark mix" shall be a reference to "Erosion Control Mix" in accordance with *Standard Specification*, *Section 619 - Mulch*.

Project Specific Information and Requirements

The following information and requirements apply specifically to this Project. The temporary soil erosion and water pollution control measures associated with this work shall be addressed in the SEWPCP.

This project is considered **SENSITIVE** in accordance with the BMP Manual. The Contractor's SEWPCP shall comply with Section II.B., <u>Guidelines for Sensitive Waterbodies</u> in the BMP Manual.

A preconstruction field review is mandatory for this project. The preconstruction field review shall take place before commencing any work that involves soil disturbance or potential impacts on water quality. Attendees shall include the Environmental Coordinator, the preparer of the SEWPCP, the Resident, and a representative from the Department's ENV Water Resources Unit. The date and time shall be set by the Contractor in consultation with the Resident and ENV Water Resources Unit representative.

Newly disturbed earth shall be mulched by the end of each workday. Mulch shall be maintained on a daily basis.

Dust control items other than those under *Standard Specification*, *Section 637 – <u>Dust Control</u>*, if applicable, shall be included in the plan.

Permanent slope stabilization measures shall be applied within one week of the last soil disturbance.

Permanent seeding shall be done in accordance with *Standard Specification, Section 618* - <u>Seeding</u> unless the Contract states otherwise.

Town:Gardiner-Brunswick PIN:#15114.00 DATE:3-17-08

SPECIAL PROVISION SECTION 656

Temporary Soil Erosion and Water Pollution Control

Culvert inlet and outlet protection shall be installed within 48 hours of culvert installation, or prior to a storm event, whichever is sooner.

After November 1 the Contractor shall use winter stabilization methods, such as Erosion Control Mix as specified in *Standard Specification*, *Section 619 - Mulch*. If required, spring procedures for permanent stabilization shall also be described in the plan. Use of this product for overwinter temporary erosion control will be incidental to the contract and be paid for as part of Pay Item 656.75.

All disturbed ditches shall be stabilized by the end of each workday. Stabilization shall be maintained on a daily basis.

Erosion control blanket shall be installed in the bottoms of all ditches except where a stone lining is planned. Seed shall be applied prior to the placement of the blanket.

If check dams are used, they shall be constructed of stone in accordance with BMP Manual, Section 9. *Hay Bale Temporary Check Dams* **are not allowed**. Delete all reference to them in Section 9.

The Contractor's SEWPCP shall address in-stream work at the following locations:

Sta. #1129+00, Sta. #1091+22, Sta. #868+67, Sta. #909+50, Sta. #767+60

Stream flow shall be maintained at all times.

A cofferdam sedimentation basin is required if cofferdams are used. The basin shall be located in an upland area where the water can settle and seep into the ground or be released slowly to the resource in a manner that will not cause erosion. The location of such a cofferdam sedimentation basin shall be addressed in the SEWPCP

STANDARD DETAIL UPDATES

Standard Details and Standard Detail updates are available at: http://www.maine.gov/mdot/contractor-consultant-information/ss standard details updates.php

<u>Detail #</u> 504(15)	Description Diaphragms	Revision Date 12/30/02
507(04)	Steel Bridge Railing	2/05/03
526(33)	Concrete Transition Barrier	8/18/03
645(06)	H-Beam Posts – Highway Signing	7/21/04
645(09)	Installation of Type II Signs	7/21/04
626(09)	Electrical Junction Box for Traffic Signals and Lighting	2/25/05
604(01)	Catch Basins	11/16/05
604(05)	Type "A" & "B" Catch Basin Tops	11/16/05
604(06)	Type "C" Catch Basin Tops	11/16/05
604(07)	Manhole Top "D"	11/16/05
604(09)	Catch Basin Type "E"	11/16/05
606(02)	Multiple Mailbox Support	11/16/05
606(07)	Reflectorized Beam Guardrail Delineator Details	11/16/05
609(06)	Vertical Bridge Curb	11/16/05
504(23)	Hand-Hold Details	12/08/05
609(03)	Curb Type 3	6/27/06
609(07)	Curb Type 1	6/27/06
535(01)	Precast Superstructure - Shear Key	10/12/06
535(02)	Precast Superstructure - Curb Key & Drip Notch	10/12/06
535(03)	Precast Superstructure - Shear Key	10/12/06

Page 1 of 2

535(04)	Precast Superstructure - Shear Key	10/12/06
535(05)	Precast Superstructure - Post Tensioning	10/12/06
535(06)	Precast Superstructure - Sections	10/12/06
535(07)	Precast Superstructure - Precast Slab & Box	10/12/06
535(08)	Precast Superstructure - Sections	10/12/06
535(09)	Precast Superstructure - Sections	10/12/06
535(10)	Precast Superstructure - Sections	10/12/06
535(11)	Precast Superstructure - Sections	10/12/06
535(12)	Precast Superstructure - Sections	10/12/06
535(13)	Precast Superstructure - Sections	10/12/06
535(14)	Precast Superstructure - Stirrups	10/12/06
535(15)	Precast Superstructure - Plan	10/12/06
535(16)	Precast Superstructure - Reinforcing	10/12/06
535(17)	Precast Superstructure - Notes	10/12/06
801(01)	Drives on Sidewalk Sections	2/06/07
801(02)	Drives on Non-Sidewalk Sections	2/06/07
535(03)	Precast Superstructure - Shear Key	12/5/07
535(04)	Precast Superstructure - Shear Key	12/5/07
535(05)	Precast Superstructure - Post Tensioning	12/5/07
535(17)	Precast Superstructure - Notes	12/5/07
801(01)	Drives on Sidewalk Sections	1/04/08
801(02)	Drives on Non-Sidewalk Sections	1/04/08
203(03)	Backslope Rounding	1/29/08

Page 2 of 2 186

SUPPLEMENTAL SPECIFICATION

(Corrections, Additions, & Revisions to Standard Specifications - Revision of December 2002)

SECTION 101 CONTRACT INTERPRETATION

101.2 Definitions

<u>Closeout Documentation</u> Replace the sentence "A letter stating the amount..... DBE goals." with "DBE Goal Attainment Verification Form"

Add "<u>Environmental Information</u> Hazardous waste assessments, dredge material test results, boring logs, geophysical studies, and other records and reports of the environmental conditions. For a related provision, see Section 104.3.14 - Interpretation and Interpolation."

Add "<u>Fabrication Engineer</u> The Department's representative responsible for Quality Assurance of pre-fabricated products that are produced off-site."

<u>Geotechnical Information</u> Replace with the following: "Boring logs, soil reports, geotechnical design reports, ground penetrating radar evaluations, seismic refraction studies, and other records of subsurface conditions. For a related provision, see Section 104.3.14 - Interpretation and Interpolation."

<u>SECTION 102</u> DELIVERY OF BIDS

- 102.7.1 Location and Time Add the following sentence "As a minimum, the Bidder will submit a Bid Package consisting of the Notice to Contractors, the completed Acknowledgement of Bid Amendments form, the completed Schedule of Items, 2 copies of the completed Agreement, Offer, & Award form, a Bid Bond or Bid Guarantee, and any other Certifications or Bid Requirements listed in the Bid Book."
- <u>102.11.1 Non-curable Bid Defects</u> Replace E. with "E. The unit price and bid amount is not provided or a lump sum price is not provided or is illegible as determined by the Department."

SECTION 103 AWARD AND CONTRACTING

103.3.1 Notice and Information Gathering Change the first paragraph to read as follows: "After Bid Opening and as a condition for Award of a Contract, the Department may require an Apparent Successful Bidder to demonstrate to the Department's satisfaction that the Bidder is responsible and qualified to perform the Work."

<u>SECTION 104</u> GENERAL RIGHTS AND RESPONSIBILITIES

<u>104.3.14 Interpretation and Interpolation</u> In the first sentence, change "...and Geotechnical Information." to "...Environmental Information, and Geotechnical Information." Delete the entire Section 104.5.9 and replace with the following:

"104.5.9 Landscape Subcontractors The Contractor shall retain only Landscape Subcontractors that are certified by the Department's Environmental Office Landscape Unit."

SECTION 105 GENERAL SCOPE OF WORK

Delete the entire Section 105.6 and replace with the following:

105.6.1 Department Provided Services The Department will provide the Contractor with the description and coordinates of vertical and horizontal control points, set by the Department, within the Project Limits, for full construction Projects and other Projects where survey control is necessary. For Projects of 1,500 feet in length, or less: The Department will provide three points. For Projects between 1,500 and 5,000 feet in length: The Department will provide one set of two points at each end of the Project. For Projects in excess of 5,000 feet in length, the Department will provide one set of two points at each end of the Project, plus one additional set of two points for each mile of Project length. For non-full construction Projects and other Projects where survey control is not necessary, the Department will not set any control points and, therefore, will not provide description and coordinates of any control points. Upon request of the Contractor, the Department will provide the Department's survey data management software and Survey Manual to the Contractor, or its survey Subcontractor, for the exclusive use on the Department's Projects.

105.6.2 Contractor Provided Services Utilizing the survey information and points provided by the Department, described in Subsection 105.6.1, Department Provided Services, the Contractor shall provide all additional survey layout necessary to complete the Work. This may include, but not be limited to, reestablishing all points provided by the Department, establishing additional control points, running axis lines, providing layout and maintenance of all other lines, grades, or points, and survey quality control to ensure conformance with the Contract. The Contractor is also responsible for providing construction centerline, or close reference points, for all Utility Facilities relocations and adjustments as necessary to complete the Work. When the Work is to connect with existing Structures, the Contractor shall verify all dimensions before proceeding with the Work. The Contractor shall employ or retain competent engineering and/or surveying personnel to fulfill these responsibilities.

The Contractor must notify the Department of any errors or inconsistencies regarding the data and layout provided by the Department as provided by Section 104.3.3 - Duty to Notify Department If Ambiguities Discovered.

105.6.2.1 Survey Quality Control The Contractor is responsible for all construction survey quality control. Construction survey quality control is generally defined as, first, performing initial field survey layout of the Work and, second, performing an independent check of the initial layout using independent survey data to assure the accuracy of the initial layout; additional iterations of checks may be required if significant discrepancies are discovered in this process. Construction survey layout quality control also requires written documentation of the layout process such that the process can be followed and repeated, if necessary, by an independent survey crew.

105.6.3 Survey Quality Assurance It is the Department's prerogative to perform construction survey quality assurance may, or may not, be performed by the Department. Construction survey quality assurance is generally defined as an independent check of the construction survey quality control. The construction survey quality assurance process may involve physically checking the Contractor's construction survey layout using independent survey data, or may simply involve reviewing the construction survey quality control written documentation. If the Department elects to physically check the Contractor's survey layout, the Contractor's designated surveyor may be required to be present. The Department will provide a minimum notice of 48 hours to the Contractor, whenever possible, if the Contractor's designated surveyor's presence is required. Any errors discovered through the quality assurance process shall be corrected by the Contractor, at no additional cost to the Department.

105.6.4 Boundary Markers The Contractor shall preserve and protect from damage all monuments or other points that mark the boundaries of the Right-of-Way or abutting parcels that are outside the area that must be disturbed to perform the Work. The Contractor indemnifies and holds harmless the Department from all claims to reestablish the former location of all such monuments or points including claims arising from 14 MRSA § 7554-A. For a related provision, see Section 104.3.11 - Responsibility for Property of Others.

SECTION 106 QUALITY

<u>106.4.3 Testing</u> Change the first sentence in paragraph three from "...maintain records of all inspections and tests." to "...maintain original documentation of all inspections, tests, and calculations used to generate reports."

<u>106.6 Acceptance</u> Add the following to paragraph 1 of A: "This includes Sections 401 - Hot Mix Asphalt, 402 - Pavement Smoothness, and 502 - Structural Concrete - Method A - Air Content."

Add the following to the beginning of paragraph 3 of A: "For pay factors based on Quality Level Analysis, and"

106.7.1 Standard Deviation Method Add the following to F: "Note: In cases where the mean of the values is equal to either the USL or the LSL, then the PWL will be 50 regardless of the computed value of s."

Add the following to H: "Method C Hot Mix Asphalt: PF = [55 + (Quality Level *0.5)] * 0.01"

SECTION 107 TIME

107.3.1 General Add the following: "If a Holiday occurs on a Sunday, the following Monday shall be considered a Holiday. Sunday or Holiday work must be approved by the Department, except that the Contractor may work on Martin Luther King Day, President's Day, Patriot's Day, the Friday after Thanksgiving, and Columbus Day without the Department's approval."

<u>107.7.2 Schedule of Liquidated Damages</u> Replace the table of Liquidated Damages as follows:

From	Up to and	Amount of Liquidated
More Than	Including	Damages per Calendar Day
\$0	\$100,000	\$100
\$100,000	\$300,000	\$200
\$300,000	\$500,000	\$400
\$500,000	\$1,000,000	\$575
\$1,000,000	\$2,000,000	\$750
\$2,000,000	\$4,000,000	\$900
\$4,000,000	and more	\$1,875

SECTION 108 PAYMENT

<u>108.4 Payment for Materials Obtained and Stored</u> First paragraph, second sentence, delete the words "...Delivered on or near the Work site at acceptable storage places."

SECTION 109 CHANGES

- <u>109.1.1 Changes Permitted</u> Add the following to the end of the paragraph: "There will be no adjustment to Contract Time due to an increase or decrease in quantities, compared to those estimated, except as addressed through Contract Modification(s)."
- 109.1.2 Substantial Changes to Major Items Add the following to the end of the paragraph: "Contract Time adjustments may be made for substantial changes to Major Items when the change affects the Critical Path, as determined by the Department"
- 109.4.4 Investigation / Adjustment Third sentence, delete the words "subsections (A) (E)"

109.5.1 Definitions - Types of Delays

- <u>B. Compensable Delay</u> Replace (1) with the following; "a weather related Uncontrollable Event of such an unusually severe nature that a Federal Emergency Disaster is declared. The Contractor will only be entitled to an Equitable Adjustment if the Project falls within the geographic boundaries prescribed under the disaster declaration."
- 109.7.2 Basis of Payment Replace with the following: "Equitable Adjustments will be established by mutual Agreement for compensable items listed in Section 109.7.3-Compensable Items, based upon Unit or Lump Sum Prices. If Agreement cannot be reached, the Contractor shall accept payment on a Force Account basis as provided in Section 109.7.5 Force Account Work, as full and complete compensation for all Work relating to the Equitable Adjustment."
- <u>109.7.3 Compensable Items</u> Replace with the following: "The Contractor is entitled to compensation for the following items, with respect to agreed upon Unit or Lump Sum Prices:

- 1. Labor expenses for non-salaried Workers and salaried foremen.
- 2. Costs for Materials.
- 3. A 15 % markup on the totals of Items 1 and 2 of this subsection 109.7.3 for home office overhead and profit of the Contractor, its Subcontractors and suppliers, and any lower tier Subcontractors or suppliers, with no mark-ups on mark-ups.
- 4. Cost for Equipment, based on Blue Book Rates or leased rates, as set forth in Section 109.7.5(C), or the Contractor's Actual Costs if determined by the Department to be lower
- 5. Time.
- 6. Subcontractor quoted Work, as set forth below in Section 109.7.5 (F)."

109.7.5 Force Account Work

C. Equipment

Paragraph 2, delete sentence 1 which starts; "Equipment leased...."

Paragraph 6, change sentence 2 from "The Contractor may furnish..." to read "If requested by the Department, the Contractor will produce cost data to assist the Department in the establishment of such rental rate, including all records that are relevant to the Actual Costs including rental Receipts, acquisition costs, financing documents, lease Agreements, and maintenance and operational cost records." Add the following paragraph; "Equipment leased by the Contractor for Force Account Work and actually used on the Project will be paid for at the actual invoice amount plus 10% markup for administrative costs."

Add the following section;

"<u>F. Subcontractor Quoted Work</u> When accomplishing Force Account Work that utilizes Subcontractors, the Contractor will be allowed a maximum markup of 5% for profit and overhead on the Subcontractor's portion of the Force Account Work."

SECTION 110 INDEMNIFICATION, BONDING, AND INSURANCE

Delete the entire Section 110.2.3 and replace with the following:

<u>110.2.3 Bonding for Landscape Establishment Period</u> The Contractor shall provide a signed, valid, and enforceable Performance, Warranty, or Maintenance Bond complying with the Contract, to the Department at Final Acceptance.

The bond shall be in the full amount for all Pay Items for work pursuant to Sec 621, Landscape, payable to the "Treasurer - State of Maine," and on the Department's forms, on exact copies thereof, or on forms that do not contain any significant variations from the Department's forms as solely determined by the Department.

The Contractor shall pay all premiums and take all other actions necessary to keep said bond in effect for the duration of the Landscape Establishment Period described in Special Provision 621.0036 - Establishment Period. If the Surety becomes financially insolvent, ceases to be licensed or approved to do business in the State of Maine, or stops operating in the United States, the Contractor shall file new bonds complying with this Section within 10 Days of the date the Contractor is notified or becomes aware of such change.

All Bonds shall be procured from a company organized and operating in the United States, licensed or approved to do business in the State of Maine by the State of Maine Department of Business Regulation, Bureau of Insurance, and listed on the latest Federal Department of the Treasury listing for "Companies Holding Certificates of Authority as Acceptable Sureties on Federal Bonds and as Acceptable Reinsuring Companies."

By issuing a bond, the Surety agrees to be bound by all terms of the Contract, including those related to payment, time for performance, quality, warranties, and the Department's self-help remedy provided in Section 112.1 - Default to the same extent as if all terms of the Contract are contained in the bond(s).

Regarding claims related to any obligations covered by the bond, the Surety shall provide, within 60 Days of Receipt of written notice thereof, full payment of the entire claim or written notice of all bases upon which it is denying or contesting payment. Failure of the Surety to provide such notice within the 60-day period constitutes the Surety's waiver of any right to deny or contest payment and the Surety's acknowledgment that the claim is valid and undisputed.

SECTION 202 REMOVING STRUCTURES AND OBSTRUCTIONS

<u>202.02</u> Removing Buildings Make the following change to the last sentence in the final paragraph, change "...Code of Maine Regulations 401." to "...Department of Environmental Protection Maine Solid Waste Management Rules, 06-096 CMR Ch. 401, Landfill Siting, Design and Operation."

SECTION 203 EXCAVATION AND EMBANKMENT

<u>203.01 Description</u> Under b. Rock Excavation; add the following sentence: "The use of perchlorate is not allowed in blasting operations."

<u>SECTION 502</u> STRUCTURAL CONCRETE

- 502.05 Composition and Proportioning; TABLE #1; NOTE #2; third sentence; Change "...alcohol based saline sealer..." to "alcohol based silane sealer...". Add NOTE #6 to Class S Concrete.
- <u>502.0502</u> Quality Assurance Method A Rejection by Resident Change the first sentence to read: "For an individual sublot with <u>test results failing to meet the criteria in Table #1, or if the calculated pay factor for Air Content is less than 0.80......"</u>
- <u>502.0503</u> Quality Assurance Method B Rejection by Resident Change the first sentence to read: "For material represented by a verification test with <u>test results failing to meet the criteria</u> in Table #1, the Department will....."
- <u>502.0505</u> Resolution of Disputed Acceptance Test Results Combine the second and third sentence to read: "Circumstances may arise, however, where the Department may" 502.10 Forms and False work
- <u>D. Removal of Forms and False work</u> 1., First paragraph; first, second, and third sentence; replace "forms" with "forms and false work"

502.11 Placing Concrete

- G. Concrete Wearing Surface and Structural Slabs on Precast Superstructures Last paragraph; third sentence; replace "The temperature of the concrete shall not exceed 24° C [75° F} at the time of placement." with "The temperature of the concrete shall not exceed 24° C [75° F} at the time the concrete is placed in its final position."
- <u>502.15 Curing Concrete</u> First paragraph; replace the first sentence with the following; "All concrete surfaces shall be kept wet with clean, fresh water for a curing period of at least 7 days after concrete placing, with the exception of vertical surfaces as provided for in Section 502.10 (D) Removal of Forms and False work."

Second paragraph; delete the first two sentences.

Third paragraph; delete the entire paragraph which starts "When the ambient temperature...."

Fourth paragraph; delete "approved" to now read "...continuously wet for the entire curing period..."

Fifth paragraph; second sentence; change "...as soon as it is possible to do so without damaging the concrete surface." to "...as soon as possible."

Seventh paragraph; first sentence; change "...until the end of the curing period." to "...until the end of the curing period, except as provided for in Section 502.10(D) - Removal of Forms and False work."

<u>502.19 Basis of Payment</u> First paragraph, second sentence; add "pier nose armor" to the list of items included in the contract price for concrete.

SECTION 503 REINFORCING STEEL

<u>503.06 Placing and Fastening</u> Change the second paragraph, first sentence from: "All tack welding shall be done in accordance with Section 504, Structural Steel." to "All tack welding shall be done in accordance with AWS D1.4 Structural Welding Code - Reinforcing Steel."

SECTION 504 STRUCTURAL STEEL

<u>504.09 Facilities for Inspection</u> Add the follow as the last paragraph: "Failure to comply with the above requirements will be consider to be a denial to allow access to work by the Contractor. The Department will reject any work done when access for inspection is denied."

504.18 Plates for Fabricated Members Change the second paragraph, first sentence from: "...ASTM A 898/A 898 M..." to "...ASTM A 898/A 898 M or ASTM A 435/A 435 M as applicable and..."

<u>504.31 Shop Assembly</u> Add the following as the last sentence: "The minimum assembly length shall include bearing centerlines of at least two substructure units."

504.64 Non Destructive Testing-Ancillary Bridge Products and Support Structures Change the third paragraph, first sentence from "One hundred percent..." to "Twenty five percent..."

SECTION 535 PRECAST, PRESTRESSED CONCRETE SUPERSTRUCTURE

<u>535.02 Materials</u> Change "Steel Strand for Concrete Reinforcement" to "Steel Strand." Add the following to the beginning of the third paragraph; "Concrete shall be Class P conforming to the requirements in this section. 28 day compressive strength shall be as stated on the plans. Coarse aggregate...."

<u>535.05 Inspection Facilities</u> Add the follow as the last paragraph: "If the above requirements are not met, the Contractor shall be considered to be in violation of Standard Specification 104.2.5 – Right to Inspect Work. All work occurring during a violation of this specification will be rejected."

535.26 Lateral Post-Tensioning Replace the first paragraph; "A final tension..." with "Overstressing strands for setting losses cannot be accomplished for chuck to chuck lengths of 7.6 m [25 ft] and less. In such instances, refer to the Plans for all materials and methods. Otherwise, post-tensioning shall be in accordance with PCI standards and shall provide the anchorage force noted in the Plans. The applied jacking force shall be no less than 100% of the design jacking force."

SECTION 603 PIPE CULVERTS AND STORM DRAINS

603.0311 Corrugated Polyethylene Pipe for Option III Replace the Minimum Mandrel Diameter Table with the following:

	- · · · · · · · · · · · · · · · · · · ·	1	
Nominal Size	Minimum Mandrel	Nominal Size	Minimum Mandrel
US Customary (in)	Diameter (in)	Metric (mm)	Diameter (mm)
12	11.23	300	280.73
15	14.04	375	350.91
18	16.84	450	421.09
24	22.46	600	561.45
30	28.07	750	701.81
36	33.69	900	842.18
42	39.30	1050	982.54
48	44.92	1200	1122.90

<u>SECTION 604</u> MANHOLES, INLETS, AND CATCH BASINS

604.02 Materials Add the following:

"Tops and Traps 712.07 Corrugated Metal Units 712.08 Catch Basin and Manhole Steps 712.09"

SECTION 605 UNDERDRAINS

<u>605.05 Underdrain Outlets</u> Make the following change:

In the first paragraph, second sentence, delete the words "metal pipe".

SECTION 606 GUARDRAIL

606.02 Materials Delete the entire paragraph which reads "The sole patented supplier of multiple mailbox...." and replace with "Acceptable multiple mailbox assemblies shall be listed on the Department's Approved Products List and shall be NCHRP 350 tested and approved." Delete the entire paragraph which reads "Retroreflective beam guardrail delineators...." and replace with "Reflectorized sheeting for Guardrail Delineators shall meet the requirements of Section 719.01 - Reflective Sheeting. Delineators shall be fabricated from high-impact, ultraviolet and weather resistant thermoplastic.

606.09 Basis of Payment First paragraph; delete the second and third sentence in their entirety and replace with "Butterfly-type guardrail reflectorized delineators shall be mounted on all Wbeam guardrail at an interval of every 10 posts [62.5 ft] on tangents sections and every 5 posts [31.25 ft] on curved sections as directed by the Resident. On divided highways, the delineators shall be yellow on the left hand side and silver/white on the right hand side. On two-way

Page 9 of 21 195

roadways, the delineators shall be silver/white on the right hand side. All delineators shall have retroreflective sheeting applied to only the traffic facing side. Reflectorized guardrail delineators will not be paid for directly, but will be considered incidental to the guardrail items."

SECTION 609 CURB

609.04 Bituminous Curb f., Delete the requirement "Color

Natural (White)"

SECTION 615 LOAM

615.02 Materials Make the following change:

Organic Content

Percent by Volume

Humus

"5% - 10%", as determined by Ignition Test

SECTION 618 SEEDING

618.01 Description Change the first sentence to read as follows: "This work shall consist of furnishing and applying seed" Also remove ",and cellulose fiber mulch" from 618.01(a). 618.03 Rates of Application In 618.03(a), remove the last sentence and replace with the following: "These rates shall apply to Seeding Method 2, 3, and Crown Vetch."

In 618.03(c) "1.8 kg [4 lb]/unit." to "1.95 kg [4 lb]/unit."

618.09 Construction Method In 618.09(a) 1, sentence two, replace "100 mm [4 in]" with "25 mm [1 in] (Method 1 areas) and 50 mm [2 in] (Method 2 areas)"

618.15 Temporary Seeding Change the Pay Unit from Unit to Kg [lb].

SECTION 620 GEOTEXTILES

620.03 Placement Section (c)

Title: Replace "Non-woven" in title with "Erosion Control".

First Paragraph: Replace first word "Non-woven" with "Woven monofilament".

Second Paragraph: Replace second word "Non-woven" with "Erosion Control".

620.07 Shipment, Storage, Protection and Repair of Fabric Section (a)

Replace the second sentence with the following: "Damaged geotextiles, <u>as identified by</u> the Resident, shall be repaired immediately."

620.09 Basis of Payment

Pay Item 620.58: Replace "Non-woven" with "Erosion Control" Pay Item 620.59: Replace "Non-woven" with "Erosion Control"

SECTION 621 LANDSCAPING

<u>621.0036 Establishment Period</u> In paragraph 4 and 5, change "time of Final Acceptance" to "end of the period of establishment". In Paragraph 7, change "Final Acceptance date" to "end of the period of establishment" and change "date of Final Acceptance" to "end of the period of establishment".

SECTION 626 HIGHWAY SIGNING

626.034 Concrete Foundations Add to the following to the end of the second paragraph: "Precast and cast-in-place foundations shall be warranteed against leaning and corrosion for two years after the project is completed. If the lean is greater than 2 degrees from normal or the foundation is spalling within the first two years, the Contractor shall replace the foundation at no extra cost."

SECTION 627 PAVEMENT MARKINGS

627.10 Basis of Payment Add to the following to the end of the third paragraph: "If allowed by Special Provision, the Contractor may utilize Temporary Bi-Directional Yellow and White(As required) Delineators as temporary pavement marking lines and paid for at the contract lump sum price. Such payment will include as many applications as required and removal."

SECTION 637 DUST CONTROL

637.06 Basis of Payment Add the following after the second sentence of the third paragraph: "Failure by the Contractor to follow Standard Specification or Special Provision - Section 637 and/or the Contractor's own Soil Erosion and Pollution Control Plan concerning Dust Control and/or the Contractor's own Traffic Control Plan concerning Dust Control and/or visible evidence of excessive dust problems, as determined by the Resident, will result in a reduction in payment, computed by reducing the Lump Sum Total by 5% per occurrence per day. The Department's Resident or any other representative of the Department reserves the right to suspend the work at any time and request a meeting to discuss violations and remedies. The Department shall not be held responsible for any delay in the work due to any suspension under this item. Additional penalties may also be assessed in accordance with Special Provision 652 - Work Zone Traffic Control and Standard Specification 656 - Temporary Soil Erosion and Water Pollution Control."

SECTION 639 ENGINEERING FACILITIES

<u>639.04 Field Offices</u> Change the forth to last paragraph from: "The Contractor shall provide a fully functional desktop copier..." to "....desktop copier/scanner..."

<u>Description</u> Change "Floor Area" to "Floor Area (Outside Dimension)". Change Type B floor area from "15 (160)" to "14.4 (155)".

SECTION 652 MAINTENANCE OF TRAFFIC

652.2.3 Flashing Arrow Board Delete the existing 5 paragraphs and replace with the following: Flashing Arrow Panels (FAP) must be of a type that has been submitted to AASHTO's National Transportation Product Evaluation Program (NTPEP) for evaluation and placed on the Maine Department of Transportations' Approved Products List of Portable Changeable Message Signs & Flashing Arrow Panels.

FAP units shall meet requirements of the current Manual on Uniform Traffic Control Devices (MUTCD) for Type "C" panels as described in Section 6F.56 - Temporary Traffic Control Devices. An FAP shall have matrix of a minimum of 15 low-glare, sealed beam, Par 46 elements capable of either flashing or sequential displays as well as the various operating modes as described in the MUTCD, Chapter 6-F. If an FAP consisting of a bulb matrix is used, each element should be recess-mounted or equipped with an upper hood of not less than 180 degrees. The color presented by the elements shall be yellow.

FAP elements shall be capable of at least a 50 percent dimming from full brilliance. Full brilliance should be used for daytime operation and the dimmed mode shall be used for nighttime operation. FAP shall be at least 2.4 M x 1.2 M [96" x 48"] and finished in non-reflective black. The FAP shall be interpretable for a distance not less than 1.6 km [1 mile].

Operating modes shall include, flashing arrow, sequential arrow, sequential chevron, flashing double arrow, and flashing caution. In the three arrow signals, the second light from the arrow point shall not operate.

The minimum element on-time shall be 50 percent for the flashing mode, with equal intervals of 25 percent for each sequential phase. The flashing rate shall be not less than 25 nor more than 40 flashes per minute. All on-board circuitry shall be solid state.

Primary power source shall be 12 volt solar with a battery back-up to provide continuous operation when failure of the primary power source occurs, up to 30 days with fully charged batteries. Batteries must be capable of being charged from an onboard 110 volt AC power source and the unit shall be equipped with a cable for this purpose.

Controller and battery compartments shall be enclosed in lockable, weather-tight boxes. The FAP shall be mounted on a pneumatic-tired trailer or other suitable support for hauling to various locations, as directed. The minimum mounting height of an arrow panel should be 2.1 M [7 feet] from the roadway to the bottom of the panel.

The face of the trailer shall be delineated on a permanent basis by affixing retro-reflective material, known as conspicuity material, in a continuous line as seen by oncoming drivers.

A portable changeable message sign may be used to simulate an arrow panel display."

<u>652.2.4 Other Devices</u> Delete the last paragraph and add the following:

"652.2.5 Portable Changeable Message Sign Trailer mounted Portable Changeable Message Signs (PCMS) must be of a type that has been submitted to AASHTO's National

Transportation Product Evaluation Program (NTPEP) for evaluation and placed on the Maine Department of Transportations' Approved Products List of Portable Changeable Message Signs & Flashing Arrow Panels. The PCMS unit shall meet or exceed the current specifications of the Manual on Uniform Traffic Control Devices (MUTCD), 6F.55.

The front face of the sign should be covered with a low-glare protective material. The color of the LED elements shall be amber on a black background. The PCMS should be visible from a distance of 0.8 km [0.5 mile] day and night and have a minimum 15° viewing angle. Characters must be legible from a distance of at least 200 M [650 feet].

The message panel should have adjustable display rates (minimum of 3 seconds per phase), so that the entire message can be read at least twice at the posted speed, the off-peak 85th-percentile speed prior to work starting, or the anticipated operating speed. Each message shall consist of either one or two phases. A phase shall consist of up to eight characters per line. The unit must be capable of displaying at least three lines of text with eight characters per line. Each character shall be 457 mm [18"] high. Each character module shall use at least a five wide and seven high pixel matrix. The text of the messages shall not scroll or travel horizontally or vertically across the face of the sign.

Units shall automatically adjust their brightness under varying light conditions to maintain legibility.

The control system shall include a display screen upon which messages can be reviewed before being displayed on the message sign. The control system shall be capable of maintaining memory when power is unavailable. Message must be changeable with either a notebook computer or an on-board keypad. The controller shall have the capability to store a minimum of 200 user-defined and 200 pre-programmed messages. Controller and battery compartments shall be enclosed in lockable, weather-tight boxes.

PCMS units shall have the capability of being made programmable by means of wireless communications. PCMS units shall also be fully capable of having an on-board radar system installed if required for a particular application.

PCMS' primary power source shall be solar with a battery back-up to provide continuous operation when failure of the primary power source occurs. Batteries must be capable of being charged from a 110 volt AC power source. The unit must also be capable of being operated solely from a 110 volt AC power source and be equipped with a cable for this purpose.

The PCMS shall be mounted on a trailer in such a way that the bottom of the message sign panel shall be a minimum of 2.1 M [7 ft] above the roadway in urban areas and 1.5 M [5 ft] above the roadway in rural areas when it is in the operating mode. PCMS trailers should be of a heavy duty type with a 51 mm [2"] ball hitch and a minimum of four leveling jacks (at each corner). The sign shall be capable of being rotated 360° relative to the trailer. The face of the trailer shall be delineated on a permanent basis by affixing retro-reflective material, known as conspicuity material, in a continuous line as seen by oncoming drivers."

652.3.3 Submittal of Traffic Control Plan In item e. change "A list of all certified flaggers..." to "A list of all the Contractor's certified flaggers..."

In the last paragraph add the following as the second sentence: "The Department will review and provide comments to the Contractor within 14 days of receipt of the TCP."

<u>652.3.5 Installation of Traffic Control Devices</u> In the first paragraph, first sentence; change "Signs shall be erected..." to "Portable signs shall be erected..." In the third sentence; change "Signs must be erected so that the sign face..." to "Post-mounted signs must also be erected so that the sign face..."

652.4 Flaggers Replace the first paragraph with the following; "The Contractor shall furnish flaggers as required by the TCP or as otherwise specified by the Resident. All flaggers must have successfully completed a flagger test approved by the Department and administered by a Department-approved Flagger-Certifier who is employing that flagger. All flaggers must carry an official certification card with them while flagging that has been issued by their employer. Flaggers shall wear safety apparel meeting ANSI 107-1999 Class 2 risk exposure and clearly identify the wearer as a person, shall be visible at a minimum distance of 300 m [1000 ft], and shall wear a hardhat with retroreflectivity. For nighttime conditions, Class 3 apparel should be considered, retroreflective or flashing SLOW/STOP paddles shall be used, and except in emergency situations the flagger station shall be illuminated to assure visibility."

Second paragraph, first sentence; change "...have sufficient distance to stop before entering the workspace." to "...have sufficient distance to stop at the intended stopping point." Third sentence; change "At a spot obstruction..." to "At a spot obstruction with adequate sight distance,..."

Fourth paragraph, delete and replace with "Flaggers shall be provided as a minimum, a 10 minute break, every 2 hours and a 30 minute or longer lunch period away from the work station. Flaggers may only receive 1 unpaid break per day; all other breaks must be paid. Sufficient certified flaggers shall be available onsite to provide for continuous flagging operations during break periods. Breaker flaggers will not be paid for separately, but shall be considered incidental to the appropriate pay item."

652.8.2 Other Items Replace the last paragraph with the following: "There will be no payment made under any 652 pay items after the expiration of the adjusted total contract time."

SECTION 653 POLYSTYRENE PLASTIC INSULATION

653.05 Placing Backfill In the second sentence; change "...shall be not less than 150 mm [6 in] loose measure." to "...shall be not less than 250 mm [10 in] loose measure." In the third sentence; change "...crawler type bulldozer of not more than 390 kg/m² [80 lb/ft²] ground contact pressure..." to "...crawler type bulldozer of not more than 4875 kg/m² [2000 lb/ft²] ground contact pressure..."

653.06 Compaction In the last sentence; change "...not more than 390 kg/m² [80 lb/ft²] ground contact..." to "...not more than 4875 kg/m² [2000 lb/ft²] ground contact..."

SECTION 656 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL

656.5.1 If Pay Item 656.75 Provided Replace the second paragraph with the following: "Failure by the Contractor to follow Standard Specification or Special Provision - Section 656 and/or the Contractor's own Soil Erosion and Pollution Control Plan will result in a reduction in payment, computed by reducing the Lump Sum Total by 5% per occurrence per day. The Department's Resident or any other representative of the Department reserves the right to suspend the work at any time and request a meeting to discuss violations and remedies. The Department shall not be held responsible for any delay in the work due to any suspension under this item."

SECTION 701 STRUCTURAL CONCRETE RELATED MATERIALS

701.10 Fly Ash - Chemical Requirements Change all references from "ASTM C311" to "ASTM C114".

SECTION 703 AGGREGATES

703.05 Aggregate for Sand Leveling Change the percent passing the 9.5 mm [3/8 in] sieve from "85 – 10" to "85 – 100"

703.06 Aggregate for Base and Subbase Delete the first paragraph: "The material shall have..." and replace with "The material shall have a minimum degradation value of 15 as determined by Washington State DOT Test Method T113, Method of Test for Determination of Degradation Value (March 2002 version), except that the reported degradation value will be the result of testing a single specimen from that portion of a sample that passes the 12.5 mm [½ in] sieve and is retained on the 2.00 mm [No. 10] sieve, minus any reclaimed asphalt pavement used."

703.07 Aggregates for HMA Pavements Delete the forth paragraph: "The composite blend shall have..." and replace with "The composite blend, minus any reclaimed asphalt pavement used, shall have a Micro-Deval value of 18.0 or less as determined by AASHTO T 327. In the event the material exceeds the Micro Deval limit, a Washington Degradation test shall be performed. The material shall be acceptable if it has a value of 30 or more as determined by Washington State DOT Test Method T 113, Method of Test for Determination of Degradation Value (March 2002 version) except that the reported degradation value will be the result of testing a single composite specimen from that portion of the sample that passes the 12.5mm [1/2 inch] sieve and is retained on the 2.00mm [No 10] sieve, minus any reclaimed asphalt pavement used."

<u>703.09 HMA Mixture Composition</u> The coarse and fine aggregate shall meet the requirements of Section 703.07. The several aggregate fractions for mixtures shall be sized, graded, and combined in such proportions that the resulting composite blends will meet the grading requirements of the following table.

AGGREGATE GRADATION CONTROL POINTS						
	Nominal Maximum Aggregate SizeControl Points (Percent Passing)					
SIEVE	TYPE 25	TYPE 19	TYPE 12.5	TYPE 9.5	TYPE 4.75	
SIZE	mm	mm	mm	mm	mm	
	PERCENT BY WEIGHT PASSING - COMBINED AGGREGATE					
37.5 mm	100					
25 mm	90-100	100				
19 mm	-90	90-100	100			
12.5 mm		-90	90-100	100	100	
9.5 mm		-	-90	90-100	95-100	
4.75 mm		-	-	-90	80-100	
2.36 mm	19-45	23-49	28-58	32-67	40 - 80	
1.18 mm		-	-	-	-	
600 m		-	-	-	-	
300 m		-	-	-	-	
75 m	1-7	2-8	2-10	2-10	2-10	

Gradation Classification---- The combined aggregate gradation shall be classified as coarse-graded when it passes below the Primary Control Sieve (PCS) control point as defined in the following table. All other gradations shall be classified as fine-graded.

GRADATION CLASSIFICATION

PCS Control Point for Mixture Nominal Maximum Aggregate Size						
(% passing)						
Nominal Maximum Aggregate	TYPE 25	TYPE 19	TYPE 12.5	TYPE 9.5		
Size	mm	mm	mm	mm		
Primary Control Sieve	4.75 mm	4.75 mm	2.36 mm	2.36 mm		
PCS Control Point (% passing)	40	47	39	47		

If a Grading "D" mixture is allowed per Special Provision Section 403, it shall meet the following gradation and the aggregate requirements of Section 703.07.

Sieve	Percentage by Weight		
Designation	Passing Square Mesh Sieves		
½ inch	100		
³ / ₈ inch	93-100		
No. 4	60-80		
No. 8	46-65		
No. 16	25-55		
No. 30	16-40		
No. 50	10-30		
No. 100	6-22		
No. 200	3.0-8.0		

<u>703.18 Common Borrow</u> Replace the first paragraph with the following: "Common borrow shall consist of earth, suitable for embankment construction. It shall be free from frozen material, perishable rubbish, peat, and other unsuitable material including material currently or previously contaminated by chemical, radiological, or biological agents unless the material is from a DOT project and authorized by DEP for use."

703.22 Underdrain Backfill Material Change the first paragraph from "...for Underdrain Type B..." to "...for Underdrain Type B and C..."

SECTION 706 NON-METALLIC PIPE

706.06 Corrugated Polyethylene Pipe for Underdrain, Option I and Option III Culvert Pipe Change the first sentence from "...300 mm diameters to 900 mm" to "...300 mm diameters to 1200 mm" Delete, in it's entirety, the last sentence which begins "This pipe and resins..." and replace with the following; "The manufacturing plants of polyethylene pipe shall be certified by the Eastern States Consortium. Polyethylene pipe shall be accepted based on third party certification by the AASHTO's National Transportation Product Evaluation Program."

SECTION 709 REINFORCING STEEL AND WELDED STEEL WIRE FABIC

709.03 Steel Strand Change the second paragraph from "...shall be 12mm [½ inch] AASHTO M203M/M203 (ASTM A416/A416M)..." to "...shall be 15.24 mm [0.600 inch] diameter AASHTO M203 (ASTM A416)..."

SECTION 710 FENCE AND GUARDRAIL

710.03 Chain Link Fabric Add the following sentence: "Chain Link fabric for PVC coated shall conform to the requirements of AASHTO M181, Type IV-Class B."

710.07 Guardrail Posts Section b. change "...AASHTO M183/M183M..." to "...AASHTO M 270M/M 270 Grade 250 (36)..."

SECTION 712 MISCELLANEOUS HIGHWAY MATERIALS

712.06 Precast Concrete Units In the first paragraph, change "...ASTM C478M..." to "...AASHTO M199..." Delete the second paragraph and replace with the following; "Approved structural fibers may be used as a replacement of 6 x 6 #10 gauge welded wire fabric when used at an approved dosage rate for the construction of manhole and catch basin units. The material used shall be one of the products listed on the Maine Department of Transportation's Approved Product List of Structural Fiber Reinforcement." Delete the fifth paragraph and replace with the following; "The concrete mix design shall be approved by the Department. Concrete shall contain 6% air content, plus or minus 1½% tolerance when tested according to AASHTO T152. All concrete shall develop a minimum compressive strength of 28 MPa [4000 psi] in 28 days when tested according to AASHTO T22. The absorption of a

specimen, when tested according to AASHTO T280, Test Method "A", shall not exceed nine percent of the dry mass."

Add the following:

<u>"712.07 Tops, and Traps</u> These metal units shall conform to the plan dimensions and to the following specification requirements for the designated materials.

Gray iron or ductile iron castings shall conform to the requirements of AASHTO M306 unless otherwise designated."

<u>712.08 Corrugated Metal Units</u> The units shall conform to plan dimensions and the metal to AASHTO M36/M36M. Bituminous coating, when specified, shall conform to AASHTO M190 Type A.

712.09 Catch Basin and Manhole Steps Steps for catch basins and for manholes shall conform to ASTM C478M [ASTM C478], Section 13 for either of the following material:

- (a) Aluminum steps-ASTM B221M, [ASTM B211] Alloy 6061-T6 or 6005-T5.
- (b) Reinforced plastic steps Steel reinforcing bar with injection molded plastic coating copolymer polypropylene. Polypropylene shall conform to ASTM D 4101.
- 712.23 Flashing Lights Flashing Lights shall be power operated or battery operated as specified.
 - (a) Power operated flashing lights shall consist of housing, adapters, lamps, sockets, reflectors, lens, hoods and other necessary equipment designed to give clearly visible signal indications within an angle of at least 45 degrees and from 3 to 90 m [10 to 300 ft] under all light and atmospheric conditions.

Two circuit flasher controllers with a two-circuit filter capable of providing alternate flashing operations at the rate of not less than 50 nor more than 60 flashes per minute shall be provided.

The lamps shall be 650 lumens, 120 volt traffic signal lamps with sockets constructed to properly focus and hold the lamp firmly in position.

The housing shall have a rotatable sun visor not less than 175 mm [7 in] in length designed to shield the lens.

Reflectors shall be of such design that light from a properly focused lamp will reflect the light rays parallel. Reflectors shall have a maximum diameter at the point of contact with the lens of approximately 200 mm [8 in].

The lens shall consist of a round one-piece convex amber material which, when mounted, shall have a visible diameter of approximately 200 mm [8 in]. They shall distribute light and not diffuse it. The distribution of the light shall be asymmetrical in a downward direction. The light distribution of the lens shall not be uniform, but shall consist of a small high intensity portion with narrow distribution for long distance throw and a larger

low intensity portion with wide distribution for short distance throw. Lenses shall be marked to indicate the top and bottom of the lens.

(b) Battery operated flashing lights shall be self-illuminated by an electric lamp behind the lens. These lights shall also be externally illuminated by reflex-reflective elements built into the lens to enable it to be seen by reflex-reflection of the light from the headlights of oncoming traffic. The batteries must be entirely enclosed in a case. A locking device must secure the case. The light shall have a flash rate of not less than 50 nor more than 60 flashes per minute from minus 30 °C [minus 20 °F] to plus 65 °C [plus 150 °F]. The light shall have an on time of not less than 10 percent of the flash cycle. The light beam projected upon a surface perpendicular to the axis of the light beam shall produce a lighted rectangular projection whose minimum horizontal dimension shall be 5 degrees each side of the horizontal axis. The effective intensity shall not have an initial value greater than 15.0 candelas or drop below 4.0 candelas during the first 336 hours of continuous flashing. The illuminated lens shall appear to be uniformly bright over its entire illuminated surface when viewed from any point within an angle of 9 degrees each side of the vertical axis and 5 degrees each side of the horizontal axis. The lens shall not be less than 175 mm [7 in] in diameter including a reflex-reflector ring of 13 mm [½ in] minimum width around the periphery. The lens shall be vellow in color and have a minimum relative luminous transmittance of 0.440 with a luminance of 2854° Kelvin. The lens shall be one-piece construction. The lens material shall be plastic and meet the luminous transmission requirements of this specification. The case containing the batteries and circuitry shall be constructed of a material capable of withstanding abuse equal to or greater than 1.21 mm thick steel [No. 18 U.S. Standard Gage Steel]. The housing and the lens frame, if of metal shall be properly cleaned, degreased and pretreated to promote adhesion. It shall be given one or more coats of enamel which, when dry shall completely obscure the metal. The enamel coating shall be of such quality that when the coated case is struck a light blow with a sharp tool, the paint will not chip or crack and if scratched with a knife will not powder. The case shall be so constructed and closed as to exclude moisture that would affect the proper operation of light. The case shall have a weep hole to allow the escape of moisture from condensation. Photoelectric controls, if provided, shall keep the light operating whenever the ambient light falls below 215 lx [20 foot candles]. Each light shall be plainly marked as to the manufacturer's name and model number.

If required by the Resident, certification as to conformance to these specifications shall be furnished based on results of tests made by an independent testing laboratory. All lights are subject to random inspection and testing. All necessary random samples shall be provided to the Resident upon request without cost to the Department. All such samples shall be returned to the Contractor upon completion of the tests.

- 712.32 Copper Tubing Copper tubing and fittings shall conform to the requirements of ASTM B88M Type A [ASTM B88, Type K] or better.
- <u>712.33 Non-metallic Pipe, Flexible</u> Non-metallic pipe and pipe fittings shall be acceptable flexible pipe manufactured from virgin polyethylene polymer suitable for transmitting liquids intended for human or animal consumption.

712.34 Non-metallic Pipe, Rigid Non-metallic pipe shall be Schedule 40 polyvinylchloride (PVC) that meets the requirement of ASTM D1785. Fittings shall be of the same material.

<u>712.341 Metallic Pipe</u> Metallic pipe shall be ANSI, Standard B36.10, Schedule 40 steel pipe conforming to the requirements of ASTM A53 Types E or S, Grade B. End plates shall be steel conforming to ASTM A36/A36M.

Both the sleeve and end plates shall be hot dip galvanized. Pipe sleeve splices shall be welded splices with full penetration weld before galvanizing.

<u>712.35 Epoxy Resin</u> Epoxy resin for grouting or sealing shall consist of a mineral filled thixotropic, flexible epoxy resin having a pot life of approximately one hour at 10°C [50°F]. The grout shall be an approved product suitable for cementing steel dowels into the preformed holes of curb inlets and adjacent curbing. The sealant shall be an approved product, light gray in color and suitable for coating the surface.

712.36 Bituminous Curb The asphalt cement for bituminous curb shall be of the grade required for the wearing course, or shall be Viscosity Grade AC-20 meeting the current requirements of Subsection 702.01 Asphalt Cement. The aggregate shall conform to the requirements of Subsection 703.07. The coarse aggregate portion retained on the 2.36 mm [No. 8] sieve may be either crushed rock or crushed gravel.

The mineral constituents of the bituminous mixture shall be sized and graded and combined in a composite blend that will produce a stable durable curbing with an acceptable texture.

Bituminous material for curb shall meet the requirements of Section 403 - Hot Bituminous Pavement.

712.37 Precast Concrete Slab Portland cement concrete for precast slabs shall meet the requirements of Section 502 - Structural Concrete, Class A.

The slabs shall be precast to the dimension shown on the plans and cross section and in accordance with the Standard Detail plans for Concrete Sidewalk Slab. The surface shall be finished with a float finish in accordance with Subsection 502.14(c). Lift devices of sufficient strength to hold the slab while suspended from cables shall be cast into the top or back of the slab.

712.38 Stone Slab Stone slabs shall be of granite from an acceptable source, hard, durable, predominantly gray in color, free from seams which impair the structural integrity and be of smooth splitting character. Natural color variations characteristic of the deposit will be permitted. Exposed surfaces shall be free from drill holes or indications of drill holes. The granite slabs in any one section of backslope must be all the same finish.

The granite slabs shall be scabble dressed or sawed to an approximately true plane having no projections or depressions over 13 mm [½ in] under a 600 mm [2 ft] straightedge or over 25 mm [1 in] under a 1200 mm [4 ft] straightedge. The arris at the intersection of the top surface and exposed front face shall be pitched so that the arris line is uniform throughout the length of the installed slabs. The sides shall be square to the exposed face unless the slabs are to be set

on a radius or other special condition which requires that the joints be cut to fit, but in any case shall be so finished that when the stones are placed side by side no space more than 20 mm [3/4 in] shall show in the joint for the full exposed height.

Liftpin holes in all sides will be allowed except on the exposed face.

SECTION 717 ROADSIDE IMPROVEMENT MATERIAL

717.03 C. Method #3 - Roadside Mixture #3 Change the seed proportions to the following:

Crown Vetch 25%
Perennial Lupine 25%
Red Clover 12.5%
Annual Rye 37.5%

717.05 Mulch Binder Change the third sentence to read as follows:

"Paper fiber mulch may be used as a binder at the rate of 2.3 kg/unit [5 lb/unit]."

SECTION 720 STRUCTURAL SUPPORTS FOR HIGHWAY SIGNS, LUMINAIRES, AND TRAFFIC SIGNALS

<u>720.08 U-Channel Posts</u> Change the first sentence from "..., U-Channel posts..." to "..., Rib Back U-Channel posts..."

SECTION 722 GEOTEXTILES

- <u>722.01 Stabilization/Reinforcement Geotextile</u> Add the following to note #3; "The strengths specified in the columns labeled" <50%" and " $\geq 50\%$ " refer to the elongation at which the geotextile material was tested. For example; if a fabric is tested at 15% elongation then it must meet or exceed the minimum strength shown in the "<50%" column. Submittals must include the percent elongation at which the material was tested."
- <u>722.02 Drainage Geotextile</u> Add the following to note #3; "The strengths specified in the columns labeled"<50%" and " \geq 50%" refer to the elongation at which the geotextile material was tested. For example; if a fabric is tested at 15% elongation then it must meet or exceed the minimum strength shown in the "<50%" column. Submittals must include the percent elongation at which the material was tested."
- 722.01 Erosion Control Geotextile Add the following note to Elongation in the Mechanical Property Table; "The strengths specified in the columns labeled"<50%" and "≥ 50%" refer to the elongation at which the geotextile material was tested. For example; if a fabric is tested at 15% elongation then it must meet or exceed the minimum strength shown in the "<50%" column. Submittals must include the percent elongation at which the material was tested."

APPENDIX A TO DIVISION 100

SECTION 1 - BIDDING PROVISIONS

- A. <u>Federally Required Certifications</u> By signing and delivering a Bid, the Bidder certifies as provided in all certifications set forth in this Appendix A Federal Contract Provisions Supplement including:
- Certification Regarding No Kickbacks to Procure Contract as provided on this page 1 below.
- Certification Regarding Non-collusion as provided on page 1 below.
- Certification Regarding Non-segregated Facilities as provided by FHWA Form 1273, section III set forth on page 21 below.
- "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion" as provided by FHWA Form 1273, section XI set forth on page 32 below.
- "Certification Regarding Use of Contract Funds for Lobbying" as provided by FHWA Form 1273, section XII set forth on page 35 below.

Unless otherwise provided below, the term "Bidder", for the purposes of these certifications, includes the Bidder, its principals, and the person(s) signing the Bid. Upon execution of the Contract, the Bidder (then called the Contractor) will again make all the certifications indicated in this paragraph above. Upon execution of the Contract, the Bidder (then called the Contractor) will again make all the certifications indicated in this paragraph above.

<u>CERTIFICATION REGARDING NO KICKBACKS TO PROCURE CONTRACT</u> Except expressly stated by the Bidder on sheets submitted with the Bid (if any), the Bidder hereby certifies, to the best of its knowledge and belief, that it has not:

- (A) employed or retained for a commission, percentage, brokerage, contingent fee, or other consideration, any firm or person (other then a bona fide employee working solely for me) to solicit or secure this contract;
- (B) agreed, as an express or implied condition for obtaining this contract, to employ or retain the services of any firm or person in connection with carrying out the contract, or;
- C) paid, or agreed to pay, to any firm, organization, or person (other than a bona fide employee working solely for me) any fee, contribution, donation, or consideration of any kind for, or in connection with, procuring or carrying out the contract;

By signing and submitting a Bid, the Bidder acknowledges that this certification is to be furnished to the Maine Department of Transportation and the Federal Highway Administration, U.S. Department of Transportation in connection with this contract in anticipation of federal aid highway funds and is subject to applicable state and federal laws, both criminal and civil.

<u>CERTIFICATION REGARDING NONCOLLUSION</u> Under penalty of perjury as provided by federal law (28 U.S.C. §1746), the Bidder hereby certifies, to the best of its knowledge and belief, that:

the Bidder has not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of competitive bidding in connection with the Contract.

For a related provisions, see Section 102.7.2 (C) of the Standard Specifications - "Effects of Signing and Delivery of Bids" - "Certifications", Section 3 of this Appendix A entitled "Other Federal Requirements" including section XI - "Certification Regarding Debarment, Suspension, Ineligibility, and Voluntary Exclusion" and section XII. - "Certification Regarding Use of Contract Funds for Lobbying."

B. Bid Rigging Hotline To report bid rigging activities call: 1-800-424-9071

The U.S. Department of Transportation (DOT) operates the above toll-free "hotline" Monday through Friday, 8:00 a.m. to 5:00 p.m., eastern time. Anyone with knowledge of possible bid rigging, bidder collusion, or other fraudulent activities should use the "hotline" to report such activities.

The "hotline" is part of the DOT's continuing effort to identify and investigate highway construction contract fraud and abuse and is operated under the direction of the DOT Inspector General. All information will be treated confidentially and caller anonymity will be respected.

SECTION 2 - FEDERAL EEO AND CIVIL RIGHTS REQUIREMENTS

Unless expressly otherwise provided in the Bid Documents, the provisions contained in this Section 2 of this "Federal Contract Provisions Supplement" are hereby incorporated into the Bid Documents and Contract.

A. <u>Nondiscrimination & Civil Rights - Title VI</u> The Contractor and its subcontractors shall not discriminate on the basis of race, color, national origin, or sex in the performance of this Contract. The Contractor shall carry out applicable requirements of 49 CFR Part 26 in the award and administration of DOT assisted contracts. Failure by the Contractor to carry out these requirements is a material breach of this contract, which may result in the termination of this contract or such other remedy as the Department deems appropriate. The Contractor and subcontractors shall comply with Title VI of the Civil Rights Act of 1964, as amended, and with all State of Maine and other Federal Civil Rights laws.

For related provisions, see Subsection B - "Nondiscrimination and Affirmative Action - Executive Order 11246" of this Section 2 and Section 3 - Other Federal Requirements of this "Federal Contract Provisions Supplement" including section II - "Nondiscrimination" of the "Required Contract Provisions, Federal Aid Construction Contracts", FHWA-1273.

B. <u>Nondiscrimination and Affirmative Action - Executive Order 11246</u> Pursuant to Executive Order 11246, which was issued by President Johnson in 1965 and amended in 1967 and 1978, this Contract provides as follows.

The Contractor shall take specific affirmative actions to ensure equal employment opportunity. The evaluation of the Contractor's compliance with these specifications shall be based upon its efforts to achieve maximum results from its actions. The Contractor shall

document these efforts fully, and shall implement affirmative action steps at least as extensive as the following:

- 1. Ensure and maintain a working environment free of harassment, intimidations, and coercion at all sites, and in all facilities at which the Contractor's employees are assigned to work. The Contractor, where possible, will assign two or more women to each construction project. The Contractor shall specifically ensure that all forepersons, superintendents, and other on-site supervisory personnel are aware of and carry out the Contractor's obligation to maintain such a working environment, with specific attention to minority or female individuals working at such sites or in such facilities.
- 2. Establish and maintain a current list of minority and female recruitment sources, provide written notification to minority and female recruitment sources and to community organizations when the Contractor or its union have employment opportunities available, and to maintain a record of the organization's responses.
- 3. Maintain a current file of the names, addresses and telephone numbers of each minority and female off-the-street applicant and minority or female referral from a union, a recruitment source or community organization and of what action was taken with respect to each such individual. If such individual was sent to the union hiring hall for referral and was not referred back to the Contractor by the union or, if referred, not employed by the Contractor, this shall be documented in the file with the reason therefore, along with whatever additional actions the Contractor may have taken.
- 4. Provide immediate written notification to the Department's Civil Rights Office when the union or unions with which the Contractor has a collective bargaining agreement has not referred to the Contractor a minority person or woman sent by the Contractor, or when the Contractor has other information that the union referral process has impeded the Design-Builder's efforts to meet its obligations.
- 5. Develop on-the-job training opportunities and/or participate in training programs for the area which expressly include minorities and women, including upgrading programs and apprenticeship and trainee programs relevant to the Contractor's employment needs, especially those programs funded or approved by the Department of Labor. The Contractor shall provide notice of these programs to the sources compiled under B above.
- 6. Disseminate the Contractor's EEO policy by providing notice of the policy to unions and training programs and requesting their cooperation in assisting the Contractor in meeting its EEO obligation; by including it in any policy manual and collective bargaining agreement; by publicizing it in the company newspaper, annual report, etc.; by specific review of the policy with all management personnel and with all minority and female employees at least once a year; and by posting the company EEO policy on bulletin boards accessible to all employees at each location where construction work is performed.
- 7. Review, at least annually, the company's EEO policy and affirmative action obligations under these specifications with all employees having any responsibility for hiring, assignment, layoff, termination, or other employment decisions including specific review

of these items with on-site supervisory personnel such as Superintendents, General Forepersons, etc., prior to the initiation of construction work at any job site. A written record shall be made and maintained identifying the time and place of these meetings, persons attending, subject matter discussed, and disposition of the subject matter.

- 8. Disseminate the Contractor's EEO policy externally by including it in any advertising in the news media, specifically including minority and female news media, and providing written notification to and discussing the Contractor's EEO policy with other Contractor's and Subcontractors with whom the Contractor does or anticipates doing business.
- 9. Direct its recruitment efforts, both orally and written to minority, female and community organizations, to schools with minority and female students and to minority and female recruitment and training organizations serving the Contractor's recruitment area and employment needs. Not later that one month prior to the date for the acceptance of applications for apprenticeship or other training by any recruitment source, the Contractor shall send written notification to organizations such as the above describing the openings, screenings, procedures, and test to be used in the selection process.
- 10. Encourage present minority and female employees to recruit other minority persons and women and, where reasonable, provide after school, summer and vacation employment to minority and female youth, both on the site and in other areas of a Contractor's workforce.
- 11. Validate all tests and other selection requirements.
- 12. Conduct, at least annually, an inventory and evaluation at least of all minority and female personnel for promotional opportunities and encourage these employees to seek or to prepare for, through appropriate training, etc., such opportunities.
- 13. Ensure that seniority practices, job classifications, work assignments and other personnel practices, do not have a discriminatory effect by continually monitoring all personnel and employment related activities to ensure that the EEO policy and the Contractor's obligations under these specifications are being carried out.
- 14. Ensure that all facilities and company activities are non segregated except that separate or single-user toilet and necessary changing facilities shall be provided to assure privacy between the sexes
- 15. Document and maintain a record of all solicitations of offers for subcontracts from minority and female construction Contractor's and suppliers, including circulation of solicitations to minority and female Contractor associations and other business associations.
- 16. Conduct a review, at least annually, of all supervisors' adherence to and performance under the Contractor's EEO policies and affirmative action obligations.

C. <u>Goals for Employment of Women and Minorities</u> Per Executive Order 11246, craft tradesperson goals are 6.9% women and .5% minorities employed. However, goals may be adjusted upward at the mutual agreement of the Contractor and the Department. Calculation of these percentages shall not include On-the-Job Training Program trainees, and shall not include clerical or field clerk position employees.

For a more complete presentation of requirements for such Goals, see the federally required document "Goals for Employment of Females and Minorities" set forth in the next 6 pages below.

Start of GOALS FOR EMPLOYMENT OF FEMALES AND MINORITIES Federally Required Contract Document

§60-4.2 Solicitations

(d) The following notice shall be included in, and shall be part of, all solicitations for offers and bids on all Federal and federally assisted construction contracts or subcontracts in excess of \$10,000 to be performed in geographical areas designated by the Director pursuant to \$60-4.6 of this part (see 41 CFR 60-4.2(a)):

Notice of Requirement for Affirmative Action to Ensure Equal Opportunity (Executive Order 11246)

- 1. The Offeror's or bidder's attention is called to the "Equal Opportunity Clause" and the "Standard Federal Equal Employment Specifications" set forth herein.
- 2. The goals and timetables for minority and female participation, expressed in percentage terms for the Contractor's aggregate work force in each trade on all construction work in the covered area, are as follows:

Goals for female participation in each trade

6.9%

Goals for minority participation for each trade

Maine

001 Bangor, ME

0.8%

Non-SMSA Counties (Aroostook, Hancock, Penobscot, Piscataguis, Waldo, Washington)

002 Portland-Lewiston, ME

SMSA Counties: 4243 Lewiston-Auburn, ME 0.5%

(Androscoggin)

6403 Portland, ME 0.6%

(Cumberland, Sagadahoc)

Non-SMSA Counties: 0.5%

(Franklin, Kennebec, Knox, Lincoln, Oxford, Somerset, York)

These goals are applicable to all the Contractor's construction work (whether or not it is Federal or federally assisted) performed in the covered area. If the contractor performs construction work in a geographical area located outside of the covered area, it shall apply the goals established for such geographical area where the work is actually performed. With regard to this second area, the contractor also is subject to the goals for both its federally involved and non federally involved construction.

The contractor's compliance with the Executive Order and the regulations in 41 CFR Part 60-4 shall be based on its implementation of the Equal Opportunity Clause, specific affirmative action obligations required by the specifications set forth in 41 CFR 60-4.3(a), and its efforts to meet the goals. The hours of minority and female employment and training must be substantially uniform throughout the length of the contract, and in each trade, and the contractor shall make a good faith effort to employ minorities and women evenly on each of its projects. The transfer of minority or female employees or trainees from Contractor to Contractor or from project to project for the sole purpose of meeting the Contractor's goals shall be in violation of the contract, the Executive Order and the regulations in 41 CFR Part 60-4. Compliance with the goals will be measured against the total work hours performed.

- 3. The Contractor shall provide written notification to the Director of the Office of Federal Contract Compliance Programs within 10 working days of award of any construction subcontract in excess of \$10,000 at any tier for construction work under the contract resulting from this solicitation. The notification shall list the name, address and telephone number of the subcontractor, employer identification number of the subcontractor, estimated dollar amount of the subcontract; estimated started and completion dates of the subcontract; and the geographical area in which the subcontract is to be performed.
- 4. As used in this Notice, and in the Contract resulting from this solicitation, the "covered area" is (insert description of the geographical areas where the contract is to be performed giving the state, county and city, if any).

STANDARD FEDERAL EQUAL EMPLOYMENT OPPORTUNITY CONSTRUCTION CONTRACT SPECIFICATIONS (EXECUTIVE ORDER 11246)

1. As used in these specifications:

- a. "Covered area" means the geographical area described in the solicitation from which this contract resulted;
- b. "Director" means Director, Office of Federal Contract Compliance Programs, United States Department of Labor, or any person to whom the Director delegates authority;
- c. "Employer identification number" means the Federal Social Security number used on the Employer's Quarterly Federal Tax Return, U.S. Treasury Department form 941;

d. "Minority" includes:

(i) Black (all persons having origins in any of the Black African racial groups not of Hispanic origin);

- (ii) Hispanic (all persons of Mexican, Puerto Rican, Cuban, Central or South American or other Spanish Culture or origin, regardless of race);
- (iii) Asian and Pacific Islander (all persons having origins in any of the original peoples of the Far East, Southeast Asia, the Indian Subcontinent, or the Pacific Islands); and
- (iv) American Indian or Alaskan Native (all persons having origins in any of the original peoples of the North America and maintaining identifiable tribal affiliations through membership and participation or community identification).
- 2. Whenever the Contractor, or any subcontractor at any tier, subcontracts a portion of the work involving any construction trade, it shall physically include in each subcontract in excess of \$10,000 the provisions of these specifications and the Notice which contains the applicable goals for minority and female participation and which is set forth in the solicitations from which this contract resulted.
- 3. If the contractor, is participating (pursuant to 41 CFR 60-4.5) in a Hometown Plan approved by the U.S. Department of Labor in the covered area either individually or through an association, its affirmative action obligations on all work in the Plan area (including goals and timetables) shall be in accordance with that Plan for those trades which have unions participating in the Plan. Contractors must be able to demonstrate their participation in and compliance with the provisions of any such Hometown Plan. Each Contractor or Subcontractor participating in an approved Plan is individually required to comply with its obligations under the EEO clause, and to make a good faith effort to achieve each goal under the Plan in each trade in which it has employees. The overall good faith performance by other Contractors for Subcontractors toward a goal in an approved Plan does not excuse any covered Contractor's or Subcontractor's failure to take good faith efforts to achieve the Plan goals and timetables.
- 4. The Contractor shall implement the specific affirmative action standards provided in paragraphs 7 a. through p. of these specifications. The goals set forth in the solicitation from which this contract resulted are expressed as percentages of the total hours of employment and training of minority and female utilization the Contractor should reasonably be able to achieve in each construction trade in which it has employees in contractors performing construction work in geographical areas where they do not have a Federal or federally assisted construction contract shall apply the minority and female goals established for the geographical areas where the work is being performed. Goals are published periodically in the Federal Register in notice form and such notices may be obtained from any Office of Federal Contract Compliance Programs office or from Federal procurement contracting officers. The Contractor is expected to make substantially uniform progress in meeting its goals in each craft during the period specific.
- 5. Neither the provisions of any collective bargaining agreement, nor the failure by a union with whom the Contractor has a collective bargaining agreement, to refer either minorities or women shall excuse the Contractor's obligations under these specifications, Executive Order 11246, or the regulations promulgated pursuant, thereto.
- 6. In order for the non working training hours of apprentices and trainees to be counted in meeting the goals, such apprentices and trainees must be employed by the Contractor during the training period, and the Contractor must have made a commitment to employ the

apprentices and trainees at the completion of their training, subject to the availability of employment opportunities. Trainees must be trained pursuant to training programs approved by the U.S. Department of Labor.

- 7. The Contractor shall take specific affirmative actions to ensure equal employment opportunity. The evaluation of the Contractor's compliance with these specifications shall be based upon its effort to achieve maximum results from its actions. The Contractor shall document these efforts fully, and shall implement affirmative action steps at least as expensive as the following:
 - a. Ensure and maintain a working environment free of harassment, intimidation, coercion at all sites, and in all facilities at which the Contractor's employees are assigned to work. The Contractor, when possible, will assign two or more women to each construction project. The Contractor shall specifically ensure that all foremen, superintendents, and other on-site supervisory personnel are aware of and carry out the Contractor's obligation to maintain such a working environment, with specific attention to minority or female individuals working at such sites or in such facilities.
 - b. Establish and maintain a current list of minority and female recruitment sources provide written notification to minority and female recruitment sources and to community organizations when the Contractor or its unions have employment opportunities available, and maintain a record of the organization's responses.
 - c. Maintain a current file of the names, addresses and telephone numbers of each minority and female off-the-street applicant and minority or female referral from a union, a recruitment sources or community organization and of what action was taken with respect to each such individual. If such individual was sent to the union hiring hall for referral and was not referred back to the Contractor by the union or, if referred, not employed by the Contractor, this shall be documented in the file with the reason therefore, along with whatever additional actions the Contractor may have taken.
 - d. Provide immediate written notification to the Director when the union or unions with which the Contractor has a collective bargaining agreement has not referred to the Contractor a minority person or woman sent by the Contractor, or when the Contractor has other information that the union referral process has impeded the Contractor's efforts to meet its obligations.
 - e. Develop on-the-job training opportunities and/or participate in training programs for the area which expressly include minorities and women, including upgrading programs and apprenticeship and trainee programs relevant to the Contractor's employment needs, especially those programs funded or approved by the Department of Labor. The Contractor shall provide notice of these programs to the sources complied under 7b above.
 - f. Disseminate the Contractor's EEO policy by providing notice of the policy to unions and training programs and requesting their cooperation in assisting the Contractor in meeting its EEO obligations; by including in any policy manual and collective bargaining agreement; by publicizing it in the company newspaper, annual report, etc.; by specific

review of the policy with all management personnel and with all minority and female employees at least once a year; and by posting the company EEO policy on bulletin boards accessible to all employees at each location where construction work is performed.

- g. Review, at least annually, the company's EEO policy and affirmative action obligations under these specifications with all employees having any responsibility for hiring, assignment, layoff, termination or other employment decisions including specific review of these items with on-site supervisory personnel such as Superintendents, General Foremen, etc., prior to the initiation of construction work at any job site. A written record shall be made and maintained identifying the time and place of these meetings, persons attending, subject matter discussed, and disposition of the subject matter.
- h. Disseminate the Contractor's EEO policy externally by including it in any advertising in the news media, specifically including minority and female news media, and providing written notification to and discussing the Contractor's EEO policy with other Contractors and Subcontractors with whom the Contractor does or anticipates doing business.
- i. Direct its recruitment, efforts, both oral and written, to minority, female and community organizations, to schools with minority and female students and to minority and female recruitment and training organizations serving the Contractor's recruitment area and employment needs. Not later than one month other training by any recruitment source, the Contractor shall send written notification to organizations such as the above, describing prior to the date for the acceptance of applications for apprenticeship or the openings, screening procedures, and tests to be used in the selection process.
- j. Encourage present minority and female employees to recruit other minority persons and women and, where reasonable, provide after school, summer and vacation employment to minority and female youth both on site and in other areas of a Contractor's work force.
- k. Validate all tests and other selection requirements where there is an obligation to do so under 41 CFR Part 60-3.
- 1. Conduct, at least annually, an inventory and evaluation at least of all minority and female personnel for promotional opportunities and encourage these employees to seek or to prepare for, through appropriate training, etc., such opportunities.
- m. Ensure that seniority practices, job classifications, work assignments and other personnel practices, do not have a discriminatory effect by continually monitoring all personnel and employment related activities to ensure that the EEO policy and the Contractor's obligations under these specifications are being carried out.
- n. Ensure that all facilities and company activities are non segregated except that separate or single-user toilet and necessary changing facilities shall be provided to assure privacy between the sexes.
- o. Document and maintain a record of all solicitations of offers for subcontracts from minority and female construction contractors and suppliers, including circulation of

solicitation to minority and female contractor associations and other business associations.

- p. Conduct a review, at least annually, of all supervisor's adherence to and performance under the Contractor's EEO policies and affirmative action obligations.
- 8. Contractors are encouraged to participate in voluntary associations which assist in fulfilling one or more of their affirmative action obligations (7 a through p.). The efforts of a contractor association, joint contractor-union, contractor-community, or other similar group of which the contractor is a member and participant, may be asserted as fulfilling any one or more of its obligations under 7 a through p. of these specifications provided that the contractor actively participates in the group, makes every effort to assure that the group has a positive impact on the employment of minorities and women in the industry, ensures that the concrete benefits of the program and reflected in the Contractor's minority and female work force participation, makes a good faith effort to meet its individual goals and timetables, and can provide access to documentation which demonstrates the effectiveness of actions take on behalf of the Contractor. The obligation to comply, however, is the Contractor's and failure of such a group to fulfill an obligation shall not be a defense for the Contractor's noncompliance.
- 9. A single goal for minorities and a separate single goal for women have been established. The Contractor, however, is required to provide equal employment opportunity and to take affirmative action for all minority groups, both make and female, and all women, both minority and non-minority. Consequently, the Contractor may be in violation of the Executive Order if a particular group is employed in a substantially disparate manner (for example, specific minority group of women is underutilized.)
- 10. The Contractor shall not use the goals and timetables or affirmative action even through the Contractor has achieved its goals for women generally, the Contractor may be in violation of the Executive Order if standards to discriminate against any person because of race, color, religion, sex, or national origin.
- 11. The Contractor shall not enter into any Subcontract with any person or firm debarred from Government contracts pursuant to Executive Order 11246.
- 12. The Contractor shall carry out such sanctions and penalties for violation of these specifications and of the Equal Opportunity Clause, including suspension, termination and cancellation of existing subcontracts as may be imposed or ordered pursuant to Executive Order 11246, as amended, and its implementation regulations by the Office of Federal Contract Compliance Programs. Any Contractor who fails to carry out such sanctions and penalties shall be in violation of these specifications and Executive Order 11246, as amended.
- 13. The Contractor, in fulfilling its obligations under these specifications, shall implement specific affirmative action steps, at least as extensive as those standards prescribed in paragraph 7 of these specifications, so as to achieve maximum results from its efforts to ensure equal employment opportunity. If the Contractor fails to comply with the

requirements of the Executive Order, the implementing regulations, or these specifications, the Director shall proceed in accordance with 41 CFR 60-4.6.

- 14. The Contractor shall designate a responsible official to monitor all employment related activity to ensure that the company EEO policy is being carried out, to submit reports relating to the provisions hereof as may be required by the Government and to keep records. Records shall at least include for each employee the name, address, telephone numbers, construction trade, union affiliation if any, employee identification number when assigned, social security number, race, sex, status (e.g. mechanic, apprentice, trainee, helper, or laborer), dates of changes in status, hours worked per week in the indicated trade, rate of pay, and location sat which the work was performed. Records be maintained in an easily understandable and retrievable form; however, to the degree that existing records satisfy this requirement, contractors shall not be required to maintain separate records.
- 15. Nothing herein provided shall be construed as a limitation upon the application of other laws which establish different standards of compliance or upon the application of requirements for the hiring of local or other area residents (e.g., those under the Public Works Employment Act of 1977 and the Community Development Block Grant Program).

End of GOALS FOR EMPLOYMENT OF FEMALES AND MINORITIES Federally Required Contract Document

D. <u>Disadvantaged Business Enterprise (DBE) Requirements</u> The Department has established an annual Disadvantaged Business Enterprise goal to be achieved through race neutral means. This goal will adjusted periodically and will be provided by Supplemental Provision. The Contractor shall comply with all provisions of this section regarding DBE participation and the Department's latest version of the Disadvantaged Business Enterprise Program Manual, said Manual being incorporated herein by reference. In the case of conflict between this Contract and said Manual, this Contract shall control. The Department reserves the right to adjust DBE goals on a project-by-project basis by addendum.

<u>Policy.</u> It is the Department's policy that DBEs as defined in 23 CFR Part 26 and referenced in the Transportation Equity Act for 21st Century of 1998, as amended from the Surface Transportation Uniform Relocation Assistance Act of 1987, and the Intermeddle Surface Transportation Efficiency Act of 1991. The intent hereto remains to provide the maximum opportunity for DBEs to participate in the performance of contracts financed in whole or in part with federal funds.

The Department and its Contractors shall not discriminate on the basis of race, color, national origin, ancestry, sex, age, or disability in the award and performance of DOT assisted contracts.

Disadvantaged Business Enterprises are those so certified by the Maine Department of Transportation Civil Rights Office prior to bid opening date.

The Department has determined that elements of a good faith effort to meet the contract goal include but are not limited to the following:

- 1. Whether the Contractor advertised in general circulation, trade association, and minority/women's-focus media concerning the subcontracting opportunities;
- 2. Whether the Contractor provided written notice to a reasonable number of specific DBEs that their interest in the contract is being solicited;
- 3. Whether the Contractor followed up on initial solicitations of interest by contacting DBEs to determine with certainty whether the DBEs were interested;
- 4. Whether the Contractor selected portions of the work to be performed by DBEs in order to increase the likelihood of meeting the DBE goals;
- 5. Whether the Contractor provided interested DBEs with adequate information about the plans, specification and requirements of the contract;
- 6. Whether the Contractor negotiated in good faith with interested DBEs, not rejecting the DBE as unqualified without sound reasons based on a thorough investigation of their capabilities;
- 7. Whether the Contractor made efforts to assist interested DBEs with other appropriate technical/financial assistance required by the Department or Contractor;
- 8. Whether the Contractor effectively used the services of available minority/women's community organizations, minority/women's business assistance offices; and other organizations that provide assistance in the recruitment and placement of DBEs.

<u>Substitutions of DBEs.</u> The following may be acceptable reasons for Civil Rights Office approval of such a change order:

- The DBE defaults, voluntarily removes itself or is over-extended;
- The Department deletes portions of the work to by performed by the DBE.

It is not intended that the ability to negotiate a more advantageous contract with another certified DBE be considered a valid basis for such a change in DBE utilization once the DBE Bid Submission review has been passed. Any requests to alter the DBE commitment must be in writing and included with the change order.

Failure to carry out terms of this Standard Specification shall be treated as a violation of this contract and will result in contract sanctions which may include withholding of partial payments totaling the creditable dollars amount which would have been paid for said DBE participation, termination of this contract or other measures which may affect the ability of the Contractor to obtain Department contracts.

Copies of the Maine Department of Transportation's DBE Program may be obtained from:

Maine Department of Transportation Civil Rights Office #16 State House Station Augusta, Maine 04333-0016 tel. (207) 624-3519 Quarterly Reporting Requirement. The Contractor must submit Semi-annual reports of actual dollars paid to Disadvantaged Business Enterprises (DBE's) on this Project to the MDOT Civil Rights Office by the end of the third week of April and October for the period covering the preceding six months considered Federal Fiscal Year periods. The reports will be submitted directly to the Civil Rights Office on the form provided in the latest version of the DBE Program Manual. Failure to submit the report by the deadline may result in a withholding of approval of partial payment estimates by the Department.

SECTION 3 - OTHER FEDERAL REQUIREMENTS

Unless expressly otherwise provided in the Bid Documents, the provisions contained in this Section 3 of this "Federal Contract Provisions Supplement" are hereby incorporated into the Bid Documents and Contract.

A. Buy America

If the cost of products purchased for permanent use in this project which are manufactured of steel, iron or the application of any coating to products of these materials exceeds 0.1 percent of the contract amount, or \$2,500.00, whichever is greater, the products shall have been manufactured and the coating applied in the United States. The coating materials are not subject to this clause, only the application of the coating. In computing that amount, only the cost of the product and coating application cost will be included.

Ore, for the manufacture of steel or iron, may be from outside the United States; however, all other manufacturing processes of steel or iron must be in the United States to qualify as having been manufactured in the United States.

United States includes the 50 United States and any place subject to the jurisdiction thereof.

Products of steel include, but are not limited to, such products as structural steel, piles, guardrail, steel culverts, reinforcing steel, structural plate and steel supports for signs, luminaries and signals.

Products of iron include, but are not limited to, such products as cast iron grates.

Application of coatings include, but are not limited to, such applications as epoxy, galvanized and paint.

To assure compliance with this section, the Contractor shall submit a certification letter on its letterhead to the Department stating the following:

"This is to certify that products made of steel, iron or the application of any coating to products of these materials whose costs are in excess of \$2,500.00 or 0.1 percent of the original contract amount, whichever is greater, were manufactured and the coating, if one was required, was applied in the United States."

B. Materials

a. Convict Produced Materials References: 23 U.S.C. 114(b)(2), 23 CFR 635.417

Applicability: FHWA's prohibition against the use of convict material only applies to Federal-aid highways. Materials produced after July 1, 1991, by convict labor may only be incorporated in a Federal-aid highway construction project if: 1) such materials have been produced by convicts who are on parole, supervised release, or probation from a prison; or 2) such material has been produced in a qualified prison facility, e.g., prison industry, with the amount produced during any 12-month period, for use in Federal-aid projects, not exceeding the amount produced, for such use, during the 12-month period ending July 1, 1987.

Materials obtained from prison facilities (e.g., prison industries) are subject to the same requirements for Federal-aid participation that are imposed upon materials acquired from other sources. Materials manufactured or produced by convict labor will be given no preferential treatment.

The preferred method of obtaining materials for a project is through normal contracting procedures which require the contractor to furnish all materials to be incorporated in the work. The contractor selects the source, public or private, from which the materials are to be obtained (23 CFR 635.407). Prison industries are prohibited from bidding on projects directly (23 CFR 635.112e), but may act as material supplier to construction contractors.

Prison materials may also be approved as State-furnished material. However, since public agencies may not bid in competition with private firms, direct acquisition of materials from a prison industry for use as State-furnished material is subject to a public interest finding with the Division Administrator's concurrence (23 CFR 635.407d). Selection of materials produced by convict labor as State-furnished materials for mandatory use should be cleared prior to the submittal of the Plans Specifications & Estimates (PS&E).

b. Patented/Proprietary Products References: 23 U.S.C. 112, 23 CFR 635.411

FHWA will not participate, directly or indirectly, in payment for any premium or royalty on any patented or proprietary material, specification, or process specifically set forth in the plans and specifications for a project, unless:

- the item is purchased or obtained through competitive bidding with equally suitable unpatented items,
- the STA certifies either that the proprietary or patented item is essential for synchronization with the existing highway facilities or that no equally suitable alternative exists, or
- the item is used for research or for a special type of construction on relatively short sections of road for experimental purposes. States should follow FHWA's procedures for "Construction Projects Incorporating Experimental Features" (experimental for the submittal of work plans and evaluations.

The primary purpose of the policy is to have competition in selection of materials and allow for development of new materials and products. The policy further permits materials and products that are judged equal may be bid under generic specifications. If only patented or proprietary products are acceptable, they shall be bid as alternatives with all, or at least a

reasonable number of, acceptable materials or products listed; and the Division Administrator may approve a single source if it can be found that its utilization is in the public interest.

Trade names are generally the key to identifying patented or proprietary materials. Trade name examples include 3M, Corten, etc. Generally, products identified by their brand or trade name are not to be specified without an "or equal" phrase, and, if trade names are used, all, or at least a reasonable number of acceptable "equal" materials or products should be listed. The licensing of several suppliers to produce a product does not change the fact that it is a single product and should not be specified to the exclusion of other equally suitable products.

c. State Preference References: 23 U.S.C. 112, 23 CFR 635.409

Materials produced within Maine shall not be favored to the exclusion of comparable materials produced outside of Maine. State preference clauses give particular advantage to the designated source and thus restrict competition. Therefore, State preference provisions shall not be used on any Federal-aid construction projects.

This policy also applies to State preference actions against materials of foreign origin, except as otherwise permitted by Federal law. Thus, States cannot give preference to in-State material sources over foreign material sources. Under the Buy America provisions, the States are permitted to expand the Buy America restrictions provided that the STA is legally authorized under State law to impose more stringent requirements.

d. <u>State Owned/Furnished/Designated Materials</u> References: 23 U.S.C. 112, 23 CFR 635.407

Current FHWA policy requires that the contractor must furnish all materials to be incorporated in the work, and the contractor shall be permitted to select the sources from which the materials are to be obtained. Exceptions to this requirement may be made when there is a definite finding, by MDOT and concurred in by Federal Highway Administration's (FHWA) Division Administrator, that it is in the public interest to require the contractor to use materials furnished by the MDOT or from sources designated by MDOT. The exception policy can best be understood by separating State-furnished materials into the categories of manufactured materials and local natural materials.

<u>Manufactured Materials</u> When the use of State-furnished manufactured materials is approved based on a public interest finding, such use must be made mandatory. The optional use of State-furnished manufactured materials is in violation of our policy prohibiting public agencies from competing with private firms. Manufactured materials to be furnished by MDOT must be acquired through competitive bidding, unless there is a public interest finding for another method, and concurred in by FHWA's Division Administrator.

<u>Local Natural Materials</u> When MDOT owns or controls a local natural materials source such as a borrow pit or a stockpile of salvaged pavement material, etc., the materials may be designated for either optional or mandatory use; however, mandatory use will require a public interest finding (PIF) and FHWA's Division Administrator's concurrence.

In order to permit prospective bidders to properly prepare their bids, the location, cost, and any conditions to be met for obtaining materials that are made available to the contractor shall be stated in the bidding documents.

Mandatory Disposal Sites Normally, the disposal site for surplus excavated materials is to be of the contractor's choosing; although, an optional site(s) may be shown in the contract provisions. A mandatory site shall be specified when there is a finding by MDOT, with the concurrence of the Division Administrator, that such placement is the most economical or that the environment would be substantially enhanced without excessive cost. Discussion of the mandatory use of a disposal site in the environmental document may serve as the basis for the public interest finding.

Summarizing FHWA policy for the mandatory use of borrow or disposal sites:

- mandatory use of either requires a public interest finding and FHWA's Division Administrator's concurrence,
- mandatory use of either may be based on environmental consideration where the environment will be substantially enhanced without excessive additional cost, and
- where the use is based on environmental considerations, the discussion in the environmental document may be used as the basis for the public interest finding.

Factors to justify a public interest finding should include such items as cost effectiveness, system integrity, and local shortages of material.

C. Standard FHWA Contract Provisions - FHWA 1273

Unless expressly otherwise provided in the Bid Documents, the following "Required Contract Provisions, Federal Aid Construction Contracts", FHWA-1273, are hereby incorporated into the Bid Documents and Contract.

Start of FHWA 1273 REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS(As revised through March 10, 1994)

I. GENERAL

- 1. These contract provisions shall apply to all work performed on the contract by the contractor's own organization and with the assistance of workers under the contractor's immediate superintendence and to all work performed on the contract by piecework, station work, or by subcontract.
- 2. Except as otherwise provided for in each section, the contractor shall insert in each subcontract all of the stipulations contained in these Required Contract Provisions, and further require their inclusion in any lower tier subcontract or purchase order that may in turn be made. The Required Contract Provisions shall not be incorporated by reference in any case. The prime contractor shall be responsible for compliance by any subcontractor or lower tier subcontractor with these Required Contract Provisions.

- 3. A breach of any of the stipulations contained in these Required Contract Provisions shall be sufficient grounds for termination of the contract.
- 4. A breach of the following clauses of the Required Contract Provisions may also be grounds for debarment as provided in 29 CFR 5.12:

```
Section I, paragraph 2;
Section IV, paragraphs 1, 2, 3, 4, and 7;
Section V, paragraphs 1 and 2a through 2g.
```

- 5. Disputes arising out of the labor standards provisions of Section IV (except paragraph 5) and Section V of these Required Contract Provisions shall not be subject to the general disputes clause of this contract. Such disputes shall be resolved in accordance with the procedures of the U.S. Department of Labor (DOL) as set forth in 29 CFR 5, 6, and 7. Disputes within the meaning of this clause include disputes between the contractor (or any of its subcontractors) and the contracting agency, the DOL, or the contractor's employees or their representatives.
- 6. Selection of Labor: During the performance of this contract, the contractor shall not:
 - a. discriminate against labor from any other State, possession, or territory of the United States (except for employment preference for Appalachian contracts, when applicable, as specified in Attachment A), or
 - b. employ convict labor for any purpose within the limits of the project unless it is labor performed by convicts who are on parole, supervised release, or probation.
- II. <u>NONDISCRIMINATION</u> (Applicable to all Federal-aid construction contracts and to all related subcontracts of \$10,000 or more.)
- 1. Equal Employment Opportunity: Equal employment opportunity (EEO) requirements not to discriminate and to take affirmative action to assure equal opportunity as set forth under laws, executive orders, rules, regulations (28 CFR 35, 29 CFR 1630 and 41 CFR 60) and orders of the Secretary of Labor as modified by the provisions prescribed herein, and imposed pursuant to 23 U.S.C. 140 shall constitute the EEO and specific affirmative action standards for the contractor's project activities under this contract. The Equal Opportunity Construction Contract Specifications set forth under 41 CFR 60-4.3 and the provisions of the American Disabilities Act of 1990 (42 U.S.C. 12101 et seq.) set forth under 28 CFR 35 and 29 CFR 1630 are incorporated by reference in this contract. In the execution of this contract, the contractor agrees to comply with the following minimum specific requirement activities of EEO:
 - a. The contractor will work with the State highway agency (SHA) and the Federal Government in carrying out EEO obligations and in their review of his/her activities under the contract.
 - b. The contractor will accept as his operating policy the following statement:

 "It is the policy of this Company to assure that applicants are employed, and that employees are treated during employment, without regard to their race, religion, sex, color, national origin, age or disability. Such action shall include: employment,

upgrading, demotion, or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship, preapprenticeship, and/or on-the-job training."

- 2. EEO Officer. The contractor will designate and make known to the SHA contracting officers an EEO Officer who will have the responsibility for and must be capable of effectively administering and promoting an active contractor program of EEO and who must be assigned adequate authority and responsibility to do so.
- 3. Dissemination of Policy. All members of the contractor's staff who are authorized to hire, supervise, promote, and discharge employees, or who recommend such action, or who are substantially involved in such action, will be made fully cognizant of, and will implement, the contractor's EEO policy and contractual responsibilities to provide EEO in each grade and classification of employment. To ensure that the above agreement will be met, the following actions will be taken as a minimum:
 - a. Periodic meetings of supervisory and personnel office employees will be conducted before the start of work and then not less often than once every six months, at which time the contractor's EEO policy and its implementation will be reviewed and explained. The meetings will be conducted by the EEO Officer.
 - b. All new supervisory or personnel office employees will be given a thorough indoctrination by the EEO Officer, covering all major aspects of the contractor's EEO obligations within thirty days following their reporting for duty with the contractor.
 - c. All personnel who are engaged in direct recruitment for the project will be instructed by the EEO Officer in the contractor's procedures for locating and hiring minority group employees.
 - d. Notices and posters setting forth the contractor's EEO policy will be placed in areas readily accessible to employees, applicants for employment and potential employees.
 - e. The contractor's EEO policy and the procedures to implement such policy will be brought to the attention of employees by means of meetings, employee handbooks, or other appropriate means.
- 4. Recruitment. When advertising for employees, the contractor will include in all advertisements for employees the notation: "An Equal Opportunity Employer." All such advertisements will be placed in publications having a large circulation among minority groups in the area from which the project work force would normally be derived.
 - a. The contractor will, unless precluded by a valid bargaining agreement, conduct systematic and direct recruitment through public and private employee referral sources likely to yield qualified minority group applicants. To meet this requirement, the contractor will identify sources of potential minority group employees, and establish with such identified sources procedures whereby minority group applicants may be referred to the contractor for employment consideration.

- b. In the event the contractor has a valid bargaining agreement providing for exclusive hiring hall referrals, he is expected to observe the provisions of that agreement to the extent that the system permits the contractor's compliance with EEO contract provisions. (The DOL has held that where implementation of such agreements have the effect of discriminating against minorities or women, or obligates the contractor to do the same, such implementation violates Executive Order 11246, as amended.)
- c. The contractor will encourage his present employees to refer minority group applicants for employment. Information and procedures with regard to referring minority group applicants will be discussed with employees.
- 5. Personnel Actions. Wages, working conditions, and employee benefits shall be established and administered, and personnel actions of every type, including hiring, upgrading, promotion, transfer, demotion, layoff, and termination, shall be taken without regard to race, color, religion, sex, national origin, age or disability. The following procedures shall be followed:
 - a. The contractor will conduct periodic inspections of project sites to insure that working conditions and employee facilities do not indicate discriminatory treatment of project site personnel.
 - b. The contractor will periodically evaluate the spread of wages paid within each classification to determine any evidence of discriminatory wage practices.
 - c. The contractor will periodically review selected personnel actions in depth to determine whether there is evidence of discrimination. Where evidence is found, the contractor will promptly take corrective action. If the review indicates that the discrimination may extend beyond the actions reviewed, such corrective action shall include all affected persons.
 - d. The contractor will promptly investigate all complaints of alleged discrimination made to the contractor in connection with his obligations under this contract, will attempt to resolve such complaints, and will take appropriate corrective action within a reasonable time. If the investigation indicates that the discrimination may affect persons other than the complainant, such corrective action shall include such other persons. Upon completion of each investigation, the contractor will inform every complainant of all of his avenues of appeal.

6. Training and Promotion.

- a. The contractor will assist in locating, qualifying, and increasing the skills of minority group and women employees, and applicants for employment.
- b. Consistent with the contractor's work force requirements and as permissible under Federal and State regulations, the contractor shall make full use of training programs, i.e., apprenticeship, and on-the-job training programs for the geographical area of contract performance. Where feasible, 25 percent of apprentices or trainees in each occupation shall be in their first year of apprenticeship or training. In the event a special provision

for training is provided under this contract, this subparagraph will be superseded as indicated in the special provision.

- c. The contractor will advise employees and applicants for employment of available training programs and entrance requirements for each.
- d. The contractor will periodically review the training and promotion potential of minority group and women employees and will encourage eligible employees to apply for such training and promotion.
- 7. Unions. If the contractor relies in whole or in part upon unions as a source of employees, the contractor will use his/her best efforts to obtain the cooperation of such unions to increase opportunities for minority groups and women within the unions, and to effect referrals by such unions of minority and female employees. Actions by the contractor either directly or through a contractor's association acting as agent will include the procedures set forth below:
 - a. The contractor will use best efforts to develop, in cooperation with the unions, joint training programs aimed toward qualifying more minority group members and women for membership in the unions and increasing the skills of minority group employees and women so that they may qualify for higher paying employment.
 - b. The contractor will use best efforts to incorporate an EEO clause into each union agreement to the end that such union will be contractually bound to refer applicants without regard to their race, color, religion, sex, national origin, age or disability.
 - c. The contractor is to obtain information as to the referral practices and policies of the labor union except that to the extent such information is within the exclusive possession of the labor union and such labor union refuses to furnish such information to the contractor, the contractor shall so certify to the SHA and shall set forth what efforts have been made to obtain such information.
 - d. In the event the union is unable to provide the contractor with a reasonable flow of minority and women referrals within the time limit set forth in the collective bargaining agreement, the contractor will, through independent recruitment efforts, fill the employment vacancies without regard to race, color, religion, sex, national origin, age or disability; making full efforts to obtain qualified and/or qualifiable minority group persons and women. (The DOL has held that it shall be no excuse that the union with which the contractor has a collective bargaining agreement providing for exclusive referral failed to refer minority employees.) In the event the union referral practice prevents the contractor from meeting the obligations pursuant to Executive Order 11246, as amended, and these special provisions, such contractor shall immediately notify the SHA.
- 8. Selection of Subcontractors, Procurement of Materials and Leasing of Equipment. The contractor shall not discriminate on the grounds of race, color, religion, sex, national origin, age or disability in the selection and retention of subcontractors, including procurement of materials and leases of equipment.

- a. The contractor shall notify all potential subcontractors and suppliers of his/her EEO obligations under this contract.
- b. Disadvantaged business enterprises (DBE), as defined in 49 CFR 23, shall have equal opportunity to compete for and perform subcontracts which the contractor enters into pursuant to this contract. The contractor will use his best efforts to solicit bids from and to utilize DBE subcontractors or subcontractors with meaningful minority group and female representation among their employees. Contractors shall obtain lists of DBE construction firms from SHA personnel.
- c. The contractor will use his best efforts to ensure subcontractor compliance with their EEO obligations.
- 9. Records and Reports. The contractor shall keep such records as necessary to document compliance with the EEO requirements. Such records shall be retained for a period of three years following completion of the contract work and shall be available at reasonable times and places for inspection by authorized representatives of the SHA and the FHWA.
 - a. The records kept by the contractor shall document the following:
 - (1) The number of minority and non-minority group members and women employed in each work classification on the project;
 - (2) The progress and efforts being made in cooperation with unions, when applicable, to increase employment opportunities for minorities and women;
 - (3) The progress and efforts being made in locating, hiring, training, qualifying, and upgrading minority and female employees; and
 - (4) The progress and efforts being made in securing the services of DBE subcontractors or subcontractors with meaningful minority and female representation among their employees.
 - b. All such records must be retained for a period of three years following completion of the contract work and shall be available at reasonable times and places for inspection by authorized representatives of the MDOT and the Federal Highway Administration.

The Contractor will submit to the MDOT a report for the month of July, indicating the total hours worked by minority, women and non-minority group employees currently engaged in each work classification required by the contract work. This information is to be reported on Form PR-1391. If on-the-job training is being required by "Training Special Provision," the Contractor will be required to furnish Form FHWA-1409. The report is required for week ending July 15 and can be obtained from MDOT, is due by week ending August 20th. This report is to be furnished directly to MDOT - Civil Rights Office.

III. <u>NONSEGREGATED FACILITIES</u> (Applicable to all Federal-aid construction contracts and to all related subcontracts of \$10,000 or more.)

- a. By submission of this bid, the execution of this contract or subcontract, or the consummation of this material supply agreement or purchase order, as appropriate, the bidder, Federal-aid construction contractor, subcontractor, material supplier, or vendor, as appropriate, certifies that the firm does not maintain or provide for its employees any segregated facilities at any of its establishments, and that the firm does not permit its employees to perform their services at any location, under its control, where segregated facilities are maintained. The firm agrees that a breach of this certification is a violation of the EEO provisions of this contract. The firm further certifies that no employee will be denied access to adequate facilities on the basis of sex or disability.
- b. As used in this certification, the term "segregated facilities" means any waiting rooms, work areas, restrooms and washrooms, restaurants and other eating areas, time clocks, locker rooms, and other storage or dressing areas, parking lots, drinking fountains, recreation or entertainment areas, transportation, and housing facilities provided for employees which are segregated by explicit directive, or are, in fact, segregated on the basis of race, color, religion, national origin, age or disability, because of habit, local custom, or otherwise. The only exception will be for the disabled when the demands for accessibility override (e.g. disabled parking).
- c. The contractor agrees that it has obtained or will obtain identical certification from proposed subcontractors or material suppliers prior to award of subcontracts or consummation of material supply agreements of \$10,000 or more and that it will retain such certifications in its files.
- IV. <u>PAYMENT OF PREDETERMINED MINIMUM WAGE</u> (Applicable to all Federal-aid construction contracts exceeding \$2,000 and to all related subcontracts, except for projects located on roadways classified as local roads or rural minor collectors, which are exempt.)

1. General:

a. All mechanics and laborers employed or working upon the site of the work will be paid unconditionally and not less often than once a week and without subsequent deduction or rebate on any account [except such payroll deductions as are permitted by regulations (29) CFR 3) issued by the Secretary of Labor under the Copeland Act (40 U.S.C. 276c)] the full amounts of wages and bona fide fringe benefits (or cash equivalents thereof) due at time of payment. The payment shall be computed at wage rates not less than those contained in the wage determination of the Secretary of Labor (hereinafter "the wage determination") which is attached hereto and made a part hereof, regardless of any contractual relationship which may be alleged to exist between the contractor or its subcontractors and such laborers and mechanics. The wage determination (including any additional classifications and wage rates conformed under paragraph 2 of this Section IV and the DOL poster (WH-1321) or Form FHWA-1495) shall be posted at all times by the contractor and its subcontractors at the site of the work in a prominent and accessible place where it can be easily seen by the workers. For the purpose of this Section, contributions made or costs reasonably anticipated for bona fide fringe benefits under Section 1(b)(2) of the Davis-Bacon Act (40 U.S.C. 276a) on behalf of laborers or mechanics are considered wages paid to such laborers or mechanics, subject to the

provisions of Section IV, paragraph 3b, hereof. Also, for the purpose of this Section, regular contributions made or costs incurred for more than a weekly period (but not less often than quarterly) under plans, funds, or programs, which cover the particular weekly period, are deemed to be constructively made or incurred during such weekly period. Such laborers and mechanics shall be paid the appropriate wage rate and fringe benefits on the wage determination for the classification of work actually performed, without regard to skill, except as provided in paragraphs 4 and 5 of this Section IV.

- b. Laborers or mechanics performing work in more than one classification may be compensated at the rate specified for each classification for the time actually worked therein, provided, that the employer's payroll records accurately set forth the time spent in each classification in which work is performed.
- c. All rulings and interpretations of the Davis-Bacon Act and related acts contained in 29 CFR 1, 3, and 5 are herein incorporated by reference in this contract.

2. Classification:

- a. The SHA contracting officer shall require that any class of laborers or mechanics employed under the contract, which is not listed in the wage determination, shall be classified in conformance with the wage determination.
- b. The contracting officer shall approve an additional classification, wage rate and fringe benefits only when the following criteria have been met:
 - (1) the work to be performed by the additional classification requested is not performed by a classification in the wage determination;
 - (2) the additional classification is utilized in the area by the construction industry;
 - (3) the proposed wage rate, including any bona fide fringe benefits, bears a reasonable relationship to the wage rates contained in the wage determination; and
 - (4) with respect to helpers, when such a classification prevails in the area in which the work is performed.
- c. If the contractor or subcontractors, as appropriate, the laborers and mechanics (if known) to be employed in the additional classification or their representatives, and the contracting officer agree on the classification and wage rate (including the amount designated for fringe benefits where appropriate), a report of the action taken shall be sent by the contracting officer to the DOL, Administrator of the Wage and Hour Division, Employment Standards Administration, Washington, D.C. 20210. The Wage and Hour Administrator, or an authorized representative, will approve, modify, or disapprove every additional classification action within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary.

- d. In the event the contractor or subcontractors, as appropriate, the laborers or mechanics to be employed in the additional classification or their representatives, and the contracting officer do not agree on the proposed classification and wage rate (including the amount designated for fringe benefits, where appropriate), the contracting officer shall refer the questions, including the views of all interested parties and the recommendation of the contracting officer, to the Wage and Hour Administrator for determination. Said Administrator, or an authorized representative, will issue a determination within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary
- e. The wage rate (including fringe benefits where appropriate) determined pursuant to paragraph 2c or 2d of this Section IV shall be paid to all workers performing work in the additional classification from the first day on which work is performed in the classification.

3. Payment of Fringe Benefits:

- a. Whenever the minimum wage rate prescribed in the contract for a class of laborers or mechanics includes a fringe benefit which is not expressed as an hourly rate, the contractor or subcontractors, as appropriate, shall either pay the benefit as stated in the wage determination or shall pay another bona fide fringe benefit or an hourly case equivalent thereof.
- b. If the contractor or subcontractor, as appropriate, does not make payments to a trustee or other third person, he/she may consider as a part of the wages of any laborer or mechanic the amount of any costs reasonably anticipated in providing bona fide fringe benefits under a plan or program, provided, that the Secretary of Labor has found, upon the written request of the contractor, that the applicable standards of the Davis-Bacon Act have been met. The Secretary of Labor may require the contractor to set aside in a separate account assets for the meeting of obligations under the plan or program.
- 4. Apprentices and Trainees (Programs of the U.S. DOL) and Helpers:

a. Apprentices:

- (1) Apprentices will be permitted to work at less than the predetermined rate for the work they performed when they are employed pursuant to and individually registered in a bona fide apprenticeship program registered with the DOL, Employment and Training Administration, Bureau of Apprenticeship and Training, or with a State apprenticeship agency recognized by the Bureau, or if a person is employed in his/her first 90 days of probationary employment as an apprentice in such an apprenticeship program, who is not individually registered in the program, but who has been certified by the Bureau of Apprenticeship and Training or a State apprenticeship agency (where appropriate) to be eligible for probationary employment as an apprentice.
- (2) The allowable ratio of apprentices to journeyman-level employees on the job site in any craft classification shall not be greater than the ratio permitted to the contractor

as to the entire work force under the registered program. Any employee listed on a payroll at an apprentice wage rate, who is not registered or otherwise employed as stated above, shall be paid not less than the applicable wage rate listed in the wage determination for the classification of work actually performed. In addition, any apprentice performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed. Where a contractor or subcontractor is performing construction on a project in a locality other than that in which its program is registered, the ratios and wage rates (expressed in percentages of the journeyman-level hourly rate) specified in the contractor's or subcontractor's registered program shall be observed.

- (3) Every apprentice must be paid at not less than the rate specified in the registered program for the apprentice's level of progress, expressed as a percentage of the journeyman-level hourly rate specified in the applicable wage determination. Apprentices shall be paid fringe benefits in accordance with the provisions of the apprenticeship program. If the apprenticeship program does not specify fringe benefits, apprentices must be paid the full amount of fringe benefits listed on the wage determination for the applicable classification. If the Administrator for the Wage and Hour Division determines that a different practice prevails for the applicable apprentice classification, fringes shall be paid in accordance with that determination.
- (4) In the event the Bureau of Apprenticeship and Training, or a State apprenticeship agency recognized by the Bureau, withdraws approval of an apprenticeship program, the contractor or subcontractor will no longer be permitted to utilize apprentices at less than the applicable predetermined rate for the comparable work performed by regular employees until an acceptable program is approved.

b. Trainees:

- (1) Except as provided in 29 CFR 5.16, trainees will not be permitted to work at less than the predetermined rate for the work performed unless they are employed pursuant to and individually registered in a program which has received prior approval, evidenced by formal certification by the DOL, Employment and Training Administration.
- (2) The ratio of trainees to journeyman-level employees on the job site shall not be greater than permitted under the plan approved by the Employment and Training Administration. Any employee listed on the payroll at a trainee rate who is not registered and participating in a training plan approved by the Employment and Training Administration shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed. In addition, any trainee performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed.

- (3) Every trainee must be paid at not less than the rate specified in the approved program for his/her level of progress, expressed as a percentage of the journeyman-level hourly rate specified in the applicable wage determination. Trainees shall be paid fringe benefits in accordance with the provisions of the trainee program. If the trainee program does not mention fringe benefits, trainees shall be paid the full amount of fringe benefits listed on the wage determination unless the Administrator of the Wage and Hour Division determines that there is an apprenticeship program associated with the corresponding journeyman-level wage rate on the wage determination which provides for less than full fringe benefits for apprentices, in which case such trainees shall receive the same fringe benefits as apprentices.
- (4) In the event the Employment and Training Administration withdraws approval of a training program, the contractor or subcontractor will no longer be permitted to utilize trainees at less than the applicable predetermined rate for the work performed until an acceptable program is approved.
- c. Helpers. Helpers will be permitted to work on a project if the helper classification is specified and defined on the applicable wage determination or is approved pursuant to the conformance procedure set forth in Section IV.2. Any worker listed on a payroll at a helper wage rate, who is not a helper under a approved definition, shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed.
- 5. Apprentices and Trainees (Programs of the U.S. DOT). Apprentices and trainees working under apprenticeship and skill training programs which have been certified by the Secretary of Transportation as promoting EEO in connection with Federal-aid highway construction programs are not subject to the requirements of paragraph 4 of this Section IV. The straight time hourly wage rates for apprentices and trainees under such programs will be established by the particular programs. The ratio of apprentices and trainees to journeymen shall not be greater than permitted by the terms of the particular program.
- 6. Withholding. The SHA shall upon its own action or upon written request of an authorized representative of the DOL withhold, or cause to be withheld, from the contractor or subcontractor under this contract or any other Federal contract with the same prime contractor, or any other Federally-assisted contract subject to Davis-Bacon prevailing wage requirements which is held by the same prime contractor, as much of the accrued payments or advances as may be considered necessary to pay laborers and mechanics, including apprentices, trainees, and helpers, employed by the contractor or any subcontractor the full amount of wages required by the contract. In the event of failure to pay any laborer or mechanic, including any apprentice, trainee, or helper, employed or working on the site of the work, all or part of the wages required by the contract, the SHA contracting officer may, after written notice to the contractor, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds until such violations have ceased.
- 7. Overtime Requirements. No contractor or subcontractor contracting for any part of the contract work which may require or involve the employment of laborers, mechanics, watchmen, or guards (including apprentices, trainees, and helpers described in paragraphs 4

and 5 above) shall require or permit any laborer, mechanic, watchman, or guard in any workweek in which he/she is employed on such work, to work in excess of 40 hours in such workweek unless such laborer, mechanic, watchman, or guard receives compensation at a rate not less than one-and-one-half times his/her basic rate of pay for all hours worked in excess of 40 hours in such workweek.

- 8. Violation. Liability for Unpaid Wages; Liquidated Damages: In the event of any violation of the clause set forth in paragraph 7 above, the contractor and any subcontractor responsible thereof shall be liable to the affected employee for his/her unpaid wages. In addition, such contractor and subcontractor shall be liable to the United States (in the case of work done under contract for the District of Columbia or a territory, to such District or to such territory) for liquidated damages. Such liquidated damages shall be computed with respect to each individual laborer, mechanic, watchman, or guard employed in violation of the clause set forth in paragraph 7, in the sum of \$10 for each calendar day on which such employee was required or permitted to work in excess of the standard work week of 40 hours without payment of the overtime wages required by the clause set forth in paragraph 7.
- 9. Withholding for Unpaid Wages and Liquidated Damages. The SHA shall upon its own action or upon written request of any authorized representative of the DOL withhold, or cause to be withheld, from any monies payable on account of work performed by the contractor or subcontractor under any such contract or any other Federal contract with the same prime contractor, or any other Federally-assisted contract subject to the Contract Work Hours and Safety Standards Act, which is held by the same prime contractor, such sums as may be determined to be necessary to satisfy any liabilities of such contractor or subcontractor for unpaid wages and liquidated damages as provided in the clause set forth in paragraph 8 above.
- V. <u>STATEMENTS AND PAYROLLS</u> (Applicable to all Federal-aid construction contracts exceeding \$2,000 and to all related subcontracts, except for projects located on roadways classified as local roads or rural collectors, which are exempt.)
- 1. Compliance with Copeland Regulations (29 CFR 3). The contractor shall comply with the Copeland Regulations of the Secretary of Labor which are herein incorporated by reference.
- 2. Payrolls and Payroll Records:
 - a. Payrolls and basic records relating thereto shall be maintained by the contractor and each subcontractor during the course of the work and preserved for a period of 3 years from the date of completion of the contract for all laborers, mechanics, apprentices, trainees, watchmen, helpers, and guards working at the site of the work.
 - b. The payroll records shall contain the name, social security number, and address of each such employee; his or her correct classification; hourly rates of wages paid (including rates of contributions or costs anticipated for bona fide fringe benefits or cash equivalent thereof the types described in Section 1(b)(2)(B) of the Davis Bacon Act); daily and weekly number of hours worked; deductions made; and actual wages paid. In addition, for Appalachian contracts, the payroll records shall contain a notation indicating whether the employee does, or does not, normally reside in the labor area as defined in

Attachment A, paragraph 1. Whenever the Secretary of Labor, pursuant to Section IV, paragraph 3b, has found that the wages of any laborer or mechanic include the amount of any costs reasonably anticipated in providing benefits under a plan or program described in Section 1(b)(2)(B) of the Davis Bacon Act, the contractor and each subcontractor shall maintain records which show that the commitment to provide such benefits is enforceable, that the plan or program is financially responsible, that the plan or program has been communicated in writing to the laborers or mechanics affected, and show the cost anticipated or the actual cost incurred in providing benefits. Contractors or subcontractors employing apprentices or trainees under approved programs shall maintain written evidence of the registration of apprentices and trainees, and ratios and wage rates prescribed in the applicable programs.

- c. Each contractor and subcontractor shall furnish, each week in which any contract work is performed, to the SHA resident engineer a payroll of wages paid each of its employees (including apprentices, trainees, and helpers, described in Section IV, paragraphs 4 and 5, and watchmen and guards engaged on work during the preceding weekly payroll period). The payroll submitted shall set out accurately and completely all of the information required to be maintained under paragraph 2b of this Section V. This information may be submitted in any form desired. Optional Form WH-347 is available for this purpose and may be purchased from the Superintendent of Documents (Federal stock number 029-005-0014-1), U.S. Government Printing Office, Washington, D.C. 20402. The prime contractor is responsible for the submission of copies of payrolls by all subcontractors.
- d. Each payroll submitted shall be accompanied by a "Statement of Compliance," signed by the contractor or subcontractor or his/her agent who pays or supervises the payment of the persons employed under the contract and shall certify the following:
 - (1) that the payroll for the payroll period contains the information required to be maintained under paragraph 2b of this Section V and that such information is correct and complete;
 - (2) that such laborer or mechanic (including each helper, apprentice, and trainee) employed on the contract during the payroll period has been paid the full weekly wages earned, without rebate, either directly or indirectly, and that no deductions have been made either directly or indirectly from the full wages earned, other than permissible deductions as set forth in the Regulations, 29 CFR 3;
 - (3) that each laborer or mechanic has been paid not less that the applicable wage rate and fringe benefits or cash equivalent for the classification of worked performed, as specified in the applicable wage determination incorporated into the contract.
- e. The weekly submission of a properly executed certification set forth on the reverse side of Optional Form WH-347 shall satisfy the requirement for submission of the "Statement of Compliance" required by paragraph 2d of this Section V.
- f. The falsification of any of the above certifications may subject the contractor to civil or criminal prosecution under 18 U.S.C. 1001 and 31 U.S.C. 231.

g. The contractor or subcontractor shall make the records required under paragraph 2b of this Section V available for inspection, copying, or transcription by authorized representatives of the SHA, the FHWA, or the DOL, and shall permit such representatives to interview employees during working hours on the job. If the contractor or subcontractor fails to submit the required records or to make them available, the SHA, the FHWA, the DOL, or all may, after written notice to the contractor, sponsor, applicant, or owner, take such actions as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds. Furthermore, failure to submit the required records upon request or to make such records available may be grounds for debarment action pursuant to 29 CFR 5.12.

VI. RECORD OF MATERIALS, SUPPLIES, AND LABOR

- 1. On all Federal-aid contracts on the National Highway System, except those which provide solely for the installation of protective devices at railroad grade crossings, those which are constructed on a force account or direct labor basis, highway beautification contracts, and contracts for which the total final construction cost for roadway and bridge is less than \$1,000,000 (23 CFR 635) the contractor shall:
 - a. Become familiar with the list of specific materials and supplies contained in Form FHWA-47, "Statement of Materials and Labor Used by Contractor of Highway Construction Involving Federal Funds," prior to the commencement of work under this contract.
 - b. Maintain a record of the total cost of all materials and supplies purchased for and incorporated in the work, and also of the quantities of those specific materials and supplies listed on Form FHWA-47, and in the units shown on Form FHWA-47.
 - c. Furnish, upon the completion of the contract, to the SHA resident engineer on Form FHWA-47 together with the data required in paragraph 1b relative to materials and supplies, a final labor summary of all contract work indicating the total hours worked and the total amount earned.
- 2. At the prime contractor's option, either a single report covering all contract work or separate reports for the contractor and for each subcontract shall be submitted.

VII. SUBLETTING OR ASSIGNING THE CONTRACT

- 1. The contractor shall perform with its own organization contract work amounting to not less than 30 percent (or a greater percentage if specified elsewhere in the contract) of the total original contract price, excluding any specialty items designated by the State. Specialty items may be performed by subcontract and the amount of any such specialty items performed may be deducted from the total original contract price before computing the amount of work required to be performed by the contractor's own organization (23 CFR 635).
 - a. "Its own organization" shall be construed to include only workers employed and paid directly by the prime contractor and equipment owned or rented by the prime contractor,

with or without operators. Such term does not include employees or equipment of a subcontractor, assignee, or agent of the prime contractor.

- b. "Specialty Items" shall be construed to be limited to work that requires highly specialized knowledge, abilities, or equipment not ordinarily available in the type of contracting organizations qualified and expected to bid on the contract as a whole and in general are to be limited to minor components of the overall contract.
- 2. The contract amount upon which the requirements set forth in paragraph 1 of Section VII is computed includes the cost of material and manufactured products which are to be purchased or produced by the contractor under the contract provisions.
- 3. The contractor shall furnish (a) a competent superintendent or supervisor who is employed by the firm, has full authority to direct performance of the work in accordance with the contract requirements, and is in charge of all construction operations (regardless of who performs the work) and (b) such other of its own organizational resources (supervision, management, and engineering services) as the SHA contracting officer determines is necessary to assure the performance of the contract.
- 4. No portion of the contract shall be sublet, assigned or otherwise disposed of except with the written consent of the SHA contracting officer, or authorized representative, and such consent when given shall not be construed to relieve the contractor of any responsibility for the fulfillment of the contract. Written consent will be given only after the SHA has assured that each subcontract is evidenced in writing and that it contains all pertinent provisions and requirements of the prime contract.

VIII. SAFETY: ACCIDENT PREVENTION

- 1. In the performance of this contract the contractor shall comply with all applicable Federal, State, and local laws governing safety, health, and sanitation (23 CFR 635). The contractor shall provide all safeguards, safety devices and protective equipment and take any other needed actions as it determines, or as the SHA contracting officer may determine, to be reasonably necessary to protect the life and health of employees on the job and the safety of the public and to protect property in connection with the performance of the work covered by the contract.
- 2. It is a condition of this contract, and shall be made a condition of each subcontract, which the contractor enters into pursuant to this contract, that the contractor and any subcontractor shall not permit any employee, in performance of the contract, to work in surroundings or under conditions which are unsanitary, hazardous or dangerous to his/her health or safety, as determined under construction safety and health standards (29 CFR 1926) promulgated by the Secretary of Labor, in accordance with Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C. 333).
- 3. Pursuant to 29 CFR 1926.3, it is a condition of this contract that the Secretary of Labor or authorized representative thereof, shall have right of entry to any site of contract performance to inspect or investigate the matter of compliance with the construction safety and health

standards and to carry out the duties of the Secretary under Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C. 333).

IX. <u>FALSE STATEMENTS CONCERNING HIGHWAY PROJECTS</u> In order to assure high quality and durable construction in conformity with approved plans and specifications and a high degree of reliability on statements and representations made by engineers, contractors, suppliers, and workers on Federal-aid highway projects, it is essential that all persons concerned with the project perform their functions as carefully, thoroughly, and honestly as possible. Willful falsification, distortion, or misrepresentation with respect to any facts related to the project is a violation of Federal law. To prevent any misunderstanding regarding the seriousness of these and similar acts, the following notice shall be posted on each Federal-aid highway project (23 CFR 635) in one or more places where it is readily available to all persons concerned with the project:

NOTICE TO ALL PERSONNEL ENGAGED ON FEDERAL-AID HIGHWAY PROJECTS

18 U.S.C. 1020 reads as follows:

"Whoever, being an officer, agent, or employee of the United States, or of any State or Territory, or whoever, whether a person, association, firm, or corporation, knowingly makes any false statement, false representation, or false report as to the character, quality, quantity, or cost of the material used or to be used, or the quantity or quality of the work performed or to be performed, or the cost thereof in connection with the submission of plans, maps, specifications, contracts, or costs of construction on any highway or related project submitted for approval to the Secretary of Transportation; or

Whoever knowingly makes any false statement, false representation, false report or false claim with respect to the character, quality, quantity, or cost of any work performed or to be performed, or materials furnished or to be furnished, in connection with the construction of any highway or related project approved by the Secretary of Transportation; or

Whoever knowingly makes any false statement or false representation as to material fact in any statement, certificate, or report submitted pursuant to provisions of the Federal-aid Roads Act approved July 1, 1916, (39 Stat. 355), as amended and supplemented;

Shall be fined not more that \$10,000 or imprisoned not more than 5 years or both."

X. <u>IMPLEMENTATION OF CLEAN AIR ACT AND FEDERAL WATER POLLUTION CONTROL ACT</u> (Applicable to all Federal-aid construction contracts and to all related subcontracts of \$100,000 or more.)

By submission of this bid or the execution of this contract, or subcontract, as appropriate, the bidder, Federal-aid construction contractor, or subcontractor, as appropriate, will be deemed to have stipulated as follows:

1. That any facility that is or will be utilized in the performance of this contract, unless such contract is exempt under the Clean Air Act, as amended (42 U.S.C. 1857 et seq., as amended by Pub.L. 91-604), and under the Federal Water Pollution Control Act, as amended (33 U.S.C. 1251 et seq., as amended by Pub.L. 92-500), Executive Order 11738, and regulations

in implementation thereof (40 CFR 15) is not listed, on the date of contract award, on the U.S. Environmental Protection Agency (EPA) List of Violating Facilities pursuant to 40 CFR 15.20.

- 2. That the firm agrees to comply and remain in compliance with all the requirements of Section 114 of the Clean Air Act and Section 308 of the Federal Water Pollution Control Act and all regulations and guidelines listed thereunder.
- 3. That the firm shall promptly notify the SHA of the receipt of any communication from the Director, Office of Federal Activities, EPA, indicating that a facility that is or will be utilized for the contract is under consideration to be listed on the EPA List of Violating Facilities.
- 4. That the firm agrees to include or cause to be included the requirements of paragraph 1 through 4 of this Section X in every nonexempt subcontract, and further agrees to take such action as the government may direct as a means of enforcing such requirements.

XI. <u>CERTIFICATION REGARDING DEBARMENT, SUSPENSION, INELIGIBILITY AND VOLUNTARY EXCLUSION</u>

- 1. Instructions for Certification Primary Covered Transactions: (Applicable to all Federal-aid contracts 49 CFR 29)
 - a. By signing and submitting this proposal, the prospective primary participant is providing the certification set out below.
 - b. The inability of a person to provide the certification set out below will not necessarily result in denial of participation in this covered transaction. The prospective participant shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective primary participant to furnish a certification or an explanation shall disqualify such a person from participation in this transaction.
 - c. The certification in this clause is a material representation of fact upon which reliance was placed when the department or agency determined to enter into this transaction. If it is later determined that the prospective primary participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the department or agency may terminate this transaction for cause of default.
 - d. The prospective primary participant shall provide immediate written notice to the department or agency to whom this proposal is submitted if any time the prospective primary participant learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.
 - e. The terms "covered transaction," "debarred," "suspended," "ineligible," "lower tier covered transaction," "participant," "person," "primary covered transaction," "principal," "proposal," and "voluntarily excluded," as used in this clause, have the meanings set out

in the Definitions and Coverage sections of rules implementing Executive Order 12549. You may contact the department or agency to which this proposal is submitted for assistance in obtaining a copy of those regulations.

- f. The prospective primary participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency entering into this transaction.
- g. The prospective primary participant further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," provided by the department or agency entering into this covered transaction, without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions.
- h. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant may decide the method and frequency by which it determines the eligibility of its principals. Each participant may, but is not required to, check the nonprocurement portion of the "Lists of Parties Excluded From Federal Procurement or Nonprocurement Programs" (Nonprocurement List) which is compiled by the General Services Administration.
- i. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
- j. Except for transactions authorized under paragraph f of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency may terminate this transaction for cause or default.

Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Primary Covered Transactions

- 1. The prospective primary participant certifies to the best of its knowledge and belief, that it and its principals:
 - a. Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by any Federal department or agency;
 - b. Have not within a 3-year period preceding this proposal been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or

local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements, or receiving stolen property;

- c. Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offenses enumerated in paragraph 1b of this certification; and
- d. Have not within a 3-year period preceding this application/proposal had one or more public transactions (Federal, State or local) terminated for cause or default.

2. <u>Instructions for Certification - Lower Tier Covered Transactions</u>: (Applicable to all subcontracts, purchase orders and other lower tier transactions of \$25,000 or more - 49 CFR 29)

- a. By signing and submitting this proposal, the prospective lower tier is providing the certification set out below.
- b. The certification in this clause is a material representation of fact upon which reliance was placed when this transaction was entered into. If it is later determined that the prospective lower tier participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the department, or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment.
- c. The prospective lower tier participant shall provide immediate written notice to the person to which this proposal is submitted if at any time the prospective lower tier participant learns that its certification was erroneous by reason of changed circumstances.
- d. The terms "covered transaction," "debarred," "suspended," "ineligible," "primary covered transaction," "participant," "person," "principal," "proposal," and "voluntarily excluded," as used in this clause, have the meanings set out in the Definitions and Coverage sections of rules implementing Executive Order 12549. You may contact the person to which this proposal is submitted for assistance in obtaining a copy of those regulations.
- e. The prospective lower tier participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency with which this transaction originated.
- f. The prospective lower tier participant further agrees by submitting this proposal that it will include this clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions.

- g. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant may decide the method and frequency by which it determines the eligibility of its principals. Each participant may, but is not required to, check the Nonprocurement List.
- h. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
- i. Except for transactions authorized under paragraph e of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment.

Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion--Lower Tier Covered Transactions:

- 1. The prospective lower tier participant certifies, by submission of this proposal, that neither it nor its principals is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participation in this transaction by any Federal department or agency.
- 2. Where the prospective lower tier participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

XII. <u>CERTIFICATION REGARDING USE OF CONTRACT FUNDS FOR LOBBYING</u> (Applicable to all Federal-aid construction contracts and to all related subcontracts which exceed \$100,000 - 49 CFR 20)

- 1. The prospective participant certifies, by signing and submitting this bid or proposal, to the best of his or her knowledge and belief, that:
 - a. No Federal appropriated funds have been paid or will be paid, by or on behalf of the undersigned, to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with the awarding of any Federal contract, the making of any Federal grant, the making of any Federal loan, the entering into of any cooperative agreement, and the extension, continuation, renewal, amendment, or modification of any Federal contract, grant, loan, or cooperative agreement.
 - b. If any funds other than Federal appropriated funds have been paid or will be paid to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a

Member of Congress in connection with this Federal contract, grant, loan, or cooperative agreement, the undersigned shall complete and submit Standard Form-LLL, "Disclosure Form to Report Lobbying," in accordance with its instructions.

- 2. This certification is a material representation of fact upon which reliance was placed when this transaction was made or entered into. Submission of this certification is a prerequisite for making or entering into this transaction imposed by 31 U.S.C. 1352. Any person who fails to file the required certification shall be subject to a civil penalty of not less than \$10,000 and not more than \$100,000 for each such failure.
- 3. The prospective participant also agrees by submitting his or her bid or proposal that he or she shall require that the language of this certification be included in all lower tier subcontracts, which exceed \$100,000 and that all such recipients shall certify and disclose accordingly.

End of FHWA 1273



PIN #: 15114.00 **Town: Gardiner to Brunswick** Environmental Office Contact: Laurie Rowe (laurie.rowe@maine.gov) 215-5072 **Coordination & Permits Manager: Matt Steele** Date Submitted: 3/14/08 Database/Projex 🗵 **Section 106 and Tribal Consultation** PA ⊠ Approved □ Architectural Resources Applicable□ Archeological Resources PA 🗵 Applicable□ Approved □ Tribal Consultation Tribal Letters Sent □ Approved □ No Town & Local Hist. Society Contacted Yes \square **☒** 4(f) and 6(f) Section 4(f) Are there Right of Way Takes or Easements on Public Park Property ☐ Yes 区 No Are there Right of Way Takes or Easements on Public Recreational Property ☐ Yes ⊠ No Are there Right of Way Takes or Easements on Public Wildlife Refuge Property ☐ Yes 区 No Are there Right of Way Takes or Easements on Historic Eligible or Listed Property □Yes ⊠ No Are there Right of Way Takes or Easements on Property within a Historic District □Yes ⊠ No Has MHPC Determined an Adverse Effect □Yes ⊠ No Is a Programmatic or Full 4(f) Document Required □Yes ⊠ No LAWCON 6(f) N/A ⊠ Applicable□ Approved □ **▼ FEMA** GIS Floodplains Checked □ N/A ⊠ Applicable□ Approved □ Maine Department of Inland Fisheries and Wildlife (MDIFW) Essential Habitat GIS Essential Habitats Checked⊠ Eagle Nest N/A ⊠ Applicable □ Approved □ Piping Plover N/A ⊠ Applicable □ Approved □ Roseate Tern N/A ⊠ Applicable□ Approved □ **☒** Maine Department of Conservation/ Public Lands, Submerged Land Lease N/A ⊠ Applicable □ Not Applicable ⊠ No permit Required □ Notice Approved □ Permit Approved □ Maine Department of Environmental Protection (MDEP) Site Location of Development N/A ⊠ Applicable □ Approved □ Maine Department of Environmental Protection (MDEP), Natural Resource Protection Act No permit required □ Exempt \square (Must use erosion and sediment control and not block fish passage.) **PBR** Approved ⊠ Tier 1 Approved □ Tier 2 □ Approved □ Individual Approved □ 🖾 Army Corps of Engineers (ACOE), Section 10 of the Rivers and Harbors Act and Section 404 of the Clean Water Act. No permit required Category 1-NR□ Approved □ Category 2⊠ Approved ⊠ Category 3□ Approved □ **NOTE**: If project requires a Category 2 or 3 Permit from the ACOE, then the MaineDOT Resident **must** fill out a "Work Start Notification Form" and a "Compliance Certification Form" (when project has been completed) and send them to the address listed on the forms **☒ IN-STREAM TIMING RESTRICTIONS:** 105 Special Provision **☒** Dates instream work is allowed: June 1st to October 1st NEPA Complete

☑ Special Provision 656, Erosion Control Plan ☑ Special Provision 203, Dredge Spec and/or Hazardous Waste Spec

DEPARTMENT OF ENVIRONMENTAL PROTECTION (DEP) PERMIT BY RULE NOTIFICATION FORM

(For use with DEP Regulation, Chapter 305)

MDOT PIN: 15019:00 15114.00

Name of Applicant: State of Maine Department of Transportation

Name of Contact: Laurie Rowe

Mailing Address: 16 Station State House

State: Me. Town/City: Augusta

Zip Code: 04330-0016

Daytime Telephone #: 624-3043 Name of Wetland, Water Body or Stream: Unnamed Streams

Detailed Directions to Site: Project is located on I-295, beginning 0.03 miles south of Exit 49 off ramp in Gardiner extending to 0.08 miles north of the Exit 51 off ramp in Brunswick. REOWA 786324011

Town/City/Gardiner to Brunswick

Map #: N/A

County: Kennebec-Cumberland

Description of Project: Project scope rubbleizing the existing concrete surface and placing new pavement, update and new guardrail and guardrail end treatments, drainage updates including removing and resetting 4 instream culvert ends, and slipline of an instream culvert. New guardrail and endtreatments to be safety compliant. The project will be performed in accordance with erosion control measures conforming with the latest versions of the State of Maine Department of Transportation Standard Specifications for Highways and Bridges and the Department of Transportation's Best Management Practices for Erosion and Sediment Control.

200 5/2006	200	WOODS AND SERVICE	000000	
Part	of a	larger	DIO	ect?

□Yes ⊠No

(CHECK ONE) This project...

does □ does not ...involve work below mean low water.

I am filing notice of my intent to carry out work which meets the requirements for Permit By Rule (PBR) under DEP Regulation, Chapter 305. I have a copy of PBR Sections checked below. I have read and will comply with all of the standards.

☐Sec. (2) Soil Disturbance

☐Sec. (8) Shoreline stabilization

□Sec. (14) Piers, Wharves & Pilings

☐Sec. (3) Intake Pipes

☐Sec. (9) Utility Crossing

☐Sec. (15) Public Boat Ramps

☐Sec. (4) Replacement of Structures

☐Sec. (10) Stream Crossing

□Sec. (16) Coastal Sand Dune Projects

☐Sec. (5) REPEALED

⊠Sec. (11) State Transport. Facilities

□Sec. (17) Transfers/Permit Extension

☐Sec. (6) Movement of Rocks or Vegetation

☐Sec. (12) Restoration of Natural Areas

☐Sec. (18) Maintenance Dredging

☐Sec. (7) Outfall Pipes

□Sec. (13) F&W Creation/Enhance/Water Quality Improvement

I authorize staff of the Departments of Environmental Protection, Inland Fisheries & Wildlife, and Marine Resources to access the project site for the purpose of determining compliance with the rules. I also understand that this permit is not valid until approved by the Department or 14 days after receipt by the Department, whichever is less.

I have attached all of the following required submittals. NOTIFICATION FORMS CANNOT BE ACCEPTED WITHOUT THE NECESSARY ATTACHMENTS:

A \$55 (non-refundable) payment shall be done by internal billing.

Attach a U.S.G.S. topo map or Maine Atlas & Gazetteer map with the project site clearly marked.

Attach photographs showing existing site conditions (unless not required under standards).

Signature of Applicant:

Kenneth L Sweeney, Deputy Chief Engineer

Date: 2 15 200B

Keep the bottom copy as a record of permit. Send the form with attachments via certified mail to the Maine Dept. of Environmental Protection at the appropriate regional office listed below. The DEP will send a copy to the Town Office as evidence of the DEP's receipt of notification. No further authorization by DEP will be issued after receipt of notice. Permits are valid for two years. Work carried out in violation of any standard is subject to enforcement action.

AUGUSTA DEP STATE HOUSE STATION 17 AUGUSTA, ME 04333-0017 (207)287-2111 PORTLAND DEP 312 BANGOR DEP 106 HOGAN ROAD BANGOR, ME CANCO ROAD PORTLAND, ME 04103 (207)822-6300 PRESQUE ISLE DEP 1235 CENTRAL DRIVE PRESQUE ISLE, ME 04769 (207)764-0477 04401 (207)941-4570

OFFICE USE ONLY

\$55.00

Roo shilas

Staff CAC 2/26/08

245



MAINE PROJECT OFFICE

DEPARTMENT OF THE ARMY
NEW ENGLAND DISTRICT, CORPS OF ENGINEERS
696 VIRGINIA ROAD
CONCORD, MASSACHUSETTS 01742-2751

MAINE PROGRAMMATIC GENERAL PERMIT (PGP) AUTHORIZATION LETTER AND SCREENING SUMMARY

OFFICE OF ENVIRONMENTAL SERVICES

MAINE DEPT. OF TRANSPORTATION 16 STATE HOUSE STATION AUGUSTA, MAINE 04333	CORPS PERMIT #_ CORPS PGP ID#_	NAE-2008-00584 08-055 PBR
7.50	STATE ID#	PDR
DESCRIPTION OF WORK:		
Place fill below the ordinary high water line of several u Maine in order to replace or repair six existing deteriors plans entitled "I-295 CULVERT REPLACEMENTS, BRUNS to 1,000 s.f. (0.022 acres) of stream bed will be impacted	ated culverts beneath I-295as	
DOT PIN: 15919.00 - NEW PIN 15114.00	25 25 25 25 25 25 25 25 25 25 25 25 25 2	
LAT/LONG COORDINATES : 43.9584455° N 69.9	9617446° W USGS QUAI	BRUNSWICK, ME
I. CORPS DETERMINATION:		
Based on our review of the information you provided, we have determined th waters and wetlands of the United States. Your work is therefore authoriz Permit, the Maine Programmatic General Permit (PGP).	nat your project will have only minimal in- ed by the U.S. Army Corps of Engine	dividual and cumulative impacts on ers under the enclosed Federal
You must perform the activity authorized herein in compliance with all the ter and any conditions placed on the State 401 Water Quality Certification include including the PGP conditions beginning on page 7, to familiarize yourself with requirements; therefore you should be certain that whoever does the work fur conditions of this authorization with your contractor to ensure the contractor of	ding any required mitigation]. Please review is contents. You are responsible for cultivations and conditions. You can accomplish the work in a manner the	iew the enclosed PGP carefully, complying with all of the PGP ou may wish to discuss the at conforms to all requirements.
If you change the plans or construction methods for work within our jurisdiction authorization. This office must approve any changes before you undertake the	on, please contact us immediately to dis hem.	cuss modification of this
Condition 38 of the PGP (page 15) provides one year for completion of work expiration of the PGP on October 11, 2010. You will need to apply for reauth October 11, 2011,	that has commenced or is under contraction for any work within Corps juris	ct to commence prior to the diction that is not completed by
No work may be started unless and until all other required local, State and Fe limited to a Flood Hazard Development Permit issued by the town if neo and allow us to inspect the project. Hence, you must complete and return the weeks before the anticipated starting date. (For projects requiring mitigation,	cessary. Also, this permit requires you to e attached Work Start Notification Form	to notify us before beginning work
II. STATE ACTIONS: PENDING [X]. ISSUED[]. DENIED [
APPLICATION TYPE: PBR: X TIER 1: TIER 2: TIER	3: DMR LEAS	E: NA:
III. FEDERAL ACTIONS:		
JOINT PROCESSING MEETING: 2/21/08 LEVEL OF	F REVIEW: CATEGORY 1:	CATEGORY 2: X
AUTHORITY (Based on a review of plans and/or State/Federal applications	s): SEC 10, 404X_ 10/4	104, 103
EXCLUSIONS: The exclusionary criteria identified in the general permit do	not apply to this project.	
ESSENTIAL FISH HABITAT (EFH): EFH PRESENT Y N (CIRCL IF YES: Based on the terms and conditions of the PGP, which are intended to environmental impacts, the Corps of Engineers has preliminary determined the identified under the Magnunson-Stevens Fisheries Conservation and Manager	o ensure that authorized projects cause	no more than minimal minimal adverse effects to EFH
AGENCY OBJECTIONS/COMMENTS: EPA NO USF&WS NO . N	NMFS_NO_, SHPO_NO_, THPO_NO	2
If you have any questions on this matter, please contact my staff at 207-623-8	8367 at our Manchester, Maine Project of	Office. 3 Mar 2008
	NK J. DEL GIUDICE DAT F, PERMITS & ENFORCEMENT B	E


REGULATORY DIVISION


246




ADDITIONAL CONDITIONS FOR DEPARTMENT OF THE ARMY PROGRAMMATIC GENERAL PERMIT NO. NAE-2008-00584

- 1. This authorization requires you to 1) notify us before beginning work so we may inspect the project, and 2) submit a Compliance Certification Form. You must complete and return the enclosed Work Start Notification Form(s) to this office at least two weeks before the anticipated starting date. You must complete and return the enclosed Compliance Certification Form within one month following the completion of the authorized work and any required mitigation (but not mitigation monitoring, which requires separate submittals).
- 2. The permittee shall assure that a copy of this permit is at the work site whenever work is being performed and that all personnel performing work at the site of the work authorized by this permit are fully aware of the terms and conditions of the permit. This permit, including its drawings and any appendices and other attachments, shall be made a part of any and all contracts and sub-contracts for work which affects areas of Corps of Engineers' jurisdiction at the site of the work authorized by this permit. This shall be done by including the entire permit in the specifications for the work. If the permit is issued after construction specifications but before receipt of bids or quotes, the entire permit shall be included as an addendum to the specifications. The term "entire permit" includes permit amendments. Although the permittee may assign various aspects of the work to different contractors or sub-contractors, all contractors and sub-contractors shall be obligated by contract to comply with all environmental protection provisions of the entire permit, and no contract or sub-contract shall require or allow unauthorized work in areas of Corps of Engineers jurisdiction.
- 3. Adequate sedimentation and erosion control devices, such as geotextile silt fences or other devices capable of filtering the fines involved, shall be installed and properly maintained to minimize impacts during construction. These devices must be removed upon completion of work and stabilization of disturbed areas. The sediment collected by these devices must also be removed and placed upland, in a manner that will prevent its later erosion and transport to a waterway or wetland.
- 4. All exposed soils resulting from the construction will be promptly seeded and mulched in order to achieve vegetative stabilization.
- 5. Instream work shall be conducted between May 21 and October 1 in order to minimize impacts to fisheries and local water quality.









15917 Project Name: Gordiner - Branswick Investigator's Name: R Charley D. Gravel Additional Notes: on unstroom side in topsnam XI upstream


Profile of Culvert



Cross Section of Culvert

Plan View of Culvert





	All dimensions in feet	Existing	Proposed
L	Length of Culvert	132'	1321
Lp	Length of Pool, DS	20'	201
W,	Width of Pool, DS	9'	91
E _{RU}	Elevation Invert US	100.75	100.25
E _p	Elevation of Water-DS Pool	101.6	101.6
E _{S8}	Elevation of Streambed one pipe diameter DS	98.0	98,0

	All dimensions in feet	Existing	Proposed
E _R	Elevation of CL Road	110.3	110.3
Eros	Elev. of Top of Bank, DS	102.5	1025
Hu*	Headwall Treatment, US	Ria Ren	rierap
H _D *	Headwall Treatment, DS	Rin Ran	r. Wrant
Zu_	Slope Value, US	4:1'	4.1
Z _D	Slope Value, DS	4:1	4:1

US = Upstream; DS = Downstream; HW

Elevation of lowest downstream invert is assumed to be 100.0 all other elevations relative to it.

* Types of Headwall Treatment: RR - Rip Rap; CC - Concrete; SB - Stone Block, V - Vegetation (may enter multiple values)

		Existing			Proposed		
	All dimensions in feet	Pipe 1	Pipe 2	Pipe 3	Pipe 1	Pipe 2	Pipe 3
D	Diameter of Pipe	5'			5'		
Pr	Type of Pipe *	RCP			RCP.		
Ps	Shape of Pipe **	Round			Round		


^{*} Types of Pipes: RCP - Reinforced Concrete Pipe, CMP - Corrugated Metal Pipe, HDPE - High Density Polyethylene Pipe, PA - Pipe Arch, OB - Open Bottom; SB -Stone Box (may enter multiple values)

^{**} Shape of Pipes: Round, Oval. (for dumentar enter horizontal dumentant). Box (for diameter enter horizontal dumentarion, Arch (for diameter, enter horizontal

3/26/02


Project Name: Gardiner - Brunswick Investigator's Name: R Chaley D. Gravel Project PIN: 1547 00 Culvert Location: 868+6707 miles South & Topshan Additional Notes: Lloople to determine with of pipe as it is 340' L. Rit. siele of NB Lone.


Profile of Culvert in



Cross Section of Culvert







_	All dimensions in feet	Existing	Proposed
Lc	Length of Culvert	340'	3401
Le	Length of Pool, DS	27'	27.
WP	Width of Pool, DS	8'	8'
En	Elevation Invert US		
E _p	Elevation of Water-DS Pool	102.00	102.10
Ess	Elevation of Streambed one pipe diameter DS	102.00	102,00

	All dimensions in feet	Existing	Proposed
Eg	Elevation of CL Road	112.1	112'
Eros	Elev. of Top of Bank, DS	101.00	101.00
Hu*	Headwall Treatment, US	Rip Rap	rierup
H _D *	Headwall Treatment, DS	Rin Rap	Rigono
Zu	Slope Value, US	2:1	4:1
Z _D	Slope Value, DS	4:1	4:1

US = Upstream; DS = Downstream; HW


Elevation of lowest downstream invert is assumed to be 100.0 all other elevations relative to it.

* Types of Headwall Treatment: RR - Rip Rap; CC - Concrete; SB - Stone Block, V - Vegetation (may enter multiple values)


		Existing			Proposed		
	All dimensions in feet	Pipe I	Pipe 2	Pipe 3	Pipe 1	Pipe 2	Pipe 3
D	Diameter of Pipe	3.5'			3.5"		
PT	Type of Pipe *	RCP			ECP		
Ps	Shape of Pipe **	Round			round		

^{*} Types of Pipes: RCP - Reinforced Concrete Pipe, CMP - Corrugated Metal Pipe. HDPE- High Density Polyethylene Pipe, PA - Pipe Arch. OB - Open Bostom: SB -Stone Box (may enter multiple values)


^{**} Shape of Pipes: Resend, Oval. (for diameter ceter horizontal dimension), Box (for diameter enter horizontal dimension, Arch (for diameter, enter horizontal



Cross Section of Culvert



Plan View of Culvert



	All dimensions in feet	Existing	Proposed
4	Length of Culvert	224'	224.
Lp	Length of Pool, DS	40	1 100 2 0 2 1 2 1 2 1 1
Wp	Width of Pool, DS	1	40
ERI	Elevation Invert US	101.80	102.0
Ep	Elevation of Water-DS Pool	100,20	10,5
ESB	Elevation of Streambed one pipe diameter DS	99.50	

- 03	All dimensions in feet	Existing	Proposec
ER	Elevation of CL Road	127.90	
ETOB	Elev. of Top of Bank, DS	101.50	
Hu*	Headwall Treatment, US	Rip. Rap	101.20
Hp.*	Headwall Treatment, DS	DI 20	riera
Zu	Slope Value, US	2:10	Tipra.
Zo	Slope Value, DS	2	_Z:l
		Z:1	2:1

Elevation of lowest downstream invert is assumed to be 100.0 all other elevations relative to it.

* Types of Headwall Trentment: RR - Rip Rap; CC - Concrete; SB - Stone Block, V - Vegetation (may enter multiple values)

	All discounts of the	Existing			Proposed		
-	All dimensions in feet	Pipe I P	ipe 2	Pipe 3	Pipe 1	Pipe 2	Pipe 3
D	Diameter of Pipe	5'	MIN.		Cun		1.000
Pr	Type of Pipe *	BCEMP		Plas	- 77	101	
Ps	Shape of Pipe **	Round		1/00	yes l'bi've	-	
A		1,00.5	Contract of		10		


^{*} Types of Pipes: RCP - Reinforced Concrete P pe, CMP - Cornagated Metal Pape, HDPE- High Density Polyethylene Pape Stone Box (ma) enter multiple values)

^{**} Shape of Pipes Round, Ovel (for diameter enter horizontal dimension). Box (for diameter enter horizontal dimension, a


15919. Project Name: Finding - Bruss wick Investigator's Name: R. Chuly /D. Grand Date: 1/28/08

Additional Notes: [Set + R+. Side only 161; p.R. M. mund on T. Cight Side = median Side!


Profile of Culvert



Cross Section of Culvert



Plan View of Culvert



	All dimensions in feet	Existing	Proposed
Lc	Length of Culvert	184'	1841
Lp	Length of Pool, DS	19'	191
W,	Width of Pool, DS	7'	71
Enu	Elevation Invert US	102.00	W.501
Ep	Elevation of Water-DS Pool	102.1	1.501
Esa	Elevation of Streambed one pipe diameter DS	97.6	97.6

	All dimensions in feet	Existing	Proposed
Ea	Elevation of CL Road	131.05	13105
ETOB	Elev. of Top of Bank, DS	101.5	1015
Hu*	Headwall Treatment, US	Rip-Rap	CIPTA
H _D *	Headwall Treatment, DS	Vactorian	MAS.
Zu	Slope Value, US	2:1	7
Z _D	Slope Value, DS		
	257/	2:1	17:1

US = Upstream; DS = Downstream; HW

Elevation of lowest downstream invert is assumed to be 100.0 all other elevations relative to it.

* Types of Headwall Treatment: RR - Rip Rap; CC · Concrete; SB · Stone Block, V · Vegetation (may enter multiple values)

		Existing			Proposed		
	All dimensions in feet	Pipe I	Pipe 2	Pipe 3	Pipe 1	Pipe 2	Pipe 3
D	Diameter of Pipe	5'	To Chillian Life		51		
PT	Type of Pipe *	RCP			RCP		
Ps	Shape of Pipe **	Round			round		

^{*} Types of Pipes: RCP - Reinforced Concrete Pipe. CMP - Corrugated Metal Pipe. HDPE- High Density Polyethylene Pipe, PA - Pipe Arcn. OB - Open Boxom; SB - Stone Box (may cater multiple values)


^{**} Shape of Papes: Round, Oval. (for deameter enter horizontal demension), Box (for distracter enter horizontal demension)

CULVERT

Cross Section of Culvert

Road Surface WP Asseme Invert Elev. # 100.0 A. Eras EP

Plan View of Culvert



POOL, DS

	All dimensions in feet	Existing	Proposed
Lc	Length of Culvert	172'	-172
Lp	Length of Pool, DS	11.	111
WP	Width of Pool, DS	5'	(1
Eru	Elevation Invert US	104.5	1045
E _P	Elevation of Water-DS Pool	100.25	14.3
Esa	Elevation of Streambed one pipe diameter DS	99.3	99.3

	All dimensions in feet	Existing	Proposed
E ₈	Elevation of CL Road	126.35	126 33
E _{TOB}	Elev. of Top of Bank, DS	101.4	101 1
Hu*	Headwall Treatment, US	Rip Rap	real
H _D *	Headwall Treatment, DS	D D'	c 000
Zu	Slope Value, US	211	7
Z D	Slope Value, DS		
		2:1	2.1

Elevation of lowest downstream invert is assumed to be 100.0 all other elevations relative to it.

* Types of Headwall Treatment: RR - Rip Rap; CC - Concrete; SB - Stone Block, V - Vegetation (may enter multiple values)

	Existing	Existing			Proposed		
All dimensions in feet	Pipe !	Pipe 2	Pipe 3	Pipe 1	Pipe 2	Pipe 3	
Diameter of Pipe	4.5'			45.			
Type of Pipe *	RCP			PCP			
Shape of Pipe **	Royad			round.		11	
	Type of Pipe *	All dimensions in feet Pipe! Diameter of Pipe 4.5' Type of Pipe * RCP	All dimensions in feet Pipe! Pipe 2 Diameter of Pipe 4.5' Type of Pipe * RCP	Diameter of Pipe 4.5 ' Type of Pipe * RCP	All dimensions in feet Pipe! Pipe 2 Pipe 3 Pipe 1 Diameter of Pipe 4.5' Type of Pipe * RCP RCP	All discussions in feet Pipe! Pipe 2 Pipe 3 Pipe 1 Pipe 2 Diameter of Pipe 4.5' Type of Pipe * RCP CCP	

Types of Pipes: RCP - Reinforced Concrete Pipe, CMP - Corrugated Metal Pipe, HDPE- High Density Polyethylene Pipe, PA - Pipe Arch, UB - Open Bostom, SPI -Stone Box (may enter multiple values)

^{**} Shape of Pipes: Round, Oval. (for dismeter enter horizontal dimension), Box (for dismeter enter horizontal dimension, Arch (for dismeter, enter horizontal



(Minimum Notice: Permittee must sign and return notification within one month of the completion of work.)

COMPLIANCE CERTIFICATION FORM

Corps of Engineers Permit No:			
Name of Permittee:			
Permit Issuance Date:			
Please sign this certification and return it to and any mitigation required by the permit. but not the mitigation monitoring, which re-	You must sul	mit this after the mitigation is c	e activity complete,
***********			*****
* MAIL TO: U.S. Army Corps of Engite Policy Analysis/Technica Regulatory Division * 696 Virginia Road * Concord, Massachusetts **********************************	al Support Br 01742-2751 ********* abject to a con il to comply ion. by the abov s of the abov	anch, ATTN: Marie Farese ************************ mpliance inspection by an U.S. a with this permit you are subject e referenced permit was comp e referenced permit, and any a	Army to
Signature of Permittee		Date	
Printed Name		Date of Work Completion	
() Telephone Number	_ <u>(</u>) phone Number	A 11
2 - Seption Fullion	1 616	phone (vulnoe)	



PGP WORK START NOTIFICATION FORM (Minimum Advance Notice: Two Weeks)

MAIL TO: U.S. Army Corps of Engineers, New England District

Regulatory Branch

Policy Analysis/Technical Support Section

696 Virginia Road

Concord, Massachusetts 01742-2751

authorized the permittee(s	mit () to		The permit
The people (e.g., contractor conditions and limitations	or) listed below will		
	PLEAS	SE PRINT OR TYPE	
Name of Person/Firm:			
Business Address:			
Telephone: ())
Proposed Work Dates:	Start:		
	AMON		
	JRE:		DATE:
PERMITTEE'S SIGNATU			
PERMITTEE'S SIGNATU		TITLE:	
		TITLE:	

Chapter 305: PERMIT BY RULE <u>Section 11</u>

State Transportation Facilities

1. Introduction. A "permit by rule" or "PBR", when approved by the Department of Environmental Protection (DEP), is an approval for an activity that requires a permit under the Natural Resources Protection Act (NRPA). Only those activities described in this chapter may proceed under the PBR process. A PBR activity will not significantly affect the environment if carried out in accordance with this chapter, and generally has less of an impact on the environment than an activity requiring an individual permit. A PBR satisfies the Natural Resources Protection Act (NRPA) permit requirement and Water Quality Certification requirement.

If a proposed activity is not described in this chapter, or will not be conducted in accordance with the standards of this chapter, the applicant must obtain an individual permit prior to beginning the activity.

- **A.** Location of activity. The location of an activity may affect whether an activity qualifies for PBR, and whether review by the Department of Inland Fisheries and Wildlife is required.
 - (1) Type of resource. For some types of activities, the availability of a PBR is affected by the type of natural resource in or adjacent to which the activity is proposed. For example, an applicant proposing an activity consisting of "Movement of rocks or vegetation" may receive a PBR only if the activity will take place in a great pond, river, stream or brook. Limitations concerning the location of activities are addressed in the "Applicability" provision in each section of this chapter.
 - (2) Essential habitat. Essential habitats include areas critical to the survival of threatened and endangered species such as the bald eagle, least tern, roseate tern, and piping plover. If the activity is located in essential habitat, such as near an eagle nesting site, a PBR is only available if the applicant obtains written approval from the Department of Inland Fisheries and Wildlife (IF&W). This approval from IF&W must be submitted to the DEP with the PBR notification form, and the applicant must follow any conditions stated in the IF&W approval.
- NOTE: Maps showing areas of essential habitat are available from the Department of Inland Fisheries and Wildlife regional headquarters, municipal offices, the Land Use Regulation Commission (for unorganized territories) and DEP regional offices. If the activity is located in essential habitat, IF&W must be contacted to request and obtain a "certification of review and approval".
- **B.** Notification. The applicant must file notice of the activity with the DEP prior to beginning work on the activity. The notification must be on a form provided by the DEP and must include any submissions required in this chapter. The applicant must keep a copy to serve as the permit.

The notification form must be sent to the DEP by certified mail (return receipt requested), or hand delivered to the DEP and date stamped by the department.

C. Effective period

(1) Beginning of period. The PBR becomes effective 14 calendar days after the DEP receives the notification form, unless the DEP approves or denies the PBR prior to that date. If the DEP does not speak with or write to the applicant within this 14 day period regarding the PBR notification, the applicant may proceed to carry out the activity.

There are three exceptions regarding the effective date of an approved PBR:

- (a) Activities listed in Section 10 (Stream crossings) occurring in association with forest management are exempt from the 14 day waiting period.
- (b) Activities listed in Section 2 (Soil disturbance) and Section 10 (Stream crossings) performed or supervised by individuals currently certified in erosion control practices by the DEP are exempt from the 14 day waiting period. To be certified in erosion control practices, an individual must successfully complete all course requirements of the Voluntary Contractor Certification Program administered by the DEP's Nonpoint Source Training and Resource Center.
- (c) Activities that are part of a larger project requiring a permit under the Site Location of Development or the Storm Water Management Acts may not proceed until any required permit under those laws is obtained.
- NOTE: Activities that are part of a larger project may require other permits from the DEP also.

 These other laws may prohibit the start of construction of any part of the project unless a permit under that law is obtained. In these cases, while not a violation of this rule, starting work on a PBR approved activity would be a violation of those other applicable laws
- (2) End of period. The PBR is generally effective for 2 years from the date of approval, except that a PBR for "Replacement of structures" under Section 4 is effective for 3 years.
- NOTE: Activities that qualify under this chapter may need to meet other local, state and federal requirements. Examples -- (1) If an activity extends below the low water line of a lake, coastal wetland or international boundary water, the applicant should contact the Bureau of Parks and Lands (287-3061) concerning possible lease or easement requirements, or (2) If an activity will involve work below the mean high water line in navigable waters of the United States, the applicant should contact the Army Corps of Engineers (623-8367).
- **D. Discretionary authority.** Notwithstanding compliance with the PBR applicability requirements and standards set forth in this chapter, the DEP may require an individual permit application to be filed in any case where credible evidence indicates that the activity:
 - (1) May violate the standards of the NRPA (38 M.R.S.A. Section 480-D);
 - (2) Could lead to significant environmental impacts, including cumulative impacts; or
 - (3) Could adversely impact a resource of special concern.

If an individual permit is required pursuant to this subsection, the DEP shall notify the applicant in writing within the 14 calendar day waiting period described in sub-section (C) above. When the DEP notifies an applicant than an individual permit is required, no work may be conducted unless and until the individual permit is obtained.

E. Violations. A violation of law occurs when a person, or his or her agent, performs or causes to be performed any activity subject to the NRPA without first obtaining a permit from the DEP, or acts contrary to the provisions of a permit. The person, his or her agent, or both, may be held

responsible for the violation. Commonly, the "person" is the landowner, and the "agent" is the contractor carrying out the activity. A violation occurs when:

- (1) An activity occurs that is not allowed under PBR, whether or not a PBR notification form has been filed with and/or approved by the DEP;
- (2) An activity occurs that is allowed under PBR, but a PBR for the activity has not become effective prior to the beginning of the activity; or
- (3) An activity occurs that is allowed under PBR and a PBR for the activity is in effect, but the standards specified in this chapter are not met.

See the "applicability" provision under each activity for rules concerning what activities are allowed under PBR. A PBR is only valid for the person listed on the notification form, or for his or her agent.

Each day that a violation occurs or continues is considered a separate offense. Violations are subject to criminal penalties and civil penalties of not less than \$100 nor more than \$10,000 for each day of that violation (38 M.R.S.A. Section 349).

NOTE: A local Code Enforcement Officer (CEO) may take enforcement action for a violation of the Natural Resources Protection Act if he or she is authorized to represent a municipality in District Court, and he or she has been certified as familiar with court procedures, 30-A M.R.S.A. Section 4452(7).

Chapter 305 Section 11

State transportation facilities

A. Applicability

- (1) This section applies to the maintenance, repair, reconstruction, rehabilitation, replacement or minor construction of a State Transportation Facility carried out by, or under the authority of, the Maine Department of Transportation or the Maine Turnpike Authority, including any testing or preconstruction engineering, and associated technical support services.
- (2) This section does not apply to an activity within a coastal sand dune system.

NOTE: The construction of a transportation facility other than roads and associated facilities may be subject to the Storm Water Management Law, 38 M.R.S.A. Section 420-D.

B. Standards

- (1) Photographs of the area to be altered by the activity must be taken before work on the site begins. The photographs must be kept on file and be made available at the request of the DEP.
- (2) The activity must be reviewed by the Department of Inland Fisheries and Wildlife, the Department of Marine Resources, the Atlantic Salmon Authority, and the DEP's Division of Environmental Assessment prior to the notification being filed with the DEP. The activity must be performed according to any recommendations from these authorities.
- (3) The activity must be performed in accordance with erosion control measures conforming with the State of Maine Department of Transportation Standard Specifications for Highways and Bridges Revision of April 1995 and with the Department of Transportation's Best Management Practices for Erosion and Sediment Control, September 1997.

NOTE: Guidance on the use of erosion control best management practices can be obtained from the on site Construction Manager.

- (4) Alignment changes may not exceed a distance of 200 feet between the old and new center lines in any natural resource.
- (5) The activity may not alter more than 300 feet of shoreline (both shores added together) within a mile stretch of any river, stream or brook, including any bridge width or length of culvert.
- (6) The activity may not alter more than 150 feet of shoreline (both shores added together) within a mile stretch of any outstanding river segment identified in 38 M.R.S.A. 480-P, including any bridge width or length of culvert.
- (7) The activity must minimize wetland intrusion. The activity is exempt from the provisions of Chapter 310, the Wetland Protection Rules, if the activity alters less than 15,000 square feet of natural resources per mile of roadway (centerline measurement) provided that the following impacts are not exceeded within the 15,000 square foot area:

- (a) 1,000 square feet of coastal wetland consisting of salt tolerant vegetation or shellfish habitat; or
- (b) 5,000 square feet of coastal wetland not containing salt tolerant vegetation or shellfish habitat; or
- (c) 1,000 square feet of a great pond.

All other activities must be performed in compliance with all sections of Chapter 310, the Wetland Protection Rules, except 310.2(C), 5(A), 9(1), 9(B) and 9(C).

- (8) The activity may not permanently block any fish passage in any watercourse containing fish. The applicant must improve passage beyond what restriction may already exist unless the Department of Inland Fisheries and Wildlife, the Department of Marine Resources, the Atlantic Salmon Authority and the DEP's Division of Environmental Assessment concur that the improvement is not necessary.
- (9) Rocks may not be removed from below the normal high water line of any coastal wetland, freshwater wetland, great pond, river, stream or brook except to the minimum extent necessary for completion of work within the limits of construction.
- (10) If work is performed in a river, stream or brook that is less than three feet deep at the time and location of the activity, with the exception of culvert installation, the applicant must divert flow away from the activity while work is in progress.
 - (a) Diversion may be accomplished by the use of stable, inert material. No more than two thirds (2/3) of stream width may be diverted at one time.
 - (b) Any material used to divert water flow must be completely removed upon completion of the activity, and the stream bottom must be restored to its original condition.
 - (c) A pump may be operated, where necessary, for a temporary diversion. The pump outlet must be located and operated such that erosion or the discharge of sediment to the water is prevented.

NOTE: Guidance on the appropriate location of a diversion and materials which should be used for a stream diversion can be obtained from the on site Construction Manager.

- (11) Wheeled or tracked equipment may not operate in the water. Equipment operating on the shore may reach into the water with a bucket or similar extension. Equipment may cross streams on rock, gravel or ledge bottom.
- (12) All wheeled or tracked equipment that must travel or work in a vegetated wetland area must travel and work on mats or platforms.
- (13) Any debris or excavated material must be stockpiled either outside the wetland or on mats or platforms. Hay bales or silt fence must be used, where necessary, to prevent sedimentation. Any debris generated during the activity must be prevented from washing downstream and must be removed from the wetland or water body. Disposal of debris must be in conformance with the Maine Hazardous Waste, Septage and Solid Waste Management Act, 38 M.R.S.A. Section 1301 et seq.

- (14) Work below the normal high water line of a great pond, river, stream or brook must be done at low water except for emergency work or work agreed to by the resource agencies listed in paragraph 2 above. Measures, such as a silt boom or staked fencing, must be employed to reduce and isolate turbidity.
- (15) Perimeter controls must be installed before the work starts. Disturbance of natural resources beyond the construction limits shown on the plans is not allowed under this rule.

NOTE: Guidance on the location of construction limits can be obtained from the on site Construction Manager.

- (16) The use of untreated lumber is preferred. Lumber pressure treated with chromated copper arsenate (CCA) may be used, provided it is cured on dry land in a manner that exposes all surfaces to the air for a period of at least 21 days prior to construction. Wood treated with creosote or pentachlorophenol may not be used where it will contact water.
- (17) A temporary road for equipment access must be constructed of crushed stone, blasted ledge, or similar materials that will not cause sedimentation or restrict fish passage. Such roads must be completely removed at the completion of the activity. In addition, any such temporary roads which are in rivers, streams or brooks, must allow for a passage of stormwater flows associated with a 10-year storm.
- (18) Soil may not be disturbed during any period when soils are saturated due to rain or snow melt, except as necessary to protect work in progress or as required for bridge maintenance activities. Areas where soils are saturated (i.e. water drips from the soil when squeezed by hand, or the soil is capable of being rolled into a rod 1/8th inch in diameter that does not crumble) must be immediately mulched if they are disturbed.
- (19) Disturbed soil must be protected within one week from the time it was last actively worked, and prior to any storm event, using temporary or permanent measures such as the placement of riprap, sod, mulch, erosion control blankets, or other comparable measures.
- (20) Hay bale or straw mulch, where used, must be applied at a rate of at least one bale per 500 square feet (1 to 2 tons per acre).
- (21) If mulch is likely to be moved because of steep slopes or wind exposure, it must be anchored with netting, peg and twine, binder or other suitable method and must be maintained until a catch of vegetation is established over the entire disturbed area.
- (22) In addition to the placement of riprap, sod, erosion control blankets or mulch, additional steps must be taken where necessary to prevent sedimentation of the water Evidence of sedimentation includes visible sheet, rill or gully erosion, discoloration of water by suspended particles and/or slumping of banks. Silt fences, staked hay bales and other sedimentation control measures, where planned for, must be in place prior to the commencement of an activity, but must also be installed whenever necessary to prevent erosion and sedimentation.

NOTE: Guidance on the location and proper installation of erosion control measures can be obtained from the on site Construction Manager.

- (23) Temporary erosion control measures must be maintained and inspected weekly until the site is permanently stabilized with vegetation or other permanent control measures. Erosion control measures must also be inspected immediately prior to and following storms.
- (24) Permanent erosion control measures protecting all disturbed areas must be implemented within 30 days from the time the areas were last actively worked, or for fall and winter activities by the following June 15, except where precluded by the type of activity (e.g. riprap, road surfaces, etc.). The permanent erosion control measures must be maintained.
- (25) The applicant shall immediately take appropriate measures to prevent erosion or sedimentation from occurring or to correct any existing problems, regardless of the time of year.
- (26) Non-native species may not be planted in restored areas.
- (27) Disposal of debris must be in conformance with Maine Hazardous Waste, Septage and Solid Waste Management Act, 38 M.R.S.A. Sections 1301 et seq.
- (28) Disturbance of vegetation must be avoided, if possible. Where vegetation is disturbed outside of the area covered by any road or structure construction, it must be reestablished immediately upon completion of the activity and must be maintained.
- (29) A vegetated area at least 25 feet wide must be established and maintained between any new stormwater outfall structure and the high water line of any open water body. A velocity reducing structure must be constructed at the outlet of the stormwater outfall that will create sheet flow of stormwater, and prevent erosion of soil within the vegetated buffer. If the 25 foot vegetated buffer is not practicable, the applicant must explain the reason for a lesser setback in writing. Approval from the DEP must be in writing and any recommendations must be incorporated into the activity.
- **C. Definitions.** The following terms, as used in this chapter, have the following meanings, unless the context indicates otherwise:
 - (1) Diversion. A rerouting of a river, stream or brook to a location outside of its established channel
 - (2) Fill. a. (verb) To put into or upon, supply to, or allow to enter a water body or wetland any earth, rock, gravel, sand, silt, clay, peat, or debris; b. (noun) Material, other than structures, placed in or immediately adjacent to a wetland or water body.
 - (3) Floodplain wetlands. Freshwater wetlands that are inundated with flood water during a 100-year flood event based on flood insurance maps produced by the Federal Emergency Agency or other site specific information.
 - (4) Riprap. Rocks that are fit into place, usually without mortar, on a slope as defined in the State of Maine, Department of Transportation, Standard Specifications for Highway and Bridges, revision of April 1995.

Applicant: General Public, State of Maine Effective Date: October 11, 2005
Permit Number: NAE-2005-2164 Expiration Date: October 11, 2010

DEPARTMENT OF THE ARMY PROGRAMMATIC GENERAL PERMIT STATE OF MAINE

The New England District of the U.S. Army Corps of Engineers hereby issues a Programmatic General Permit (PGP) that expedites review of minimal impact work in coastal and inland waters and wetlands within the State of Maine.

I. GENERAL CRITERIA

Activities with minimal impacts, as specified by the terms and conditions of this PGP and on the attached Appendix A, Definition of Categories, are either:

<u>Category 1</u>: Non-reporting. Eligible without screening (provided the authorizations are obtained which this permit states are necessary for activities to be eligible for authorization under this non-reporting category), or,

<u>Category 2</u>: Reporting. Require screening and a written determination of eligibility under the PGP by the Corps after coordination with the U.S. Fish and Wildlife Service (U.S. FWS), U.S. Environmental Protection Agency (EPA) and the National Marine Fisheries Service (NMFS).

This PGP does not affect the Corps Individual Permit review process or activities exempt from Corps jurisdiction.

II. ACTIVITIES COVERED:

Work and structures that are located in, or that affect, navigable waters of the United States (U.S.) (Corps regulates under Section 10 of the Rivers and Harbors Act of 1899); the discharge of dredged of fill material into waters of the United States (Corps regulates under Section 404 of the Clean Water Act); and the transportation of dredged material for the purpose of disposal in the ocean (Corps regulates under Section 103 of the Marine Protection, Research and Sanctuaries Act).

III. PROCEDURES:

A. State Approvals

For projects authorized pursuant to this PGP, the following State approvals are also required. The applicable permits must be obtained in order for this PGP authorization to be valid (applicants are responsible for ensuring that all required State permits and approvals have been applied for and obtained):

- Maine Department of Environmental Protection (DEP): Natural Resources Protection Act (NRPA) permit, including permit-by-rule and general permit authorizations (NRPA permit issuance constitutes both the state permit and the WQC); Site Location of Development Act permit; and Maine Waterway Development and Conservation Act permit.
- Maine Department of Conservation: Land Use Regulation Commission (LURC) permit.
- Maine Department of Marine Resources: Lease.
- Maine Department of Conservation, Bureau of Parks and Lands, Submerged Lands: Lease NOTE: This PGP may authorize projects that are not regulated by the State of Maine (e.g., seasonal floats or moorings).

B. Corps Authorizations

CATEGORY 1 (Non-Reporting)

Eligibility Criteria

Activities in Maine may proceed without application or notification to the Corps if they:

- Are subject to Corps jurisdiction (see General Condition 2, Page 7),
- Meet the definition of Category 1 in Appendix A Definition of Categories, and
- Meet the General Conditions of the PGP (see Pages 7 15).

If the State or the Corps does not contact the applicant for DEP's Tier One permits during the DEP's Tier One 30-day review period, Corps approval may be assumed and the project may proceed. Refer to the Federal Screening Procedures (see Page 4) for additional information regarding screening.

Project proponents seeking Category 1 authorizations are not relieved of the obligation to comply with this PGP's General Conditions (see Page 7) and other Federal laws such as the National Historic Preservation Act, the Endangered Species Act (ESA) and the Wild and Scenic Rivers Act. Therefore, consultation with the Corps and/or outside experts such as the Maine Historic Preservation Commission and the appropriate Indian tribes is recommended when there is a high likelihood of the presence of resources of concern.

Although Category 1 projects are non-reporting, the Corps reserves the right to require screening under Category 2 or Individual Permit review if there are concerns for the aquatic environment or any other factor of the public interest (see General Condition 4, Discretionary Authority, Page 7).

Work that is not regulated by the State of Maine, but is subject to Corps jurisdiction, is eligible for Corps authorization under this PGP in accordance with the review thresholds and conditions contained herein. The Maine DEP and LURC have waived WQC for projects authorized under Categories 1 and 2 of this PGP and not subject to jurisdiction under the NRPA and LURC Land Use Districts and Standards.

Enforcement cases. This PGP does not apply to any existing or proposed activity in Corps jurisdiction associated with an on-going Corps or EPA enforcement action until such time as the enforcement action is resolved or the Corps determines that the activity may proceed independently without compromising the enforcement action. The Corps may choose not to accept applications or issue permits to any applicant with outstanding violations.

CATEGORY 2 (Reporting – Requiring Screening)

Eligibility Criteria

Activities in Maine require written approval from the Corps if they:

- Are subject to Corps jurisdiction (see General Condition 2, Page 7),
- Meet the definition of Category 2 in Appendix A Definition of Categories, and
- Meet the General Conditions of the PGP (see Pages 7 15),

These projects will be reviewed through interagency screening (see Federal Screening Procedures below) to determine whether such activities may be authorized under this PGP. To be eligible and

subsequently authorized, an activity must result in minimal impacts to the aquatic environment as determined by the Corps based on comments from the review team and the criteria listed above. Mitigation may be required to compensate for unavoidable impacts to ensure net effects of a project are minimal.

For Category 2 projects, applicants must obtain a written authorization from the Corps and State approvals as stated on Page 1.

To ensure compliance with the conditions of this PGP, consultation with the Corps and outside experts is <u>required</u>. This includes consultation with the Maine Historic Preservation Commission and the appropriate Native American Indian tribes to ensure compliance with Condition 8. Also, note the review thresholds under Category 2 apply to single and complete projects only (see General Condition 5).

Enforcement cases. See previous section.

Application Procedures

The Corps must review and approve in writing all Category 2 activities. Generally, the State will provide the Corps with a copy of State applications received, but it is ultimately the applicant's responsibility to ensure the Corps receives the application from the State. Therefore, it is recommended that applicants either verify with the Corps receipt of their application from the State (DEP or LURC), or apply directly to the Corps with either a copy of their State application or a Corps application (ENG Form 4345). Applicants must apply directly to the Corps using ENG Form 4345 if the work is not State regulated.

Upon receipt of the application, the Corps will determine if it:

- (a) requires additional information (see "information typically required" on the following page);
- (b) is appropriate for screening with the Federal resource agencies (see Category 2 Federal Screening Procedures on the following page);
- (c) is ineligible under the terms and/or conditions of this PGP; or
- (d) will require Individual Permit review, regardless of whether the terms and conditions of this PGP are met, based on concerns for the aquatic environment or any other factor of the public interest (see General Condition 4, Discretionary Authority).

If open water disposal is proposed, the Corps will make a suitability determination, fully coordinated with the Federal resource agencies, before coordinating a project at a joint processing meeting.

All Category 2 applicants shall submit a copy of their application materials to the Maine Historic Preservation Commission and the Indian tribe(s) listed on Page 17, at the same time, or before, they apply to the DEP, LURC, or the Corps, to be reviewed for the presence of historic, archaeological or tribal resources in the permit area that the proposed work may affect. Submittals to the DEP or Corps shall include information to indicate that this has been done (a copy of the applicant's cover letter to Maine Historic Preservation Commission and tribes or a copy of the Historic Preservation Commission and tribal response letters is acceptable).

Information Typically Required

The following information may not be necessary for all projects. Please see www.nae.usace.army.mil for a more comprehensive checklist. Select "Regulatory/Permitting," "Forms" and then "Application and Plan Guideline Checklist." Please check with our Maine office for project-specific requirements.

Maine PGP 3 October 11, 2005 267

- (a) purpose of project;
- (b) 8½"x 11" locus map. 8½"x 11" plan views of the entire property, including property lines, and project limits with existing and proposed conditions;
- (c) typical cross-section views of all wetland and waterway fill areas and wetland replication areas;
- (d) legible, reproducible plans. Show mean low water (MLW), mean high water (MHW) and high tide line (HTL) elevations in navigable waters;
- (e) each plan should show the NGVD 1929 equivalent for the project's vertical datum (MLW, MLLW, MHW, HTL or other tidal datum for tidal projects) with the vertical units. Do not use local datum;
- (f) wetland delineation for the site, Corps wetland delineation data sheets (see web site), and calculations of waterway and wetland impact areas (see General Condition 2);
- (g) delineation of submerged aquatic vegetation, e.g., eel grass beds, in tidal waters;
- (h) volume, type and source of fill material to be discharged into waters and wetlands, including the area(s) (in square feet or acres) of fill in wetlands, below ordinary high water in inland waters and below the high tide line in coastal waters;
- (i) limits of any Federal Navigation Project in the vicinity and State Plane Coordinates for the limits of the proposed work closest to the Federal Navigation Project;
- (j) on-site alternatives analysis. Please contact Corps for guidance;
- (k) identify and describe potential impacts to Essential Fish Habitat. See General Condition 11 and contact Corps for guidance;
- (l) photographs of wetland/waterway to be impacted.

Information typically required for dredging projects:

- (a) sediment testing, including physical (e.g., grain-size analysis), chemical and biological testing. For projects proposing open water disposal, applicants are encouraged to contact the Corps as early as possible regarding sampling and testing protocols. <u>Sampling and testing of sediments without such contact should not occur and, if done, would be at the applicant's risk.</u>
- (b) the area in square feet and volume of material to be dredged below mean high water;
- (c) existing and proposed water depths;
- (d) type of dredging equipment to be used;
- (e) nature of material (e.g., silty sand);
- (f) any existing sediment grain size and bulk sediment chemistry data for the proposed or any nearby projects;
- (g) information on the location and nature of municipal or industrial discharges and occurrence of any contaminant spills in or near the project area, location of the disposal site (include locus sheet);
- (h) shellfish survey;
- (i) identify and describe potential impacts to Essential Fish Habitat (see General Condition 11);
- (j) delineation of submerged aquatic vegetation (e.g., eelgrass beds).

Federal Screening Procedures

The Corps will review all complete applications for Category 2 projects requiring Corps approval at interagency screening meetings (or "joint processing" meetings) with the Federal resource agencies (U.S. FWS, EPA and NMFS) to determine whether such activities may be authorized under this PGP. The Federal resource agencies will comprise the interagency review team. The meetings are held at the Corps every three weeks, or coordinated as necessary to provide applicants with a timely response. The Corps and Federal resource agencies, at the branch chief or equivalent level, may agree on certain activities that do not need to be coordinated at these meetings.

If the Corps and Federal resource agencies determine that the activity is eligible for the PGP, the Corps will send an authorization letter directly to the applicant. The Corps will generally issue an eligibility determination within the State's review period, not to exceed 60 days. If the Corps determines that the activity is not eligible under the PGP or that additional information is required, the Corps will notify the applicant in writing and will send a copy of this notification to DEP or LURC.

For projects reviewed with the Federal resource agencies, the agencies may recommend, within ten business days, either 1) special conditions for projects to avoid or minimize adverse environmental effects and to ensure the terms and conditions of the PGP are met, or 2) Individual Permit review. The Corps will determine that a project is ineligible under this PGP and will begin its Individual Permit review procedures if any one of the Federal resource agencies, within ten business days of the screening meeting, expresses a concern within their area of expertise, states the resource or species that could be impacted by the project, and describes the impacts that, either individually or cumulatively, will be more than minimal.

This ten-day notice may be spoken and is not required to be fully documented, but must be confirmed with a written response within an additional ten working days from the date of the spoken comment. Written responses must be signed by the Federal resource agency field supervisor or branch chief, as appropriate, and must identify the affected resource within their area of expertise. The intent of the spoken notification is to allow the Corps to give timely notification to the applicant that additional information is needed and/or an Individual Permit may be required. The Corps may reinstate a project's eligibility under the PGP provided the Federal agencies' concerns are satisfied. The Federal resource agencies may request additional information within their area of expertise within ten business days of the screening meeting. This information shall be commensurate to the level of impact and agreed upon by the Corps. The agencies are allowed an additional ten business days after their receipt of additional information to provide special conditions or a written Individual Permit request to the Corps.

If the applicant is unable to resolve the concerns, the Corps, independently or at the request of the Federal resource agencies, will require an Individual Permit for the project. The applicant will be notified of this in writing, along with information about submitting the necessary application materials.

Minerals Management Service (MMS) Review

Projects with construction of solid fill structures or discharge of fill that may extend beyond the coastline or the baseline from which the territorial sea is measured (i.e., mean low water), must be coordinated with Minerals Management Service (MMS), Outer Continental Shelf (OCS) Survey Group, pursuant to the Submerged Lands Act (43 USC, Section 1301-1315, 33 CFR 320.4(f)). The Corps will forward project information to MMS for their review. The MMS will coordinate their determination with the Department of the Interior (DOI) Solicitor's Office. The DOI will have 15 calendar days from the date MMS is in receipt of project information to determine if the baseline will be affected. No notification to the Corps within 15-day review period will constitute a "no effect" determination. Otherwise, the solicitor's notification to the Corps may be spoken but must be followed with a written confirmation within ten business days from the date of the spoken notification. This procedure will be eliminated if the State of Maine provides a written waiver of interest in any increase in submerged lands caused by a change in the baseline resulting from solid fill structures or fills authorized under this PGP.

Emergency Situations Procedures

Emergency situations are limited to sudden, unexpected occurrences that could potentially result in an unacceptable hazard to life, a significant loss of property, or an immediate, unforeseen, and significant economic hardship if corrective action requiring a permit is not undertaken within a time period less than the normal time needed to process an application under standard procedures. If an emergency situation requires action in less than 30 days after the occurrence, it qualifies for the amended notification procedures described below.

Notification Procedures for Emergency Situations:

Any project proponent may request emergency authorization from the Corps, however the Corps will determine if a project qualifies for these emergency situation procedures. The Federal resource agencies, the Maine Historic Preservation Commission and the tribes will each designate an emergency contact and an alternate in the event the regular contact is unavailable. When an application for Category 2 work is received that the Corps determines is an "emergency" as defined above, the Corps will fax a copy of the plans and Determination of Eligibility to the agency representatives and their alternates. The resource agencies would then have 16 business hours to notify the Corps if they have any comments on authorization of the project under the PGP. Objections to the Corps determination of an "emergency" situation will not be accepted. If no response is received within 16 business hours, the Corps will proceed with a decision on the application. If the resource agencies have comments on the proposal, they will have 16 business hours to put their comments in writing. If written comments from the Federal agencies are not received within 16 business hours, the Corps will proceed with a decision on the application.

If a Federal agency requests that an Individual Permit be required for a project or requests modifications to the project based on concerns within their area(s) of expertise, the Corps will notify the applicant within one business day of receipt of that request that the project as proposed does not qualify for authorization under this PGP and the emergency Individual Permit procedures may be followed. In any event, the Corps will notify the applicant within 16 business hours of commencement of the screening process as to whether the project may proceed under this PGP.

IV. CORPS AUTHORIZATION: INDIVIDUAL PERMIT

Work that is defined in the Individual Permit category of Appendix A – Definition of Categories, or that does not meet the terms and conditions of this PGP, will require an application for an Individual Permit from the Corps (see 33 CFR Part 325.1). The screening procedures outlined for Category 2 projects will only serve to delay project review in such cases. The applicant should submit the appropriate application materials (including the Corps application form) at the earliest possible date. General information and application forms can be obtained at our web site or by calling us (see Page 16). Individual water quality certification and coastal zone management consistency concurrence are required when applicable from the State of Maine before Corps permit issuance. The Federal resource agencies' comments are due within ten working days after the Public Notice's expiration date, unless the Corps receives and approves a written request for a time extension within ten working days after the notice's expiration.

V. PROGRAMMATIC GENERAL PERMIT CONDITIONS:

The following conditions apply to activities authorized under this Maine PGP, including all Category 1 (non-reporting) and Category 2 (reporting – requiring screening) activities:

General Requirements

- 1. Other Permits. Authorization under this PGP does not obviate the need to obtain other Federal, State, or local authorizations required by law. This includes, but is not limited to, the project proponent obtaining a Flood Hazard Development Permit issued by the town, if necessary. Inquiries may be directed to the municipality or to the Maine Floodplain Management Coordinator at (207) 287-8063. See http://www.maine.gov.
- 2. Federal Jurisdictional Boundaries. Applicability of this PGP shall be evaluated with reference to Federal jurisdictional boundaries. Applicants are responsible for ensuring that the boundaries used satisfy the Federal criteria defined at 33 CFR 328-329. These sections prescribe the policy, practice and procedures to be used in determining the extent of jurisdiction of the Corps concerning "waters of the U.S." and "navigable waters of the U.S." Wetland boundaries shall be delineated in accordance with the January 1987 Corps of Engineers Wetlands Delineation Manual, located at http://www.usace.army.mil/inet/functions/cw/cecwo/reg/wlman87.pdf. The U.S. FWS publishes the National List of Plant Species that Occur in Wetlands, located at http://www.nwi.fws.gov. The Natural Resources Conservation Service (NRCS) develops the hydric soil definition and criteria, and publishes the current hydric soil lists, located at http://soils.usda.gov/use/hydric/.
- **3. Minimal Effects.** Projects authorized by this PGP shall have no more than minimal individual and cumulative adverse environmental impacts as determined by the Corps.
- 4. Discretionary Authority. Notwithstanding compliance with the terms and conditions of this permit, the Corps retains discretionary authority to require Category 2 or Individual Permit review based on concerns for the aquatic environment or for any other factor of the public interest [33 CFR 320.4(a)]. This authority is invoked on a case-by-case basis whenever the Corps determines that the potential consequences of the proposal warrant Individual Permit review based on the concerns stated above. This authority may be invoked for projects with cumulative environmental impacts that are more than minimal or if there is a special resource or concern associated with a particular project that is not already covered by the remaining conditions of the PGP and that warrants greater review. Whenever the Corps notifies an applicant that an Individual Permit may be required, authorization under this PGP is void and no work may be conducted until the individual Corps permit is obtained or until the Corps notifies the applicant that further review has demonstrated that the work may proceed under this PGP.
- 5. Single and Complete Projects. This PGP shall not be used for piecemeal work and shall be applied to single and complete projects. All components of a single project shall be treated together as constituting one single and complete project and/or all planned phases of a multi-phased project (e.g., subdivisions should include all work such as roads, utilities, and lot development) unless the Corps determines that a component has independent utility. (The *Independent Utility* test is used to determine what constitutes a single and complete project in the Corps regulatory program. A project is considered to have independent utility if it would be constructed absent the construction of other projects in the project area. Portions of a multi-phase project that depend upon other phases of the project do not have independent utility. Phases of a project that would be constructed even if the other phases were not built can be considered as separate single and complete projects with independent utility.) For linear projects, such as power lines or pipelines with multiple

crossings, the "single and complete project" (i.e., single and complete crossing) will apply to each crossing of a separate water of the U.S. (i.e., single waterbody) at that location; except that for linear projects crossing a single waterbody several times at separate and distant locations, each crossing is considered a single and complete project, and may be reviewed for Category 1 eligibility. (However, individual channels in a braided stream or river, or individual arms of a large, irregularly-shaped wetland or lake, etc., are not separate waterbodies.) If any crossing requires a Category 2 activity, then the entire linear project shall be reviewed as one project under Category 2. Also, this PGP shall not be used for any activity that is part of an overall project for which an Individual Permit is required, unless the Corps determines the activity has independent utility.

6. Permit On-Site. For Category 2 projects, the permittee shall ensure that a copy of this PGP and the accompanying authorization letter are at the work site (and the project office) authorized by this PGP whenever work is being performed, and that all personnel with operation control of the site ensure that all appropriate personnel performing work are fully aware of its terms and conditions. The entire permit authorization shall be made a part of any and all contracts and sub-contracts for work that affects areas of Corps jurisdiction at the site of the work authorized by this PGP. This shall be achieved by including the entire permit authorization in the specifications for work. The term "entire permit authorization" means this PGP and the authorization letter (including its drawings, plans, appendices and other attachments) and also includes permit modifications. If the authorization letter is issued after the construction specifications, but before receipt of bids or quotes, the entire permit authorization shall be included as an addendum to the specifications. If the authorization letter is issued after receipt of bids or quotes, the entire permit authorization shall be included in the contract or sub-contract as a change order. Although the permittee may assign various aspects of the work to different contractors or sub-contractors, all contractors and subcontractors shall be obligated by contract to comply with all environmental protection provisions contained within the entire PGP authorization, and no contract or sub-contract shall require or allow unauthorized work in areas of Corps jurisdiction.

National Concerns

- 7. St. John/St. Croix Rivers. This covers work within the Saint John and Saint Croix River basins that requires approval of the International Joint Commission. This includes any temporary or permanent use, obstruction or diversion of international boundary waters which could affect the natural flow or levels of waters on the Canadian side of the line, as well as any construction or maintenance of remedial works, protective works, dams, or other obstructions in waters downstream from boundary waters when the activity could raise the natural level of water on the Canadian side of the boundary.
- **8.** Historic Properties. Any activity authorized by this PGP shall comply with Section 106 of the National Historic Preservation Act. Information on the location and existence of historic resources can be obtained from the Maine Historic Preservation Commission, the National Register of Historic Places, and the Penobscot, Passamaquoddy, Micmac, and Maliseet Tribal Historic Preservation Officers. See Page 17 for historic properties contacts. If the permittee, either prior to construction or during construction of the work authorized herein, encounters a previously unidentified archaeological or other cultural resource, within the area subject to Department of the Army jurisdiction, that might be eligible for listing in the National Register of Historic Places, he/she shall stop work and immediately notify the District Engineer and the Maine Historic Preservation Commission and/or applicable Tribe(s).

- 9. National Lands. Activities authorized by this PGP shall not impinge upon the value of any National Wildlife Refuge, National Forest, National Marine Sanctuary, National Park or any other area administered by the National Park Service.
- 10. Endangered Species. No activity may be authorized under this PGP which:
- is likely to adversely affect a threatened or endangered species, a proposed species, designated critical habitat, or proposed critical habitat as identified under the Federal ESA,
- would result in a "take" of any threatened or endangered species of fish or wildlife, or
- would result in any other violation of Section 9 of the ESA protecting threatened or endangered species of plants.

Applicants shall notify the Corps if any listed species or critical habitat, or proposed species or critical habitat, is in the vicinity of the project and shall not begin work until notified by the District Engineer (DE) that the requirements of the ESA have been satisfied and that the activity is authorized. Information on the location of threatened and endangered species and their critical habitat can be obtained from the U.S. FWS and NMFS (see Page 16 for addresses).

11. Essential Fish Habitat. As part of the PGP screening process, the Corps will coordinate with NMFS in accordance with the 1996 amendments to the Magnuson-Stevens Fishery Conservation and Management Act to protect and conserve the habitat of marine, estuarine and anadromous finfish, mollusks, and crustaceans. This habitat is termed "Essential Fish Habitat (EFH)", and is broadly defined to include "those waters and substrate necessary to fish for spawning, breeding, feeding, or growth to maturity." Applicants may be required to describe and identify potential impacts to EFH. Conservation recommendations made by NMFS will normally be included as a permit requirement by the Corps. For additional information, see the EFH regulations at 50 CFR Part 600 (http://www.nmfs.noaa.gov). Additional information on the location of EFH can be obtained from NMFS (see Page 16 for contact information).

Any work in any aquatic habitat in the following rivers and streams, including all tributaries to the extent that they are currently or were historically accessible for salmon migration, shall not be authorized under Category 1 of the PGP and must be screened for potential impacts to EFH.

Androscoggin River	Hobart Stream	Passagassawaukeag River	Saco River
Aroostook River	Kennebec River	Patten Stream	Sheepscot River
Boyden River	Machias River	Penobscot River	St. Croix River
Dennys River	Narraguagus River	Pleasant River	Tunk Stream
Ducktrap River	Orland River	Presumpscot River	Union River
Fast Machias River		<u>-</u>	

12. Wild and Scenic Rivers. Any activity that occurs in a component of, or within 0.25 mile up or downstream of, the main stem or tributaries of a river segment of the National Wild and Scenic River System, must be reviewed by the Corps under the procedures of Category 2 of this PGP regardless of size of impact. This condition applies to both designated Wild and Scenic Rivers and rivers designated by Congress as study rivers for possible inclusion while such rivers are in an official study status. The Corps will consult with the National Park Service (NPS) with regard to potential impacts of the proposed work on the resource values of the Wild and Scenic River. The culmination of this coordination will be a determination by the NPS and the Corps that the work: (1) may proceed as proposed; (2) may proceed with recommended conditions; or (3) could pose a direct and adverse effect on the resource values of the river and an individual permit is required. If

Maine PGP 9 October 11, 2005 preapplication consultation between the applicant and the NPS has occurred whereby NPS has made a determination that the proposed project is appropriate for authorization under this PGP (with respect to Wild and Scenic River issues), this determination should be furnished to the Corps with submission of the application. (See NPS address on Page 16.) National Wild and Scenic Rivers System segments for Maine as of September 2005 include: Allagash River beginning at Telos Dam continuing to Allagash checkpoint at Eliza Hole Rapids, approximately 3 miles upstream of the confluence with the St. John River (length = 92 miles).

- 13. Federal Navigation Project. Any structure or work that extends closer to the horizontal limits of any Corps Federal Navigation Project (See Appendix B) than a distance of three times the project's authorized depth shall be subject to removal at the owner's expense prior to any future Corps dredging or the performance of periodic hydrographic surveys.
- 14. Navigation. (a) There shall be no unreasonable interference with navigation by the existence or use of the activity authorized herein and no attempt shall be made by the permittee to prevent the full and free use by the public of all navigable waters at or adjacent to the activity authorized herein. (b) The permittee understands and agrees that, if future operations by the United States require the removal, relocation, or other alteration, of the structure or work herein authorized, or if, in the opinion of the Secretary of the Army or his authorized representative, said structure or work shall cause unreasonable obstruction to the free navigation of the navigable waters, the permittee will be required, upon due notice from the Corps of Engineers, to remove, relocate, or alter the structural work or obstructions caused thereby, without expense to the United States. No claim shall be made against the United States on account of any such removal or alteration.
- 15. Federal Liability. In issuing this permit, the Federal Government does not assume any liability for the following: (a) damages to the permitted project or uses thereof as a result of other permitted or unpermitted activities or from natural causes; (b) damages to the permitted project or uses thereof as a result of current or future activities undertaken by or on behalf of the United States (U.S.) in the public interest; (c) damages to persons, property, or to other permitted or unpermitted activities or structures caused by the activity authorized by this permit; (d) design or construction deficiencies associated with the permitted work; (e) damage claims associated with any future modification, suspension, or revocation of this permit.

Minimization of Environmental Impacts

- **16. Minimization.** Discharges of dredged or fill material into waters of the United States, including wetlands, shall be avoided and minimized to the maximum extent practicable. Permittees may only fill those jurisdictional wetlands that the Corps authorizes to be filled and impact those wetlands that the Corps authorizes as secondary impacts. For coastal structures such as piers and docks, the height above the marsh at all points should be equal to or exceed the width of the deck. The height shall be measured from the marsh substrate to the bottom of the longitudinal support beam. This will help ensure sunlight reaches the area beneath the structure.
- 17. Heavy Equipment in Wetlands. Heavy equipment, other than fixed equipment (drill rigs, fixed cranes, etc.), working within wetlands shall not be stored, maintained or repaired in wetlands unless it is less environmentally damaging otherwise, and as much as possible shall not be operated there. Where construction requires heavy equipment operation in wetlands, the equipment shall

either have low ground pressure (<3 psi), or shall not be located directly on wetland soils and vegetation; it shall be placed on swamp or timber mats that are adequate to support the equipment in such a way as to minimize disturbance of wetland soil and vegetation. (See General Condition 18 below.) Other support structures that are less impacting and are capable of safely supporting equipment may be used with written Corps authorization. Similarly, not using mats during frozen, dry or other conditions may be allowed with written Corps authorization. An adequate supply of spill containment equipment shall be maintained on site.

NOTE: "Swamp mats" is a generic term used to describe structures that distribute equipment weight to prevent wetland damage while facilitating passage and providing work platforms for workers and equipment. They are comprised of sheets or mats made from a variety of materials in various sizes, and they include large timbers bolted or cabled together (timber mats). Corduroy roads, which are not considered to be swamp mats, are cut trees and/or saplings with the crowns and branches removed, and the trunks lined up next to one another.

- 18. Temporary Fill. Fill placed into waters of the U.S. (including wetlands) totaling greater than or equal to 4,300 SF (15,000 SF if a DEP Tier One Permit is issued) in total area (i.e., the sum of permanent and temporary fill areas) exceeds the Category 1 threshold and may not be discharged without written authorization from the Corps. When temporary fill is used (e.g., access roads, swamp mats, cofferdams), it shall be stabilized and maintained during construction in such a way as to prevent soil eroding into portions of waters of the U.S. where it is not authorized. Swamp or timber mats (see Gen.Cond. 17 above) are considered as temporary fill when they are removed immediately upon work completion. The area must be restored in accordance with Gen.Cond. 19.
- Unconfined temporary fill authorized for discharge into flowing water (rivers and streams) shall consist only of clean washed stone.
- Temporary fill authorized for discharge into wetlands shall be placed on geotextile fabric laid on the pre-construction wetland grade. (Swamp and timber mats are excluded from this requirement.)
- Temporary fill shall be removed as soon as it is no longer needed, and it shall be disposed of at an upland site and suitably contained to prevent subsequent erosion into waters of the U.S.
- Waters of the U.S. where temporary fill was discharged shall be restored (see Gen.Cond. 19).
- No temporary work shall drain a water of the U.S. by providing a conduit for water on or below the surface.

19. Restoration.

- Upon completion of construction, all disturbed wetland areas (the disturbance of these areas must be authorized) shall be stabilized with a wetland seed mix containing only plant species native to New England.
- The introduction or spread of invasive plant species in disturbed areas shall be controlled.
- In areas of authorized temporary disturbance, if trees are cut they shall be cut at ground level and not uprooted in order to prevent disruption to the wetland soil structure and to allow stump sprouts to revegetate the work area, unless otherwise authorized.
- Wetland areas where permanent disturbance is not authorized shall be restored to their original condition and elevation, which under no circumstances shall be higher than the pre-construction elevation. Original condition means careful protection and/or removal of existing soil and vegetation, and replacement back to the original location such that the original soil layering and vegetation schemes are approximately the same, unless otherwise authorized.

- 20. Coastal Bank Stabilization. Projects involving construction or reconstruction/maintenance of bank stabilization structures within Corps jurisdiction should be designed to minimize environmental effects, effects to neighboring properties, scour, etc. to the maximum extent practicable. For example, vertical bulkheads should only be used in situations where reflected wave energy can be tolerated. This generally eliminates bodies of water where the reflected wave energy may interfere with or impact on harbors, marinas, or other developed shore areas. A revetment is sloped and is typically employed to absorb the direct impact of waves more effectively than a vertical seawall. It typically has a less adverse effect on the beach in front of it, abutting properties and wildlife. For more information, see the Corps Coastal Engineering Manual (supersedes the Shore Protection Manual), located at http://chl.erdc.usace.army.mil. Select "Products/ Services," "Publications." Part 5, Chapter 7-8, a(2)c is particularly relevant.
- 21. Sedimentation and Erosion Control. Adequate sedimentation and erosion control management measures, practices and devices, such as phased construction, vegetated filter strips, geotextile silt fences, hay bales or other devices, shall be installed and properly maintained to reduce erosion and retain sediment on-site during and after construction. They shall be capable of preventing erosion, of collecting sediment, suspended and floating materials, and of filtering fine sediment. These devices must be removed in a timely manner upon completion of work, but not until the disturbed areas have been stabilized. The sediment collected by these devices shall be removed and placed at an upland location in a manner that will prevent its later erosion into a waterway or wetland. All exposed soil and other fills shall be permanently stabilized at the earliest practicable date.

22. Waterway Crossings.

- (a) All temporary and permanent crossings of waterbodies (waterways and wetlands) shall be suitably culverted, bridged, or otherwise designed to withstand and to prevent the restriction of high flows, to maintain existing low flows, and to not obstruct the movement of aquatic life indigenous to the waterbody beyond the actual duration of construction. (NOTE: Areas of fill and/or cofferdams must be included in total waterway/wetlands impacts to determine applicability of this PGP). (b) Aquatic Life Movements. No activity may substantially disrupt the necessary life-cycle movements of those species of aquatic life indigenous to the waterbody, including those species that normally migrate through the area, unless the activity's primary purpose is to impound water. For new permanent crossings, open bottom arches, bridge spans or embedded culverts are generally preferred over traditional culverts and should be installed when practicable. Coordination with the Corps is recommended for Category 1 projects when site constraints (e.g., placing footings) may render open bottom arches, bridge spans or embedded culverts impractical. In these cases, welldesigned culverts may actually perform better. Culverts shall be installed with their inverts embedded below existing streambed grade to avoid "hanging" and associated impediments to fish passage. The "Design of Road Culverts for Fish Passage" provides design guidance and is available at www.nae.usace.army.mil, "Regulatory/Permitting," "Other."
- (c) Culverts at waterbody crossings shall be installed in such a manner as to preserve hydraulic connectivity, at its present level, between the wetlands on either side of the road. The permittee shall take necessary measures to correct wetland damage due to lack of hydraulic connectivity. (d) Culverts and bridges shall span the waterway a minimum of 1.2 times the bankfull width in probable fish bearing waterways to qualify as a Category 1 non-reporting activity. See "Design of Road Culverts for Fish Passage," referenced in (b) above, for information on bankfull width.

Maine PGP 12 October 11, 2005 276

- (e) Projects using slip lining (retrofitting an existing culvert by inserting a smaller diameter pipe), plastic pipes, and High Density Polyethylene Pipes (HDPP) are not allowed as non-reporting Category 1 activities, either as new work or maintenance activities.
- (f) Waterbody crossings shall be culverted to at least municipal or State standards. The Maine DEP's stream crossing standards are at 06-096, Chapter 305: Permit by Rule, Section 10. Stream crossings (bridges, culverts and fords).
- (g) Waterway crossings proposed by the Maine Dept. of Transportation should conform to the MDOT Fish Passage Policy and Design Guides.
- (h) Construction equipment shall not cross streams without the use of temporary bridges, culverts, or cofferdams.
- (i) For projects that otherwise meet the terms of Category 1, in-stream construction work shall be conducted during the low flow period July 15 - October 1 in any year. Projects that are not to be conducted during that time period are ineligible for Category 1 and shall be screened pursuant to Category 2, regardless of the waterway and wetland fill and/or impact area.
- 23. Discharge of Pollutants. All activities involving any discharge of pollutants into waters of the U.S. authorized under this PGP shall be consistent with applicable water quality standards, effluent limitations, standards of performance, prohibitions, and pretreatment standards and management practices established pursuant to the CWA (33 USC 1251) and applicable State and local laws. If applicable water quality standards, limitations, etc., are revised or modified during the term of this PGP, the authorized work shall be modified to conform with these standards within six months of the effective date of such revision or modification, or within a longer period of time deemed reasonable by the District Engineer in consultation with the Regional Administrator of the EPA. Applicants may presume that State water quality standards are met with the issuance of a LURC or DEP NRPA permit.
- 24. Spawning Areas. Discharges of dredged or fill material, and/or suspended sediment producing activities in fish and shellfish spawning or nursery areas and amphibian and waterfowl breeding areas during spawning or breeding seasons shall be avoided. During all times of year, impacts to these areas shall be avoided or minimized to the maximum extent practicable.
- 25. Storage of Seasonal Structures. Coastal structures, such as pier sections and floats, that are removed from the waterway for a portion of the year (often referred to as seasonal structures) shall be stored in an upland location located above mean high water (MHW) and not in tidal wetlands. These seasonal structures may be stored on the fixed, pile-supported portion of the structure that is seaward of MHW. This is intended to prevent structures from being stored on the marsh substrate and the substrate seaward of MHW. Seasonal storage of structures in navigable waters, e.g., in a protected cove on a mooring, requires Corps and local harbormaster approval.
- 26. Environmental Functions and Values. The permittee shall make every reasonable effort to carry out the construction or operation of the work authorized herein in a manner so as to maintain as much as is practicable, and minimize any adverse impacts on existing fish, wildlife, and natural environmental functions and values.
- 27. Protection of Vernal Pools. Impacts to uplands in proximity (within 500 feet) to the vernal pools referenced in Appendix A - Definitions of Categories, shall be minimized to the maximum extent possible.

Maine PGP 13 October 11, 2005

Procedural Conditions

- **28.** Cranberry Development Projects. For cranberry development projects authorized under the PGP, the following conditions apply:
- If a cranberry bog is abandoned for any reason, the area must be allowed to revert to natural wetlands unless an Individual Permit is obtained from the Corps allowing the discharge of fill for an alternate use.
- No stream diversion shall be allowed under this permit.
- No impoundment of perennial streams shall be allowed under this permit.
- The project shall be designed and constructed to not cause flood damage on adjacent properties.
- **29. Inspections.** The permittee shall allow the District Engineer (DE) or his authorized representative(s) to make periodic inspections at any time deemed necessary in order to ensure that the work is being performed in accordance with the terms and conditions of this permit. The DE may also require post-construction engineering drawings for completed work and post-dredging survey drawings for any dredging work.
- **30.** Work Start Notification Form and Compliance Certification. Every permittee who receives a written Category 1 or 2 PGP authorization from the Corps must submit a 1) Work Start Notification Form (WSNF) two weeks before work commencement, and 2) signed Compliance Certification Form within one month following the completion of the authorized work and any required mitigation (but not mitigation monitoring, which requires separate submittals). The Corps will forward the blank WSNF and Compliance Certification Form with the authorization letter. The Compliance Certification Form will include: (a) a statement that the authorized work was done in accordance with the Corps authorization, including any general or specific conditions; (b) a statement that any required mitigation was completed in accordance with the permit conditions; and (c) the signature of the permittee certifying the completion of the work and mitigation.
- **31. Maintenance.** The permittee shall maintain the work or structures authorized herein in good condition and in conformance with the terms and conditions of this permit. This does not include maintenance of dredging projects. Maintenance dredging is subject to the review thresholds in Appendix A and/or any conditions included in a written Corps authorization. Maintenance dredging includes only those areas and depths previously authorized and dredged. Some maintenance activities may not be subject to regulation under Section 404 in accordance with 33 CFR 323.4(a)(2).
- **32. Property Rights.** This permit does not convey any property rights, either in real estate or material, or any exclusive privileges, nor does it authorize any injury to property or invasion of rights or any infringement of Federal, State, or local laws or regulations. If property associated with work authorized by the PGP is sold, the PGP authorization is automatically transferred to the new property owner. The new property owner should provide this information to the Corps in writing. No acknowledgement from the Corps is necessary.
- **33. Modification, Suspension, and Revocation.** This permit may be either modified, suspended, or revoked, in whole or in part, pursuant to the policies and procedures of 33 CFR 325.7. Any such action shall not be the basis for any claim for damages against the United States.

- **34. Restoration.** The permittee, upon receipt of a notice of revocation of authorization under this permit, shall restore the wetland or waterway to its former condition without expense to the United States and as directed by the Secretary of the Army or his authorized representative. If the permittee fails to comply with such a directive, the Secretary or his designee may restore the wetland or waterway to its former condition, by contract or otherwise, and recover the cost from the permittee.
- **35.** Special Conditions. The Corps, independently or at the request of the Federal resource agencies, may impose other special conditions on a project authorized pursuant to this general permit that are determined necessary to minimize adverse environmental effects or based on any other factor of the public interest. Failure to comply with all conditions of the authorization, including special conditions, will constitute a permit violation and may subject the permittee to criminal, civil, or administrative penalties or restoration.
- **36.** False or Incomplete Information. If the Corps makes a determination regarding the eligibility of a project under this permit and subsequently discovers that it has relied on false, incomplete, or inaccurate information provided by the permittee, the permit shall not be valid and the government may institute appropriate legal proceedings.
- 37. Abandonment. If the permittee decides to abandon the activity authorized under this general permit, unless such abandonment is merely the transfer of property to a third party, he/she must restore the area to the satisfaction of the District Engineer.

Duration of Authorization/Grandfathering:

- **38. Duration of Authorization.** This PGP expires five years from the effective date listed at the top of Page 1. Activities authorized under Category 1 of this PGP that have commenced (i.e., are under construction) or are under contract to commence in reliance upon this PGP's authorization will remain authorized provided the activity is completed within 12 months of the PGP's expiration date. Activities authorized under Category 2 of this PGP will remain authorized in accordance with the project-specific date that the Corps provides to the permittee in the PGP authorization letter, unless:
- (a) The PGP is either modified or revoked, or
- (b) Discretionary authority has been exercised on a case-by-case basis to modify, suspend, or revoke the authorization in accordance with 33 CFR 325.2 (e)(2).

39. Previously Authorized Activities.

- (a) Activities completed under the authorizations of past PGPs that were in effect at the time the activity was completed will continue to be authorized by those PGPs.
- (b) Completed projects that have received written verification or approval from the Corps, based on applications made to the Corps prior to issuance of this PGP or the previous nationwide permits, regional general permits, or letters of permission shall remain authorized as specified in each authorization.
- (c) Activities authorized pursuant to 33 CFR Part 330.3 ("Activities occurring before certain dates") are not affected by this PGP.

VI. CONTACTS FOR MAINE PROGRAMMATIC GENERAL PERMIT:

1. FEDERAL

U.S. Army Corps of Engineers
Maine Project Office
675 Western Avenue #3
Manchester, Maine 04351
(207) 623-8367
(207) 623-8206 (fax)

Federal Endangered Species
U.S. Fish and Wildlife Service
Maine Field Office
1168 Main Street
Old Town, Maine 04468
(207) 827-5938

(207) 827-5938 207-827-6099 (fax)

Wild and Scenic Rivers
National Park Service
North Atlantic Region
15 State Street
Boston, Massachusetts 02109
(617) 223-5203

2. STATE OF MAINE

Maine Department of Environmental Protection
(For State Permits & Water Quality Certifications)
Division of Land Resource Regulation
Bureau of Land and Water Quality
17 State House Station

Augusta, Maine 04333 (207) 287-2111

Eastern Maine Regional Office 106 Hogan Road Bangor, Maine 04401 (207) 941-4570

Maine Land Use Regulation Commission (LURC)
[call (800) 452-8711 for appropriate LURC office]
22 State House Station
Augusta, ME 04333-0022
(207) 287-2631
(207) 287-7439 (fax)

Federal Endangered Species & Essential Fish Habitat
National Marine Fisheries Service
One Blackburn Drive
Gloucester, Massachusetts 01939
(978) 281-9102
(978) 281-9301 (fax)

Bridge Permits
Commander (obr)
First Coast Guard District
One South Street - Battery Bldg
New York, New York 10004
(212) 668-7021

Southern Maine Regional Office 312 Canco Road Portland, Maine 04103 (201) 822-6300

Northern Maine Regional Office 1235 Central Drive - Skyway Park Presque Isle, Maine 04769 (207) 764-0477

45 Radar Road Ashland, ME 04732-3600 (207) 435-7963 (207) 435-7184 (fax) Lakeview Drive P.O. Box 1107 Greenville, ME 04441 (207) 695-2466 (207) 695-2380 (fax)

(For CZM Determinations)

State Planning Office Coastal Program 184 State Street State House Station 38 Augusta, Maine 04333 (207) 287-1009

(For Submerged Lands Leases)

Maine Department of Conservation Bureau of Parks and Lands 22 State House Station Augusta, Maine 04333 (207) 287-3061 191 Main Street East Millinocket, ME 04430 (207) 746-2244 (207) 746-2243

(For Aquaculture Leases)

Maine Department of Marine Resources P.O. Box 8
West Boothbay Harbor, Maine 04575
(207) 633-9500

3. HISTORIC PROPERTIES

Maine Historic Preservation Commission
State House Station 65
Augusta, Maine 04333-0065
(207) 287-2132
(207) 287-2335 (fax)

Aroostook Band of Micmacs

Attn: Mr. Williams Phillips, Chief 7 Northern Road Presque Isle, Maine 04769 (207) 764-1972 (207) 764-7667 (fax)

Houlton Band of Maliseet Indians

Attn: Tribal Chief 88 Bell Road Littleton, Maine 04730 (207) 532-4273, x215 (207) 532-2660 (fax) Passamaquoddy Tribe of Indians

Pleasant Point Reservation Attn: Tribal Council P.O. Box 343 Perry, Maine 04667 (207) 853-2600 (207) 853-6039 (fax)

Passamaquoddy Tribe of Indians

Indian Township Reservation Attn: Donald Soctomah, THPO P.O. Box 301 Princeton, Maine 04668 (207) 796-2301 (207) 796-5256 (fax)

Penobscot Indian Nation

Indian Island Reservation Attn: Ms. Bonnie Newsom, THPO 12 Wabanaki Way Indian Island, Maine 04468 (207) 817-7471 (207) 817-7450 (fax)

4. ORGANIZATIONAL WEBSITES:

Army Corps of Engineers

Corps of Engineers Headquarters

Environmental Protection Agency National Marine Fisheries Service

U.S. Fish and Wildlife Service

National Park Service

State of Maine

www.nae.usace.army.mil (click "Regulatory/Permitting")

www.usace.army.mil (click "Services for the Public")

www.epa.gov/owow/wetlands/

www.nmfs.noaa.gov

www.fws.gov

www.nps.gov/rivers/index.html

www.maine.gov

State of Maine -Aquaculture Guidelines www.maine.gov/dmr/aquaculture/index.htm

District Engineer Date

Date

A. INLAND WATERS AND WETLANDS	Inland Waters and Wetlands: Waters that are regulated under Section 404 of the Clean Water Act, including rivers, streams, lakes, ponds and wetlands, and excluding Section 10 Navigable Waters of the U.S. The jurisdictional limits are the ordinary high water (OHW) mark in the absence of adjacent wetlands, beyond the OHW mark to the limit of adjacent wetlands when adjacent wetlands are present, and the wetland limit when only wetlands are present. For the purposes of this PGP, fill placed in the area between the mean high water (MHW) and the high tide line (HTL), and in the bordering and contiguous wetlands ¹ to tidal waters are reviewed in the Navigable Waters section. (See II. Navigable Waters on the next page.)	ulated under Section 404 of the Clean Water Act igable Waters of the U.S. The jurisdictional limi beyond the OHW mark to the limit of adjacent ware present. For the purposes of this PGP, fill pland in the bordering and contiguous wetlands [†] to the son the next page.)	t, including rivers, streams, lakes, its are the ordinary high water etlands when adjacent wetlands are ced in the area between the mean idal waters are reviewed in the
	CATEGORY 1	CATEGORY 2	INDIVIDUAL PERMIT
(a) NEW FILL/ EXCAVATION DISCHARGES	 <4,300 SF inland waterway and/or wetland fill and associated secondary impacts (e.g., areas drained, flooded, cleared or excavated). Fill area includes all temporary and permanent fill, and excavation discharges (except for incidental fallback). Swamp mats are considered as fill. [See General Condition (GC) 18.] Provided: In-stream (e.g., rivers, streams, brooks, etc.) work limited to Jul 15 - Oct 1 In-stream work of up to 4,300 SF of fill below OHW in waterways not designated as EFH for Atlantic salmon (see GC 11, Page 9) and performed in accordance with Maine Permit By Rule standards or a LURC permit. Waterway crossings shall comply with GC 22. Projects covered by a DEP Tier One permit with no cumulative impacts >15,000 SF in inland wetlands from previous permits, unauthorized work, and/or other state permits. Subdivision fill complies with GC 5, Single and Complete Projects (see Page 7). This category excludes: Dams, dikes or activities involving water diversions. Non-State approved sediment releases/sluices from dams. 	4,300 SF to <3 acres inland waterway and/or wetland fill and associated secondary impacts (e.g., areas drained, flooded, cleared or excavated). Fill area includes all temporary and permanent fill, and excavation discharges (except for incidental fallback). Swamp mats filling any area ≥4,300 SF are reviewed in Category 2. (See GC 18, Page 11.) Includes: In-stream work, including crossings (other than spanned crossing as described in Category 1) with any discharge of fill below ordinary high water in perennial waterways designated as EFH for Atlantic salmon. Time of year restrictions determined case-by-case. Projects with proactive restoration as a primary purpose with impacts of any area ≥4,300 SF. The Corps, in consultation with State & Federal agencies, must determine that net adverse effects are not more than minimal. Specific activities with impacts of any area ≥4,300 SF required to affect the containment, stabilization, or removal of hazardous or toxic waste materials that are performed, ordered, or sponsored by a government agency with established legal or regulatory authority. Wetlands must be restored in place.	>3 acres inland waterway and/or wetland fill and secondary impacts (e.g., areas drained, flooded, cleared or excavated). Fill area includes all temporary and permanent fill, and excavation discharges (except for incidental fallback). ⁵ EIS required by the Corps. In-stream work exceeding Category 2 limits.
88 Maine PGP	 Open trench excavation in flowing waters (see GC 22, Page 12). 		October 11, 2005

$^{\circ}$
\circ
Ü
Τ,
_
October

~

	CATEGORY 1	CATEGORY 2	INDIVIDUAL PERMIT
	 Work in waters designated as EFH for Atlantic salmon (see GC 11, Page 9), unless the waterway is crossed with a span and footprints of the span abutments are outside ordinary high water with no more than 4,300 SF of associated wetland impact. Work in Special Inland Waters or Wetlands (vernal pools). Work in special aquatic sites (SAS)⁴ other than wetlands. Work within ½ mile of a Wild and Scenic River (see GC 12, Page 9). Work on National Lands (see GC 9, Pg. 9). Work affecting threatened or endangered species (see GC 10, Page 9) or EFH salmon migration (see GC 11, Page 9). 		
(b) BANK STABILIZATION PROJECTS	Inland bank stabilization <100 FT long and <1 CY of fill per linear foot below OHW.	Inland bank stabilization ≥100 FT long and/or ≥1 CY of fill per linear foot, or any amount with fill in wetlands.	
(c) REPAIR AND MAINTENANCE OF AUTHORIZED FILLS	Repair or maintenance of existing, currently serviceable, authorized fills with no substantial expansion or change in use. *Conditions of the original authorization apply, however minor deviations in fill design allowed.	Replacement of non-serviceable fills, or repair/maintenance of serviceable fill, with expansion <3 acres, or with a change in use.	Replacement of non-serviceable fill, or repair/maintenance of serviceable fill, with expansion ≥1 acre.

II. NAVIGABLE	Navigable Waters of the United States: Waters that are subject to the ebb and flow of the tide and Federally designated navigable	that are subject to the ebb and flow of the tide an	nd Federally designated navigable
WATERS	Invers (the Penobscot Kiver, Kennebec Kiver, and Lake Umbagog) (Section 10 Kivers and Harbors Act of 1899). The jurisdictional limits are the mean high water (MHW) line in tidal waters and the ordinary high water (OHW) mark in non-tidal portions of the Federally designated navigable rivers. For the purposes of this PGP, fill placed in the area between the mean high water (MHW) and the high tide line (HTL), and in the bordering and contiguous wetlands to tidal waters are also reviewed in this Navigable Waters section.	I Lake Umbagog) (Section 10 Kilvers and Harbor al waters and the ordinary high water (OHW) mainposes of this PGP, fill placed in the area betweed contiguous wetlands to tidal waters are also resisted.	s Act of 1899). The jurisal chonal ark in non-tidal portions of the an the mean high water (MHW) and viewed in this Navigable Waters
	CATEGORY 1	CATEGORY 2	INDIVIDUAL PERMIT
(a) FILL	Discharges of dredged or fill material incidental to the construction of bridges across navigable waters of the United States, including cofferdams, abutments, foundation seals, piers, and temporary construction and access fills provided the U.S. Coast Guard authorizes such discharges as part of the bridge permit. Causeways and approach fills are not included in this category and require Category 2 or Individual Permit authorization.	<1 acre fill and/or secondary waterway impacts (e.g., areas drained, flooded or cleared). Fill includes temporary and permanent waterway fill. Temporary fill or excavation <1 acre in SAS ⁴ . Permanent fill or excavation <1,000 SF in SAS ⁴ . Permanent fill and/or excavation ≥1,000 SF in SAS ⁵ when associated with a project with proactive restoration as a primary purpose. The Corps, in consultation with Federal & state agencies, must determine that net adverse effects are not more than minimal. Specific activities with impacts of any area required to affect the containment, stabilization, or removal of hazardous or toxic waste materials that are performed, ordered,	≥1 acre waterway fill and/or secondary waterways or wetland impacts (e.g., areas drained, flooded or cleared). Fill includes temporary and permanent waterway fill. Temporary fill or excavation ≥1 acre in SAS⁴. Permanent fill or excavation ≥1,000 SF in SAS⁴ other than as specified in Cat. 2 EIS required by the Corps.
		or sponsored by a government agency with established legal or regulatory authority. Wetlands must be restored in place.	
(b) REPAIR AND MAINTENANCE WORK	Repair or maintenance of existing, currently serviceable, authorized structure or fill with no substantial expansion or change in use. *Conditions of the original authorization apply. Must be rebuilt in same footprint, however minor deviations in structure design allowed ⁶	Replacement of non-serviceable structures and fills or repair/maintenance of serviceable structures or fills, with fill, replacement or expansion <1 acre, or with a change in use.	Replacement of non-serviceable structures and fills or repair/maintenance of serviceable structures or fill, with replacement or expansion ≥ 1 acre.

m

	CATEGORY 1	CATEGORY 2	INDIVIDUAL PERMIT
(c) DREDGING AND ASSOCIATED DISPOSAL	Maintenance dredging for navigational purposes <1,000 cy with upland disposal. Includes return water from upland contained disposal area. Provided: Proper siltation controls are used. Dredging & disposal operation limited to November 1 - January 15. No impact to special aquatic sites ⁴ . No dredging in intertidal areas. No work affects threatened or endangered species (see GC 10, Page 9) or EFH salmon migration (see GC 11, Page 9).	Maintenance dredging ≥1,000 CY, new dredging <25,000 CY, or projects not meeting Category 1. Includes return water from upland contained disposal areas. Provided: ■ Disposal includes 1) upland, 2) beach nourishment (above MHW) of any area provided dredging's primary purpose is navigation or sand is from an upland source and Corps, in consultation w/Federal and State agencies, determines the net adverse effects are not more than minimal; and 3) open water & confined aquatic disposal, if Corps, in consultation with Federal and State agencies, finds the material suitable.	Maintenance dredging and/or disposal (any amount) in or affecting a SAS ⁴ . See II(a) above for dredge disposal in wetlands or waters. New dredging ≥25,000 CY, or any amount in or affecting SAS ⁴ . Beach nourishment associated with dredging when the primary purpose is not navigation (i.e., aggregate/sand mining) or the material is from an upland source.
(d) MOORINGS	Private, non-commercial, non-rental, singleboat moorings authorized by the local harbormaster. Provided: Not associated with any boating facility? Not located in a Federal Navigation Project other than a Federal Anchorage. Moorings in Federal Anchorage not associated with a boating facility? No interference with navigation Not located in vegetated shallows? Within ¼ mile of the owner's residence or a public access point. Minor relocation of previously authorized moorings and moored floats consistent with Harbormaster recommendations, provided it is also consistent with local regulations, is not located in vegetated shallows, and does not interfere with navigation.	Moorings associated with a boating facility'. Moorings that don't meet the terms in Category 1 and don't require an Individual Permit. Moorings located such that they, and/or vessels docked or moored at them, are within the buffer zone of the horizontal limits¹o of a Corps Federal Channel. (See Appendix B.) The buffer zone is equal to three times the authorized depth of that channel.	Moorings within the horizontal limits ¹⁰ , or with moored vessels that extend, into the horizontal limits of a Federal Navigation Project (See App. B), except those in Federal Anchorages under Category 1. Note: Federal Navigation Projects include both Federal Channels and Federal Anchorages.
% Maine PGP		4	October 11, 2005

	CATEGORY 1	CATEGORY 2	INDIVIDUAL PERMIT
(e) STRUCTURES AND FLOATS	Reconfiguration of existing authorized structures or floats. Provided: Structures not positioned over vegetated shallows ⁸ or salt marsh. Floats supported off substrate at low tide. No dredging, additional slips or expansion. No work affects threatened or endangered species (see GC 10, Page 9) or EFH salmon migration (see GC 11, Page 9)	Private structures or floats, including floatways/skidways, built to access waterway (seasonal and permanent) Expansions to existing boating facilities?. Compliance with the following is recommended, but not required: • Pile-supported structures <400 SF, with attached floats totaling <200 SF. • Bottom anchored floats <200 SF. • Structures are <4' wide and have at least a	Structures or floats, including floatways/skidways, located such that they and/or vessels docked or moored at them are within the horizontal limits of a Corps Federal Navigation Project (see App. B). Structures and floats associated with a new or previously unauthorized boating facility?
		 1:1 height:width ratio¹¹. Floats supported above the substrate during all tides. Structures & floats not located within 25' of any vegetated shallows⁸. Moored vessels not positioned over SAS⁴. No structure located within 25' of the riparian property boundary. No structure extends across >25% of the waterway width at mean low water. Not located within the buffer zone of the horizontal limits¹⁰ of a Corps Federal Navigation Project (FNP) (See App. B). The buffer zone is equal to three times the authorized depth of that FNP. 	Note: Federal Navigation Projects include both Federal Channels and Federal Anchorages.
(f) MISCELLANEOU	(f) MISCELLANEOUS recreational use during specific events, provided they are removed within 30 days after use is discontinued. The placement of aids to navigation and regulatory markers which are approved by and installed in accordance with the requirements of the U.S. Coast Guard. (See 33 CFR part 66, Chapter I, subchapter C)."	Structures or work in or affecting tidal or navigable waters, that are not defined under any of the previous headings listed above. Includes, but is not limited to, utility lines, aerial transmission lines, pipelines, outfalls, boat ramps, floatways/skidways, bridges, tunnels and horizontal directional drilling activities seaward of the MHW line.	EIS required by the Corps. Shellfish/finfish (other than Atlantic salmon), or other aquaculture facilities with more than minimal individual and cumulative impacts to environmental resources or navigation. A 25' eelgrass set back is recommended.
28 Maine PGP		5	October 11, 2005

Oil spill clean-up temporary structures or fill. Fish/wildlife harvesting structures/fill (as defined by 33 CFR 330, App. A-4)	Shellfish/finfish (other than Atlantic salmon), or other aquaculture facilities with no more than minimal individual and cumulative	Aquaculture guidelines are provided at: www.maine.gov/dmr/aquaculture/index.htm.
	impacts to environmental resources or navigation. A 25' eelgrass set back is recommended. Aquaculture guidelines are provided at: www.maine.gov/dmr/	
include oil and gas exploration and fill for roads or construction pads.	aquaculture/index <u>.htm.</u>	
Shellfish seeding (brushing the flats ¹²) projects.		
Provided: No work in National Wildlife Refuges.		
 No work affects threatened or endangered species (see GC 10, Page 9) or EFH salmon migration (see GC 11, Page 9). 		

navigable waters) of that waterbody and is directly influenced by its hydrologic regime. Contiguous wetlands extend landward from their adjacent waterbody to a point where a natur or manmade discontinuity exists. Contiguous wetlands include bordering wetlands as well as wetlands that are situated immediately above the ordinary highwater mark and above the ¹ Bordering and Contiguous Wetlands: A bordering wetland is immediately next to its adjacent waterbody and may lie at, or below, the ordinary highwater mark (MHW in normal hydrologic influence of their adjacent waterbody. Note, with respect to the Federally designated navigable rivers, the wetlands bordering and contiguous to the tidally influenced portions of those rivers are reviewed under "II. Navigable Waters."

² Water Diversions: Water diversions are activities such as bypass pumping or water withdrawals. Temporary flume pipes, culverts or cofferdams where normal flows are maintaine within the stream boundary's confines aren't water diversions. "Normal flows" are defined as no change in flow from pre-project conditions.

during the summer. Vernal pools have no permanent or viable populations of predatory fish. Vernal pools provide the primary breeding habitat for wood frogs, spotted salamanders, ³ Special Inland Waters and Wetlands: Vernal Pools - Temporary to permanent bodies of water occurring in shallow depressions that fill during the spring and fall and may dry blue-spotted salamanders, and fairy shrimp, and provide habitat for other wildlife including several endangered and threatened species.

⁴Special Aquatic Sites: Includes wetlands and saltmarsh, mudflats, riffles and pools, and vegetated shallows.

IP Required: The greater the impacts, the more likely an Individual Permit will be required. The Corps will determine the need for compensatory mitigation on a case-by-case basi safety standards, which are necessary to make repair, rehabilitation, or replacement are permitted, provided the adverse environmental effects resulting from such repair, rehabilitation ⁶ Maintenance: Minor deviations in the structure's configuration or filled area, including those due to changes in materials, construction techniques, or current construction codes or or replacement are minimal. No seaward expansion for bulkheads or any other fill activity is considered Category 1 maintenance. Currently serviceable means useable as is or with some maintenance, but not so degraded as to essentially require reconstruction.

Boating Facilities: Facilities that provide, rent, or sell mooring space, such as marinas, yacht clubs, boat clubs, boat yards, town facilities, dockominiums, etc.

⁸ Vegetated Shallows: Subtidal areas that support rooted aquatic vegetation such as eelgrass

⁹ Mooring Location: Cannot be at a remote location to create a convenient transient anchorage.

¹⁰ Horizontal Limits: The outer edge of a Federal Navigation Project (FNP). Contact the Corps of Engineers for information on FNP's.

[&]quot;Structures: The height of structures shall at all points be equal to or exceed the width of the deck. For the purpose of this definition, height shall be measured from the marsh substrate to the bottom of the longitudinal support beam.

¹² Brushing the Flats: The placement of tree boughs, wooden lath structure, or small-mesh fencing on mudflats to enhance recruitment of soft-shell clams (Mya arenaria).

ME PGP - Appendix B