Preliminary Design Report

Johnson Road Bridge #5792 over Interstate 295

Falmouth, Maine

STP-02172(100) WIN 21721.00



Maine Department of Transportation Bridge Program

TABLE OF CONTENTS

Background Information	1
Existing Bridge	2
Location Map	3
Bridge Recommendation Form	4
Summary of Expected Impacts	6
Summary of Preliminary Design	7
Preliminary Plans	Appendix A
Photographs	Appendix B
Inspection Report	Appendix C
Existing Bridge Plans	Appendix D
Load Rating	Appendix E
Johnson Road Traffic Model Summary	Appendix F
Traffic and Accident Data	Appendix G
2016 Falmouth Bicycle & Pedestrian Plan	Appendix H
Current and Future Falmouth Development & Transportation Projects	Appendix I
Town of Falmouth – Route 1 North Vision Plan	Appendix J
Pier Concrete Chloride Testing	Appendix K
Preliminary Construction Schedules	Appendix L
Preliminary Cost Estimates	Appendix M

BACKGROUND INFORMATION

TOWN Falmouth **WIN** 21721.00 BRIDGE NO. 5792

N/A **BRIDGE** Johnson Road Bridge STATE ROUTE

FUNDING: State

PROGRAM SCOPE: **Bridge Rehabilitation**

2036 **AADT** 1,730

PROGRAM DESCRIPTION: Rehabilitation of Johnson Road/I-295 Bridge (No. 5792) over

Interstate 295, located 0.25 of a mile west of Route 1.

PROJECT BACKGROUND: This bridge was constructed in 1957 with minor rehabilitation

> work completed in 1991. The deck is currently in fair condition while the substructure is in poor condition with signs of advanced

deterioration.

JURISDICTION State Highway NHS No **FUNCTIONAL CLASSIFICATION** Local Road **CORRIDOR PRIORITY** 6 URBAN/RURAL Rural **FHWA SUFFICIENCY RATING** 35.5 **LOAD POSTING** Open, no restriction POSTED SPEED 35 mph TRAFFIC: 2016 **AADT** 1,440 **ACCIDENT DATA, CRF** 0.19

DHV

190

EXISTING BRIDGE

YEAR BUILT 1957 **SPAN LENGTHS** 39.75'-59'-59'-62' **CURB TO CURB WIDTH** 26'

TYPE OF SUPERSTRUCTURE: Four-Span Bridge composed of two separate superstructures as follows: A one-Span non-composite steel beam superstructure and a three-span continuous steel beam superstructure with both composite and noncomposite sections. The bridge has a cast-in-place deck and painted steel beams and bituminous wearing surface. Bridge rails consist of 1' wide concrete parapets topped by aluminum alloy guardrail.

GENERAL CONDITION: Steel beams are in generally satisfactory condition (6) with prevalent light rusting. Concrete deck is in fair condition (5) with minor transverse cracking with light efflorescent staining and isolated delamination and spalling with exposed rebar. Wearing surface has minor to moderate alligator cracking.

TYPE OF SUBSTRUCTURE: Concrete stub abutments on H-piles. Concrete 3-column piers on Hpiles.

GENERAL CONDITION: The substructure is in poor condition (4). Abutments and wingwalls have scattered minor cracking. West pier cap has prevalent moderate cracking and isolated areas of spalled and delaminated concrete and shear cracking at the north face bearing area. West pier bearings are severely misaligned and are in need of rehabilitation.

LOAD RATINGS: OPERATING INVENTORY HL-93 Truck 27.72 Tons 21.24 Tons 0.77 0.59 Rating Factor

LEGAL LOADS

Controlling Configuration: Configuration 3

> Rating Factor 0.83

Controlling Member: Interior Girder (Negative Moment over Pier 3)

STRUCTURALLY DEFICIENT

FUNCTIONALLY OBSOLETE

Yes

MAINTENANCE PROBLEMS: Maintenance issues include deterioration of the bituminous wearing surface, vehicular damage of the West end bridge rail, cracking and exposed rebar on the underside of the deck, misaligned bearings at the West Pier and cracking and deterioration of pier columns and abutment backwalls.


MAINTENANCE WORK: Evidence of patching on piers.

PREVIOUS STRUCTURE: Original structure

OTHER COMMENTS: None

LOCATION MAP

Falmouth, Johnson Road Bridge #5792, WIN 21721.00 Johnson Road over Interstate 295





Latitude: 43° 44′ 32.19" N, Longitude: 70° 13′ 27.2" W

BRIDGE RECOMMENDATION FORM

TOWN	Falmouth	BRIDGE	Johnson Road Bridge	BRIDGE NO.	5792
DESIGNED BY	WSP	DATE 12/12/	2018	WIN	21721.00
APPROVED BY	-	_DATE		STATE ROU	re n/a
APPROVED BY		DATE			

PROJECT: Complete bridge replacement. Two-span bridge with integral abutments on Hpiles. New bridge will be widened to accommodate two lanes of traffic, two 5' shoulders, and one sidewalk. Approximately 200' of approach work to widen the approach shoulders and add a sidewalk is also included.

ALIGNMENT DESCRIPTION: The proposed horizontal alignment will match the existing Johnson Road alignment. From the western limits of work, the proposed profile starts at station 11+00.00 with a station 11+00.00 with a vertical tangent of 4.87%. At station 11+12.50 a 100 ft sag vertical curve will be utilized with an exiting grade of 8.00%. This grade continues to station 13+12.50 where a 150 ft crest vertical curve is implemented. The exiting grade of 3.50% continues from station 14+62.50 to the eastern limits of work, tying back into the existing profile at station 17+62.50.

APPROACH SECTION: Two 11' lanes, two 5'-0" shoulders, and one 6'-0" sidewalk to the south. The approach shoulders taper to match the existing 2'+/- shoulders. On the south side of the approaches, within the project limits, a sidewalk will be installed.

SPANS 121'-10" - 121'-10" 12° back on left SKEW

LOADING HL-93 Modified for Strength I **DESIGN SPEED** 35 mph

SUPERSTRUCTURE: Proposed superstructure will consist of a 9" reinforced concrete bare deck with integral wearing surface on five (5) welded steel plate girders. The superstructure will be 2-span continuous. The steel superstructure will be metalized. Four bar steel traffic barrier will be installed on the sidewalk and three bar steel traffic barrier installed on the brush curb. The out-to-out bridge width will be 41'-4". The new superstructure will provide a 16'-0" minimum vertical clearance over I-295.

ABUTMENTS: Cast-in-place reinforced concrete integral abutments with in-line wingwalls supported on H-piles. Maximum 2:1 slopes will be utilized for grading in front of and adjacent to the proposed abutments. The sloped area under the bridge will be treated with Crushed Stone Slope Protection. Abutments are skewed at 12 degrees back on left to align with the I-295 alignment below.

PIERS: Cast-in-place reinforced concrete wall pier. The ends of the wall pier will be constructed with a negative batter and each face will receive a recessed panel with formliner finish, similar to the geometry and finishes as detailed on the Lunt Road Bridge Replacement project (WIN21723). The wall pier will be supported by H-piles consisting of existing pier H-piles to be re-used and new H-Piles to be installed. The pier is skewed at 12 degrees back on left to align with the I-295 alignment.

AVAILABLE SOILS INFORMATION: Geotechnical investigation was not scoped as part of the preliminary design phase. Subsurface exploration and geotechnical evaluation will be performed during final design. The boring logs for the existing Johnson Road bridge, dated June 1957, can be found in the existing plans included as Appendix D.

ADDITIONAL DESIGN FEATURES: A sidewalk will be added to the south side of the new bridge. The bridge approaches will be widened to include a sidewalk within the project limits of construction.

MAINTENANCE OF TRAFFIC: The bridge will be closed for a maximum of 95 consecutive calendar days between March 2020 and August 2020. Traffic will be detoured to Bucknam Road with a formal signed detour route.

CONSTRUCTION SCHEDULE: One construction season including landscaping.

ADVERTISING DATE: August 2019

		Program Amount	Available Funding	Estimated Project Cost	Shortfall/ Surplus
Prelimir	nary Engineering	\$260,000	\$260,000	\$300,000	-\$40,000
	Right-of-Way	\$15,000	\$15,000	\$0	\$15,000
Construction [Structure	\$2,250,000	\$2,250,000	\$3,825,000	-\$1,575,000
Construction	Approaches	72,230,000	72,230,000	\$405,000	-\$405,000
Construc	tion Engineering	\$250,000	\$250,000	\$300,000	-\$50,000
	Total	\$2,775,000	\$2,775,000	\$4,830,000	-\$2,055,000

ADDITIONAL BORINGS REQUIRED? Yes

ADDITIONAL GEOTECHNICAL EVALUATIONS REQUIRED? Yes

APPROVED DESIGN EXCEPTIONS: N/A

COMMENTS BY ENGINEER OF DESIGN:

SUMMARY OF EXPECTED IMPACTS

RIGHT OF WAY	Number of:	Property Owners	0	
		Buildings to Be Taken	0	
	Type of Acquisitions:	☐ Fee Simple	☐ Easement	

UTILITIES: Two 3" diameter electrical conduit embedded in south curb. Overhead utilities along south fascia

COAST GUARD PERMIT NEEDED? No

FAA PERMIT NEEDED? No

 \square Temporary Rights \square Temporary Road

ENVIRONMENTAL COORDINATION

Team Member: Kristen Chamberlain

NEPA/STIP	N/A- No Federal Funds
Section 106	N/A- No Federal Funds
Section 4(f)	N/A-No USDOT Funds
Federal Endangered	No Federal Nexus
Species	
State Endangered	Least bitterns in project area. Coordinated with IF&W no further action
Species	required.
Essential Fish Habitat	No in-water work.
Fish Passage	N/A
In-Stream Window	N/A
Hazardous Material	No hazardous waste review required.
Dredge Material	N/A
Stormwater/MS4	N/A
DEP/LUPC	No jurisdiction
ACOE	No jurisdiction
Mitigation	N/A
Other	

Avoidance & Minimization: The proposed bridge and approach work are located within existing MaineDOT ROW.

SUMMARY OF PRELIMINARY DESIGN

1. BACKGROUND:

The Johnson Road Bridge (#5792) between Middle Road and Route 1 spans over NB and SB of Interstate 295 in Falmouth, Maine. The existing bridge consists of two separate structures: A 39.75' non-composite deck, simply supported bridge and a three-span, composite deck, continuous bridge (59'-59'-62') for a total span length of 219.75'. The bridge was built in 1957 and consists of steel stringers with a 7" thick deck with bituminous overlay. The abutments are composed of reinforced concrete founded on H-Piles, and all three piers are 3-column bents with concrete caps on H-piles. The original bridge cross section was 26' curb to curb, with 2'-6" concrete curb on both fascias. Both bridge railings consist of a 1' wide concrete parapet with extruded aluminum alloy railing, for a total out to out width of 33'-0".

Rehabilitative work was completed on the structure in 1991. This work included replacing the bituminous wearing surface and membrane waterproofing, cleaning and painting the existing structural steel and bearings, replacing the existing joint at Pier 1 with armored compression seals, modifying the existing expansion joint at the East Abutment, rehabilitating existing concrete as needed, connecting the existing approach guardrail to the existing concrete parapet, resetting the existing approach guardrail and rehabilitating the approach roadway at both ends of the bridge.

The bridge is scoped for rehabilitation/replacement in the Department's 2018-2020 Working Plan with a total budget of \$2.775 million for PE, ROW and Con/CE. During the process of preliminary design, alternatives considering deck replacement/superstructure widening and complete bridge replacement were explored.

2. EXISTING CONDITIONS:

Per the existing 2016 inspection report, provided by MaineDOT, the existing steel beams are in generally satisfactory condition (6) with prevalent light rusting. Isolated moderate to heavy rusting at the west pier girder ends and bearings is present. State records indicate the minimum clearance of the structure over I-295 is 14'-6" for the southbound lanes at the right shoulder.

The existing 2016 inspection report indicates the concrete deck is in fair condition (5) with minor cracking and light efflorescent staining and isolated delaminations and spalling. Collision damage to the west end bridge rail has broken off the transition piece and end post. The wearing surface has prevalent minor to moderate alligator cracking.

As indicated in the existing 2016 inspection report, the substructure is in poor condition (4). Abutments have scattered minor cracking. Piers are in good condition except for the west pier cap which shows moderate cracking and isolated areas of spalled and delaminated concrete and shear cracking at the north face bearing area. Although the inspection report indicates the piers are in generally good condition, recent testing of the pier columns at piers 2 and 3 show high chloride contents – indicative of deteriorated concrete and potential reinforcement corrosion (see 'Pier Column Concrete Testing' section for additional information). West pier

bearings are severely misaligned and in need of rehabilitation. The west pier bearings are currently blocked up with timber cribbing.

Pier Column Concrete Testing

In August 2018, MaineDOT sampled concrete cores from each of the three columns of the center median pier and east pier to test for chloride content. The west pier was not sampled as it is anticipated that this pier will be substantially rehabilitated or replaced with each design alternative to be evaluated. The field log, core locations and test reports can be viewed in Appendix K. Concrete cores were sampled at locations on the pier columns that are within the splash zone for de-icing salts from I-295. Extended exposure to deicing salts can result in a buildup of chloride within the concrete. Once chloride concentrations between 1.0 to 2.0 lb/CY1 of concrete are reached adjacent to reinforcing steel, corrosion of the reinforcement is likely. According to the existing as-built plans, the pier columns have 2" of cover to the #4 ties.

Cores 1-3 were sampled along the southern side of the east pier columns. Each of these cores show high chloride levels from the surface to approximately 1.5" deep, ranging from 8.33 lb/CY to 12.22 lb/CY. At a minimum depth of 2" to a max depth of 5.25" (concrete surrounding existing reinforcement), the chloride content ranges from 1.21 lb/CY to 6.53 lb/CY. Core no. 4 was taken on the north side of the northernmost column of the east pier and exhibits lower chloride content (3.47 lb/CY 1.5" deep and 0.74 lb/CY 3" to 3.5" deep). The chloride content found in these concrete samples indicate that corrosion of the pier column reinforcing steel is likely. The columns exhibit minor cracking in the splash zone and the middle column shows evidence of previous concrete repair (patching).

¹Mindess, Sidney; Young, J. Francis & Darwin, David. (2002). *Concrete* (2nd ed). Prentice Hall.

3. **UTILITIES**

There are aerial wires approximately 5 feet off the south fascia that span over I-295. Aerial utilities onsite include:

- 3-phase power cables (owned by Central Maine Power Company)
- Communication Cables (owned by Consolidated Communications)
- Communication Cables (owned by Spectrum)

There is an existing underground waterline (owned by Portland Water District) approximately 60 feet south of the existing bridge's southern fascia. This waterline passes under I-295 NB and SB. Construction activities are not anticipated to impact the waterline.

The existing east abutment has an electrical conduit affixed to the north wingwall and to the front of the stub abutment. The conduit appears to originate/terminate at a stub utility pole just northeast of the existing wingwall and enters the ground on the south side (front face) of the east abutment.

The existing aerial facilities south of the bridge will likely require permanent relocation for design alternatives that consider structure widening/replacement to the south. Further utility coordination is required during final design to coordinate construction activities.

4. **GEOMETRIC ALIGNMENT**

To achieve a 16'-0" minimum vertical clearance over I-295, the proposed profile along Johnson Road shall be raised. The western limits of proposed work will tie into the existing profile at station 11+00.00 with a vertical tangent of 4.87%. At station 11+12.50 a 100 ft sag vertical curve will be utilized with an exiting grade of 8.00%. This grade continues to station 13+12.50 where a 150 ft crest vertical curve is implemented. The exiting grade of 3.50% continues from station 14+62.50 to the eastern limits of work, tying back into the existing profile at station 17+62.50.

The proposed horizontal alignment closely matches the existing Johnson Road horizontal alignment. The majority of the proposed bridge is located on a horizontal tangent. The west end of the bridge and west approach are located on a horizontal curve with a 4100 ft radius. over the bridge. The proposed work does not require a realignment of Johnson Road, only a widening to account for the widened shoulder and addition of a sidewalk on the south side of the road.

5. **EXISTING BRIDGE LOAD RATING**

As part of preliminary design, an LRFR load rating for the existing bridge was developed. The bridge is comprised of two superstructures: the western-most span is a single span simply supported non-composite concrete deck on rolled steel beams and the remaining three spans are continuous with a partially composite concrete deck on rolled steel beams.

The governing HL-93 inventory rating for the single span was determined to be 1.01 for an interior girder with all legal load configurations rating greater than 1.0. The governing HL-93 inventory rating for the 3-span continuous portion of the bridge was determined to be 0.59 for an interior girder at pier 3 (negative moment). The typical interior girder rated less than 1.0 for all legal load configurations with the exception of Truck Configurations 7 & 8. The governing legal load rating factor was 0.83 for both Truck Configurations 3 & 6.

The controlling fatigue prone details on the structure are the Category E partial-length welded cover plates with tapered ends that are narrower than the flange. A Fatigue Limit State Rating Factor for infinite fatigue life was computed in accordance with the MaineDOT Load Rating Guide. A controlling fatigue rating factor of 0.33 at the termination of the Pier 3 cover plate located on the exterior girder line was calculated. The remaining fatigue life at this location was determined to be 138 years using a Resistance Factor for Evaluation of 1.2.

In reviewing the existing load rating, the governing rating location for both interior and exterior beams is for moment in the negative flexure region over the pier. Long unbraced lengths of the bottom flanges in these regions (bottom flange is the compression flange in negative flexure regions) govern the load carrying capacity with lateral torsional buckling being the controlling design criteria. Preliminary analysis of the existing stringers, considering proposed loadings, indicate that providing additional brace points along the bottom flange will help to reduce the unbraced length of the compression flange in these critical areas, resulting in increased load carrying capacity for the existing stringers. The addition of new braces to the bottom flange would not be a complex retrofit and would not be a significant additional cost to other rehabilitation efforts.

At a minimum, the design alternatives consider a deck replacement. The new deck will be made composite with the steel superstructure by installing shear connectors. Carrying the shear connectors through the negative flexure region of the continuous stringers would allow for negative moment steel in the deck to be considered in the load carrying capacity of the bridge. Carrying shear studs through the negative moment region of the stringers to provide composite behavior throughout the stringer would not be a complex retrofit and would not be a significant additional cost to the overall rehabilitation efforts.

The above retrofits would improve the load carrying capacity of the existing bridge, likely resulting in all legal load truck configurations rating greater than 1.0. However, even with considering the above retrofits, it is unlikely that the existing superstructure could be strengthened to produce a rating factor greater than 1.0 for the HL-93 truck. Johnson Road is classified as corridor priority (CP) 6. Based on the criteria for rehabilitated bridges provided in Engineering Instruction S1, a rehabilitated bridge with CP 6 may be posted. Considering additional bottom flange braces in the negative flexure areas and including a fully composite concrete deck, the existing superstructure could be strengthened to not require posting.

The existing structure Load Rating Report can be found in Appendix E.

6. **TRAFFIC**

The bridge carries Johnson Road over I-295 NB & SB with 2016 traffic volumes of 1440 AADT with 5% trucks. The AADT volumes on I-295 are 27,010 and 25,680 for northbound and southbound respectively. Additional traffic data is included in Appendix G.

Accident data was reviewed and there is not a significant amount of crashes in the project area. The accident data is included in Appendix G.

7. **COMMUNITY OUTREACH**

A preliminary public meeting with representatives and residents from the Town of Falmouth was conducted on July 11, 2018 to provide initial information about the proposed project and to elicit questions, comments, and concerns from the public to be considered when analyzing design alternatives.

In June 2017, the Town of Falmouth completed a Route 1 North Vision Plan. This plan envisions a new sidewalk on Johnson Road across I-295, calling for a sidewalk to be installed on the south side of Johnson Road from Route 1 to Middle Road. A copy of this document can be found in Appendix J. The Town also supports the inclusion of bicycle lanes on Johnson Road as there are few east-west connections across I-295. Bicycle lanes currently exist on Route 1 and there are newly installed bike lanes on Middle Road, from the new roundabout on Longwoods Road to the Cumberland town line.

With consideration given to MaineDOT's Complete Streets Policy, the rehabilitation of the Johnson Road bridge provides the opportunity to improve safety for motorists, bicyclists and pedestrians using the bridge. The bridge does not currently provide pedestrian access and the shoulders (2'-0"+/-) are too narrow to be safely used by bicyclists. The Town of Falmouth has demonstrated its commitment to increasing pedestrian and bicycle mobility throughout the town by playing an active role in recently completing and currently programmed transportation improvement projects to ensure that bicycle and pedestrian accessibility is addressed whenever feasible. In July 2018, the Falmouth Town Council included in its FY 2018-19 Work Plan the task of taking the Route 1 North Vision Plan through the next step of Preliminary Engineering, demonstrating commitment from the Town to implement this Vision Plan. In accordance with the 'Project Relevance and Feasibility' section of the Complete Streets Policy and in consideration of efforts being made locally in the Town of Falmouth to provide better pedestrian and bicycle connectivity, improvements to pedestrian and bicycle facilities were added to the scope of this project to be evaluated as the alternatives for consideration.

8. PRELIMINARY GEOTECHNICAL EVALUATION & RECOMMENDATIONS

Preliminary design did not include new geotechnical investigations.

Per the existing bridge plans, the existing abutments and piers are supported on H-piles. A copy of the existing boring logs can be found in the existing plans in Appendix D.

Bridge widening/replacement alternatives will require additional geotechnical investigations as part of final design.

9. **RIGHT OF WAY**

Right-of-way lines provided by MaineDOT are shown on the General Plan included in Appendix A. Property acquisitions are not anticipated for the alternatives under consideration.

10. PROJECT SCHEDULE

The preliminary project schedule for the recommended alternative calls for project advertisement in August 2019. Construction would begin in spring 2020.

11. PURPOSE AND NEED

The primary goals for this project, at a minimum, are to address structural deficiencies throughout the existing bridge, address non-vehicular mobility over the bridge, and improve vertical clearance under the bridge over I-295.

The most recent bridge inspection report, conducted 4/21/2016, indicates the bridge deck is in fair condition with the superstructure in satisfactory condition. The substructure is shown to be in poor condition because of the extensive deterioration at the west pier cap. See section 2, Existing Conditions, for additional discussion pertaining to the bridge condition. The most recent LRFR bridge rating, completed October 2018, reveals rating factors of 0.59 for the HL-93 design truck and 0.83 for the governing MaineDOT Legal Load Configuration. See section 5, Existing Bridge Load Rating, for additional discussion pertaining to the structural deficiencies noted in the bridge rating.

The existing bridge does not provide pedestrian access across the structure and has substandard 1'-6"+/- shoulders. The existing under clearance over I-295 is 14'-6" with a required minimum equal to 16'-0" over the interstate.

12. SUMMARY OF DESIGN ALTERNATIVES

This project was initially scoped as a bridge rehabilitation considering a deck replacement and repair/replacement of the existing west pier. The preliminary design evaluates the following design alternatives:

- 1. Rehabilitation: Replace existing deck and west pier, with no widening.
- 2. Superstructure Replacement & Widening: Replace existing superstructure and replace existing west pier. Add pier extensions and widen superstructure to accommodate 5' shoulders and inclusion of a sidewalk.
- 3. Complete Bridge Replacement: Replace entire bridge with two-span integral steel girder bridge. New bridge will be widened to accommodate 5' shoulders and include a sidewalk.

Alternative 1: Bridge Rehabilitation – This alternative consists of replacing the existing 33'-0" deck with a composite 9" thick concrete deck with integral wearing surface. 3-Bar Traffic/Bicycle Railing would be provided, resulting in a bridge cross-section comprised of two 11'-0" travel lanes and two 3'-10" shoulders. These shoulders do not meet the 4'-0" minimum for spans greater than 200' as specified in the BDG, Section 4.1.2; however, as this alternative is considered a rehabilitation, the 3'-10" shoulders should be acceptable and offer an improvement over the existing 2'+/- shoulders.

After the existing deck is removed, additional braces will be installed in the negative moment regions of the 3-span continuous superstructure. Additional bottom flange braces in the negative moment regions will help to reduce the unbraced length of the beam compression flange and help to improve the load carrying capacity of the member. The addition of bottom flange bracing and making the deck fully composite with the steel beams will help to improve the overall load rating. With these improvements, it is anticipated that all legal load combinations will rate greater than 1.0 for both interior and exterior girders. The HL-93 rating factors will also improve; however, it is anticipated that the HL-93 vehicle will still rate less than 1.0.

After the existing deck is removed, the existing steel superstructure will need to be dismantled and temporarily stored. The existing steel beams will be re-used in the final condition; however, as pier 1 requires reconstruction and each substructure unit will require new beam seats to help increase the vertical clearance over I-295, dis-assembling and then re-erecting is recommended as opposed to jacking and shoring the steel beams in place. The existing piles at pier 1 will be re-used and supplemental piles added (as required by final design).

The concrete testing performed on the pier columns at piers 2 & 3 indicate high chloride content through the pier columns. As piers 2 & 3 will be re-used, removal of the deteriorated concrete and installation of concrete jackets are recommended for all remaining pier columns.

To improve joint leakage concerns at the abutments, this alternative considers the use of a slab over backwall detail to move the joint away from the abutment seats. The use of a link slab over pier 1 could be investigated during final design in an effort to eliminate a deck joint directly over the pier.

Considering a full closure of the Johnson Road bridge with conventional construction methods, it is estimated that the bridge closure period will need to be 60 consecutive calendar days. See Appendix L for the preliminary construction schedule.

This alternative addresses some of the structural deficiencies noted for the existing bridge by replacing the existing concrete deck with a new deck fully composite with the existing steel stringers by installing shear connectors along the full length of the bridge and by providing additional brace points in the negative moment regions. Both features help to improve the load carrying capacity, improving the load rating to have rating factors greater than 1.0 for all MaineDOT Legal Load combinations. The existing heavily deteriorated west pier is proposed to be replaced and the remaining two piers are proposed to be rehabilitated. The proposed redecking also improves safety for vehicular and bicycle traffic over the bridge by providing 3'-10" shoulders and standard bridge rail. However, by not widening the bridge, the desired shoulder width of 5' and inclusion of a sidewalk is not attainable. Vertical clearance under the proposed rehabilitated structure is improved from 14'-6" to 16'-0" by reconstructing the existing beam seats to enable the existing steel beams to be set higher and by raising the profile over the bridge.

The overall construction cost estimate for Alternative 1, considering conventional construction methods utilizing a full closure of the Johnson Road bridge and detour on existing roads is approx. \$2.58 million (see Appendix M). Painting of the existing steel superstructure is not included in this cost estimate.

Alternative 2: Superstructure Replacement and Widening - This alternative consists of replacing the existing superstructure with a new, wider steel superstructure with a composite 9" thick concrete deck with integral wearing surface. The bridge cross-section will be comprised of two 11'-0" lanes, two 5'-0" shoulders, one 6'-0" sidewalk and 3-Bar and 4-Bar Traffic/Bicycle/Pedestrian railing for a total out-to-out width equal to 41'-4". To accommodate the wider superstructure, substructure extensions will be necessary. As the majority of the superstructure widening occurs to the south of the existing center of bridge, the substructure widening should occur on the south side. The new five girder cross-section will utilize metalized steel girders.

After the existing superstructure is removed, the west pier (pier 1) will be demolished and reconstructed. The reconstructed pier will be widened to the south to accommodate the new superstructure. Similar to Alternative 1, existing piers 2 and 3 will be rehabilitated by removing deteriorated concrete and installing concrete jackets. Unlike Alternative 1, this option does not require dis-assembling and re-erecting the existing steel superstructure.

The substructure widening will require additional H-Piles to be driven. The abutment stems at abutments 1 and 2 will be lengthened and new southern wingwalls constructed. Piers 2 and 3 will each require an additional column founded on an independent pile supported foundation.

The proposed superstructure will be four-span continuous, eliminating the existing joint over pier 1. To improve joint leakage concerns at the abutments, this alternative considers the use of a slab over backwall detail to move the joint away from the abutment seats. A complete superstructure replacement enables the design of a shallower superstructure depth, which helps to further improve the vertical clearance over I-295. A shallower superstructure

minimizes the change in profile and subsequent limits of roadway work to provide the 16'-0" vertical clearance. New steel beams will also improve the load-carrying capacity of the bridge.

Considering a full closure of the Johnson Road bridge with conventional construction methods, it is estimated that the bridge closure period will need to be 75 consecutive calendar days. See Appendix L for the preliminary construction schedule.

This alternative addresses the structural deficiencies noted for the existing bridge by replacing the existing superstructure with a new steel superstructure and fully composite concrete deck. The new steel superstructure is designed for the MaineDOT HL-93 Modified load which results in rating factors greater than 1.0 for the HL-93 truck and all MaineDOT Legal Load combinations. The existing heavily deteriorated west pier is proposed to be replaced and the remaining two piers are proposed to be rehabilitated. The proposed superstructure widening improves safety for vehicular, bicycle, and pedestrian users over the bridge by providing wider shoulders, a sidewalk, and standard bridge rail. The 5'-0" shoulders meet the criteria set forth by the Town of Falmouth to be used as bicycle lanes. The 6'-0" sidewalk provides access for pedestrians to cross the bridge when there was not previously a sidewalk. The 6'-0" sidewalk also meets the Town of Falmouth's request for a sidewalk on the bridge greater than 5'-0" wide to help facilitate snow removal based on the sidewalk clearing equipment the Town uses.

The overall construction cost estimate for Alternative 2, considering conventional construction methods utilizing a full closure of the Johnson Road bridge and detour on existing roads is approx. \$3.82 million (see Appendix M).

Alternative 3: Complete Bridge Replacement – This alternative consists of completely replacing the existing 4-span bridge with a new 2-span structure with a deck section width equal to 41′-4″. The new bridge would provide one 6′-0″ sidewalk to the south, two 5′-0″ shoulders, and two 11′-0″ travel lanes. The new superstructure would consist of 5 girders spaced at 9′-0″ with a composite 9″ thick concrete deck with integral wearing surface. The new steel girders are proposed to be metalized.

The proposed median pier will be a wall pier with similar geometry and aesthetics to the new Lunt Road bridge (currently being constructed). Due to the narrow median, the new wall pier will be constructed in the same approximate location as the existing 3-column bent. The new pier will be supported by H-piles consisting of existing pier H-piles to be re-used and new H-Piles to be installed.

The proposed two-span structure will utilize equal spans. As the existing bridge has unequal spans, the proposed east abutment piles will be installed between the front and back rows of the existing abutment piles. Equalizing the spans pushes the proposed west abutment piles behind the existing west abutment and wingwalls. Shortening the spans by installing the proposed east abutment in front of the existing east abutment was eliminated due to concerns about potential interference with existing battered piles.

Considering a full closure of the Johnson Road bridge with conventional construction methods, it is estimated that the bridge closure period will need to be 95 consecutive calendar days. See Appendix L for the preliminary construction schedule.

This alternative addresses the structural deficiencies noted for the existing bridge by completely replacing the existing structure with a new bridge. The new bridge will be designed

considering the HL-93 modified loading and will therefore rate for the HL-93 and all MaineDOT Legal Load combinations. The new bridge will be designed to provide a minimum 16'-0" vertical clearance over I-295 by raising the profile over the bridge. The new bridge improves safety for vehicular, bicycle, and pedestrian users over the bridge by providing wider shoulders, a sidewalk, and standard bridge rail. The 5'-0" shoulders meet the criteria set forth by the Town of Falmouth to be used as bicycle lanes. The 6'-0" sidewalk provides access for pedestrians to cross the bridge when there was not previously a sidewalk. The 6'-0" sidewalk also meets the Town of Falmouth's request for a sidewalk on the bridge greater than 5'-0" wide to help facilitate snow removal based on the sidewalk clearing equipment the Town uses.

The overall construction cost estimate for Alternative 3, considering conventional construction methods utilizing a full closure of the Johnson Road bridge and detour on existing roads is approx. \$4.23 million (see Appendix M).

13. EVALUATION OF DESIGN & CONSTRUCTION COMPONENTS

Town of Falmouth Input

The Town of Falmouth has multiple transportation improvement, large residential and commercial projects planned over the next several years, as well as the anticipated replacement of the Bucknam Road and Lunt Road bridges, which cross I-295 within 2 miles of Johnson Road, within the next three (3) years. A list of projects planned in and around the Town of Falmouth in the upcoming years can be found in Table 1.

Transportation Project	Scope	Status
Middle Road/Longwoods Road/Woods	Roundabout by MaineDOT	
Road Intersection		
Middle Road/ Falmouth Road/ Bucknam	Intersection Improvement by	
Road Intersection	Town	
Lunt Road Bridge over I-295	Bridge Replacement by	Construction scheduled for 2019.
	MaineDOT	
Bucknam Road Bridge over I-295	Bridge Replacement by	Construction scheduled for 2020.
	MaineDOT	
Northbound I-295	New traffic signal by	To be constructed concurrently
exit/entrance/Bucknam Road	MaineDOT	with the Bucknam Road Bridge
		Replacement
Falmouth Turnpike Spur/Route 1	Spur Bridge and Ramp	Future
	Redevelopment by Developer	
Middle Road		Conceptual Design Phase

Table 1: Transportation Projects in Falmouth, ME

With the large number of projects planned in and around Falmouth in the near future, minimizing the total duration of construction/traffic related impacts from the Johnson Road bridge project would be a valuable benefit for the local community.

Construction Costs Comparison

The bridge is scoped for rehabilitation in the Department's 2018-2020 Working Plan with a total budget of \$2.775 million for PE, ROW and Con/CE. Construction cost estimates were developed for each design alternative. A summary of estimated construction costs is provided below:

Construction Cost Estimates					
Rehabilitation	Superstructure Replacement	Complete Bridge			
	& Widening	Replacement			
\$2.58 Million	\$3.82 Million	\$4.23 Million			

Table 2: Design Alternatives Construction Cost Comparison

The preliminary cost estimates for each construction approach can be viewed in Appendix M. Construction costs were estimated considering the recent bid prices from WIN021723.00 Lunt Road Bridge Replacement. This project is representative for the work anticipated on the Johnson Road project as the bridge is located in Falmouth, requires work over I-295 and was recently awarded (Fall 2018).

Impacts to Johnson Road & Local Traffic

The bridge carries Johnson Road over I-295 NB & SB with 2016 traffic volumes of 1440 AADT with 5% trucks. The 2016 AADT volumes on I-295 are 27,010 and 25,680 for northbound and southbound respectively.

MaineDOT modeled anticipated traffic performance for various construction scenarios for the Johnson Road bridge reconstruction/replacement. The scenarios considered include:

- 1. Existing Conditions
- 2. Existing Conditions with anticipated improvements (programmed roundabout on Middle Road, new Lunt Road and Bucknam Road bridges, and signal at Bucknam Road/I-295 NB Ramps)
- 3. Johnson One-Lane: Alternating one-way traffic maintained on open lane by temporary traffic signal at the Johnson Road bridge over I-295.
- 4. Johnson Road bridge Closed: Johnson Road bridge would be completely closed with surrounding signalized intersections adjusted to accommodate changes in traffic flow.

The overall performance measures include vehicles denied entry (vehicles unable to enter the one-hour simulation due to congestion in the simulation model) and queue length (95th percentile for left turns and right turns, 50th percentile for thru movements). Intersection-level performance measures include volume/capacity ratio (by intersection movement) and total delay (extra travel time due to congestion, measured in vehicle hours).

As part of the traffic analysis, MaineDOT calculated user costs for each scenario. In addition to the user costs associated with delay, costs were also estimated for the additional distance traveled by detoured traffic. A summary of the estimated user costs is in Table 3.

Johnson I	Road User Impa	cts and Cost	S						
			Improved		Johnson Rd		John	son Rd E	ridge
			Falmouth		Bridge		Clos	ed, Adjus	ted
			Network		One Lane		Traffi	c and Sig	gnals
PM Peak	-Hour Travel								
	Vehicles De	nied Entry	0		0			1	
	Delay (VHT)		84		93			79	
Delay Imp	pacts								
	Peak-Hour [Delay (VHT)	0		9			-5	
	Daily Delay	(VHT)	0		34			-19	
	Daily User C	Costs			\$ 438		\$	(243)	
Detour Im	npacts								
	Daily Distan	ce (VMT)	0		0			1310	
	Daily Travel	Time (VHT)	0		0			37	
	Daily User C	Costs			\$ -		\$	851	
Total	Daily User C	osts			\$ 438		\$	607	
Interstate	Closure User In	noacts	via I-295	via US 1					
		its 10 and 15							
		speed	65	30	mph	Increase in	1		
		distance	3.64		miles	travel cost			
		travel time	0.056		hours	S/vehicle			
		travel cost	0.78		\$/vehicle	\$ 1.02			

Table 3: Johnson Road Summary of User Costs

This analysis highlights that the 'Full Closure' (\$607 per day) and 'One Lane' (\$438 per day) scenarios have similar impacts to Johnson Road traffic. These relatively low user costs indicate that abbreviated full or partial closures of the Johnson Road bridge may be feasible.

As part of the traffic simulation, MaineDOT analyzed the impacts to local Town of Falmouth intersections considering the above construction scenarios. Intersection performance was evaluated considering level of service (LOS). The analysis includes overall performance measures of 'vehicles denied entry' into the model and 'total delay' in vehicle-hours. See Table 4 for a summary of the analysis. Due to relatively low traffic volumes on Johnson Road, the ability of local roads and intersections to temporarily handle additional traffic from Johnson during, and the small difference in user costs between a 'Full Closure' and 'One Lane' approach, a full bridge closure is recommended.

Falmouth - PM Peak Hour								
	Alternatives							
Intersections	Existing		Improved		Johnson Or		Johnson Clo	sed
	LOS - delay	Q>Storage	LOS - delay	Q>Storage	LOS - delay	Q>Storage	LOS - delay	Q>Storage
Vehicles Denied Entry	194		0		(1	
Total Delay	78		84		93	3	79	
Johnson-Middle	OK	OK	OK	OK	OK	OK	A-1.8	OK
One-Lane Johnson					C-30.7	OK		
Johnson-US1	OK	OK	OK	OK	OK	OK	A-7.2	OK
Long Woods-Middle	OK	OK	OK	OK	OK	OK	A-7.5	OK
Falmouth/Bucknam-Middle	С	EBT50 WBR95 SBL95	D-41.4	EBT50 WBR95 NBR95 SBL95	D-38.3	EBT50 WBR95 NBR95 SBL95	C-27.0	NBT95 NBR95
Bucknam-SB ramps	С	WBT50 SBT50	B-16.9	EBL95 WBT50 SBT50	B-16.1	EBL95 WBT50 SBT50	B-15.1	ок
Bucknam-NB ramps	С	SBT>>	B/C-19.5	OK	B/C-19.3	ок	C-23.2	EBL95 EBT95 WBT95
Bucknam-US1	В	EBL95	C-24.5	EBL95 NBL95 SBT50	C-21.6	EBL95 NBL95 SBT50	C/B-20.7	EBL95 EBT95 SBT95
Lunt-Falmouth	OK	OK	OK	OK	OK	OK	OK	OK
Lunt-Middle	OK	OK	OK	OK	OK	OK	OK	0K
Lunt-Depot	OK	OK	OK	OK	OK	OK	OK	OK
Depot-US1	C/B	OK	C-21.2	EBR95	C-21.2	EBR95	C-21.9	EBR95
Clearwater-US1	А	ок	A-7.4	ок	A-7.9	ок	A-8.2	EBT95 NBT95 SBT95
Hunter-US1	A-2.3	OK	A-2.3	OK	A-3.0	OK	A-3.3	NBT95
Planned and Programmed Im Long Woods-Middle	provements		in place		in place		in place	
Bucknam-NB ramps			in place		in place		in place	
Falmouth/Bucknam-Middle			in place		iii piace		in place	
Bold queue indicates spillbad	k to upstream	intersection						
LOS - delay based on overall	intersection de	elay and sign	alized LOS s	cale				
Temporary treatments					install temp	orary signal		

Table 4: LOS Summary for Surrounding Intersections

The 'Full Closure' scenario does not show significant deterioration in LOS compared to the 'Existing – Improved' or 'One Lane' scenarios. The lowest LOS for the 'Full Closure' scenario is a 'C' with comparable 'Vehicles Denied Entry' and 'Total Delay' to both the 'Existing – Improved' and 'One Lane' construction approaches.

Due to relatively low traffic volumes on Johnson Road and the ability of local roads and intersections to temporarily handle additional traffic from Johnson during a full bridge closure, an on-site temporary bridge is not recommended. A temporary bridge with the necessary temporary approach work would add substantial construction costs to the project (estimated at approximately \$1 million). In addition, temporary ROW acquisitions would likely be necessary in order to construct the approach embankments along the eastern approach to the bridge.

Impacts to I-295

The Johnson Road bridge spans over both northbound and southbound of Interstate 295. The ability to minimize construction and traffic related impacts to I-295 to the extent practical is a critical component when considering possible construction approaches.

With consideration given to the high traffic volumes experienced during the daytime hours on I-295, the Contractor will not be permitted to utilize single lane closures and/or full closures on I-295 during the day between 6:00 AM and 10:00 PM. The Contractor will be allowed a limited number of full closures on I-295 for the work activities specified below with the following restrictions.

- Single lane closures on I-295: 10:00 PM to 5:00 AM (Sunday Night thru Thursday Night)
- Full closures on I-295: 1:00 AM to 5:00 AM (Monday AM thru Friday AM)

MaineDOT's evaluation of hourly traffic volumes on I-295 indicated that full closures could begin earlier (12:00 AM) and single lane closures could start earlier and end later (9:00 PM to 7:00 AM NB and 8:00 PM to 6:00 AM SB); however, it is recommended that the more restrictive work windows listed above be utilized. During a full closure on I-295, traffic would be detoured off I-295 to Route 1 to avoid the project site. Due to the early morning time restrictions for full closure, MaineDOT's analysis indicates an approximate \$1 per vehicle user cost for the detour. See Table 5 for a summary of anticipated full closures required on I-295. As temporary nighttime single lane closures on I-295 do not significantly impact the traveling public (as at least one lane of traffic is maintained in each direction and traffic volumes on I-295 are low during the times allowed), a set number of single lane closures has not been developed.

	Rehabilitation - Deck Replacement	Superstructure Replacement & Widening	Complete Bridge Replacement
Total Number of temp. 'Full Closures on I-295'	14	16	16
Existing Structure Demolition	8	8	8
Steel Erection	0	8	8

Table 5: Summary of Full Closures on I-295

Construction Duration

As indicated by the user cost calculations comparing a phased construction with alternating one-way traffic (\$438/day) and a single phase approach with a full bridge closure and detour on existing roads (\$607/day), the impacts to the traveling public are relatively small for either construction approach. The major advantage of a single phase full closure construction approach is realized by reducing the overall construction duration (construction exposure) and minimizing the impacts to I-295. For each activity that requires nighttime single lane or full closures on I-295, the total number of occurrences would be doubled for a phased construction approach compared to a single phase full closure. As such, single phase construction with a full bridge closure and detour on existing roads is the preferred construction approach. Preliminary Construction Schedules were developed for each design alternative considering single phase construction with full closure (see Appendix L).

A summary of construction durations requiring full bridge closure is summarized below for each design alternative:

Johnson Road Closure (Calendar Days)					
Rehabilitation – Deck	Superstructure Replacement	Complete Bridge			
Replacement	& Widening	Replacement			
60 CD	75 CD	100 CD			

Table 6: Summary of Construction Durations

All construction approaches consider a 6-day work week. The anticipated durations consider the work window restrictions for activities that may require single lane or full closures on I-295.

All construction cost estimates and construction schedules were developed considering conventional construction techniques. Due to the limited anticipated bridge closure period and the low user costs associated with a full bridge closure, accelerated bridge construction (ABC) techniques are not anticipated to provide significant value to the project. The use of precast substructure elements could decrease the overall bridge closure period; however, the additional construction costs associated with precast elements is unlikely to be offset by a reduction in user costs. Use of large precast elements may also impact the total number of night closures required on I-295. All pier work is proposed to be CIP, not requiring night closures (other than to initially setup median work zones). If precast pier elements were utilized, larger equipment (i.e. cranes) would likely be needed to setup on the interstate to erect these members – requiring additional night closures on I-295. As such, ABC techniques were not included in development of the preliminary construction cost estimates or preliminary construction schedules.

Evaluation Matrix

An evaluation matrix was developed to show a summary of the evaluation criteria for the Johnson Road bridge construction approach. See Table 7.

Evaluation	Matrix - Johnson Road Bridge over	Interstate 2	295, Falmo	uth, ME	
	DESIGN ALTERNATIVES	1	2	3	
		Rehabilitation - Deck Replacement	Superstructure Replacement & Widening	Complete Bridge Replacement	
		¢620,000,00	Ć4 225 000 00	\$4 0C4 000 00	
	Superstructure	\$628,000.00	\$1,325,000.00	\$1,864,000.00	
	Abutments	\$174,000.00	\$440,000.00	\$470,000.00	
	Pier	\$336,000.00	\$513,000.00	\$395,000.00	
	Structural Excavation & Borrow	\$18,000.00	\$65,000.00	\$77,000.00	
CONSTRUCTION COST	Existing Bridge Removal	\$260,000.00	\$320,000.00	\$400,000.00	
	Substructure Rehabilitation & Superstructure Dis-assembly	\$380,000.00	\$200,000.00	\$0.00	
	Approaches	\$298,000.00	\$338,000.00	\$338,000.00	
	Miscellaneous	\$273,000.00	\$289,000.00	\$324,000.00	
	Mobilization	\$210,000.00	\$321,000.00	\$359,000.00	
	Total Cost	\$2,580,000.00	\$3,820,000.00	\$4,230,000.00	
	Anticipated worst-case impact to intersection LOS	С	С	С	
	User Cost associated with delays from 'Full Closure of Johnson Road Bridge'	\$607.00 per day			
TRAFFIC IMPACTS &	User Cost associated with delays from 'One-Way Thru Traffic on Johnson Road Bridge'	\$438.00 per day			
USER COSTS	User Cost associated with delays from detour for 'Full Closures on I-295' (NB + SB between 1:00 AM & 5:00 AM)	\$1,161.00 per 4 hr full closure			
	Total User Cost from 'Full Closure of Johnson Road Bridge'	\$36,420.00	\$45,525.00	\$60,700.00	
	Total User Cost from 'Full Barrel Closures on I-295'	\$16,254.00	\$18,576.00	\$18,576.00	
	TOTAL USER COSTS DURING PARTIAL/FULL CLOSURE	\$52,674.00	\$64,101.00	\$79,276.00	
	Overall Construction Duration	1 Const. Seasons	1 Const. Seasons	1 Const. Season	
	Number of Days requiring <i>full closure</i> of Johnson Road bridge	60	75	100	
	Total Number of temp. 'Full Closures on I-295'	14	16	16	
CLOCLIDE BURNETICS			-	8	
CLOSURE DURATION	Existing Structure Demolition	8	8	0	
CLOSURE DURATION	Existing Structure Demolition Steel Erection	8	8		
CLOSURE DURATION				8	
CLOSURE DURATION	Steel Erection	0	8	8	

Table 7: Evaluation Matrix

14. CONCLUSIONS & RECOMMENDATIONS

As discussed in Section 13 – Evaluation of Design & Construction Components – Impacts to Johnson Road & Local Traffic, a full closure of the Johnson Road bridge with detour using local roads is anticipated to have minimal adverse impacts to the traveling public compared to a staged construction approach utilizing alternating one-way traffic. A full closure with local detour is preferable compared to staged construction due to a reduced total construction duration and fewer anticipated nighttime closures on I-295. An onsite detour via temporary bridge is not recommended due to high costs and limited ROW. As a result, each design alternative was evaluated considering a full closure of the Johnson Road bridge with a detour on local roads.

Alternative 1 does not satisfy all parts of project's Purpose & Need statement. The proposed improvements are not anticipated to enable the bridge to rate greater than 1.0 for the HL-93 truck and the desired wider shoulders and sidewalk are not attainable. In addition, Alternative 1 will require the existing steel superstructure to be dis-assembled and re-erected to increase the vertical clearance over I-295 and to allow existing Pier 1 to be reconstructed. Although Alternative 1 has the lowest anticipated construction cost, the construction cost estimate does not include the costs associated with future painting of the existing steel superstructure. The proposed improvements identified in Alternative 1 do not fully satisfy the main objectives of the project. Alternative 1 is not recommended to be advanced to final design.

Alternatives 2 and 3 each satisfy all parts of the project's Purpose & Need statement. Alternative 2 is estimated to have a lower construction cost. Both alternatives are anticipated to have similar impacts to local & I-295 traffic and will require similar overall construction durations. Alternative 2 requires substantial rehabilitation of the existing piers 2 and 3 to remain and complete reconstruction of pier 1. Considering the potential for future growth, the existing 4-span configuration, re-used in Alternative 2, is restrictive for potential widening of I-295. Alternative 3 utilizes a two-span structure, eliminating the existing piers 1 and 3 located in the shoulders. Alternative 3 would enable the widening of I-295 in both directions.

Alternative 3 is estimated to cost approximately \$410k more than Alternative 2. The relatively small cost difference between a completely new bridge and a widened/rehabilitated existing bridge comes down to the following key work items:

- Alternative 2 estimates approx. \$200k in rehabilitation costs to the existing piers/abutments to remain.
- Alternative 2 requires more equipment mobilizations as five separate substructure units require new piles to be installed (Alt. 3 requires three locations).

It is recommended that the existing Johnson Road bridge be replaced in its entirety with a new two-span structure to be constructed in a single phase, utilizing a full bridge closure with detour on local roads.

The following design features are recommended for final design:

- The existing bridge (33'-0" out-to-out) shall be replaced in its entirety by a two-span fully integral bridge (41'-4" out-to-out).
- All concrete shall be cast-in-place.
- All structural steel shall be metalized.
- 9" CIP concrete composite deck (8" structural, 1" integral wearing surface).
- Reinforcing steel shall be stainless steel throughout the deck, approach slab, abutments, and pier.
- The existing Johnson Road profile shall be adjusted to increase vertical clearance over I-295 to achieve a minimum 16'-0" under clearance.
- Traffic on Johnson Road shall be detoured on local roads during the full closure of the bridge.

The bridge replacement, using conventional construction techniques with a full bridge closure and local detour is estimated at \$3.825 million and the approach modification cost is \$0.405 million. The resulting total construction cost is approximately \$4.23 million. The total project

cost, including PE, ROW, Construction and CE is \$4.83 million. The preliminary construction cost estimate for the recommended alternative is included in Appendix M.

The proposed project schedule targets advertisement for construction in August 2019.

Appendix A

Preliminary Plans

STATE OF MAINE DEPARTMENT OF TRANSPORTATION

SPECIFICATIONS

Design: Load and Resistance Factor Design per AASHTO LRFD Bridge Design Specifications, Eigth Edition, 2017.

DESIGN LOADING

Live LoadHL - 93 Modified for Strength I

TRAFFIC DATA

Current (2016) AADT	
Future (2036) AADT	1,730
DHV - % of AADT	
Design Hour Volume	190
% Heavy Trucks (AADT)	
% Heavy Trucks (DHV)	
Directional Distribution (DHV)	
18 kip Equivalent P 2.0	27
18 kip Equivalent P 2.5	
Design Speed (mph)	

MATERIALS

Concrete:	
Curbs and Transition Barriers	Class "LP"
All Other	Class "A"
Reinforcing Steel	
Stainless Steel	ASTM A955/A955M, Grade 75
Structural Steel:	
All Material (except as noted)	ASTM A709, Grade 50 (Metalized)
High Strength Bolts	ASTM F3125, Grade A325 Type 1
	(Galvanized)

BASIC DESIGN STRESSES

Concrete:	
Class "LP"	f'c = 5,000 psi
Class "A"	f'c = 4,000 psi
Reinforcing Steel:	
Stainless	f y = 75,000 psi
Structural Steel:	
ASTM A709, Grade 50	F y = 50,000 psi
	25, Type 1 $F \mu = 120,000 \text{ psi}$
	· · · · · · · · · · · · · · · · · · ·



FALMOUTH CUMBERLAND COUNTY JOHNSON ROAD BRIDGE OVER INTERSTATE 295 PROJECT NO. 021721.00 PROJECT LENGTH 0.14 mi BRIDGE NO. 5792

UTILITIES

Consolidated Communications Central Maine Power Company Spectrum

MAINTENANCE OF TRAFFIC

Bridge closed during construction. Traffic detoured on local roads.

PROJECT LOCATION:	On Johnson Road Over Interstate 295 Latitude 43°44'32" N Longitude 70°13'27" W
PROGRAM AREA:	Bridge Program
OUTLINE OF WORK:	Bridge Replacement



INDEX OF SHEETS

Description

Preliminary Plan

Typical Sections (1 of 2) Typical Sections (2 of 2)


Title Sheet


Sheet No.

SHEET NUMBER

OF 5









IC

SHEET NUMBER


OF 5

BRIDGE 295 CUMBERLAND






PROPOSED BRIDGE SECTION



TYPICAL MILL & OVERLAY SECTION

STA 10.00.00 TO STA 10.50.00 STA 17.80.08 TO STA 18.30.08


Scale: 1/4" = 1'-0"



WESTERN APPROACH SECTION

STA 10.50.00 TO STA 12.95.52

Scale: 1/4" = 1'-0"



BRIDGE 295 CUMBERLAND SEC FALMOUTH \mathcal{O} SHEET NUMBER

OF 5

Appendix B

Photographs



Photo 1: Bridge Elevation Looking South



Photo 2: Topside Looking East

Appendix D

Existing Bridge Plans

B.P.R. STATE FED. AID SHEET TOTAL PROJ. NO. SHEETS **FALMOUTH**

STATE OF MAINE

STATE HIGHWAY COMMISSION

PLAN AND PROFILE

STATE HIGHWAY"95"

FALMOUTH

CUMBERLAND COUNTY

FEDERAL AID PROJECT NO. I - 95 -4(5)

JOHNSON ROAD BRIDGE

IIN. . 50 FT. (PLAN ∫HOR. IIN. = 50 FT. PROFILE VER. IIN. * 5 FT. SCALES (HOR. 11N. + 10 FT. VER. IIN. = 10 FT.

INDEX OF SHEETS

TITLE PAGE SHEET NO. I SHEET NO. 2 TYPICAL SECTIONS QUANTITIES SHEET NO. 3 SHEET NO. 4-6 STANDARD DETAILS

SHEET NO. 8-9 PLAN AND PROFILE STA, 2+03 TO 12+50

CROSS SECTIONS SHEET NO. 18-24 BRIDGE

SHEET NO. 10-17 SPECIAL DETAILS - BOX CULVERT SHEET NO. 7

UTILITIES SHEET NO. BA

5TA. 12+50 JOHN5ON RD. 5TA. 2+03 JOHNSON RD. STA.6+52.53 JOHNSON RD. = STA. 276+85.90 INTERSTATE To Route 1 --To Middle Road 4 E Detour SHEET #8


All work contemplated under this contract to be governed by and in conformity with the Standard Specifications for Highways and Bridges adopted January 1956, except as modified on the plans and in the special provisions.

Datum: Mean Sea Level

Boring Data shown on these plans represent only the findings of the site of borings and are not in themselves representations of actual sub-surface conditions. The contractor is to form his own opinion and make his own interpretation of the borings. The engineer does not warrant the finding to be accurate or complete.



AS BUILT 1959



CONVENTIONAL SIGNS

UNFENCED PROPERTY FENCE RIGHT OF WAY LINE TRAVELED WAY

RETAINING WALL

RAILROAD

TROLLEY POLE

POWER POLE

TEL. POLE

MARSH

A.D.T. (1955) = 300 A.D.T. (1975) = 420D.H.V. (1975) =42 D (1975) = 55% T(1975) = 11% V = 40 M.P.H.

PREPARED BY

FAY, SPOFFORD & THORNDIKE, INC. BOSTON-PORTLAND ENGINEERS

APPROVED: MAINE STATE HIGHWAY COMMISSION

DEPARTMENT OF COMMERCE BUREAU OF PUBLIC ROADS REGION I APPROVED:

DIVISION ENGINEER

75-180


DATE


and the second s

The second secon

3" BITUMINOUS CONCRETE SURFACE TYPE "A"

I'GRAVEL SURFACE COURSE





15:7"

12:0"

12:0"

12:0"

12:0"

Temp. Wooden Guard Fence

3"Crown

Grade

15" Gravel Surface

Course (Bituminous


Treated). 741 C.Y. per
100 L.F.

NORMAL Defour

> GUARD RAIL 8' Shoulder

Johnson Road

CUT



O 2 3 4 5 INCHES


STATE HIGHWAY COMMISSION AUGUSTA, MAINE

PORTLAND-YARMOUTH INTERSTATE

TYPICAL CROSS SECTIONS

SHEET NO. 2 OF 24 SCALE HOR. 1"-5"

Qm-14 62 8. M.R.L. RGME W. J.F.R.



PRELIMINARY TREES REMOVED DESCRIPTION 9"702 18" Pine 10+59

		1 010110	5
STATION	LEFT	RIGHT	NC
2450	150'		1
2+57		61'	1
4+67	150'		7
5+/8		86'	1
7+ 88	85'		/
8+22		74'	/
9+50	50'	50'	2
11+0	50'		1

GRANITE	CURB	TYPEI	Ţ
STA. TO STA.	S/DE	LENGTH	HIND
5+17.2776 5+33.27	47.	16'	Straight
5+24.29 To 5+40.29	RT.	16'	"
7+87.02 % 8+03.02	LT.	. 16'	4
7+94.04 TO 8+10:04	RT.	16'	- //

Р	RELIM	IINARY		
TEMP GL	IARD	RAIL	TYPE "	<u> </u>
5TA, TO STA.	SIDE	LENGTH	END ANCH.	REMARK
26-60 - 29:00	47.	240'	-8-	Detour
26+80 - 29+00	RT.	220'	2	Detour

	F	RELIMI	NARY	
	TEMP WO	ODEN	GUARD	EENCE
-	STA, TO STA.	510E	LENGTH	REMARKS
-	29.04-34.48	LT.	544'	Retour
+	29+04-34-16	AT.	5/2'	Defour

		FINA	L	
G	JARD	RAIL	- TYPE "E"	
STA. TO STA.	SIDE	LENGTH	END WINGS	REMARKS
2 + 22 TO 2+47	Rt	37.5'	2	
2+90 TO 5+40	Rt.	262.5	2	
7+95 TO 9+95	Rt.	200.0'	2	
2+15 TO 3+53	Lt.	150.0'	2	
3+95 TO 5+32	Lt.	150.0'	2	
7+89 TO 9+76	Lt.	187.5	2	·
		ļ		
		1		
PC	RIAL	3LE	BARRICAL	DES
2+75±				1
10.50=				
	or as b	uilt deta	iils see plan ai	nd profile skeets.
		AVEL:		

RELIMINARY - FOI	r as built details see plan and profile sheets.
	GRAVEL BASE
STA. TO STA.	DESCRIPTION
2 + 03 TO 12+50	6"Crushed Gravel, 18 Gravel
DETOUR 25.76,27,70 35.64,90	15" Grovel
	

	DAIL	IEWAY5
TATION	SIDE	REMARKS
2+67	RT.	1" Gravel Surface ! 15" Grovel Bose
3 + 72	47.	1' Gravel Surface - 15' Gravel Base
10+22	RT.	2" Bit. Conc. Type"A" - 15" Gravel Bose
10+74	LT.	L'Grovel Surface - 15" Gravel Base
12:55	47.	- 1" Gravel Surface 15" Gravel Boss

LOA	AM, SEEL	D, HAY MULCH
STA. 70 STA.	SIDE	REMARKS
2 + 07 70 5 + 38	47.	Johnson Ad. & Counter Weig
2+14 TO 5+45	AT.	" "
2+53 TO 4+19 .	RT.	Lown Beplacement After Detour Removal
Bridge Slopes	LT. &RT.	Full Section To Bridge Paving
7+82 TO 12+50	LT.	Johnson Rd.
7+89 TO 12+50	P.T.	" "
9.77 TO 10:16	· RT.	Lown Replacement After Detour Removal
2.50 TO 5.90	Detour	
7.65 TO 10.50	Détour	N H H H AND
5 Driveways		See Driveways
Note: 3'Loam, 216 Hay/s	Y.	

	SODDING	PRELIMINARY
5TA. TO 5TA.	5108	REMARKS
2.33 70 2.50	RT.	50d Ditch
3+50 TO 3+95	AT	5od Ditch
5+12	LT.	Sodded Gutter Outlet
5 • 17	RT.	Sod Ditch
9.55 70 10.14	RT.	304 011317
5,55 10 10 14		
10.10 10 10.70	47.	Rebuild Existing Lown
10.95 10 12.25	LT.	* * * *
11-70 TO 12:50	F.A.A.	

			FINAL		
	D	RIVE	WAY	CULV	ERTS
STATION	SIDE	8IZE	LENGTH	HIND	REMARKS
2+40 70 3+91	AT.	30"	148'	CMP	
3+38 70 3+88	L7:	24"	72'	CMP	2 Conc.Endwall
10+12 70 10+30	AT.	154	18'	CMP	2 " "
10+60 70 10+88	47	15"	281	CMP	2 " "
			·		
		1			
			FILIAL		

		FINAL		
A	OADW	AY C	CULVE	ERTS
STATION	BIZE	LENGTH		
3+50	9'×7'	126'	See F	Van Sheet 788
-Defour 28 +4/	-604	-50'-	CMP.	-To Be Removed

FINAL ESTIMATED QUANTITIES Preliminary

ITEM	DESCRIPTION	QUANTITY	UNIT	FALMO
201-5	Clearing		ACM	3
202-5	Removing Trees (9'-24')		Each	
202-6	Removing Trees (over 24')		Eoch	Prince:
203-9	Earth Excavation	5600	C, Y,	3,132
204-10	Structural Earth Excavation - Drainage	1400	C.Y.	1,426.8
04-14	Structural Earth Excavation - Piere	150	C,Y,	99,9
205-8	Common Borrow	35,000	CX	42,485
205-9	Granular Borrow	8400	C.Y.	3,180
302-7	Gravel Bose Course - In Place Measurement	3350	CY	3,731,4
	*Gravel for Foundations (Box Culvert)	250	C.Y.	2 4, 5
3 02-9	Crushed Grovel Base Course In Place Measurement	600	C.Y.	548,9
507-8	Reinforced Portland Cement Concrete Approach Slabs	60	5.Y.	37,40
308-5	Overhaul (In Place Measure)	15,000	Y.M.	27,12 <i>C</i>
308.6	Overhaul (Pil Meagurs)	27,000	Y.M.	phot i
309.5	Stripping Pits	12000	C.Y,	part of the same o
401-11 .	Gravel Surface Coarse	100	C.Y.	6
402-16	Stone Chips	55	Ton	41.15
104-28	Bituminious Concrete Surface Course Type "A"	470	Ton	448,2
501-7.	Road Tar	2700	Gal.	1,633
-/ · · · · · · · · · · · · · · · · · · ·	C 3 series field	***	! !	
601-11	15" Corrugated Metal Pipe	90	L.F.	47
601-14	24"Corrugaled Metal Pipe	60	L.F.	7.5
601-14 601-15	30"Corrugated Nietal Pipe	120	L.F.	138
001-13 001-23	Defour Drainage Structures	Lump Sum	4.5	Lump Sum
	Portland Cement Concrete, Abulments & Retaining Walls	200	C.Y.	202,19
701-33	DECEMBER CONCRETE, MULLIPORTO Q METUTING VIOLES	4xc worthware and fine arrived		A STATE OF THE PARTY OF THE PAR
701-37	P.C.C. Substructure, Columns, Column Bases, Bents, Collision Walls, Girders, Struts, Etc.	200	C.Y.	187.56
	Collision Walls, Giraels, Strats, Lic.	120	CY	118,65
70/-38	Portland Cement Concrete, Floor Slabs Portland Cement Concrete, Superstructure Slabs	150	C.Y.	51.65
201-39	P.C.C. Roadway and Sidewalk Slabs on Steel Bridges	250	C.Y.	248,59
101-40		4	C.Y.	11.08
701-45	P.C.C. Culvert Endwalls	1500	Bb/6.	1,419.44
701-47	Portland Cement		Each	6
701-50	Wrought Iron Scuppers	6	·	
701-52	P.C.C. Box Culvert Sidewalls, Wingwalls, & Wingwall Footings	/40	C.Y.	154.10
702-103	Structural Steel, Fabricated & Delivered	182, 900 182, 9 00	166.	169,084.68 169,084.68
702-104	Structural Steel, Erection	115,000	Lbs.	112,532.74
705-13	Reinforcing Steel, Delivered		Lbs.	112,532.74
705-14	Reinforcing Steel, Placing	115,000 Lump Sum	The second secon	Lump Sum
705-17	Shear Connectors		L.F.	
708-16	Steel H-beam Piles 42 lbs./ft.	6300	5.Y.	5,897
709-6	Membrane Waterproofing	7/0		671.30
710-6	Waterproofing Joints	30	4.F.	30.82
804-6	French Drains	50	C.Y	45.32
306.7	Aluminum Roll. Delivered and Erected	505	L.F.	504,30
901-8	Granite: Curp + Type I.	64	L.F	64
905-23/		500	C.F.	499.1
905-27	Guard Rail + Type "E"	900	L.F.	937.5
905-27A	Guard Rail -Type "E" (Post 7'-9" Centers)	65	2.A	50
905·3/A		4	5och	44
905-34	End Wings		Goch	12
905.37	Temporary Wooden Guard Fence	1100	L.F.	1,186.1
907-10	Hand Laid Riprap	30	CY	102.9
907-/2	Slope Poving for Bridge	450	S.Y.	445.7
908-9	Loam Borrow	1100	C.Y.	1, 354
909-7	Bodding	900	5.7	1,057.1
910-10	Seeding - Parkway Mixture	90	Unit	95.25
912-6	Hay Mulch	10	Ton	10.45
914.6	Project Markers		Each	
915-6	Aight of Way Monuments	11	Eoch	9
928-6	Portable Barricade With Flashing Warning Lights	Jump Sum	Z.5,	
U 60 0	Allowance for pile cut-offs		L.F.	492.4
E WOS		and the state of t	L.F.	726
	Underdrain Type "B" Structural Rock Excar Drainage		C.Y.	8.5
	- VIIIOINI OI NOON DAWY - VINIINAY"		\ F.A	1 · · · · · · · · · · · · · · · · · · ·
\$ 1	2 Polymond add to Class Prings	17	11 - 7	
	3 Repair and add to Slope Paving Straighten Rockers		F.A.	

* See M.S.H.C. Std. Spees, pg. 78 Item 302-6(C) ** See M.S.H.C. Std. Spec. pg. 60 Item 204-9(a) PRELIMINARY


AND BORROW
5,600CY.
- 2283 C.Y.
3317 C.Y.
X 80 %
2654 C.Y.
10 170 011
42,/32 C.Y
- 23C.Y.
42,109C.Y
- 2,654C.K
39,455 C.Y.
×110 %
43,400 C.Y.
isted locations of Mix. Earth L
m unlisted locations


This contract shall include the placing of embankment, and the removal of excavation on the interstate road to the lines and grades shown on the cross sections from Station 276+25 to Station 278+25. At these stations the work shall be completed on a line parallel to the Station 278+25. At these stations the work shall be completed on a line parallel to the Centerline of Johnson Rd. and then graded outward from this centerline on a six to one slope porallel to the interstate centerline. This work will not include the placing of any material above the subgrade or the placing of any drainage structures.

The timber cribs on the Johnson Rd. detour are to be 8'x8'x7' high and constructed of 6"x8"x8' timbers spiked at the corners. A timber coping is to be placed over the pipe. QUANTITIES These cribs will be paid for in the lump sum bid for the 60" cm.p.

75-182


2 3 4 5 INCHES





O 1 2 3 4 5 INCHES

make make to fine women's representative and the second second second second second second second second second



PROFILE-JOHNSON RD. DETOUR FALMOUTH 75 70 65 55 50

Strage Profile Lt. Edge
Symptograph of the Company of the Company

0 1 2 3 4 5 INCHES

PV1. - Sta. 3/+25 Elev - 35.57 PVI- Sta. 27+ 75 Elev- 30.80 Y.C. - 150' M. - 107 N.C. - 250 M. - 3.01 P.V.S.-Sta. 26+50 Elev.-36.20 V.C.-100' M.-0.54'

Rt. Edge Profile Lt. Edge
Pvmt.
Grade Pvmt.

· ·

90

85

රර

75

70

65

60

55

50

45

35

30


25


20


15


-1. [10


P.V.I. 34+25 Elev. 68.57 V.C. 200' M 1.35'
















O 1 2 3 4 5 INCHES



Applications of the state of th


Boston Blue Print-200-4-67



Mean Dia. = 5" 1"Min ---SINGLE SPIRAL STUDS (3 Per Pitch) DOUBLE SPIRAL

r for Sole Plate = = + 3" r for Rocker Web = 2 + 2"

And the second s



14 & Swedge Bolt

Boston Blue Print-200-4-57

TYPE J (FIXED BERRING) Scale: 1;"=1-0"

Length of Cover Plate TYPICAL COVER PLATE DETAIL No Scale


SHEAR CONNECTOR DETAILS

Scale: 12"=1-0"

Plate Fillet Thickness Weld 3/8"to 3/4" 5/16"

B. P. R. STATE FED. AID SHEET TOTAL PROJ. NO. NO. SHEETS

FALMOUTH



Spiral Notes

1. All spirals to be fabricated with 34 & plain bars and to have a mean diameter of 5 inches.

2. Spirals to be welded to stringer flonge with two &" fillet welds, 24" long at each point of contact.

3. Spiral lengths given on froming plan are net lengths and do not include any allowance

4. Where spiral sections are joined, they shall be lapped for a distance of one-half the smaller pitch.

AS BUILT - NO REVISION

STATE HIGHWAY COMMISSION AUGUSTA, MAINE

PORTLAND-YARMOUTH INTERSTATE

JOHNSON ROAD OVER INTERSTATE


STANDARD FRAMING DETAILS

SHEET NO. 16 OF 24 SCALE AS NOTED

FAY, SPOFFORD & THORNDIKE, INC. ENGINEERS BOSTON, MASS. ENGINEERS

<u> 0m-14</u> 로함 75-196


Confidence of the Confidence o




the standing of the standard o


75-197


Qm-14 27





d 1 2 3 4 5 INCHES





















NOTES

- 1. IF THE DEPTH OF DETERIORATED CONCRETE EXTENDS TO THE REINFORCING BARS, THEN REMOVE CONCRETE TO A MINIMUM DEPTH OF 1" BEYOND THE REINFORCING STEEL.
- 2. RESETTING EXISTING POSTS AND INSTALLATION OF PROPOSED GUARD RAIL POSTS TO BE INCIDENTAL TO ITEM 606.364.


PROJECT NUMBER


MAINE IR-95-4(65) /6 25

- 3. TERMINAL CONNECTOR AND ATTACHMENTS TO THE EXISTING CONCRETE PARAPET TO BE INCIDENTAL TO ITEM NO. 606.364.
- 4. AFTER THE EXISTING BITUMINOUS PAVEMENT HAS BEEN REMOVED THE CONTRACTOR MAY BE DIRECTED BY THE ENGINEER TO REHABILITATE AREAS OF THE DECK. PAYMENT WILL BE MADE UNDER ITEMS 518.30 OR 518.31 WHICHEVER IS APPLICABLE.
- 5. PROPOSED REINFORCING STEEL SHALL HAVE A MINIMUM COVER OF 2" UNLESS OTHERWISE INDICATED.
- 6. PROTECTIVE COATING FOR CONCRETE SURFACES SHALL BE APPLIED TO ALL EXPOSED SURFACES OF CONCRETE PATCHING AND THE IMMEDIATE SURROUNDING AREA AS DIRECTED BY THE ENGINEER.



TYPICAL COLUMN REHABILITATION DETAIL








DETERIORATED CONCRETE. THE ENGINEER SHALL VERIFY ACTUAL QUANTITY OF SURFACE AREA TO BE REHABILITATED.

TYPICAL ABUTMENT REHABILITATION - PLAN



EXISTING CONCRETE TO BE REMOVED PROPOSED CONCRETE

> PIN NO. 003280.00 BRIDGE NO. 5792

STATE OF MAINE DEPARTMENT OF TRANSPORTATION

ONE CATE STREET PORTSMOUTH, N.H. 03801 (603) 431-2520

JOHNSON ROAD 99

I-95

FALMOUTH, MAINE CUMBERLAND COUNTY DETAILS & ESTIMATE OF QUANTITIES

SHEET 2 OF 3

AUGUSTA, MAINE

506.172 FIELD PAINTING EXISTING STRUCTURAL STEEL ANS P.

The second second second


182,000 lbs.

1" CLEAR MIN. (TYP.)

EXISTING REINFORCING -

TYPICAL PIER CAP REHABILITATION DETAIL

HATCH AREA DENOTES AREA OF DETERIORATED CONCRETE. ENGINEER SHALL VERIFY ACTUAL QUANTITY OF SURFACE AREA TO BE REHABILITATED. (SEE NOTE 1)



Appendix F

Johnson Road Traffic Model Summary

Falmouth - PM Peak Hour								
	Alternatives							
Intersections	Existing		Improved		Johnson On	e-Lane	Johnson Clo	sed
	LOS - delay	Q>Storage	LOS - delay	Q>Storage	LOS - delay	Q>Storage	LOS - delay	Q>Storage
Vehicles Denied Entry	194		0)	0		1	
Total Delay	78		84		93		79	
Johnson-Middle	OK	OK	OK	OK	OK	OK	A-1.8	OK
One-Lane Johnson					C-30.7	OK		
Johnson-US1	OK	OK	OK	OK	OK	OK	A-7.2	OK
Long Woods-Middle	OK	OK	OK	OK	OK	OK	A-7.5	OK
Falmouth/Bucknam-Middle	С	EBT50 WBR95 SBL95	D-41.4	EBT50 WBR95 NBR95 SBL95	D-38.3	EBT50 WBR95 NBR95 SBL95	C-27.0	NBT95 NBR95
Bucknam-SB ramps	С	WBT50 SBT50	B-16.9	EBL95 WBT50 SBT50	B-16.1	EBL95 WBT50 SBT50	B-15.1	ок
Bucknam-NB ramps	С	SBT>>	B/C-19.5	ОК	B/C-19.3	ок	C-23.2	EBL95 EBT95 WBT95
Bucknam-US1	В	EBL95	C-24.5	EBL95 NBL95 SBT50	C-21.6	EBL95 NBL95 SBT50	C/B-20.7	EBL95 EBT95 SBT95
Lunt-Falmouth	OK	OK	OK	OK	OK	OK	OK	OK
Lunt-Middle	OK	OK	OK	OK	OK	OK	OK	OK
Lunt-Depot	OK	OK	OK	OK	OK	OK	OK	OK
Depot-US1	C/B	OK	C-21.2	EBR95	C-21.2	EBR95	C-21.9	EBR95
Clearwater-US1	А	ок	A-7.4	ок	A-7.9	ок	A-8.2	EBT95 NBT95 SBT95
Hunter-US1	A-2.3	OK	A-2.3	OK	A-3.0	OK	A-3.3	NBT95
Planned and Programmed Imp Long Woods-Middle Bucknam-NB ramps	provements		in place		in place		in place	
Falmouth/Bucknam-Middle								
Bold queue indicates spillbac	k to upstream	intersection						
LOS - delay based on overall	intersection de	lay and sign	alized LOS s	cale				
T		_			:			
Temporary treatments					install tempo	orary signal		

Johnson Road	User Impa	cts and Costs	3						
			Improved		Johnson Rd		Johns	son Rd E	Bridge
			Falmouth		Bridge		Closed, Adjuste		
			Network		One Lane		Traffic and Signals		gnals
PM Peak-Hour	Travel								
V	ehicles Der	nied Entry	0		0			1	
D	elay (VHT)	_	84		93			79	
Delay Impacts									
Р	eak-Hour D	elay (VHT)	0		9			-5	
D	aily Delay	(VHT)	0		34			-19	
D	aily User C	osts			\$ 438		\$	(243)	
Detour Impacts	3								
D	aily Distand	ce (VMT)	0		0			1310	
D	Daily Travel Time (VHT)		0		0			37	
D	aily User C	osts			\$ -		\$ 851		
Total D	Daily User Costs \$ 438		\$	607					
	erstate Closure User Impacts		via I-295	via US 1					
В	etween Exi	ts 10 and 15							
		speed	65		mph	Increase in			
		distance	3.64		miles	travel cost			
		travel time	0.056		hours	\$/vehicle			
		travel cost	0.78	1.80	\$/vehicle	\$ 1.02			

Appendix G


Traffic and Accident Data

					STAT	FILE: Falmo	outh				
				INTE	CRDEPARTM						
							e of Request:		Return:7/22/2016		
						Late	est Date Ne				
	To:	Ed Han			Dept.:			MDOT, Bridge Program			
	From:	Janet Damren 4-3462				Dep		Bridge Prograi	<u>m</u>		
	Subject:	Request	for Traff	<u>ic Information</u>		Project Manager:			Joel Kittredge		
	TOWN(S):		Falmout	<u>h</u>		P.I.N.			Consultant Proj		
	COUNTY: <u>Cumberland</u>				ROUTE:						
	LOCAT DESCRIE			n Road/I-295 b a mile west of l		hich carri	ies Johnson	Rover over I-29	95, located		
				y Changes or Relocation (Attach Sketch)		Turning Movement needed (Provide Locations under Comments)			oe Under Comments		
	Please Check Box if Applicable:			(Tittaen breten)	(1 Tovide Locations under Comments)			other Fredse Beserve	or onder comments		
	Prep By:			Sec. 1 Falmouth -	<u>Sec. 2</u>	<u> </u>	Sec. 3	<u>Sec. 4</u>	<u>Sec. 5</u>		
	Description	of Section	<u>1S</u>	Johnson Road NW/O Harriette Street							
1	Latest AAD	T (Year)		1440 (2013)		=					
2	Current	2016	AADT	<u>1440</u>		-					
3	Future	2026	AADT	<u>1580</u>		-					
4	Future	2036	AADT	<u>1730</u>		-					
5	DHV - % of	AADT		<u>11%</u>	%	<u>)</u>	%	%	%		
6	Design Hourly Volume 19			<u>190</u>		<u>-</u>					
7	% Heavy Trucks (AADT)			<u>5%</u>	%	<u>)</u>	%	%	%		
8	% Heavy Tr	ucks (DH	V)	<u>3%</u>	%	<u>)</u>	%	%	<u></u> %		
9	Direct.Dist.	(DHV)		<u>50%</u>	%	<u>2</u>	<u></u> %	<u></u> %	%		
10	18-KIP Equ	ivalent P 2	2.0	<u>27</u>		-					
11	18-KIP Equ	ivalent P 2	2.5	<u>25</u>		<u>-</u>					
	Notes or Remarks: 18-Kip ESALS is based on 20 year life										
	PLEASE PROVIDE: (1) PIN NUMBER, (2) THE CURRENT & FUTURE YEARS FOR WHICH YOU WANT AADT CALCULATED, AND SEND TO MIKE MORGAN. (A LOCATION MAP IS NO LONGER NEEDED.) TRAFFIC REQUESTS WILL BE FILLED ON A FIRST COME / SERVE BASIS. PLEASE SEND WHEN PROJECT KICKS OFF!! Need Only Data Items Numbered									F!!!!	
	Comm	ents:	No Heavy	Truck data availab	ole. Assumed 5% l	Heavy Truck	KS.				

Appendix L

Preliminary Construction Schedules

WIN 21721.00 - Falmouth Johnson Road Bridge over I-295 Alternative 1 **Deck Replacement with Substructure Rehabilitation - Preliminary Construction Schedule** Task Task Name Duration Start Predecessors November December 7/28 8/4 8/11 8/18 8/25 9/1 9/8 9/15 9/22 9/29 10/6 10/13 10/20 10/27 11/3 11/10 11/17 11/24 12/1 12/8 12/15 12/22 12/29 1/5 1/12 1/19 1/26 2/2 2/9 2/16 2/23 3/1 3/8 3/15 3/22 3/29 4/5 4/12 4/19 4/26 5/3 5/10 5/17 5/24 5/31 6/7 6/14 6/21 6/28 7/5 7/12 7/19 7/26 8/2 8/75 1 Advertise Project 0 days Wed 8/7/19 Wed 8/7/19 4 Week AD period 4 wks Wed 8/7/19 Tue 9/3/19 1 Bid Review/Award of Contract Wed 9/4/19 Tue 9/10/19 2 Processing of Construction Contract 1 mon Wed 9/11/19 Tue 10/8/19 3 ■ NTP 0 days Tue 10/8/19 Tue 10/8/19 4 Mobilization 10 wks Wed 10/9/19 Tue 12/17/195 7 Install Shielding over I-295 10 days Wed 2/12/20 Tue 2/25/20 6FS+2 mons Place Signage for Detour Route 10 Days in 10 days Tue 3/10/20 7 2/26/20 Advance of Closure 9 III School Close Johnson Road Bridge 0 days Mon 3/16/20 Mon 3/16/208 10 Begin Bridge closure period 60 days Mon 3/16/2(Fri 6/5/20 Remove Existing Deck (Day & Night Wor8 days Mon 3/16/20 Tue 3/24/20 9 Install Temporary Support Towers to 5 days Mon Fri 3/20/20 9 3/16/20 Jack Superstructure Jack Steel Superstructure (Nights) 8 days Wed 3/25/20 Thu 4/2/20 12,11 Demo Existing Pier 1 5 days Fri 4/3/20 Wed 4/8/20 13 Install additional Pier 1 Piles 2 days Thu 4/9/20 Fri 4/10/20 14 3 days Sat 4/11/20 Tue 4/14/20 15 Cure Pier 1 Footing 2 days Wed 4/15/20 Thu 4/16/20 16 4 days Fri 4/17/20 Tue 4/21/20 17 Cure Pier 1 Columns 2 days Wed 4/22/20 Thu 4/23/20 18 3 days Fri 4/24/20 Mon 4/27/2019 Add Add'l Steel Bracing 5 days Fri 4/3/20 Wed 4/8/20 13 Substructure Rehab (Piers 2 & 3 & Abut 20 days Fri 4/3/20 Sat 4/25/20 13 Install Bearings 5 days Tue 4/28/20 Sat 5/2/20 20,22 Lower Superstructure (Nights) 3 days Mon 5/4/20 Wed 5/6/20 21,23 10 days Thu 5/7/20 Mon 5/18/2024 3 days Tue 5/19/20 Thu 5/21/20 25 Fri 5/22/20 Fri 5/22/20 26 28 🖺 🔫 2 days Sat 5/23/20 Mon 5/25/2027 Install Joints 29 FTP Curb & Bridge Rail Anchor Bolts 4 days Tue 5/26/20 Fri 5/29/20 28 30 🖺 📑 3 days Sat 5/30/20 Tue 6/2/20 29 31 🛂 🧠 Install bridge rail 2 days Wed 6/3/20 Thu 6/4/20 30 32 Striping 1 day Fri 6/5/20 Fri 6/5/20 31 Re-Open Johnson Road Bridge 0 days Fri 6/5/20 Fri 6/5/20 32 Substantial Completion 0 days Fri 6/5/20 Fri 6/5/20 33SS Punch List Items 2 mons Mon 6/8/20 Fri 7/31/20 34 Project Completion 0 days Fri 7/31/20 Fri 7/31/20 35 Manual Summary Rollup Start-only Project: Lunt Road Bridge Staged Task **Project Summary** External Milestone Inactive Milestone Manual Task Deadline Critical Split Date: Fri 12/14/18 External Tasks Manual Summary Finish-only Summary Inactive Task Inactive Summary Duration-only Progress Page 1



WIN 21721.00 - Falmouth

Johnson Road Bridge over I-295

Alternative 2

| Superstructure Replacement with Substructure Replacement with Su

60 Project Completion

0 days Tue 8/18/20 Tue 8/18/20 59

8/18

WIN 21721.00 - Falmouth Johnson Road Bridge over I-295 Alternative 3 **Complete Bridge Replacement - Preliminary Construction Schedule** Task Task Name Duration Start Predecessors October November 1 Advertise Project 0 days Wed 8/7/19 Wed 8/7/19 2 4 Week AD period 4 wks Wed 8/7/19 Tue 9/3/19 1 Bid Review/Award of Contract 1 wk Wed 9/4/19 Tue 9/10/19 2 Processing of Construction Contract 1 mon Wed 9/11/19 Tue 10/8/19 3 0 days Tue 10/8/19 Tue 10/8/19 4 Mobilization 10 wks Wed 10/9/19 Tue 12/17/195 Install Shielding over I-295 10 days Wed 2/12/20 Tue 2/25/20 6FS+2 mons Place Signage for Detour Route 10 Days in Advance 10 days Wed Tue 3/10/20 7 of Closure Close Johnson Road Bridge 0 days Mon 3/16/20 Mon 3/16/20 8 92 days Mon 3/16/2(Tue 7/21/20 Begin Bridge closure period Remove Existing Superstructure (Day & Night Worl 12 days Mon 3/16/20 Sat 3/28/20 9 Demo Existing Substructures 10 days Mon 3/30/20 Thu 4/9/20 11 13 🚤 **Abutment 1 Construction** 15 days Fri 4/10/20 Mon 4/27/20 Install Abutment Piles 3 days Fri 4/10/20 Mon 4/13/2012 FTP Abutment Stem & Wingwalls 8 days Tue 4/14/20 Wed 4/22/2014 Cure Abutment 4 days Thu 4/23/20 Mon 4/27/2015 **Abutment 2 Construction** 15 days Tue 4/14/20 Thu 4/30/20 18 🔜 Install Abutment Piles 3 days Tue 4/14/20 Thu 4/16/20 14 19 嘱 FTP Abutment Stem & Wingwalls 8 days Fri 4/17/20 Sat 4/25/20 18 20 🚤 Cure Abutment 4 days Mon 4/27/20 Thu 4/30/20 19 30 days Fri 4/17/20 Thu 5/21/20 **Pier Construction Install Piles** 8 days Fri 4/17/20 Sat 4/25/20 18 23 🚤 FTP Pier Footing 6 days Mon 4/27/20 Sat 5/2/20 22 3 days Mon 5/4/20 Wed 5/6/20 23 Cure Pier Footing FTP Pier Wall 10 days Thu 5/7/20 Mon 5/18/20 24 Cure Pier Wall 3 days Tue 5/19/20 Thu 5/21/20 25 5 days Fri 5/22/20 Wed 5/27/2016,20,26 Install Bearings Steel Superstructure Erection (Night Work) 15 days Thu 5/28/20 Sat 6/13/20 27 29 🚤 FTP Deck 15 days Mon 6/15/20 Wed 7/1/20 28 Cure Deck 3 days Thu 7/2/20 Mon 7/6/20 29 31 🚤 Groove Deck 1 day Tue 7/7/20 Tue 7/7/20 30 32 🚤 2 days Wed 7/8/20 Thu 7/9/20 31 Install Joints FTP Curb & Bridge Rail Anchor Bolts 4 days Fri 7/10/20 Tue 7/14/20 32 34 🚤 Cure Curbs 3 days Wed 7/15/20 Fri 7/17/20 33 Install bridge rail 2 days Sat 7/18/20 Mon 7/20/2034 Striping 1 day Tue 7/21/20 Tue 7/21/20 35 Re-Open Johnson Road Bridge 0 days Tue 7/21/20 Tue 7/21/20 36 **Substantial Completion** 0 days Tue 7/21/20 Tue 7/21/20 37SS 39 Punch List Items 2 mons Wed 7/22/20 Tue 9/15/20 38 9/15 40 Project Completion 0 days Tue 9/15/20 Tue 9/15/20 39 Manual Summary Rollup Start-only Project: Lunt Road Bridge Staged Task **Project Summary** External Milestone Inactive Milestone Manual Task Critical Split Date: Fri 12/14/18 Manual Summary Finish-only Summary External Tasks Inactive Task Inactive Summary Duration-only Page 1