Local Project Administration Manual & Resource Guide

### **Construction Administration**



### **Construction Administration**

onstruction typically follows a contract award to the successful bidder. Once the job begins, the agency administering a project must document and inspect the work. Most of the time, this is a full-time responsibility.

Chapter 11 of this Manual provides guidance on the topics listed below:

- Oversight responsibilities (page 11-1);
- Pre-construction meeting (page 11-2);
- Contractor payrolls (page 11-3);
- Contract modifications (page 11-4);
- Construction documentation (page 11-5);
- Materials testing (page 11-7);
- Buy America *updated* (page 11-8);
- Project bulletin board / Commercially Useful Function / Final inspection (page 11-10);
- Final contractor payment / Closeout / As-Built plans (page 11-11);
- Appendix 11A: Administrative checklist (page 11-12);
- Appendix 11B: Submittals to MaineDOT *updated* (page 11-15); and
- Appendix 11C: Sample field book entries (page 11-22).

#### 11.1 Oversight Responsibilities

A local agency must assign an employee with appropriate technical qualifications or a consultant with pre-qualification status from MaineDOT to document and inspect the work. This person – known as the resident inspector or as the resident, for short – protects an agency's interests by enforcing the plans and specifications, logging daily activities on a job site, checking payrolls, and verifying the quantities of materials.

■ Additionally, a local agency must arrange for a paving inspector and concrete technician, with required certifications, to be on site for work involving hot-mix asphalt and concrete. See Section 11.6 (Materials Testing) on page 11-7.

A resident inspector likely to be assigned to jobs with funding from MaineDOT must have taken <u>Documentation Training</u> within the previous year before starting on a project. If the training isn't offered, the standard LPA Training or Construction Training may be substituted. Contact the MaineDOT local projects coordinator: <a href="https://www.maine.gov/mdot/lpa/contact/">https://www.maine.gov/mdot/lpa/contact/</a>.

If the resident will be a consultant, a local agency must go by the hiring procedures in Chapter 2 (Hiring Consultants) and seek proposals from firms pre-qualified for construction management under MaineDOT service number 601.00: https://www.mainedot.gov/cpo/prequal/.



The resident inspector (or a different, approved inspector) must be on site for major tasks such as excavation, drainage work, paving, and concrete placement. Most often, this will be a **full-time** responsibility to be sure the following tasks are performed:

Inspecting the work, documenting quantities, and checking lines and grades.
Reviewing certified contractor payrolls, as covered in Section 11.3 (Contractor Payrolls).
Coordinating contract modifications. MaineDOT must concur with modifications <b>before</b> they are signed, as covered in Section 11.4 (Contract Modifications).
Keeping a daily log and other field records, as discussed in Section 11.5 (Construction Documentation).
Arranging for testing of aggregates, pavement and concrete  – and rejecting failing materials.
Monitoring the contractor's traffic control plan to ensure safe travel in the work zone.
Checking compliance with environmental commitments and permit requirements, including erosion-control provisions.
Approving contractor payments for satisfactory work, after verifying quantities.
Checking labor compliance, including project bulletin board setup. A diagram is online: <a href="https://www.mainedot.gov/civilrights/sfp/">https://www.mainedot.gov/civilrights/sfp/</a>

#### 11.2 Pre-construction Meeting

The primary event before work begins is the pre-construction meeting, typically involving the contractor, local project administrator, resident inspector, utility representatives, and MaineDOT construction manager. (*Refer to Letter 17*, on page 11-16, for a sample agenda.)

A pre-construction meeting should be held at least **one week** before the scheduled start of work. It should cover the requirements placed on the prime contractor, coordinate the schedule, and establish the frequency of progress meetings. Refer to MaineDOT's *Standard Specifications*, section 104.4.2 (Preconstruction Conference).

The local project administrator should prepare an agenda and invite the participants. Afterward, minutes should be sent to the participants and other parties, including public-safety agencies if there will be lane closures or detours.

- **⊃** If a project will require multiple utility relocations, a separate **pre-utility meeting** may be held at the discretion of the local project administrator.
- → A stand-alone pre-pave meeting must be held before paving starts. This mandatory meeting typically involves the local project administrator, paving contractor, resident inspector, the MaineDOT construction manager and other and appropriate personnel

#### **11.3 Contractor Payrolls**

#### ☐ 11.3.1: Elation System

The prime contractor and subcontractors on federal projects must submit payrolls electronically in the online Elation system to verify Davis-Bacon wage compliance. Upon awarding a contract, a local agency should email the information below to MaineDOT's Contracts Section, which will set up a project in the system:

- Work Identification Number (WIN);
- Name and email of the resident inspector;
- Name and address of the prime contractor;
- Amount of the contract award:
- Dates of advertise, bid opening and award;
- Construction start date:
- Contract completion date stipulated in the contract;
- Subcontractor information, with the service provided and subcontract amount;
- County in which the work will take place;
- Wage Rate General Decision and modification numbers, such as ME100011-Mod-0.

An Elation user's manual is online: www.mainedot.gov/contractors/publications/

#### **□** 11.3.2: Payroll Verification

The resident inspector must make sure that contractors on federal projects comply with the Davis-Bacon wage decision. Typical responsibilities consist of the following:

- Checking contractor payrolls for completeness, accuracy, and compliance issues; and
- Ensuring that the duties performed and hours put in by workers covered by Davis-Bacon are consistent with what contractors are reporting in the Elation system.

After contract award, the resident must check for missing classifications and rates. If the federal wage decision is incomplete, the **prime contractor** must request missing classifications and rates through the Elation system.

Requests must be coordinated with MaineDOT's Civil Rights Office, which may be reached by phone at 207-624-3066 or online at <a href="https://www.mainedot.gov/civilrights/contact/">www.mainedot.gov/civilrights/contact/</a>.

#### **□** 11.3.3: Payroll Interviews

Every 90 days, the resident must interview **two covered workers** from the prime contractor and all subcontractors that were on site at least **five days** during a 90-day period. Interviews must be voluntary, confidential and in-person. Standard Form 1445 (Labor Standards Interview) is available in the Elation payroll system.

The resident inspector will compare information from the interviews against a contractor's certified payroll report for a given period. The resident must address any discrepancies.

MaineDOT Contact: Angela Latno: 207-624-3519 angela.latno@maine.gov

#### **□** 11.3.4: State Payrolls

Contractors on state-only projects, such as through the Small Harbor Improvement Program, the Heads Up! pedestrian safety program and the Municipal Partnership Initiative, should submit certified payrolls verifying that they are paying at least the Maine Department of Labor's prevailing wage rates. Each submittal should include a "Statement of Compliance" that the payrolls are correct and complete.

→ A standard Certified Payroll Form from the Maine Department of Labor should be used: www.maine.gov/labor/labor\_stats/publications/wagerateconst/index.shtml

#### 11.4 Contract Modifications

Occasionally, the local agency managing a project and its contractor will need to change the terms of the construction contract, which requires a contract modification.

A contract modification, also called a change order, must be drafted by the resident inspector or local project administrator – NOT the contractor. If a local agency expects MaineDOT to participate financially in a modification, MaineDOT's construction manager must concur with the change before associated work begins. Otherwise, MaineDOT may deny reimbursement for work covered by a modification.

A draft contract modification must be sent to MaineDOT's construction manager for review and concurrence in the format of <u>Letter 18</u>, on page 11-18, with two pieces of information:

- An independent cost estimate for the additional work; and
- A statement addressing the associated contract time. If there is no change, write **0 days**.

A contract modification form may be downloaded from the "Construction Field Documents" section of MaineDOT's LPA website: <a href="https://www.mainedot.gov/lpa/lpadocuments/">www.mainedot.gov/lpa/lpadocuments/</a>

A contract modification generally is necessary for any of the following:

- A change in the specifications;
- A substitution of materials;
- A change in the testing requirements;
- A change or extra work within the scope of the contract;
- A design change beyond the scope of the contract;
- Adding payment or credit for incentives/disincentives;
- A change of 25 percent or more in a major item, defined as 10 percent or more of the contract amount.
- An adjustment in the contract completion date.

#### 11.5 Construction Documentation

Keeping accurate, detailed field records is vital. Briefly covered on the next two pages are the standard field documents on a project, with an explanation of how to fill them out.

- **⊃** For detailed information on construction documentation, refer to two online publications:
  - MaineDOT Record Keeping Manual: <a href="www.mainedot.gov/contractors/support/">www.mainedot.gov/contractors/support/</a>
  - MaineDOT Construction Manual: www.mainedot.gov/contractors/publications/

#### ☐ 11.5.1: Project Diary

The resident inspector on a project must keep either a bound field book or an electronic log, using a program such as FieldManager, to record the daily activities of the prime contractor and subcontractors.

This document, commonly called a project diary, should record the following, at a minimum:

Weather, since rain or cold could affect the work;	SOKKIA
Pay items worked on each day, by project stationing;	FIELD
The number of workers on site, with their job classifications, to be checked against contractor payrolls;	
Major pieces of equipment on site such as excavators, loaders, compactors, bulldozers, graders, pavers, and rollers;	N-FOR
Field measurements by pay item number, with quantities of materials, against contractor requests for payment;	to be checked
Grade checks for items such as subgrade, top of gravel (fine-grading), backslopes to ensure that the work meets the plans and specifications	
Drainage measurements by stationing for items such as catch basins a computations from outlet to inlet;	nd pipes, with
Source and disposition of excavation, borrow, gravel and pavement gr	rindings; and
Noteworthy events, such as:	
<ul> <li>Traffic accidents, which also require an accident report or near-</li> </ul>	miss form:

- Traffic accidents, which also require an accident report or near-miss form;
- Contractor adherence to the traffic control and erosion control plans;
- Directives given to the contractor by the resident inspector;
- Discussions with property owners and other abutters; and
- Disputes with the contractor or issues with quality that could lead to a claim.

Refer to Appendix 11C, starting on page 11-22, to find sample field book entries.

#### ☐ 11.5.2: Drainage Book

A separate drainage book may be needed for large, complex projects. Such supplemental documentation should be kept at the discretion of the resident inspector.

Each run of pipe and catch basin should have a separate page in a drainage book. The resident should note items such as lengths of pipe installed, catch basins placed, gravel used for traffic maintenance, undercutting and bedding material used, ledge removed (if applicable), and riprap at pipe inlets and outlets.

#### ☐ 11.5.3: Final Quantity Book

All bid items in the contract and all work orders involving additional payment must be entered in a final quantity book. This book maintains a reference trail leading from the final pay quantity for an item to the original documentation, such as notes of inspection and acceptance, measurements, or calculations made in a daily report. Entries must be signed and dated.

The final quantity book should have one item per page, as follows:

Item number description and quantity should be at the top of the page;
The final quantity should be entered at the bottom and so labeled;
Pages should be set up for original measurements or computations;
Pages set up with a total-to-date column;
Entries and computations initialed and dated;
Calculation of the final quantity must be shown, after an item is completed.

#### 11.5.4: Testing File

Before construction, MaineDOT establishes mandatory Minimum Testing Requirements for aggregates, pavement, concrete and other materials. These requirements establish the frequencies and types of materials tests to be performed.

The resident inspector should set up a testing file for all test reports and other data that document the quality of materials installed on a project. The file should be set up by material and based on the Minimum Testing Requirements, which should be kept at the front of the testing file and used as a guide.

In the testing file, the resident or a designated inspector should explain how a failing test result was resolved, such as whether a failing material was removed and replaced. Results of failing tests should be shared with the MaineDOT construction manager, who may be able to help remove an issue.

At MaineDOT, a testing file typically is bound by a black pressboard binder with a white label marked "Testing File" - with location and WIN. Tabs are used to identify and separate the items.

#### 11.6 Materials Testing

Materials placed on projects with federal and state funds must meet MaineDOT's specifications. Proper testing of items such as gravel, pavement and concrete will help to ensure their performance and durability. After accepting the final PS&E package for a project, MaineDOT will prepare Minimum Testing Requirements listing the type and frequency of materials tests.

Before construction, the resident inspector may request a meeting with MaineDOT personnel – including the construction manager and the quality-assurance engineer – to go over the testing requirements. Possible topics include the timing of tests, testing procedures and documentation.

Each test result must be logged in a testing file, as covered in subsection 11.5.4 (Testing File). A local agency should notify the MaineDOT construction manager of a failing test. In such a case, MaineDOT may help to resolve the issue.

#### ☐ 11.6.1: Aggregates

A local agency must use an **independent**, **accredited laboratory** to test all aggregates installed on a project, such as gravels, underdrain sand, crushed stone and granular borrow. A certified inspector must obtain samples and conduct any required on-site tests for compaction and other properties, as set out in the Minimum Testing Requirements.

**Note:** The agency overseeing a project cannot use the same testing laboratory as the lab doing the contractor's quality-control work. This should be covered at the pre-construction meeting.

Testing labs are listed under MaineDOT pre-qualification service number 804.00, Laboratory Materials Testing and Exploration: <a href="https://www.mainedot.gov/cpo/prequal/#prequal4">www.mainedot.gov/cpo/prequal/#prequal4</a>

#### ☐ 11.6.2: Pavement

An inspector certified by the Northeast Transportation Technician Certification Program (NTTCP) must be on site during paving work. The inspector will perform tasks such as checking that hot-mix asphalt pavement is placed at the proper temperature (275 to 325 degrees F) and preparing core samples for testing.

Pavement core samples with ID tags filled out must be taken to a **MaineDOT testing lab**, either in Freeport or Bangor, where MaineDOT staff will perform the required tests. Testing of pavements must be covered in detail at the pre-pave meeting for a project.

#### **□** 11.6.3: Concrete

A technician certified by the American Concrete Institute (ACI) must be on site for concrete placements to test mix properties such as air content, temperature, and water/cement ratio. The technician will document the mixtures and prepare the sample cylinders that will be used to measure compressive strength and permeability at a testing lab.

Cylinders with ID tags must be taken to the closest **MaineDOT testing lab**, either in Freeport or Bangor. They should be kept in an on-site cure box for one day before being taken to the lab.

#### 11.7 Buy America

For decades, the Federal Highway Administration (FHWA) has required steel and iron products permanently incorporated into federally funded projects to be produced in the United States. Failing to comply with "Buy America" requirements jeopardizes federal funding.

Under Buy America, covered in 23 CFR part 635.410, the manufacturing processes for steel and iron products, including the application of coatings, must occur domestically. Raw materials, however, may be sourced from other countries.



Listed below are examples of steel and iron products covered under Buy America on FHWA-funded projects:

- Steel guardrail, steel piles, steel culverts, and structural and reinforcing steel;
- Structural plates and steel supports for highway signs, luminaries and signals;
- Cast iron frames and grates; and
- Applications, during fabrication, of coatings such as epoxy, galvanized (zinc) and paint.

#### ☐ 11.7.1 Build America, Buy America - NEW

In late 2022, a new federal law broadened the Buy American requirements. The Build America, Buy America Act (BABA) expanded the list of items that must be produced in the United States to cover more than steel and iron products.

As of November 10, 2022, construction materials permanently incorporated into projects funded by the FHWA must comply with Buy America requirements, which means that manufacturing must take place domestically.

Under the law, the new category of "construction materials" consists primarily of the following:

- Non-ferrous metals:
- Plastic and polymer-based products such as PVC, composite building materials, and polymers used in fiber-optic cables;
- Glass including optical glass;
- Lumber; and
- Drywall.

**Exclusions:** Excluded from the construction materials category are cement and cementitious materials, aggregates, and aggregate-binding agents and additives.

**Waiver:** Because of a national waiver, BABA does not cover manufactured products, defined as two or more of the materials listed above that are combined through fabrication. Such products also include items with at least one of the listed materials combined with a material not listed (including steel/iron) through a manufacturing process.

#### **□** 11.7.2: Buy America Certifications

The prime contractor must provide mill certifications for steel and iron products, along with manufacturer certifications for product coatings. The contractor also must certify that all products and construction materials subject to Buy America and BABA comply with the law.

The resident inspector must verify the submitted certifications before the contractor may install permanent products subject to Buy America and BABA.

#### **□** 11.7.3: Other Work on Federal Contracts

Buy America applies to all work that is part of a federally funded contract, including local work paid for with local funds. If, for example, local utility work is added to a federally funded contract, Buy America generally applies to that work – even if the work is performed without federal funds.

#### **□** 11.7.4: Exceptions

MaineDOT expects that applicable products used on federally funded projects will comply with Buy America. If a local agency, during design, believes that Buy America cannot be met – or if a contractor contends that certain items subject to Buy America cannot be acquired – the MaineDOT project manager should be contacted immediately to discuss the concerns.

**Dottom line:** Projects funded through the FHWA are expected to comply with Buy America.

#### **□** 11.7.5: Federal Transit Administration Projects

Buy America also applies to projects funded by the Federal Transit Administration (FTA), which has requirements for contracts and purchases greater than \$150,000.

FTA Buy America requirements generally cover the following:

- Iron and steel used in construction;
- Manufactured products used in construction; and
- Mass transit vehicles, commonly called rolling stock.

As with FHWA projects, the FTA requires a contractor certification. If an FTA project will have steel, iron or manufactured products covered by Buy America, each bidder must complete and submit an appropriate Buy America certification. Similarly, requests for waivers must be submitted to the FTA, through MaineDOT, for consideration.

Build America, Buy America (BABA) also applies to FTA projects. For grants obligated on or after November 10, 2022, the FTA will add construction materials to the categories of products on federally funded transit projects that must be manufactured in the United States. Additional information about FTA requirements under BABA is available at the link cited below.

Note: The FTA website provides general guidance: https://www.transit.dot.gov/buyamerica

#### 11.8 Project Bulletin Board

The prime contractor by law must display a set of posters on a bulletin board informing employees of their rights. The board must be installed by the first day of construction and stay in place until completion.

The bulletin board must be placed where it will be accessible to employees and the public all the time, commonly outside the field office used by the contractor or resident inspector. It must be sealed or otherwise protected from bad weather and remain readable for the duration of a project.



A standard poster packet is online: <a href="https://www.mainedot.gov/civilrights/sfp/">www.mainedot.gov/civilrights/sfp/</a>

#### 11.9 Commercially Useful Function

The resident inspector on a federal project must verify that a Disadvantaged Business Enterprise (DBE) firm hired as a subcontractor on the project is performing the services listed in its subcontract with its own equipment and workers. This is the "Commercially Useful Function" (CUF) of the DBE company.

The resident must verify that the employees on site are listed on the DBE company's payrolls and not on the payroll of a different company, such as the prime contractor. The resident must perform a CUF review when:

- A DBE firm initially shows up and during the peak period of the DBE's work; and
- A DBE firm on the job site is not listed on the prime contractor's DBE Utilization Form.

Commercially Useful Function Form is online: www.mainedot.gov/civilrights/dbe/

#### 11.10 Final Inspection

Upon finishing a project, the prime contractor sends the local agency administering the project written notification that the work is considered complete. At this point, the local administrator sets up a walk-through involving the resident inspector, contractor, and MaineDOT's project manager and construction manager. (*Use Letter 19, on page 11-20.*)

Meeting at the job site, the parties inspect the project for incomplete or unsatisfactory work. Afterward, they develop a "punch list" of items that must be addressed before the local agency will accept the project as complete.

Once a final inspection determines that the contractor has addressed all punch-list items, the local agency managing a project notifies the contractor in writing that physical work is complete and in compliance with the contract.

A sample Completion of Physical Work Notification is online under the category labeled "Construction Field Documents": <a href="https://www.mainedot.gov/lpa/lpadocuments/">www.mainedot.gov/lpa/lpadocuments/</a>

#### 11.11 Final Contractor Payment

After sending the prime contractor a Completion of Physical Work Notification, a local agency may make final payment to that contractor under the following conditions:

- ☐ There are no claims or disagreements with quantities;
- ☐ There are no liquidated damages against the contractor;
- ☐ There is no remaining work to be done in the field; and
- ☐ The contractor has submitted the final documents listed below, as applicable:
  - Request for final payment, with statement that all bills have been paid;
  - Agreement with final quantities;
  - Buy America certifications (federal projects);
  - Materials certifications (all projects); and
  - Quality-control certification under Standard Specification 106.4.3, "Testing."

#### 11.12 Closeout

Once a local agency has made the final payment to its contractor, the local project administrator should request from MaineDOT's project manager an accounting of MaineDOT's internal charges to a project, as described in Chapter 1 of this Manual, "Administration & Finance."

Upon receiving the documentation, the local administrator should calculate the matching share of those charges and send MaineDOT's project manager a final invoice formatted after <u>Letter 20</u>. (An example is found on page 11-21).

The local share of MaineDOT's charges will be deducted from the final reimbursement payment to the local agency managing a project. Upon making final payment, MaineDOT will terminate the local agency agreement signed at project kickoff and then close out the project.

#### 11.13 As-Built Plans

As-built plans are the original design plans that have been revised in the field to document a project as constructed. They are used as a reference for future design and maintenance efforts.



As-built plans for locally administered projects on state highways must be sent to MaineDOT's project manager as .pdf files with the <u>final invoice</u> submittal (Letter 20).

"As-builts" typically consist of a full-sized set of plans marked up either electronically or by hand using a red, medium felt-tip marker or a blue/black medium ballpoint pen. They may include alignment modifications, substitutions of materials, and additions or deletions of items.

On each revised sheet, the reviser should write in the lower right corner "Revised As-Built" and initial; on unchanged plan sheets, the reviser should write "As-Built" and initial. Upon completion of all changes, the reviser should sign and date the title sheet of the marked-up plans.

## **Appendix 11A:**Administrative Checklist

(Construction Administration)

(Updated in 2023)



#### **CHECKLIST: CONSTRUCTION ADMINISTRATION**

	Obtain Minimum Testing Requirements from MaineDOT's project manager (PM).
	Send award information to MaineDOT to enter project in the Elation payroll system.
	☐ MaineDOT contact is Angela Latno: (207) 624-3519 or Angela.Latno@maine.gov
	☐ Prime contractor and all subcontractors must be set in in the Elation system.
Pr	e-Construction Tasks
П	Send notice of pre-construction meeting and agenda ( <u>Letter 17</u> ) to the following:
_	☐ Contractor;
	☐ Utilities;
	□ Resident Inspector;
	☐ MaineDOT's PM and construction manager.
	Note: A separate pre-pave meeting must be held before any paving work may take place.
	Pre-construction meeting held on:
	☐ Pre-pave meeting held on:
	Contractor schedule received on:
	Quality Control (QC) Plan and Mix Designs received from Contractor on:
	☐ Contractor must submit them at least 30 days before the work is scheduled to begin.
	Contractor Traffic Control Plan submitted to MaineDOT for review.
	□ MaineDOT Approval Date:
	Contractor Soil Erosion Water Pollution Control Plan approved by resident inspector.
Те	sting & Documentation
	Field Book created to record the following information:
	☐ Weather, crew & equipment, hours worked, and contractor activities;
	☐ Field measurements to document materials quantities for payment to the contractor;
	□ Noteworthy events (accidents, discussions with owners, disputes with contractor).
	Pit authorizations completed.
	Waste area agreements completed.
	Project bulletin board erected: <a href="https://www.mainedot.gov/civilrights/sfp/">https://www.mainedot.gov/civilrights/sfp/</a>
	☐ Condition of signs must be noted weekly in a project field book.
	Testing file set up for each item in Minimum Testing Requirements.
	• Check with MaineDOT to learn if Hot Mix Asphalt / Portland Cement Concrete plant has been
	inspected recently or needs to be inspected: <u>Kevin.cummings@maine.gov</u>
	Materials Tests:
	A garagetes must be tested at an independent, appredited laboratory
	Aggregates must be tested at an independent, accredited laboratory.
	Hot-mix asphalt and concrete are tested at one of MaineDOT's labs, in Bangor or Freeport.
	☐ Hot-mix asphalt and concrete are tested at one of MaineDOT's labs, in Bangor or Freeport.  Subcontractor Approvals: <a href="https://www.mainedot.gov/contractors/publications/">https://www.mainedot.gov/contractors/publications/</a>
	☐ <u>Hot-mix asphalt and concrete</u> are tested at one of MaineDOT's labs, in Bangor or Freeport.

	Federal projects: Weekly certified payrolls received electronically from <u>all</u> contractors.  □ Certified payroll checked in Elation system for compliance with Davis-Bacon wage rates.
	<ul> <li>Federal projects: Employees interviewed to verify Davis-Bacon wage rate compliance.</li> <li>□ Voluntary interviews held every 90 days with 2 covered workers from the following:</li> <li>■ Prime contractor;</li> <li>■ All subcontractors on site 5 or more days during a 90-day period.</li> </ul>
	Federal Projects: Commercially Useful Function Form sent to MaineDOT, if applicable.
	<ul> <li>Federal Projects: "Build America, Buy America" (Special Provision 105).</li> <li>□ Buy America certifications must be received before steel iron products – as well as construction materials covered by new Build America, Buy America requirements – are installed.</li> </ul>
	Progress payments to contractor:
	<ul> <li>□ Prepare estimate and review with contractor, or receive and check estimate from contractor.</li> <li>□ Once approved, process estimate and send payment to contractor.</li> </ul>
	Final Quantity Book created:
	☐ Book set up by item numbers;
	☐ Pages set up for original measurements (or computations from plan dimensions);
	Pages set up with a total-to-date column;
	Entries and computations initialed and dated;
	☐ After item is completed, compute final quantity.
Co	ntract Modifications
	<ul> <li>Modifications to the construction contract are handled as follows:</li> <li>□ Prepare an independent cost estimate for the additional work.</li> <li>□ Note the time associated with the change. (If no change, note 0 additional days.)</li> <li>□ Send draft modification to MaineDOT construction manager for review (<u>Letter 18</u>).</li> </ul>
	<ul> <li>□ Prepare an independent cost estimate for the additional work.</li> <li>□ Note the time associated with the change. (If no change, note 0 additional days.)</li> </ul>
	<ul> <li>□ Prepare an independent cost estimate for the additional work.</li> <li>□ Note the time associated with the change. (If no change, note 0 additional days.)</li> <li>□ Send draft modification to MaineDOT construction manager for review (<u>Letter 18</u>).</li> </ul>
<u> </u>	<ul> <li>□ Prepare an independent cost estimate for the additional work.</li> <li>□ Note the time associated with the change. (If no change, note 0 additional days.)</li> <li>□ Send draft modification to MaineDOT construction manager for review (<u>Letter 18</u>).</li> <li>Obtain MaineDOT's written concurrence with contract modification, by email.</li> </ul>
<u> </u>	<ul> <li>□ Prepare an independent cost estimate for the additional work.</li> <li>□ Note the time associated with the change. (If no change, note 0 additional days.)</li> <li>□ Send draft modification to MaineDOT construction manager for review (<u>Letter 18</u>).</li> <li>Obtain MaineDOT's written concurrence with contract modification, by email.</li> <li>Send modification to contractor for signature.</li> <li>□ When contractor has signed, local project administrator signs and dates the modification.</li> </ul>
<u> </u>	<ul> <li>□ Prepare an independent cost estimate for the additional work.</li> <li>□ Note the time associated with the change. (If no change, note 0 additional days.)</li> <li>□ Send draft modification to MaineDOT construction manager for review (<u>Letter 18</u>).</li> <li>Obtain MaineDOT's written concurrence with contract modification, by email.</li> <li>Send modification to contractor for signature.</li> <li>□ When contractor has signed, local project administrator signs and dates the modification.</li> <li>□ Send copy of the executed modification to the contractor, with a copy to MaineDOT.</li> </ul>
<u> </u>	<ul> <li>□ Prepare an independent cost estimate for the additional work.</li> <li>□ Note the time associated with the change. (If no change, note 0 additional days.)</li> <li>□ Send draft modification to MaineDOT construction manager for review (Letter 18).</li> <li>Obtain MaineDOT's written concurrence with contract modification, by email.</li> <li>Send modification to contractor for signature.</li> <li>□ When contractor has signed, local project administrator signs and dates the modification.</li> <li>□ Send copy of the executed modification to the contractor, with a copy to MaineDOT.</li> <li>mpletion</li> <li>Final inspection performed by Municipality, MaineDOT and contractor (Letter 19).</li> <li>□ Inspection Date:</li></ul>
Co	<ul> <li>□ Prepare an independent cost estimate for the additional work.</li> <li>□ Note the time associated with the change. (If no change, note 0 additional days.)</li> <li>□ Send draft modification to MaineDOT construction manager for review (Letter 18).</li> <li>Obtain MaineDOT's written concurrence with contract modification, by email.</li> <li>Send modification to contractor for signature.</li> <li>□ When contractor has signed, local project administrator signs and dates the modification.</li> <li>□ Send copy of the executed modification to the contractor, with a copy to MaineDOT.</li> <li>mpletion</li> <li>Final inspection performed by Municipality, MaineDOT and contractor (Letter 19).</li> <li>□ Inspection Date:</li></ul>
Co	<ul> <li>□ Prepare an independent cost estimate for the additional work.</li> <li>□ Note the time associated with the change. (If no change, note 0 additional days.)</li> <li>□ Send draft modification to MaineDOT construction manager for review (Letter 18).</li> <li>Obtain MaineDOT's written concurrence with contract modification, by email.</li> <li>Send modification to contractor for signature.</li> <li>□ When contractor has signed, local project administrator signs and dates the modification.</li> <li>□ Send copy of the executed modification to the contractor, with a copy to MaineDOT.</li> <li>mpletion</li> <li>Final inspection performed by Municipality, MaineDOT and contractor (Letter 19).</li> <li>□ Inspection Date:</li> <li>□ Final "punch list" of items completed on:</li> <li>Final Quantity Book finalized by resident inspector.</li> </ul>
Co	<ul> <li>□ Prepare an independent cost estimate for the additional work.</li> <li>□ Note the time associated with the change. (If no change, note 0 additional days.)</li> <li>□ Send draft modification to MaineDOT construction manager for review (Letter 18).</li> <li>Obtain MaineDOT's written concurrence with contract modification, by email.</li> <li>Send modification to contractor for signature.</li> <li>□ When contractor has signed, local project administrator signs and dates the modification.</li> <li>□ Send copy of the executed modification to the contractor, with a copy to MaineDOT.</li> <li>mpletion</li> <li>Final inspection performed by Municipality, MaineDOT and contractor (Letter 19).</li> <li>□ Inspection Date:</li> <li>□ Final "punch list" of items completed on:</li> <li>Final Quantity Book finalized by resident inspector.</li> <li>Completion of Physical Work Notification sent to contractor, signed by each DBE.</li> </ul>
Co.	<ul> <li>□ Prepare an independent cost estimate for the additional work.</li> <li>□ Note the time associated with the change. (If no change, note 0 additional days.)</li> <li>□ Send draft modification to MaineDOT construction manager for review (Letter 18).</li> <li>Obtain MaineDOT's written concurrence with contract modification, by email.</li> <li>Send modification to contractor for signature.</li> <li>□ When contractor has signed, local project administrator signs and dates the modification.</li> <li>□ Send copy of the executed modification to the contractor, with a copy to MaineDOT.</li> <li>mpletion</li> <li>Final inspection performed by Municipality, MaineDOT and contractor (Letter 19).</li> <li>□ Inspection Date:</li></ul>

## **Appendix 11B:**Submittals to MaineDOT

☐ To obtain electronic documents, go to the section labeled "Letters to MaineDOT" on the LPA Documents web page: <a href="https://www.maine.gov/mdot/lpa/lpadocuments/">https://www.maine.gov/mdot/lpa/lpadocuments/</a>

### AGENDA ITEMS FOR PRE-CONSTRUCTION MEETING (Federally Funded Project)

- 1. Introductions
- 2. Review Scope of Project
  - a. Acknowledge Amendments
  - b. Completion Date
  - c. Liquidated Damages
- 3. Permits Obtained (if required)
- 4. Construction Safety
  - a. Primary consideration during construction
  - b. Emergency contact list including 24 hour contacts
  - c. Contractor safety plan to be provided
  - d. Traffic Control Plan (TCP) must be reviewed and approved by Maine DOT
- 5. Schedule for the completion of work to be provided
  - a. Are there utility issues?
  - b. Update schedule as required
  - c. Daily construction activities to be recorded
  - d. Town must pay contractor first, then request reimbursement on a monthly basis
- 6. Labor Requirements
  - a. Davis-Bacon wage rates apply if project has federal money
  - b. Certified payrolls with classifications to be submitted & reviewed: Elations
  - c. Payroll labor interviews
  - d. DBE participation & CUF form
- 7. Construction Control
  - a. Minimum Testing Requirements
  - b. Subcontract Approval (FHWA-1273 must be inserted in all subcontracts)
  - c. Measurement & documentation of materials used for payment purposes
  - d. Engineering oversight of activities
  - e. Manufacturer's certification for materials
  - f. Soil Erosion and Water Pollution Plan (SEWPCP)
  - g. Quality control plans, mix design submittals, pre-pave meeting
  - h. Buy America: steel/iron product certifications must be received before payment for that item, if a project has federal money
- 8. Submittals
  - a. Requests for Information (RFIs)
  - b. Change Orders require MaineDOT review; must include detailed description of scope change, independent cost estimate & time
  - c. Notification of anticipated issues, claims or disputes

, Construction Manager Maine Department of Transportation Bureau of Project Development, Multimodal Program 16 State House Station Augusta, ME 04333-0016
Bureau of Project Development, Multimodal Program 16 State House Station
16 State House Station
16 State House Station
Augusta, ME 04333-0016
11084014, 1112 0 1000 0010
Subject: Contract Modification Request  MaineDOT WIN
Dear:
Attached for your review is Contract Modification # for [insert project scope] in the Municipality of The change will consist of [insert description of contract modification including scope change and/or extra costs].
An independent estimate of the cost of the additional work is attached. This modification will add [number of days] to the original contract.
(Instructions: The amount of time required by the modification must be noted. If there is no change in the schedule, then state "0 days" or indicate that the modification will not change the amount of time associated with the contract.)
If you need additional information, please let me know.
Sincerely,
Local Project Administrator
Cc: MaineDOT Project Manager

PROJECT DESCRIPTION:			
CONTRACT MOD. NO.:			
PROJECT WIN:			
MUNICIPALITY:			
DATE ISSUED:			
To:, you are hereby accordance with the provisions of your Contrwithout the required signatures. Payment will	act. The work will		
(By signing this Order, the Contractor agrees that all resolved by this Order. No other compensation will be		relating to the described	l work are satisfactorily
DESCRIPTION:			
REASON:			
COST:			
Amount of this Order: \$			
Original Contract Amount		\$	
Total Cost of this Contract Modification		\$	
Total Cost of all Contract Modifications Inc	luding this Mod	\$	
Percentage of Contract for this Mod		%	
Total Percentage of Contract including all M	Iods	%	
Total Contract Amount Including this Mod		\$	
Additional Days Added (This Mod):	New	Completion Date:	
TITLE:	SIGNATURE:		DATE:
Resident or Inspector			
Contractor			
Municipality			

[Date]
Subject: Final Inspection, MaineDOT WIN
Dear:
Your attendance is requested at the Final Inspection for [insert project scope] in the Municipality of on [insert date/time]. At the time, we can make available all documentation and testing required for the project.
If you need additional information, please let me know.
Sincerely,
Local Project Administrator

Cc: MaineDOT Project Manager

*INSTRUCTIONS:* This must be submitted on letterhead with all requested documentation. [Date] \_\_\_\_\_, Project Manager Maine Department of Transportation Bureau of Project Development, Multimodal Program 16 State House Station Augusta, ME 04333-0016 **Subject: Final Invoice and Notification of Completion of Work** MaineDOT WIN \_\_\_\_\_; Contract # \_\_\_\_ This Municipality of \_\_\_\_\_ certifies that the contractor has completed all work on the project in accordance with the construction contract and approved modifications, and that: • The Municipality has accepted the work; • The Municipality has measured and reconciled final quantities with the contractor, with all supporting documentation of such; • The Municipality has paid all contracted parties in full; and • There are no outstanding claims or disputes associated with the project. Accordingly, the Municipality submits this final invoice with supporting documentation requesting reimbursement of \$\_\_\_\_\_ as MaineDOT's \_\_\_\_\_% share of expenditures for the invoice period, \_\_\_\_\_\_. I understand that the Municipality's \_\_\_\_\_% share of MaineDOT's charges to the project will be reconciled and deducted from this final invoice. The following also are attached: 1.) Consultant Evaluation; 2.) Contractor Evaluation; and 3.) As-Built Plans for the project. By signing this invoice, I certify to the best of my knowledge and belief that the information provided is true, complete, and accurate, and the expenditures, disbursements, and cash receipts are for the purposes and objectives set forth in the terms and conditions of the federal funding award. I am aware that any false, fictitious, or fraudulent information, or the omission of any material fact, may subject me to criminal, civil or administrative penalties for fraud, false statements, false claims or otherwise (U.S. Code Title 18, Section 1001 and Title 31, Sections 3729-3730 and 3801-3812.) Sincerely, \_\_\_\_\_, Local Project Administrator Enclosures: Final billing, Consultant Evaluation, Contractor Evaluation, and As-Built Plans

# **Appendix 11C: Sample Field Book Entries**



WEATHER										& LIABLE CONTRISUB		DISPOSITION OF ANY EXCAVATION	OF AD VEL AND ROBDOW		NON ADHERANCE TO	SPEC'S: MTCD'S & SEWPC	MOOT OFFECTIVES GIVEN TO CONTRACTOR	IONS, CHANGES IN	S & REWOR		HAREOFILY STATTING		TED TO POTENTIAL	AIMS	S WITH TOWN DEETCH! S	RS	NTS & OTHER HAZARDS	
_	PERSONEL		PERSONEL	EQUIPMENT	28		EQUIPMENT	2)	CTIVITIES	ITEM NUMBER, LOCATION & LIMBLE CONTRISUB	_[	<b>Ş</b> ₹	OF AND DISPOSITION OF	NON-ROUTINE ACTIVITIES	A: CONTRACTORS' NON	CONTRACT SPEC'	A. MOOT DESECTIVE		DESIGN, UNDERC	-	THE JOB FOR THE TYPE OF WOR	_	D: ANYTHING RELATED	CONTRACTOR CLAIMS	E. ANY DISCUISIONS MI	UTILITIES	G: TRAFFIC ACCIDENTS	LH7 4 9 L777
DATE DAY	MDOT: PERS	CONTENTO	, -	EQUI	SUB CONTRACTOR	PERS	TO STATE OF THE ST	VISITORS	PROJECT ACTIVI		_	SOURCE		NON						]								

2002	6/12/2002 FRIDAY			SUNNY 80 S	S
MDOT:	811L 81TTE 81LY 808	BITTERMAN, RES 1808 BENNET, I	RESIDENT 7, INSPECTOR		
	6:00AM TO	5:00 PM			
	1 SUPT		1 COMPRESSOR	SOR	
	5 WORKERS	3	2 TRUCKS		
	2 LARGE EKC	(C.	1 5 TON N	5 TON VIB ROLLER	
	1 APE		1 CHAMPIC	CHAMPION GRADER	
	1 D6 DOZER	8			
HASTINGS	TREE REMOVAL	VAL SERVICES	CES		
5 65	ITEMS 652,361 AND 656,75	556.75			
MTCD AND	SEWPC INSPECTED	۵	AND ACCEPTED	D FOR THE	WEEK
ITEM 201	23 SINGLE TREE	TREE			
	HASTINGS	AND	REMOVED S	SINGLE TREE	AT THE
	THE CORN	THE CORNER OF PINE	STREET AND RT	JD RT 4	
603.	159	12" OPT II	12" OPT III CULV PIPE	11.	
	INSTALLED	12" OPT I	CULV PIPE	AT STA 12	12+56 RT
604.097	260	6' B1-C CA	6' BI-C CATCH BASIN		
	INSIALLED	¥	SIA 12+56 RI		
ITEM 631.		STUMP CHIPPER	PPER		
	1ASTINGS	USED STU	USED STUMP CHIPPER	TO GRIND	2 STUMPS
ИПСС	M&H MULCHED ALL DISTURBED AREAS	STURBED A	REAS		
LAIN	COMPLAINT FROM BILL SIMPSON	NOSAWIS 7	_\_`	PROJ SUPT ABOUT	DELAYS
IT/	FROM UTILITIES NOT	SHOWN O	SHOWN ON PLANS AS WELL AS	S WELL AS	MOTS
PRODUCTION.	DN. HE THE	Y WILL KE	HE THEY WILL KEEP RECORDS FOR POSSIBLE	FOR POSS	BLE
1. HE	CLAIM. HE HAS ALSO	REQUESTED	D INFORM	INFORMATION ON	
ALTERNAT	E WORK AT	тне отне	THE OTHER END OF THE PROJEC	HE PROJEC	
3	2				
CAITEDEN	. 0717		12 02		
	BY : B111 B1	BAII TEKMAN	20-21-0		

BITTERMAN, V BOB BENNET V BOB BENNET N BOB BENNET N 3+00 TO 4 N THE SUBGRA THE N PLAC THE NO THE W SO AM +/ V SO AM +/			FAIR 60'S	
6:00AM TO 5:00 PM 1 SUPILIER 1 SUPILIER 1 SUPICKS 2 TRUCKS 2 LARGE EXC. 1 5 TON VIB ROLLER 1 APE 1 APE 1 O.STA 3+00 TO 4+25 1 CHAMPION GRADER 1 AFTER PLACING-COMPACTING LOWER LAYER RAVEL, THE SUBGRADE MATERIAL BEGAN TC INTO THE LOWER ASC GRAVEL LIFT. THE RESIDENT THE CONTRACTOR TO EXCAUATE AND REMOVE THE WAS THEN PLACED ON THE SUB-GRADE SURFACE IE WAS THEN PLACED ON THE SUB-GRADE SURFACE IE WAS THEN PLACED ON THE SUB-GRADE SURFACE THE WAS THEN PROLECT TO NOTE SUB-GRADE THE CONTRACTOR TO EXCAUATE WILL BE PAID THE CONTRACTOR TO EXCAUATE ON THE RESIDENT THE WAS THEN PROLECT TODAY AT THIS WAS THEN ON THE PROJECT TODAY AT TO COO AM +/ VEHICLE NO 1 FORD EXPLORER THES BY TOLL BAMINGTON THE DAY TOLL AMONG ZONE. THE FARMINGTON THE DAY TOLL AMONG ZONE. THE FARMINGTON THE POLICE ACCIDENT REPORT TO ACCIDENT REPORT AND FORWARDED TO THE MDOT TOTAL  SYSTELL BITTERMAN 06-16-02	BILL BITTERMAN, BILLY BOB BENNE	I, RESIDENT ET, INSPECTOR		
6:00AM TO 5:00 PM  1 SUPT  1 SUPT  2 LARGE EXC.  1 S TON VIB ROLLER  1 APE  1 CHAMPTON GRADER  1 APE  1 CHAMPTON GRADER  1 O STA 3+00 TO 4+25  AFTER PLACING/COMPACTING LOWER LAYER  RAVEL, THE SUBGRADE MATERIAL BEGAN TO  INTO THE LOWER ASC GRAVEL LIFT. THE RESIDENT  ITH CONTRACTOR TO EXCAVATE AND REMOVE  THE CONTRACTOR TO EXCAVATE AND REMOVE  THE CONTRACTOR TO EXCAVATE AND REMOVE  LACING ASC GRAVEL. THIS WORK WILL BE PAID  THE CONTRACTOR TO EXCAVEL THIS WORK WILL BE PAID  THE MAS THEN PLACED ON THE SUB-GRAVEL.  COK 4 PAGES 5 THROUGHT FOR FIELD MEASUREMENTS  V STABILIZATION GEOTEXTILE WILL BE PAID  DENTS WORK ORDER #1 (AMOCO 2006 INSTALLED)  AS AN ACCIDENT ON THE PROJECT TODAY AT  AT 10:00 AM +/ VEHICLE NO 1 (FORD EXPLORER  ASTA 10:00 AM +/ VEHICLE NO 1 (FORD EXPLORER  ASTA 10:00 AM +/ VEHICLE NO 1 (FORD EXPLORER  ASTA 10:00 AM +/ VEHICLE NO 1 (FORD EXPLORER  ASTA 1 WHICH WAS STOPPED FOR FLAGER  A COPY OF THE POLICE/ACCIDENT REPORT  EVER WITHIN THE POLICE/ACCIDENT REPORT  A COPY OF THE POLICE/ACCIDENT REPORT  BY: BILL BITTERMAN 06-16-02				
1 SUPT  1 COMPRESSOR  5 WORKERS  2 TRUCKS  1 APE  1 CHAMPION GRADER  1 APE  1 CHAMPION GRADER  1 O. STA 3+D0 TO 4+25  AFTER PLACING/COMPACTING LOWER LAYER  GRAVEL, THE SUBGRADE MATERIAL BEGAN TO  INTO THE LOWER ASC GRAVEL LIFT. THE RESIDENT  THE WAS THEN PLACED ON THE SUB-GRADE SURFACE  TAMINATED GRAVEL. ROADWAY STABILIZATION  THE CONTRACTOR TO EXCAVATE AND REMOVE  THAN SO 3-20 COMMON EXC AND 304 10 ASC-GRAVEL.  COX 4 PAGES 5 THROUGH 7 FOR FIELD MEASIREMENTS  STABILIZATION GEOTEXTILE WILL BE PAID  BENTS WORK ORDER #1 (AMOCO 2006 INSTALLED)  AS AN ACCIDENT ON THE PROJECT TODAY AT  TO:00 AM +/ VEHICLE NO 1 FORD EXPLORER  A TO:00 AM +/ VEHICLE NO 2 CHEVY S-10  763784 J. WHICH WAS STOPPED FOR FLAGGER  A COPY OF THE POLICE/ACCIDENT WAS  GRITED BY JOEL RAMINGTON  WERE SATISFACTORY. REFER TO CORRESPONDENCE  A CODY OF THE POLICE/ACCIDENT REPORT  ED ACCIDENT REPORT AND FORWARDED TO THE MDOT  PT.  8Y : BILL BITTERMAN 06-16-02	6:00AM TO 5:00	Н		
5 WORKERS  2 LARGE EKC.  1 5 TON VIB ROLLER  1 4PE  1 CHAMPTON GRADER  1 APE  1 CHAMPTON GRADER  1 CHER LATING/COMPACTING LOWER LAYER  1 CHAMINATED GRAVEL LIFT. THE RESIDENT  1 THE CONTRACTOR TO EXCAVATE AND REMOVE  1 CHAMINATED GRAVEL. THIS WORK WILL BE PAID  1 CHAMINATED GRAVEL. THIS WORK WILL BE PAID  1 CON A PAGES 5 THROUGH T FOR FIELD MEASUREMENTS  1 CON A PAGES 5 THROUGH T FOR FIELD MEASUREMENTS  1 STABILIZATION GEOTEXTILE WILL BE PAID  1 STABILIZATION GEOTEXTILE WILL BE ALCODAY AT  1 STABILIZATION GEOTEXTILE WILL BE ALCODAY  2 STABILIZATION GEOTEXTILE WILL BE ACCIDENT WAS  2 STABILIZATION THE WORK ZONE. THE ACCIDENT WAS  2 STATED BY JOEL RAMICH OF THE FARMINGTON  2 STABIL BITTERMANN DO-16-02  2 STACLDENT REPORT AND FORWARDED TO THE MDOT  2 PT.  3 STACLDENT REPORT AND FORWARDED TO THE MDOT  3 STACLDENT REPORT AND FORWARDED TO THE MDOT  3 STACLDENT REPORT AND FORWARDED TO THE MDOT  4 COPY OF THE POLICE/ACCIDENT REPORT	1 SUPT		SSOR	
1 J TON VIB ROLLER  1 APE  1 APE  1 CHAMPTON GRADER  1 CHAMPTON GRADER  1 CHAMPTON GRADER  1 C. STA 3+00 TO 4+25  1 AFTER PLACTING/COMPACTING LOWER LAYER  1 AFTER PLACING/COMPACTING LOWER LAYER  1 AFTER PLACING/COMPACTING LOWER LAYER  1 AND THE CONTRACTOR TO EXCAVATE AND REMOVE  1 AMINATED GRAVEL. ROADWAY STABILIZATION  1 THE CONTRACTOR TO EXCAVATE AND REMOVE  1 AMINATED GRAVEL. ROADWAY STABILIZATION  1 THE WAS THEN PLACED ON THE SUB-GRADE SURFACE  1 ACTING ASC GRAVEL. THIS WORK WILL BE PAID  1 THE WAS THEN PLACED ON THE SUB-GRADE SURFACE  1 ACTING ASC GRAVEL. THIS WORK WILL BE PAID  1 THEN 203.20 COMMON EXC AND 304 10 ASC-GRAVEL.  1 COX 4 PAGES 5 THROUGHT FOR FILLED MEASGREMENTS  1 STABILIZATION GEOTEXTILE WILL BE PAID  1 DENTS WORK ORDER #1 (AMOCO 2006 INSTALLED)  2 AT 10:00 AM +/ VEHICLE NO 1 (FORD EXPLORER  2 AT 10:00 AM +/ VEHICLE NO 2 (CHEVY S-1C  2 ASTRA I) WHICH WAS STOPPED FOR FLAGGER  1 ALL SIGNS WERE UP AND TRAFFIC CONTROL  2 ACCIDENT REPORT AND FORWARDED TO THE MDOT  3 ACCOY OF THE POLICEACCIDENT REPORT  4 ACOY OF THE POLICEACCIDENT REPORT  4 ACOY OF THE POLICEACCIDENT REPORT  5 AT 10:00 AM +/ STOPPED FOR EXPERSIONDENCE  4 ACOY OF THE POLICEACCIDENT REPORT  5 AT 11 BITTERMAN 06-16-02	5 WORKERS	2 TRUCKS		
1 APE  1 CHAMPTON GRADER  1 CHAMPTON GRADER  1 CHAMPTON GRADER  1 10. STA 3+00 TO 4+25  1 ATTER PLACTNG/COMPACTING LGWER LAYER  1 ATTER PLACTNG/COMPACTING LGWER LAYER  1 ATTER PLACTNG/COMPACTING LGWER LAYER  1 AMINATED GRAVEL LIFT. THE RESIDENT  1 THE CONTRACTOR TO EXCAVATE AND REMOYE  1 AMINATED GRAVEL. ROADWAY STABILIZATION  1 LE WAS THEN PLACED ON THE SUB-GRADE SURFACE  1 ACTNG ASC GRAVEL. THIS WORK WILL BE PAID  1 TEM 203.20 COMMON EYC AND 304 10 ASC-GRAVEL.  1 COX 4 PAGES 5 THROUGH T FOR FIELD MEASUREMENTS  1 STABILIZATION GEOTEXTILE WILL BE PAID  1 DENTS WORK ORDER #1 (AMOCO 2006 INSTALLED)  2 SAT 10:00 AM +/ VEHICLE NO 1 FORD EXPLORER  2 AT 10:00 AM +/ VEHICLE NO 1 FORD EXPLORER  2 AT 10:00 AM +/ VEHICLE NO 1 FORD EXPLORER  2 AT 10:00 AM +/ VEHICLE NO 1 FORD EXPLORER  3 AT 10:00 AM +/ VEHICLE NO 1 FORD EXPLORER  4 SAN ACCIDENT ON THE WORK ZONE THE ACCIDENT WAS SATED BY JOEL RAMINGTON  4 SATED BY JOEL RAMICH OF THE FARMINGTON  4 COPY OF THE POLICE/ACCIDENT REPORT  5 AT 18 ACCIDENT REPORT AND FORWARDED TO THE MDOT  5 AT 18 ACCIDENT REPORT AND FORWARDED TO THE MDOT  5 AT 18 ACCIDENT REPORT AND FORWARDED TO THE MDOT  5 AT 18 ACCIDENT REPORT AND FORWARDED TO THE MDOT  5 AT 18 ACCIDENT REPORT AND FORWARDED TO THE MDOT  5 AT 18 ACCIDENT REPORT AND FORWARDED TO THE MDOT  5 AT 18 ACCIDENT REPORT AND FORWARDED TO THE MDOT  5 AT 18 ACCIDENT REPORT AND FORWARDED TO THE MDOT  5 ACCIDENT REPORT AND THE MODEL AND THE MOD THE	2 LARGE EXC.		IB ROLLER	
ATTER PLACING/COMPACTING LOWER LAYER  AFTER PLACING/COMPACTING LOWER LAYER  BAVEL, THE SUBGRADE MATERIAL BEGAN TC  THE CONTRACTOR TO EXCAVATE AND REMOVE  THE CONTRACTOR TO EXCAVATE AND REMOVE  THE CONTRACTOR TO EXCAVATE AND REMOVE  THE WAS THEN PLACED ON THE SUB-GRADE SURFACE  LACING ASC GRAVEL. THIS WORK WILL BE PAID  TEM 203.20 COMMON EYC AND 304 10 ASC-GRAVEL.  COCK 4 PAGES 5 THROUGH 7 FOR FIELD MEASUREMENTS  Y STABILIZATION GEOTEXTILE WILL BE PAID  DENTS WORK ORDER #1 (AMOCO 2006 INSTALLED)  DENTS WORK ORDER #2 (AMOCO 2006 INSTALLED)  AS AN ACCIDENT ON THE PROJECT TODAY AT  AT 10:00 AM +/ VEHICLE NO 2 (CHEVY S-10  743784 JJ NEAR-ENDED VEHICLE NO 2 (CHEVY S-10  743784 JJ NHICH WAS STOPPED FOR FLAGGRA  AES WITHIN THE WORK ZONE THE FARMINGTON  WERE SATISFACTORY. REFER TO CORRESPONDENCE  A COPY OF THE POLICE/ACCIDENT REPORT  BY: BILL BITTERMAN 06-16-02	1 APE	1 CHAMPIC	NO GRADER	
AFTER PLACING/COMPACTING LCWER LAYER RAVEL, THE SUBGRADE MATERIAL BEGAN TO THE CONTRACTOR TO EXCAVATE AND REMOVE THAMINATED GRAVEL LIFT. THE RESIDENT THE WAS THEN PLACED ON THE SUB-GRADE SURFACE UACING ASC GRAVEL. THIS WORK WILL BE PAID THE WAS THEN PLACED ON THE SUB-GRADE SURFACE UACING ASC GRAVEL. THIS WORK WILL BE PAID THE WAS THEN PLACED ON THE SUB-GRADE SURFACE UACING ASC GRAVEL. THIS WORK WILL BE PAID THE WAS THEN PLACED ON THE PROJECT TODAY AT STABILIZATION GEOTEXTILE WILL BE PAID DENTS WORK ORDER #1 (AMOCO 2006 INSTALLED) THE AN ACCIDENT ON THE PROJECT TODAY AT TO COMMON EXCURENT OF THE FARMINGTON THE WORK ZONE. THE FARMINGTON THE SIGNS WERE UP AND TRAFFIC CONTROL WERE SATISFACTORY. REFER TO CORRESPONDENCE TO ACCIDENT REPORT AND FORWARDED TO THE MDOT THE SIGNS WERE UP AND FORWARDED TO THE MDOT THE SIGNS WERE UP AND FORWARDED TO THE MDOT THE SIGNS WERE UP AND FORWARDED TO THE MDOT THE SIGNS WERE UP AND FORWARDED TO THE MDOT THE SIGNS WERE UP AND FORWARDED TO THE MDOT THE SIGNS WERE UP AND FORWARDED TO THE MDOT THE SIGNS WERE UP AND FORWARDED TO THE MDOT THE SIGNS WERE UP AND FORWARDED TO THE MDOT THE SIGNS WERE UP AND FORWARDED TO THE MDOT THE SIGNS WERE UP AND FORWARDED TO THE MDOT THE SIGNS WERE UP AND FORWARDED TO THE MDOT THE SIGNS WERE UP AND FORWARDED TO THE MDOT THE SIGNS WERE UP AND FORWARDED TO THE MDOT THE SIGNS WERE UP AND FORWARDED TO THE MDOT THE SIGNS WERE UP AND FORWARDED TO THE MDOT THE SIGNS WERE UP AND FORWARDED TO THE MDOT THE SIGNS WERE UP AND FORWARDED TO THE MDOT THE SIGNS WERE UP AND TRAFFILL SIGNS WERE U	OT 00+8: ATS: 01 P	4+25		
RAVEL, THE SUBGRADE MATERIAL BEGAN TO  INTO THE LOWER ASC GRAVEL LIFT. THE RESIDENT  D THE CONTRACTOR TO EXCAVATE AND REMOVE  ITH WAS THEN PLACED ON THE SUB-GRADE SURFACE  UACING ASC GRAVEL. ROADWAY STABILIZATION  ILE WAS THEN PLACED ON THE SUB-GRADE SURFACE  UACING ASC GRAVEL. THIS WORK WILL BE PAID  TEM 203.20 COMMON EXC AND 304 10 ASC-GRAVEL.  NOOK 4 PAGES 5 THROUGH 7 FOR FIELD MEASUREMENTS  Y STABILIZATION GEOTEXTILE WILL BE PAID  DENTS WORK ORDER #1 (AMOCO 2006 INSTALLED)  AS AN ACCIDENT ON THE PROJECT TODAY AT  5 AT 10:00 AM + VEHICLE NO 1 (FORD EXPLORER  O 763784 I) WHICH WAS STOPPED FOR FLAGERR  WEES WITHIN THE WORK ZONE. THE ACCIDENT WAS  GATED BY JOEL RAMICH OF THE FRAINNGTON  WERE SATISFACTORY. REFER TO CORRESPONDENCE  O ACCIDENT REPORT AND FORWARDED TO THE MDOT  PT.  ED ACCIDENT REPORT AND FORWARDED TO THE MDOT  PT.  ED ACCIDENT REPORT AND FORWARDED TO THE MDOT  PT.	AFTER PLACING/	COMPACTING LC	WER LAYER	
1 INTO THE LOWER ASC GRAVEL LIFT. THE RESIDENT DITHE CONTRACTOR TO EXCAVATE AND REMOVE ITAMINATED GRAVEL. ROADWAY STABILIZATION ILE WAS THEN PLACED ON THE SUB-GRADE SURFACE UACING ASC GRAVEL. THIS WORK WILL BE PAID ITEM 203.20 COMMON EXC AND 304 10 ASC-GRAVEL. ROOK 4 PAGES 5 THROUGH 7 FOR FIELD MEASUREMENTS Y STABILIZATION GEOTEXTILE WILL BE PAID DENTS WORK ORDER #1 (AMOCO 2006 INSTALLED) DENTS WORK ORDER #1 (AMOCO 2006 INSTALLED) AS AN ACCIDENT ON THE PROJECT TODAY AT 5 AT 10:00 AM +/ VEHICLE NO 1 FORD EXPLORER O 4356 JJ) REAR-ENDED VEHICLE NO 2 (CHEVY S-1C O 743784 I) WHICH WAS STOPPED FOR FLAGGER WHES WITHIN THE WORK ZONE. THE ACCIDENT WAS GATED BY JOEL RAMICH OF THE FRAINGTON WERE SATISFACTORY. REFER TO CORRESPONDENCE O ACCIDENT REPORT AND FORWARDED TO THE MDOT PT. ED ACCIDENT REPORT AND FORWARDED TO THE MDOT PT. ED ACCIDENT REPORT AND FORWARDED TO THE MDOT PT.	SRAVEL, THE SUBGI	RADE MATERIAL	BEGAN TC	
D THE CONTRACTOR TO EXCAVATE AND REMOVE  ITAMINATED GRAVEL. ROADWAY STABILIZATION  ILE WAS THEN PLACED ON THE SUB-GRADE SURFACE  PLACING ASC GRAVEL. THIS WORK WILL BE PAID  ITEM 203.20 COMMON EXC AND 304 10 ASC-GRAVEL.  ROCK 4 PAGES 5 THROUGH 7 FOR FIELD MEASUREMENTS  Y STABILIZATION GEOTEXTILE WILL BE PAID  DENTS WORK ORDER #1 (AMOCO 2006 INSTALLED)  DENTS WORK ORDER #1 (AMOCO 2006 INSTALLED)  ASS AN ACCIDENT ON THE PROJECT TODAY AT  AS AN ACCIDENT ON THE PROJECT TODAY AT  AS AN ACCIDENT ON THE PROJECT TODAY AT  AS AN ACCIDENT ON THE PROJECT TODAY AT  WES WITHIN THE WORK ZONE. THE ACCIDENT WAS  GATED BY JOEL RAMICH OF THE FARMINGTON  WERE SATISFACTORY. REFER TO CORRESPONDENCE  A COPY OF THE POLICE/ACCIDENT REPORT  ED ACCIDENT REPORT AND FORWARDED TO THE MDOT  PPT.  BY : BILL BITTERMAN 06-16-02	: INTO THE LOWER	ASC GRAVEL LI	T. THE RE	SIDENT
TAMINATED GRAVEL. ROADWAY STABILIZATION THE WAS THEN PLACED ON THE SUB-GRADE SURFACE VACING ASC GRAVEL. THIS WORK WILL BE PAID THE WAS THEN PLACED ON THE SUB-GRADE SURFACE VACING ASC GRAVEL. THIS WORK WILL BE PAID THE 203.20 COMMON EXC AND 304 10 ASC-GRAVEL. THE WORK ORDER #1 (AMOCO 2006 INSTALLED) AS AN ACCIDENT ON THE PROJECT TODAY AT AS AN ACCIDENT WAS STOPPED FOR FLAGGER THE WORK ZONE. THE FARMINGTON WERE SATISFACTORY. REFER TO CORRESPONDENCE THE POLICE ACCIDENT REPORT ED ACCIDENT REPORT AND FORWARDED TO THE MDOT THE BILL BITTERMAN 06-16-02	D THE CONTRACTO	R TO EXCAVATE	AND REMO	/E
THE WAS THEN PLACED ON THE SUB-GRADE SURFACE  LACTING ASC GRAVEL. THIS WORK WILL BE PAID  TEM 203.20 COMMON EYC AND 304 10 ASC-GRAVEL.  ROCK 4 PAGES 5 THROUGH 7 FOR FIELD MEASUREMENTS  Y STABILIZATION GEOTEXTILE WILL BE PAID  DENTS WORK ORDER #1 (AMOCO 2006 INSTALLED)  DENTS WORK ORDER #1 (AMOCO 2006 INSTALLED)  AS AN ACCIDENT ON THE PROJECT TODAY A1  A5 AN ACCIDENT ON THE PROJECT CONTROL  WERE SATISFACTORY. REFER TO CORRESPONDENCE  ED ACCIDENT REPORT AND FORWARDED TO THE MDOT  PT.  BY: BILL BITTERMAN 06-16-02	TAMINATED GRAVE	-L. ROADWAY S	ABILIZATI	3
TACING ASC GRAVEL. THIS WORK WILL BE PAID TEM 203.20 COMMON EYC AND 304 10 ASC-GRAVEL. NOCK 4 PAGES 5 THROUGH 7 FOR FIELD MEASUREMENTS Y STABILIZATION GEOTEXTILE WILL BE PAID DENTS WORK ORDER #1 (AMOCO 2006 INSTALLED)  WENTS WORK ORDER #1 (AMOCO 2006 INSTALLED)  AS AN ACCIDENT ON THE PROJECT TODAY AT  WERE WITHIN THE WORK ZONE. THE FARMINGTON  WERE SATISFACTORY. REFER TO CORRESPONDENCE  A COPY OF THE POLICE/ACCIDENT REPORT  BY : BILL BITTERMAN 06-16-02	ILE WAS IHEN PL	ACED ON THE SL	B-GRADE S	URFACE
1EM 203.20 COMMON EXC AND 304 10 ASC-GRAVEL. COK 4 PAGES 5 THROUGH 7 FOR FIELD MEASUREMENTS  Y STABILIZATION GEOTEXTILE WILL BE PAID DENTS WORK ORDER #1 (AMOCO 2006 INSTALLED)  AS AN ACCIDENT ON THE PROJECT TODAY AT  AS AN ACCIDENT ON THE PROJECT TODAY AT  A T 10:00 AM +/ VEHICLE NO 1 FORD EXPLORER  A 326 JJ) REAR-ENDED VEHICLE NO 2 (CHEVY S-1C  T 63784 I) WHICH WAS STOPPED FOR FLAGGER  A 2356 JJ) REAR-ENDED VEHICLE NO 2 (CHEVY S-1C  T 63784 I) WHICH WAS STOPPED FOR FLAGGER  A 23784 I) WHICH WAS STOPPED FOR FLAGGER  A COPY OF THE POLICE/ACCIDENT REPORT  ED ACCIDENT REPORT AND FORWARDED TO THE MDOT  PT.  EY: BILL BITTERMAN 06-16-02	LACING ASC GRAVI	FL. THIS WORK	WILL BE PA	<i>ID</i>
VECK 4 FAGES 5 THROUGH / FOR FLELD MEASUREMENTS  Y STABILIZATION GEOTEXTILE WILL BE PAID  DENTS WORK ORDER #1 (AMOCO 2006 INSTALLED)  AS AN ACCIDENT ON THE PROJECT TODAY AT  AT 10:00 AM +/ VEHICLE NO 1 (FORD EXPLORER  O 763784 I) WHICH WAS STOPPED FOR FLAGGER  UES WITHIN THE WORK ZONE. THE FARMINGTON  EPT. ALL SIGNS WERE UP AND TRAFFIC CONTROL  WERE SATISFACTORY. REFER TO CORRESPONDENCE  A COPY OF THE POLICE/ACCIDENT REPORT  ED ACCIDENT REPORT AND FORWARDED TO THE MDOT  PT.  BY: BILL BITTERMAN 06-16-02	ILM ZUS. ZU COMMO	IN EXC AND 304	10 ASC-6k	AVEL.
DENTS WORK ORDER #1 (AMOCO 2006 INSTALLED)  45 AN ACCIDENT ON THE PROJECT TODAY A1  5 AT 10:00 AM +/ VEHICLE NO 1 (FORD EXPLORER  7 A3784 I) WHICH WAS STOPPED FOR FLAGGER  125 WITHIN THE WORK ZONE. THE FARMINGTON  6 ATED BY JOEL RAMICH OF THE FARMINGTON  6 ATED BY JOEL RAMICH OF THE FARMINGTON  6 ACOPY OF THE POLICE/ACCIDENT REPORT  6 ACCIDENT REPORT AND FORWARDED TO THE MDOT  77  77  78  79  70  71  72  74  75  75  76  76  77  76  77  76  77  77	V CTAPT TATTON	CECTENTIFE W	TLD MEASO	KEMENIS
45 AN ACCIDENT ON THE PROJECT TODAY AT  AS AN ACCIDENT ON THE PROJECT TODAY AT  AT 10:00 AM +/ VEHICLE NO 1 (FORD EXPLORER  A356 JJ) REAR-ENDED VEHICLE NO 2 (CHEVY S-10  763784 I) WHICH WAS STOPPED FOR FLAGGER  LES WITHIN THE WORK ZONE. THE FARMINGTON  GATED BY JOEL RAMICH OF THE FARMINGTON  WERE SATISFACTORY. REFER TO CORRESPONDENCE  A COPY OF THE POLICE/ACCIDENT REPORT  ED ACCIDENT REPORT AND FORWARDED TO THE MDOT  PT.  BY: BILL BITTERMAN 06-16-02	NEVITE WOD YOU			150
45 AN ACCIDENT ON THE PROJECT TODAY AT 5 AT 10:00 AM +/ VEHICLE NO 1 FORD EXPLORER 5 AT 10:00 AM +/ VEHICLE NO 1 FORD EXPLORER 5 AT 10:00 AM +/ VEHICLE NO 1 FORD EXPLORER 6 A 356 JJ) REAR-ENDED VEHICLE NO 2 (CHEVY 5-10 6 763784 I) WHICH WAS STOPPED FOR FLAGGER 6 A TED BY JOEL RAMICH OF THE FARMINGTON 6 A TED BY JOEL RAMICH OF THE FARMINGTON 6 A TED BY JOEL RAMICH OF THE FARMINGTON 6 A COPY OF THE POLICE ACCIDENT REPORT 6 D ACCIDENT REPORT AND FORWARDED TO THE MDOT 7 PT. 6 BY: BILL BITTERMAN 06-16-02			7 100	()
8Y: BILL BITTERMAN 06-16-02	AS AN ACCIDENT	ON THE PROJEC	TODAY AT	
9 4356 JJ) REAR-ENDED VEHICLE NO 2 (CHEVY S-1C) 763784 I) WHICH WAS STOPPED FOR FLAGGER THES WITHIN THE WORK ZONE. THE ACCIDENT WAS SATED BY JOEL RAMICH OF THE FARMINGTON WERE UP AND TRAFFIC CONTROL WERE SATISFACTORY. REFER TO CORRESPONDENCE A COPY OF THE POLICE/ACCIDENT REPORT PT.  ED ACCIDENT REPORT AND FORWARDED TO THE MDOT PPT.  BY: BILL BITTERMAN 06-16-02		VEHICLE NO 1	FORD EXPL	ORER
7 763784 I) WHICH WAS STOPPED FOR FLAGGER 1/LES WITHIN THE WORK ZONE. THE ACCIDENT WAS 5/417ED BY JOEL RAMICH OF THE FARMINGTON 1/LES WITHIN THE WORK ZONE. THE FARMINGTON 1/LES WITHIN THE WORK ZONE. THE FARMINGTON 1/LES WITHING WARE UP AND TRAFFIC CONTROL 1/LES WITHING FOR THE POLICE ACCIDENT REPORT 1/LES ACCIDENT REPORT AND FORWARDED TO THE MDOT 1/LES WITHING FOR THE MOOT 1/LES WITHING FOR THE MOOT 1/LES WITHING FOR THE FARMAN 06-16-02	7 4356 JJ) REAR-EI	NDED VEHICLE N	IO 2 (CHEV)	' S-1C
UES WITHIN THE WORK ZONE. THE ACCIDENT WAS SATED BY JOEL RAMICH OF THE FARMINGTON FOT. ALL SIGNS WERE UP AND TRAFFIC CONTROL WERE SATISFACTORY. REFER TO CORRESPONDENCE A COPY OF THE POLICE/ACCIDENT REPORT AND FORWARDED TO THE MDOT PT.  BY: BILL BITTERMAN 06-16-02	763784 I) WHICH	I WAS STOPPED	FOR FLAGG	<b>3</b> 2
BY : BILL BITTERMAN 06-16-02	LES WITHIN THE	WORK ZONE. TH	IE ACCIDEN	T WAS
WERE SATISFACTORY. REFER TO CORRESPONDENCE A COPY OF THE POLICE/ACCIDENT REPORT ED ACCIDENT REPORT OF THE MOOT OF THE POLICE/ACCIDENT REPORT OF THE MOOT OF THE MO	SATED BY JOEL RA	MICH OF THE F.	RMINGTON	
WERE SATISFACTORY. REFER TO CORRESPONDENCE A COPY OF THE POLICE ACCIDENT REPORT ED ACCIDENT REPORT AND FORWARDED TO THE MDOT PPT. BY: BILL BITTERMAN 06-16-02	JEPT. ALL SIGNS W	ERE UP AND TRA	FFIC CONT	ROL
A COPY OF THE POLICE/ACCIDENT REPORT ED ACCIDENT REPORT AND FORWARDED TO THE MDOT PPT.  BY: BILL BITTERMAN 06-16-02	VI.	ORY. REFER TO C	ORRESPON	SENCE
ED ACCIDENT REPORT AND FORWARDED TO THE MDOT PPT.  BY: BILL BITTERMAN 06-16-02	A COPY OF THE PO	JLICE/ACCIDENT	REPORT	
PT. 8Y: BILL BITTERMAN 06-16-02	ED ACCIDENT REPC	RT AND FORWA	RDED TO TI	IE MDOT
BY: BILL BITTERMAN 06-16-02	<u>:</u> PT.			
BY: BILL BITTERMAN 06-16-02				
BY : BILL BITTERMAN 06-16-02				
8Y : BILL BITTERMAN Ø6-16-02				
BY: BILL BITTERMAN 06-16-02				
	BY : BILL BITTERA	NAN 06-16-02		

				VICE	ED,	25		7	<i>20</i> 8	WORK H PITJ	STA 2+00 V AREA, ED ON PAID AS +00,	    &
FAIR 70'S		SOR	B ROLLER	1 PAVER, 12 TRUCKS, 1 SERVICE BOBCAT.	12 UNSKILLED	STA 22+00 TO 35+25	TO 35+25	CALL FROM BILL COBURN-FABRICATION INSPECTOR RE: CONRETE CURBING. BILL HAD SOME CONCERNS ABOUT THE PERMABILITY. HE WILL VIST GAGNE THEIR VEAZIE	TOMORROW AND WILL E-MAIL ME THE RESULTS OF THE TEST IF THERE IS A PROBLEM, REFER TO CORRES. FILE FOR RECORD.	20 TO 5+00, EXCESS MATERIALS FROM INSLOPE WORK AND TAKEN TO APPROVED WASTE AREA (SMITH PIT)	STA 2+00 TO 12+00, PIKES RECLAIMER ON PROJECT, STA TO STA 5+00 TO REMOVE PVMT IN FULL EXCAVATION ARE LOADER PLACING MAT'L IN TRUCKS TO BE STOCKPILED ON SITE AND PLACED AS ASC AT A LATER DATE. TO BE PAID COMMON EXC AND ASC. RECLAIMED STA 5+00 TO 12+00. GRADED AND COMPACTED, TO BE PAID AS 307.	ON SITE TO TEST 307 COMPACTION TERMAN 6-17-02
	RESIDENT T. INSPECTOR	1 COMPRESSOR 2 TRUCKS	1 5 TON VIB ROLLER	1VER, 12 TRI CAT.	,7 SKTLLED, S		STA 22+00 TO 35+25	CALL FROM BILL COBURN-FABRICATION INSPECTOR RE: CONRETE CURBING BILL HAD SOME CONCERNS ABO THE PERMABILITY. HE WILL VIST GAGNE THEIR VEAZIE	NE THE RESU EFER TO CO	STA 2+00 TO 5+00, EXCESS MATERIALS FROM REMOVED AND TAKEN TO APPROVED WASTE	STA 2+00 TO 12+00, PIKES RECLAIMER ON PROJECT, STO STA 5+00 TO REMOVE PVMT IN FULL EXCAVATION LOADER PLACING MAT'L IN TRUCKS TO BE STOCKPILED SITE AND PLACED AS ASG AT A LATER DATE. TO BE PACOMMON EXC AND ASG. RECLAIMED STA 5+00 TO 12+0 GRADED AND COMPACTED, TO BE PAID AS 307.	TO TEST 30;
	BILL BITTERMAN, RESIDENT BILLY BOB BENNET, INSPECTOR	м <i>ч 00:9</i> м			PERSONNEL: 1 SUPT, 1 FOREMAN, 7 SKILLED 2 LABORERS & 2 QC/QA WORKERS	ITEM 304 104 FINEGRADE COMPLETE AND ACCEPTED	BEGAN AT.	RN-FABRIC 5. BILL HAL 7. WILL VIS	L E-MAIL A PROBLEM, R	XCESS MAT	PIKES RECLAIMER ON OVE PUMT IN FULL EX T.L. IN TRUCKS TO BE ASE AT A LATER DATE SG. RECLAIMED STA 5 TED, TO BE PAID AS STA	
MONDAY	BILL BITT	6:00AM TO 6:00 PM 1 SUPT 5 WORKERS	2 LARGE EXC.	PIKE IND, 4 ROLLERS, 1 WATER TRUCK & 1	L: 1 SUPT, SS & 2 QC/0	104 E COMPLETE	ITEM 403.207 PAVING OPERATIONS BEGAN AT	N BILL COBU TE CURBIN ABILITY. HI	N AND WIL HERE IS A	20 TO 5+00, E. AND TAKEN	STA 2+00 TO 12+00, I TO STA 5+00 TO 12+00, I TO STA 5+00 TO REM LOADER PLACING MAT SITE AND PLACED AS COMMON EXC AND AS GRADED AND COMPAC	DENNY DOYLE, MDOT ENTERED BY : BILL BI
6/17/02	MDOT:	М&Н:		SUB: PIKE TRUCK, 1	PERSONNE 2 LABOREI	ITEM 304, 104 FINEGRADE CO	ITEM 403. PAVING OP	CALL FROM RE: CONRI THE PERM	TOMORRO TEST IF T RECORD.	STA 2+00 REMOVED	STA 2+00 TC STA 2+00 TC TO STA 5+00 LOADER PLAC STTE AND PL COMMON EX GRADED AND	DENINY DC ENTERED I

		VOLUME		487.5	2925		487.5	3900 CF		44 CY							<i>"8</i>							
	RED ENDS)	LENGTH		22	75		22	IMF =		= 144.							DFPTH = 1							
>	20+00 TO 21+25 (TAPERED ENDS)	AREA SF	0	00	χς	39	,	TOAL VOLUME		ON = (3900)/27	١٠ ١	Š	1-08-02											
COMMON EXCAVATION	20+00 TO 2	<i>рЕРТН</i>	0	4 67	1.5	1.5′	,	0		HIS SECTION	OTV = 144 44 CV		TTERMAN .	20	3									
COMMON	STA AREA	W1 W2	0 0	190 180	27 47	24' 28'		0	20	TOTAL VOLUME FOR THIS			ENTERED BY : BILL BITTERMAN 11-08-02	7. 400 4.0	CHECKED BY: ABC 1-C-US									
202.20	COMMON EXC ST. FROST HEAVE AREA	SECTION	1	,	٧	B	,	4	ITEM 202.	TOTAL VO	TTFM 304 104 45G		ENTERED E		CHECKED B									

													117	<u>}</u>									
	DWAY ELEV	VOLUME	ζ,	21	33.6	10.5	11.2	76.3 CY		68.67 CY	TRUCK MEASUREMENTS			WITH ONE ADDITIONAL LOAD BY TRUCK INC.	76.3 CV 10.5	è	86.8 CY		69.44 CV				
	REGRADING ENTRANCE TO MATCH NEW ROADWAY ELEI	VOLUME	VOL/LOAD	10.5	11.2	10.5	11.2	TOTAL	REDUCTION	.9(76.3) =	TRUCK MEA		RETURNED	אר בטאט פא	TOTAL TRK #117			REDUCTION	.8(86.8) =	1-08-02			
1361	TO MATC	NO OF	LOADS	2	3	I	1		T.M. QTY	>	PAGE 60 FOR		D EXC AND	AUDITION				VTQ.	QTY	BITTERMAN I	.03		
#Y/ cT4 14.25	FNTRANC	TRUCK	NO	117	120	117	120			P TOTAL QIY	800K #4 P	104	TRUCK REMOVED EXC	MILM CIVI					TOTAL	BY : BILL BI	V: ABC 1-2-03		
202.20 COMMON E	EGRADIN		DATE	37530	37530	10/2/2002	10/2/2001			ITEM 202.	REFER TO	ITEM 304.1	NOTE: TRU						ITEM 304.104	ENTERED B	CHECKED BY:		

COMMON EXCAVATION		990		96 10															
COMMON		CONSTRUCTION BK 3 PG	INSP DIARY BK 4 PG 3	CONSTRUCTION BK 3 PG 10															
202.20	REF	CONSTRUCT	INSP DIAR	CONSTRUCT															

203.21 ROCK EXCAVATION	VAITON		600 CY & \$12.00	\$12.00
STA	QTY	ACC. QTV	ENT BY	DATE
17+80	11.59~	11.59~	888	8/20/2002
	2.46 ~	14.05~	888	8/12/2002
22+20	14.6 ~	28.65 ~	888	8/12/2002
QUANTITY:	Y: 24.64 CY			
ENTERED BY : BILL B	BILL BITTERMAN 11-08-02	1-08-02		
CHECKED BY: ABC 1-2-03	-03 ~			

-	_ 		200	202	200	200	202	200	200	200	200	202	200	202	202	20	_	 _	_			 		_	_	_	 			_
		DATE	6/20/2002	6/20/2002	2002/02/9	2002/02/9	6/21/2002	6/21/2002	2002/92/9	6/27/2002	6/27/2002	6/27/2002	6/27/2002	6/27/2002	6/27/2002	7/1/2002		>		3-05										
!	ENT	BY	888	888	888	888	888	888	888	BBB	888	888	BBB	888	BBB	888		1790 FT		NAN 11-0	-2-03									
1	ACC.	LENGTH	125' ~	220'~	~ ,08Z	320′~	445'~	<i>602</i> , <i>&lt;</i>	1040'~	1140'~	1265'~	1290'~	1315'~	1365'~	1465'~	1790'~		QUANTITY: 1790 FT		ILL BITTER	CHECKED BY: BWD1-2-03									
		LENGTH	125'~	> 26	~ ,09	40, ~	125′ ~	160' ~	435'~	100,~	125'~	25' ~	25' ~	20, ~	100, ~	325' ~		FINAL PAY		ENTERED BY : BILL BITTERMAN 11-08-02	CHECKE									
		STA	3+25RT	5+00RT	6+00RT	6+75RT	9+50RT	11+90RT	12+00 LT	22+50RT	24+50RT	25+55RT	26+75RT	28+25RT	29+50RT	30+00LT		1		ENT										
T		STA	2+00RT	4+05FT	5+40RT	6+35RT	8+25RT	10+80RT	1+00 TL	21+50RT	23+25RT	25+35RT	26+50RT	27+75 RT	28+50RT	21+00LT											T			

		Smith's					Ames														
		waste hauled to					waste hauled to														
		cord to pla			1 PAGE 5		cord to pla		1 DACE 8	2 700 1											
	7.	completed accord to plan/spec,	waste area		SP DIARY #	7	completed accord to plan/spec,	אמאופ מופמ	SP NTABY #	W / YUTO "											
REF.	DIRECT ENT.	-		-	RFF TO IN	DIRECT ENT.			DEF TO TASP OTABY #1 PACE	VC											

8	TE		37478														_ 							-
\$12.	DATE		4	_	Н	_	Н				-	4	_			4	_	_	Ц	4	4	_	_	+
600 CY @ \$12.00	ENT BY		888	999																				
	4CC. QTV		275	318.93					11-08-02															
BORROW	417		275	42.5				QUANTITY: 318.93 CY	BILL BITTERMAN	00	3													
203.25 GRANULAR BORROW	STA		32+00	19+75					Y : BILL BI	707.70	7. ABC 1-6													Ī
203.25	STA		30+00	33+28 KI 19+00				FINAL PAY	ENTERED BY :	711E7VEN BV. 187 1 2 02	רחבראבט פ.													Ī

			JE		S & SPEC	1														
	TEWED AND	LAN QTY	ON OUTSIL		D TO PLAN	INDERCUT)	MAINTENACE OF TRAFFIC													
	ENGINEERS ESTIMATE WAS REVIEWED BE REASONABLE AND ACCURATE.	SREED TO F	EXCAVATI	SIRECTED.	COMPLETE	NATION (L	FIC													
	S ESTIMAT NABLE AN	TRACTOR A	DDITIONAL	TS OR AS	E BACKFILL	ONAL EXC	E OF TRAF													
	NOTE: THE ENGINEERS ESTIMATE WAS REVI APPEARS TO BE REASONABLE AND ACCURATE.	NO 1; CON	LUS ANY A	TION LIMI	4 PG 2 MULTI PLATE BACKFILL	OR ADDITI	MAINTENAC													
REF	NOTE: THE A	REF: RWO NO 1; CONTRACTOR ABREED TO PLAN QTY	PAYMENT P	OF EXCAVATION LIMITS OR AS DIRECTED.	BK 4 PG 2 N	4 PG 2	BK 4 PG 2 A													

		37489							_ 				_ 		_ 	_ 			_			_		-
<u>}</u>	DATE	3/																						
304.104 AGGREGATE SUBBASE COURSE GRAVEL-FLAIN QTY	ENT BY	888																						
יטטאטר שא	ACC. OTY	900			669.44				, 00 00	70-90-1														
שרששטר -	710	009			69.44			: 669.44 CY	, 147 77	ICKMAN	03													
	574	0			21+25			FINAL PAY QUANTITY: 669.44 C	10 / 10 / /	ENTERED BY : BILL BY I LERMAN 11-08-02	CHECKED BY: ABC 1-2-03													
	574	0			20+00			FINAL PAY	0 470000	באוראבט פ	CHECKED B													

			IDE			PG 22-32													
7514/67		LAN QTY	ON OUTS.		10	P DIARY P													
1446 DEI	ABLE AND ACCURATE.	REED TO H	EXCAVATI	DIRECTED.	DE CHECKS	s, REF INS													
2 50 7744 47	NABLE AND	RACTOR A	DITIONAL	TS OR AS	FOR FINEFRADE CHECKS	IN DRIVE													
CAICTAICE	BE REASO	JO 1; CONT	US ANY AL	TION LIMI	THRU 16 FC	MATL USED IN DRIVES, REF INSP DIARY													
REF TIME	APPEARS TO BE REASONABLE AND ACCURATE	REF: RWO NO 1; CONTRACTOR AGREED TO PLAN QTY	PAYMENT PLUS ANY ADDITIONAL EXCAVATION OUTSIDE	OF EXCAVATION LIMITS OR AS	BK 3 PG 4 TI	ADDITION ,													

LE	FT	5	ΓΑ	R	I&HT
16'	12'		3	12'	16'
	14 3	15	00 —		
1					₩ <b>1</b>
_					2
					7
2		15	• <i>50</i>		70 7
7	,		į l		777
اب	1		1		4 4
<b>8</b>		16	-00		2 8
92	1		-	100	12 2
98			4	1	177H 886
<del>2</del>		4.0	50	10	8 2
9		10	<b>-50</b>		49
5			ļ		0 B
9					TO BE WITHEN ALLOWABLE ENT BY 886 8-2-02
<i>i</i> y,	i i	<i>17</i> :	-00	1	
8			1	1	18 8
ŽΙ	10		1	i e	≳े ≧ं
र्छ ।		17	-50	<u> </u>	<u> </u>
<u> </u>		2/	30	-	1 2 4 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
2					<del>  5</del> <del> </del>
		. =		<u> </u>	3 -
		18	-00		TOLERANCES
TOLERANCES, ENT BY BBB 8-2-02					15
_					<del>- X</del>
2		18	<b>5</b> 0		2
9	1		1		9
8-3-02				İ	8-3-02
<del>-20</del>	1	19	-00	1	<u>₹ % </u>
99				+	2 9
88			/		NITT-15
<del>~</del>	a a	40			5 7
9		19	<b>-50</b>	1	<u> </u>
LERANCES ENT BY 8BE 8			-		4 FOUND TO BE WITHIN
<i>\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\</i>			.V	F.	5 3
23	§ .	20	+00		& FOUND ERANCES
3				L	\{ \bar{y}
7			1	H	0 4
8		20	<b>-5</b> 0	1	1 <u>1</u> (2)
	Till Till	20	30		201
5				1	95
Lų					CHECKED VABLE TO
78	]	21	-00	l.	ZHECK 14BLE
WABLE	CI IE NUE	ח אם ח	MITH 10-	10 02	9 3
ō	CHECKE	U 07 B.	7/11 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	10-02	6
<del>3</del> 1				12	1 31

LE	FT	STA	RIG	HT
16'	12'	Ć.	12'	16'
-2%	-2%	15+00	-2.0%	-2%
25"	24"	2 <mark>!</mark> "	24"	24.75
-2%	-1.50%	15+50	-2.0%	-2%
<i>24.25</i> "	23.25"	21"	24"	24.75
-2%	-1.0%	16+00	-2.0%	-2%
<i>23.5</i> "	22.5"	2!"	24"	24.75
-2%	-0.50%	16+50	-2.0%	-2%
<i>22.75</i> "	21.75"	2!"	24"	<i>24.75</i>
-2%	+1.0%	17+00	-2.0%	-2%
20.5"	19.5"	21"	24"	<i>24.75</i>
-2%	+2.5%	17+50	-3.0%	-3.0%
18.5"	17.5"	2 <mark>!</mark> "	25.25"	26.75
-2%	+4.0%	18+00	-4.0%	-4.0%
16.25"	15.25"	2!"	26.25"	<i>28.75</i>
-2%	+4.0%	18+50	-4.0%	-4.0%
16.25"	15.25"	2 <mark>!</mark> "	26.25"	28.75
-2%	+2.5%	19+00	-3.0%	-3.0%
18.5"	17.5"	21"	25.25"	<i>26.75</i>
-2%	+1.0%	19+50	-2.0%	-2%
20.5"	19.5"	21"	24"	24.75
-2%	-0.5%	20+00	-2.0%	-2%
<i>22.75</i> "	21.75"	21"	24"	24.75
-2%	-1.5%	20+50	-2.0%	-2%
24.25"	23.25"	2!"	24"	24.75
-2%	-2.0%	21+00	-2.0%	-2%
25"	24"	21"	24"	24.75

RIGHT	-	16'	•	778	1V.		0- 07							- 1	- 1		12/\ V/1					D3	HO		Z	9- <sub>8</sub>	ç-8												0.3% 0.3%			- 1
ď	1	12.																																								
574	-		<b>–</b> 15+00			15+50			16+00			42.50	00.01			17+00		;	17+50			18+00		   	18+50			19+00			19+50			20+00			20,50	20	+	21.00	27.70	
ET	ľ	12.																																								+
197	1	16.	•			ā	<i>7</i> 0-	2-	8	98	77	18	7 1	<b>^</b> / <u>-</u> 2	7	´S.	2	/ <i>V</i> &	¥3	70	л		_	*	20	2-1	ç-,	8	78	77 /	18	1/	V <i>3</i>	5:	<del>3</del> 21	V 10	ES	770	24.	37	84	111

	ACCUM	M.L.	1,856.25 ~	1 3,651.75 ~	1,300.00 \$ 4,951.75 \$		1,649.25 \$ 6,601.00 \$	1,540.50 > 8,141.50 >		8,141.50 ~		(JING)			TCIPATING)								
		M.L.	1,856.25	1,795.50	1,300.00		1,649.25	1,540.50		>		(PARTICIPATING)			(NON-PAR								
12.5 MM	ACCUM	Q77			•		,649.25 \$ 8,011,75	79, 792.25	10,756.00	10756.50	>	) MG	1-08-02		> <u>5NC</u>	1-08-02							
		QTY	1,856.25	1, 795.50 🕹	1,601.25	1,109.50	1,649.25	1,780.50	963.75 🗸		230.50	: 10.756.00	BITTERMAN 11-08-02	> 60	: 230.50 TONS	TTERMAN !	.03 ×						
403.208 HOT MIX ASPHALT,		DATE	8/4/2002	8/5/5005	8/6/2002	8/7/2002	8/16/2002	8/17/2002	8/18/2002		37487	FINAL PAY QUANTITY:	BILL	CHECKED BY: ABC 1-2-03	QUANTITY:	ENTERED BY : BILL BITTERMAN 11-08-02	CHECKED BY: ABC 1-2-03						
403.208	COVER	SLIP NO	3456	3457	3458	3460	3461	3466	3469	TOTALS	3470	FINAL PAY	ENTERED BY :	CHECKED BY	FINAL PAY	ENTERED B	CHECKED B						

					*												PAID BY									
, p /2 000	i i	DAIE	8/5/2002	8/6/2002	8/7/2002	8/8/2002	8/17/2002	8/18/2002	8/19/2002					770			10 BE									
	į	ENI BY	888	888	888	888	888	888	888					4 PAGE 23FOR		!	MAPLE LANE									
101/00:11:00	() 	ON 101	1	I	1 1	1 1	2	2 >	2	>						i	NG MIX ON	<u>~</u>								
	ACCUM	Ŝ			301.25 😽	1,410.75		1,650.75	2614.50	2614 50				FCTORS DI	2		RITCIPALL	FARMINGTO								
10,000 MG	SHLDR	<u> </u>			301.25 😽	1,109.50 😽		240.00 ~	963.75 🗸					* REF INSP	BREAKDOWN	,	** NON-PARITCIPALING	TOWN OF								

652.33	DRUMS				
DATE	<i>E</i> 4	DEE	ENT	DATE	
COUNTED	EA	REF	ВУ	DATE	
9-27-01	10	DIRECT ENT	BBB	9/27/2002	
10-15-01	22		BBB	10/05/2002	
10-30-01	22		BBB	10/10/2002	
<i>10-25-01</i>	36	▼	BBB	10/25/2002	
11-05-01	66	BK 3 PGE XX	<b>✓</b> BBB	11/5/2002	
11-10-01	25	DIRECT ENT	BBB	11/20/2002	
11-17-01	30	DIRECT ENT	<i>BBB</i>	12/5/2002	
MAXIMUM	AMOUNT	= 66 DRUMS	· •		
FINAL PAY	QUANTIT	': 66 EA	~		
ENTERED B	Y : BILL BI	TTERMAN I	2-10-02		
			2-10-02		
	Y : BILL B1 Y: ABC 1-2		2-10-02		
			2-10-02		
			2-10-02		
			2-10-02		
			2-10-02		
			2-10-02		
			2-10-02		
			2-10-02		
			2-10-02		
			2-10-02		
			2-10-02		
			/2-10-02		
			2-10-02		
			2-10-02		
			72-10-02		
			72-10-02		
			72-10-02		

50 EA @ \$	65.00		
			_

030.73	TEMP SOIL EROSIG	ON AND WATER POLLUTION	<b>V</b>
ACCEPTED	INSPECTED	WEEK ENDING	
O.K.		8/8/2002	
	O.K.	8/15/2002	
	O.K.	8/22/2002	
	O.K.	8/29/2002	
	O.K.	9/6/2002	
	REF TO REMARKS	9/10/2002	
	KET TO KENTIKKO	271072002	
	REF TO REMARKS	9/11/2002	
	O.K.	9/13/2002	
	O.K.	9/20/2002	
FINAL PAY	QUANTITY: 1 LS Q	<i>1F \$20,000</i> ✓	
ENTERED I	Y : BILL BITTERMA	N 11-08-02	
CHECKED E	Y: ABC 1-2-03 🗸		
CHECKED E	Y: ABC 1-2-03 🗸		
CHECKED E	Y: ABC 1-2-03 🗸		
CHECKED E	Y: ABC 1-2-03 ✓		
CHECKED E	Y: ABC 1-2-03 ✓		
CHECKED E	3Y: ABC 1-2-03 ✓		
CHECKED E	3Y: ABC 1-2-03 ✓		
CHECKED E	3Y: ABC 1-2-03 ✓		
CHECKED E	3Y: ABC 1-2-03 ✓		
CHECKED E	Y: ABC 1-2-03 ✓		
CHECKED E	Y: ABC 1-2-03 ✓		
CHECKED E	Y: ABC 1-2-03 ✓		
CHECKED E	Y: ABC 1-2-03 ✓		
CHECKED E	Y: ABC 1-2-03 ✓		
CHECKED E	Y: ABC 1-2-03 ✓		
CHECKED E	Y: ABC 1-2-03 ✓		
CHECKED E	Y: ABC 1-2-03 ✓		
CHECKED E	Y: ABC 1-2-03 ✓		
CHECKED E	Y: ABC 1-2-03 ✓		
CHECKED E	Y: ABC 1-2-03 ✓		
CHECKED E	3Y: ABC 1-2-03 ✓		
CHECKED E	3Y: ABC 1-2-03 ✓		
CHECKED E	Y: ABC 1-2-03 ✓		

	1 L.S. @\$	20,000				
	REMARKS					
	MIKE CLAR	K, OES, RE	VISED AND	APPROVED	SEWPCP, PA	IY 10%
	<i>PAID 50%</i>					
~	DEDCUT \$1					SPENCE
				ARY PAGE 4		
~	DEDCUT \$1					SPENCE
	DATED 9/1	1/02 AND F	ROJECT DI	ARY PAGE 7	0	
	NOTE: THE					#
		W.O. 55, I	FOR A \$200	LS DEDUC		
						<del></del> -
						<del></del> -

